# Underground Injection Control Program Class VI Well for Geological Sequestration of Carbon Dioxide

# Wells CCS#5, #6, and #7 Permit Application




Archer Daniels Midland Company
Decatur, Illinois

April, 2023

# Contents

1. Executive Summary ..... 5

1.1 Introduction 5
1.2 Injection Plan 6
1.3 Injection Fluid 6

2. General Information ..... 7

2.1 Applicant and Site Information 7
2.2 Cross-Reference Table to Class VI Injection Well Rules 9
2.3 List of Abbreviations Used in this Application 9

3. Site Geologic Characterization ..... 13

3.1 Regional geology and geologic structure 13
3.2 Faults and fractures 20
3.2.1 Interpreted faults based on reprocessed 3D seismic data and Structural Update ..... 20
3.2.2 Fractures implied by microseismic recorded at IBDP ..... 23
3.3 Injection and confining zone characteristics 24
3.3.1 Variogram Analysis ..... 26
3.3.2 Petrophysical Modeling of Effective Porosity and Permeability Interpolation ..... 30
3.4 Hydrologic and hydrogeologic Information 36
3.4.1 Water quality data 38
3.5 Geochemical Data and Compatibility of $CO_2$ 41
3.6 Geomechanical and Petrophysical Information 43
3.6.1 Formation Pressure ..... 43
3.6.2 Rock Strength ..... 43
3.6.3 In-Situ Stress ..... 43
3.6.4 Confining Zone Integrity ..... 44
3.7 Injection & confining zone mineralogy, petrology, and lithology 47
3.7.1 Mt Simon Sandstone ..... 47
3.7.2 Eau Claire Shale ..... 48
3.8 Seismic history, seismic sources, and seismic risk 50
3.8.1 Injection Pressure and Microseismicity ..... 53
3.9 Air and Soil Gas Monitoring 56
3.10 Facies changes in the injection or confining zone 56
3.11 Injection zone storage capacity 59
3.12 Confining zone integrity 61

4. Area of Review (AoR) Delineation and Corrective Action Plan ..... 64

4.1 Conceptual site model 64

4.2 Computational AoR delineation model 69
4.2.1 Pressure Delineation Model ..... 69
4.2.2 Reservoir Modeling Results ..... 71
4.2.3 Sensitivity Discussion ..... 72
4.3 Artificial penetrations within the AoR 78
4.3.1 Tabulation of Wells within the AoR ..... 78
4.4 AoR and Corrective Action Plan 79
5. Financial Responsibility Plan ..... 84
5.1 Area of Review and Corrective Action Cost Estimate 84
5.2 Injection Well Plugging and Site Reclamation Estimate 84
5.3 Post-Injection Site Care Cost Estimate 84
5.5 Emergency and Remedial Response Cost Estimate 85
6. Well Construction Details ..... 89
6.1 Well Hole Diameters and Injection Intervals 89
6.2 Casing Specifications 89
6.3 Tubing Specifications 91
6.4 Tubing and Packer Pressure Gauge and Compatibility 95
7. Pre-Injection/Operational Testing Plan ..... 96
7.1 Tests during well drilling/construction 96
7.1.1 Deviation Checks and casing design ..... 96
7.1.2 Mechanical Integrity Testing and Logging During and after Casing Installation ..... 97
7.2 Injection zone characterization and core sampling 101
7.2.1 Historic injection zone fluid characterization and core sampling ..... 101
7.2.2 Proposed Coring and Fluid Sampling Program ..... 103
7.3 Fracture pressure and downhole hydrogeologic testing of conditions 104
7.3.1 Historic testing ..... 105
7.3.2 Proposed CCS#5, CCS#6 and CCS#7 testing program ..... 107
7.4 Injection and confining zone formation testing 108
7.5 Quality Assurance Surveillance Plan (QASP) 108
8. Site Operating Plan ..... 109
8.1 Injection rate 109
8.2 Maximum injection pressure 109
8.3 $CO_2$ volume 109
8.4 Annulus pressure 110
8.4.1 Regulatory Requirements ..... 110
8.4.2 Casing, Tubing, Annulus Pressure, Average and Maximum ..... 110
8.5 Well stimulation procedures 110

8.5.1 Regulatory Requirements....110
8.5.2 Stimulation Programs or Methods and Description of Stimulation Fluids....111
8.5.3 Determination that Stimulation will not Interfere with Containment....118
8.6 $CO_2$ stream characteristics 118
8.7 Injection Well Operating Requirements 119
8.7.1 Precautions to Prevent Well Blowouts....119
8.7.2 Circumstances Under Which Injection Must Cease....119
9. Testing and Monitoring Plan....121
9.1 $CO_2$ stream analysis 121
9.1.1 Sampling Methods....121
9.1.2 Laboratory to be Used/Chain of Custody Procedures....122
9.2 Mechanical integrity and corrosion testing 122
9.2.1 Sample Description....122
9.2.2 Sample Exposure....122
9.2.3 Sample Handling and Monitoring....123
9.2.4 Mechanical Integrity Testing....123
9.3 Pressure fall-off testing 123
9.3.1 Pressure Fall-off Test Procedure....123
9.4 Groundwater quality monitoring 124
9.4.1 Identification of Monitored Intervals....124
9.4.2 Direct Monitoring Methods....125
9.4.3 Indirect Monitoring Methods....127
9.4.4 Analytical and Field Parameters for Groundwater Samples....128
9.5 $CO_2$ plume and pressure front tracking 130
9.5.1 Direct Monitoring Methods....130
9.5.2 Indirect Monitoring Methods....137
9.6 Testing and monitoring plan QASP 138
9.7 Reporting Requirements 138
9.7.1 Electronic Reporting....138
9.7.2 Semi-Annual Reports....138
9.7.3 24-Hour Reporting....139
9.7.4 Reports on Well Tests and Workovers....140
9.7.5 Advance Notice Reporting....140
9.7.6 Additional Reports....140
9.7.7 Records....141

10. Well Plugging Plan ..... 142
10.1 Facility Information 142
10.2 Summary 142
10.3 Planned Tests or Measures to Determine Bottom-hole Reservoir Pressure 143
10.4 Planned External Mechanical Integrity Test(s) 143
10.5 Information on Cement Plugs 143
10.3 Narrative Description of Plugging Procedures 148
11. Post-Injection Site Care and Site Closure Plan ..... 151
11.1 Pressure differential and position of the $CO_2$ plume and pressure front 151
11.2 Post-injection phase monitoring plan 153
11.2.1 Groundwater Quality Monitoring ..... 153
11.2.2 Carbon Dioxide Plume and Pressure Front Tracking ..... 156
11.3 Alternative PISC timeframe 159
11.4 Non-endangerment demonstration criteria 161
11.5 Monitoring well plugging and site closure plan 165
11.5.1 Plugging the Verification Monitor Wells ..... 166
11.5.2 Plugging the Geophysical Well(s) ..... 170
11.5.3 Planned Remedial/Site Restoration Activities ..... 172
11.6 Quality Assurance and Surveillance Plan (QASP) 173
12. Emergency and Remedial Response Plan ..... 174
APPENDICIES ..... 175
APPENDIX A: Financial Responsibility Documents ..... 176
APPENDIX B: Area of Review Well Database ..... 177
APPENDIX C: Quality Assurance and Surveillance Plan ..... 178
APPENDIX D: Existing Site Wells Coring Summary ..... 179
APPENDIX E: Stimulation Attachments and Procedures ..... 180
APPENDIX F: Cross-Reference Table of Class VI Injection Well Rules (40 CFR Subpart H) ..... 181
APPENDIX G: $CO_2$ Resistant Cement Technical Specification ..... 182

# 1. Executive Summary

## 1.1 Introduction

The Archer Daniels Midland (ADM) Company ("Operator") proposes an addition to the existing underground injection project at its agricultural products and biofuels production facility located in Decatur, Illinois. The goal of this additional neighboring injection site is to add three (3) underground injection wells to accept and retain industrial-scale volumes of carbon dioxide ($CO_2$) for permanent geologic sequestration. Two pre-existing Carbon Capture and Sequestration (CCS) wells with associated equipment have previously been constructed and operated at the main Decatur facility, and permit applications have been submitted for a third and fourth well. This permit application is being submitted for three additional wells to be located on leased property north of the ADM production facility that are named Well #5, Well #6, and Well #7 (CCS#5, CCS#6, and CCS#7) in this application document and related submissions.

Carbon Capture and Sequestration at Well #5, Well #6, and Well #7 (CCS#5, CCS#6, and CCS#7) is to begin injection upon permit approval at an approximate rate of 3,050 metric tons per day (MT/day). At least 1.1 million MT per well will be injected annually to these three wells.

The proposed sequestration site at the ADM facility will be supplied with $CO_2$ from ADM or 3rd party carbon capture systems, including but not limited to:

- Pre-combustion systems
- Oxy-combustion systems
- Post combustion systems
- $CO_2$ from ADM's various ethanol and cogeneration facilities including but not limited to Decatur, IL; Clinton, IA; and Cedar Rapids, IA.

Sensitive, Confidential, or Privileged Information [redacted] Following cessation of the operational period, ADM proposes a post-injection monitoring and site closure period of 10 years.

The new facilities include not only the injection wells CS#5, CCS#6 and CCS#7, but also injection zone monitoring/verification wells VW#4 and VW#5, a geophysical well associated with each injection well (GM#5, GM#6, and GM#7) and a pipeline to transport the $CO_2$ to the injection wells. The three well cluster comprised of VW#4 and VW#5 will meet $CO_2$ sequestration monitoring requirements for the three well aggregate (CCS#5, CCS#6, and CCS#7).

The proposed sequestration site at the ADM facility will be supplied with nearly pure $CO_2$ from various processes as outlined in Section 8.6, $CO_2$ stream characteristics.

ADM will leverage the knowledge and experience gained from historical site characterization and existing site CCS operations to design, construct, and operate the $CO_2$ collection, compression, dehydration, and injection facility capable of delivering and sequestering over 1 million MTs per year of $CO_2$ per well into the Mt. Simon.

The construction phase of the project is expected to last 18-24 months, allowing the commissioning and operation of the new well facilities to occur beginning in January 2025.

## 1.2 Injection Plan

The proposed mass to be injected is to be approximately 3,050 metric tons (MT)/day of supercritical $CO_2$ per well (CS#5, CCS#6 and CCS#7). A cumulative $CO_2$ mass of 13.2 million tons per well is projected over approximately twelve years of operation, for a total of 39.6million tons combined for CCS #5-7. Including injection from CCS #1-4, total injection at the site is projected to be 95 million tons. Injection is scheduled to begin in January 2025. Injection rates will be metered and are projected to remain continuous during the injection period.

Sensitive, Confidential, or Privileged Information [redacted]

Sensitive, Confidential, or Privileged Information [redacted]

During the period prior to injection, additional assessment of perforation strategies and subsequent modeling will take place to further predict the behavior of the $CO_2$ plume based on the data collected during injection well installation, in part, by comparing it to data already collected from the other wells at the site. Permeability-thickness and the injectivity of several sub-intervals (layers) within the Mt. Simon will be quantified and assessed, to understand the distribution of advective $CO_2$ within these intervals.

## 1.3 Injection Fluid

Information pertaining to composition, quantity, origin and other data of the proposed $CO_2$ streams are presented in Section 8.6 $CO_2$ stream characteristics.

CCS#5, CCS#6 and CCS#7 will be operated at a maximum daily injection rate of 3,050 MT/day/well and average annual average injection rate of 1.1 million MT/year/well from the combined $CO_2$ sources addressed in Section 8.6, with injection beginning in February 2026. The total injection mass, over the life of the well, is anticipated to be 13.2 million tons per well.

# 2. General Information

## 2.1 Applicant and Site Information

| | |
|---|---|
| Applicant: | Archer Daniels Midland Company – Corn Processing |
| USEPA Identification No. | ILD984791459 |
| IEPA Identification No. | 1150155136 |
| Facility Contact: | Mr. Douglas Kirk, Plant Manager |
| Mailing Address: | 4666 Faries Parkway<br>Decatur, IL 62526 |
| Phone: | 217-451-6330 |

Injection Well Location:

CCS#5 (Proposed):
+39° 57' 47.32", -89° 00' 43.33" (NAD 1983)
Southwest corner of Section 32
Township 18N, Range 02E
Decatur, Macon County Illinois

CCS#6 (Proposed):
+39° 57' 48.15”, -88° 58' 48.7" (NAD 1983)
Northeast of Section 04
Township 17N, Range 02E
Decatur, Macon County Illinois

CCS#7 (Proposed):
+39° 56' 54.21", -88° 59' 36.19" (NAD 1983)
Northeast of Section 08
Township 17N, Range 02E
Decatur, Macon County Illinois

Site Information:

| | |
|---|---|
| County: | Macon |
| SIC Codes: | 2046 – wet corn milling<br>2869 – industrial organic chemicals,<br>ethanol 2075 – soybean oil mills<br>2076 – vegetable oil mills |
| Owner/Operator: | Archer Daniels Midland Company – Corn Processing<br>4666 Faries Parkway<br>Decatur, IL 62526 |
| Operator Status: | Private |
| Phone: | 1-800-637-5843 |
| Indian Lands: | The site is not located on Indian lands. |

Existing Environmental Permits:

| | |
|---|---|
| NPDES | Industrial Storm Water Permit IL0061425 |
| UIC | IL-115-6A-0001<br>IL-115-6A-0002 |
| RCRA | None |
| Other | Various air permits, including Title V Clean Air Act Permit (#96030038) |
| Other | Sanitary District of Decatur Pre-Treatment, Permit #200 |

Nature of Business:

ADM is a manufacturer of biodiesel, ethanol, soybean oil and meal, corn sweeteners, flour, and other value-added food and feed ingredients. The CCS#5, CCS #6 and CCS #7 wells will be used to manage $CO_2$ generated by these ADM manufacturing operations and for managing $CO_2$ generated at offsite facilities as discussed in Section 8.6 of this document.

## 2.2 Cross-Reference Table to Class VI Injection Well Rules

See APPENDIX F: Cross-Reference Table of Class VI Injection Well Rules (40 CFR Subpart H) for list of regulations and how this application meets applicable requirements.

## 2.3 List of Abbreviations Used in this Application

| | |
|---|---|
| 2D | two-dimensional |
| 3D | three-dimensional |
| ADM | Archer Daniels Midland |
| aka | also known as |
| AoR | area of review |
| API | American Petroleum Institute |
| bbls | barrels |
| BGL | below ground level |
| BHA | bottom hole assembly |
| BHCT | bottom hole circulating temperature |
| BHST | bottom hole static temperature |
| BOD | basis of design |
| BOP | blow out preventer |
| bpm | barrels per minute |
| B-T gauge | Bourdon-tube gauge |
| BTC | buttress thread & coupling |
| BTU | British thermal unit |
| C | Celsius |
| CaCl2 | calcium chloride |
| CaCO3 | calcium carbonate |
| CBL | cement bond log |
| CCS | carbon capture and sequestration |
| cf | cubic feet |
| cf/sk | cubic feet per sack |
| CFR | Code of Federal Regulations |
| cm | centimeter(s) |
| $CO_2$ | carbon dioxide |
| cp | centipoises (viscosity unit) |
| csg | casing |
| cu | capture units |
| D&CWOP | Drill and complete well on paper |
| e.g. | for example |
| EMR | electronic memory recorder |
| EOR | enhanced oil recovery |
| EOT | end of tubing |

| | |
|---|---|
| est. | estimate |
| etc. | et cetera |
| EUE | external upset end |
| F | Fahrenheit |
| FIT | formation integrity test |
| FEED | front end engineering design |
| FOT | fall-off test |
| FS | full scale |
| ft | foot or feet |
| ft/hr | feet per hour |
| ft/min | feet per minute |
| gal/sk | gallons per sack |
| g/L | grams per liter |
| gpm | gallons per minute |
| GR | gamma ray |
| H2S | hydrogen sulfide |
| HAZOP | Hazard and Operability Study |
| hp | horsepower |
| hr(s) | hour(s) |
| IBDP | Illinois Basin – Decatur Project |
| IBOP | inside blowout preventer |
| ID | inside diameter |
| IEPA | Illinois Environmental Protection Agency |
| IL-ICCS | Illinois – Industrial Carbon Capture and Sequestration |
| in. | inch(es) |
| ISGS | Illinois State Geological Survey |
| KB | kelly bushing (depth referenced to) |
| KCl | potassium chloride |
| km | kilometer(s) |
| L (l) | liter(s) |
| Lb (lbs) | pound (pounds) |
| Lb/ft (lbm/ft) | pounds per foot |
| Lb/sk | pounds per sack |
| LCM | lost circulation material |
| LTC | long thread & coupling |
| M (m) | meter(s) |
| m/hr | meters per hour |
| MASIP | maximum allowable surface injection pressure |
| MDT | modular dynamic tester |
| mD | millidarcy (millidarcies) |
| MD | measured depth |
| meV | milli electronvolts |
| mg/L | milligrams per liter |
| MFC | multi-finger caliper |
| MGSC | Midwest Geologic Sequestration Consortium |
| MI | move in |
| mi. | miles |
| mL | milliliter |

| | |
|---|---|
| mmscf | million standard cubic feet |
| MO | move out |
| Mol. | mole |
| MOSDAX | modular subsurface data acquisition system |
| µPa | microPascal |
| MPa | MegaPascal |
| MSL | mean sea level |
| MT | metric tonnes |
| MT/day | metric tonnes per day |
| MVA | monitoring, verification, and accounting |
| N2 | nitrogen (atmospheric) |
| NaCl | sodium chloride |
| N/A | not applicable |
| ND | nipple down |
| NPDES | National Pollution Discharge Elimination System |
| NRC | Nuclear Regulatory Commission |
| NU | nipple up |
| O2 | oxygen (atmospheric) |
| OD | outside diameter |
| Pa | Pascal (pressure unit) |
| P&A | plugging and abandonment |
| P&ID | Piping & Instrument Diagram |
| PBTD | Plug back total depth |
| PCSD | Process Control Strategy Diagram |
| PFD | process flow diagram |
| PFO | pressure fall off |
| PISC | post-injection site care |
| POOH | pull out of hole |
| Poz | pozzolan |
| ppg | pounds per gallon |
| ppb | parts per billion |
| ppf | pounds per foot |
| ppm | parts per million |
| ppmv | parts per million by volume |
| ppmwt | parts per million by weight |
| psi | pounds per square inch |
| psia | pounds per square inch atmospheric |
| psig | pounds per square inch gauge |
| psi/ft | pounds per square inch per foot |
| PV | plastic viscosity |
| QA | quality assurance |
| QHSE | quality, health, safety, and environment |
| Qty | quantity |
| RCC | Richland Community College |
| RD | rig down |
| RU | rig up |
| RST | reservoir saturation tool |
| RSTPro | trademark reservoir saturation tool |

| | |
|---|---|
| S (sec) | seconds |
| SCS | Schlumberger Carbon Services |
| SCMT | slim cement mapping tool |
| sk(s) | sack(s) |
| SIP | surface injection pressure |
| SP | spontaneous potential |
| SPF | slots per foot |
| SRPG | surface-readout pressure gauge |
| SRTs | step rate tests |
| SS | stainless steel |
| STC | short thread & coupling |
| TBD | to be determined |
| tbg | tubing |
| TD | total depth |
| TDS | total dissolved solids |
| TEC | tri-ethylene glycol |
| TIH | trip in hole |
| TIW | Texas Iron Works (pressure valve) |
| TOH | trip out of hole |
| TVD | true vertical depth |
| UIC | underground injection control |
| US DOE | United States Department of Energy |
| USEPA | United States Environmental Protection Agency |
| USDW | underground source of drinking water |
| USGS | United States Geological Survey |
| USIT | ultrasonic imaging tool |
| V (v) | volt |
| VFD | variable frequency drive |
| VSP | vertical seismic profile |
| WFL | water flow log |
| WOC | wait on cement |

# 3. Site Geologic Characterization

## 3.1 Regional geology and geologic structure

The following information, previously presented in the CCS#2 submission, summarizes the regional geology associated with the ADM projects:

Sensitive, Confidential, or Privileged Information [redacted]

Regional geologic characterization of the Mt. Simon Formation has been summarized by several authors (e.g., Medina and Rupp, 2012). Sensitive, Confidential, or Privileged Information [redacted] A stratigraphic column specific to the project is shown in Figure 3.1-1 that displays the petrophysical results of characterizing the Mt Simon Formation locally using data from CCS#1. The facies of the Lower Mt. Simon are a mixture of several depositional environments that include subaqueous coast, subaerial coast, lagoon, river, plain, and eolian plain (Freiburg J. T., 2016). Sensitive, Confidential, or Privileged Information [redacted]

STRATIGRAPHIC COLUMN OF THE ILLINOIS BASIN





**Figure 3.1-1.** Stratigraphic Column for the Illinois Basin (ISGS, 2011)

Sensitive, Confidential, or Privileged Information




**Figure 3.1-2.** Petrophysics at CCS#1 (gamma ray, porosity, and permeability)

The CCS#1 and CCS#2 well submissions that were previously reviewed and approved by US EPA included a through discussion of regional and site geology. Conclusions presented in these submittals indicate that: "

Sensitive, Confidential, or Privileged Information

Figure 3.1-4 presents the location of 2D seismic lines and Figure 3.1-5 presents interpreted faults and miscroseismic events near ADM.

Sensitive, Confidential, or Privileged Information

**Figure 3.1-3.** Regional structural features map showing no regional structures within a 25-mile radius of the ADM Plant near Decatur, Macon County.

Seismic reflection data were acquired over the site to identify the presence of faults and geologic structures in the vicinity of the proposed well site. Sensitive, Confidential, or Privileged Information





**Figure 3.1-4.** Location of 2D and 3D Seismic and contoured Precambrian surface (depth SSTVD). 2D seismic lines are presented in blue (Knox 501, Know 101 and Knox 601). The purple square within the CCS #1-4 area is the location of 3d seismic. Red lines show the location of the modeled plumes in the CCS 5-7 and CCS 1-4 areas (95 Mt as modeled in 2088) and the white outline is the total 7 well 95 Mt pressure boundary in 2043. See Section 4 for additional information regarding plume and pressure boundary modeling and results.

Sensitive, Confidential, or Privileged Information




**Figure 3.1-5. Interpreted faults and miscroseismic events near ADM.** The surface is the Precambrian basement, the orange lines represent the intersection of the interpreted faults from the 3D with the Precambrian, and the blue points are the recorded microseismic events. Extent of the 3D survey, 2D lines, and 2088 95 MT $CO_2$ plume are shown. The several linear cluster of events show a low degree of correlation between microseismic events and interpreted faulting.

Site geologic interpretations pertaining to regional and local stratigraphy and structure were verified and augmented by ADM's collection of log and core data at existing wells CCS#1, CCS#2, VW #1, and VW#2 that included permeability and porosity data. These data are presented on well logs included in Attachment A that summarize data obtained from geophysical logs and core data.

Well logs presented in Attachment A also present the regional thickness of the injection and confining zones gained through the analysis of data acquired via the installation of site deep monitoring wells and injection wells CCS#1, CCS#2, VW#1 and VW#2. Logs presented in Attachment A confirm stratigraphic thickness and lateral distribution at the previously logged and cored locations. Regional thickness at the proposed CCS#5, CCS#6, and CCS#7 locations will be verified through geophysical well log analysis, and will include the collection of core to further verify formation thickness.

Additionally, geologic data pertaining to intervals from 3,000 ft to ground surface are presented in geophysical logs included in Attachment A.

**References**

Freiburg, J. T. (2014). A Depositional and Diagenetic Characterization of the Mt . Simon Sandstone at the Illinois Basin - Decatur Project Carbon Capture and Storage Site , Decatur , Illinois , USA, 73.

Freiburg, J. T. (2016, 05 17). *Current Research on the Mt. Simon Geology; Refining the Lower Mt. Simon Depositional Interpretation.* Retrieved from http://www.sequestration.org/resources/PAGMay2016Presentations/04-Freiburg_IBDP_PAG_2016_Mt-Simon.pdf: http://www.sequestration.org/resources/PAGMay2016Presentations/04-Freiburg_IBDP_PAG_2016_Mt-Simon.pdf

Frommelt, D., 2010. Letter to the Illinois Environmental Protection Agency, Subject: CCS Well #1 Completion Report, Archer Daniels Midland Company – UIC Permit UIC-012-ADM, dated May 5, 2010.

ISGS. (2011). *Stratigraphic Column for the Illinois Basin .*

Medina, C. R., & Rupp, A. J. (2012). Reservoir characterization and lithostratigraphic division of the Mount Simon Sandstone (Cambrian): Implications for estimations of geologic sequestration storage capacity. *Environmental Geosciences*, 1-15.

Nelson, W.J., 1995. Structural features in Illinois, Illinois State Geological Survey Bulletin 100, 144 p.

Smith, V. L., & Leetaru, H. E. (2014). *2D Seismic Reflection Data across Central Illinois.* Schlumberger Carbon Services.

## 3.2 Faults and fractures

Based on the site-specific data collected and analyses that have been completed using these data, there is very low risk for faulting or fracturing being present near the proposed CCS #5, CCS #6, and CCS #7 wells that has any potential to impact the arrestment properties of the confining zone at the site. In addition to characterization of the site geology that supports the sealing properties of the cap rocks, during the injection phase of the project to date wherein $CO_2$ was managed in the Mt. Simon at the nearby CCS#1 and CCS#2 wells (beginning in 2012), no loss of containment has been detected and no microseismic events occurred above the injection zone.

Faulting does not and will not contribute to lack of containment because:

- Sensitive, Confidential, or Privileged Information [redacted]

Sensitive, Confidential, or Privileged Information [redacted]

### 3.2.1 Interpreted faults based on reprocessed 3D seismic data and Structural Update

Reprocessed Seismic Data. Recent 2019 reprocessing of the 3D seismic cube was performed to boost the upper frequency band of the 3D seismic data, resulting in a crisper image of the injection zone and the Precambrian basement. The continuity observed in the original seismic section (yellow box in the lower panel of Figure 3.2-1) was disrupted by frequency boosting (in the upper panel, Figure 3.2-1). After the higher frequencies were boosted in the 3D cube, an edge detection algorithm was applied to the reprocessed data, which identified discontinuities in the 3D seismic that may be attributed to depositional changes or may be related to limited faulting. The next step was to apply an Ant-tracking algorithm to the edge detection cube to planarize these discontinuities. When constrained by a stereonet filter, Ant-tracking will produce only near-vertical features that imply faulting. However, there is significant uncertainty associated with the use of this algorithm, based on this seismic quality, to identify faults so the location of any features interpreted as faults is suspect. Also, the manual interpretation performed using the Ant-track cube as a guide is a subjective process, and interpretations can vary significantly between interpreters.

As discussed in Section 3.1 and presented in Figures 3.1-4 and 3.1-5, regional surfaces were expanded in 2021 from the original 3D seismic interpretation-based area to a 60x60 mile region using three 2D seismic lines: Sensitive, Confi [redacted] he surfaces that could not be interpreted using the 2D lines: the Eau Claire Limestone, the Eau Claire Shale, the Mt. Simon D, the Mt. Simon C, the Mt. Simon B, the Mt. Simon A Upper Conformal, the Mt. Simon A Lower Conformal, and the Argenta were conformally gridded between the interpretable surfaces to maintain thicknesses.

In 2023, the 3d geocellular model was expanded again to a 52-mile x 58-mile region (utilizing the updated 60 x 60 mile structure surfaces) to more accurately simulate the CCS5-7 proposed well injection grouping. Sensitive, Confidential, or Pri [redacted] These updated structure surfaces matched trends seen in public online sources.

The new global 3d geocellular tartan grid configuration, with variable cell sizes, is 373 x 557 x 110 cells (totaling 22,853,710) in the x, y, and z directions, respectively. The smallest grid cells around the injectors and observation wells were 200 ft × 200 ft (61m x 61m) laterally. The vertical thickness of each cell varies depending on the zone thickness.

Sensitive, Confidential, or Privileged Information




**Figure 3.2-1. Original seismic processing (bottom panel) and 2019 reprocessing (top panel).** Note the lateral continuity of the Mt. Simon C in the yellow box on the bottom panel, as compared to the disruption in the seismic signature in the yellow box on the upper panel.

Sensitive, Confidential, or Privileged Information

Sensitive, Confidential, or Privileged Information




**Figure 3.2-2. Association of interpreted faults and microseismic events at or near CCS #1 (IBDP).** The surface is the Precambrian basement, the white lines represent the intersection of the interpreted faults from the 3D with the Precambrian, and the blue points are the recorded microseismic events. There are several linear clusters of events which show a low degree of correlation with the interpreted faulting.

### 3.2.2 Fractures implied by microseismic recorded at IBDP

Sensitive, Confidential, or Privileged Information

Sensitive, Confidential, or Privileged Information




**Figure 3.2-3 – Cross section through IDBP from Dando, 2021 (a) and histogram of the depth below the confining zone for microseismic events (b).** The cross section shows the majority of microseismic events occur in the Precambrian, with some in the Argenta and Lower Mt. Simon. The histogram shows the depth of events below the Eau Claire shale.

Based on information presented in the above discussions and figures, no new faults were identified in the CCS#4, CCS#5, CCS#6 and CCS#7 locations relative to those previously identified after incorporating 2D seismic data. All known regional faulting is presented in previous discussions in this section.

## 3.3 Injection and confining zone characteristics

The CCS#1 and CCS#2 approved permit applications included detailed information pertaining to general and specific injection and confining zone characteristics. The following information summarizes data presented in the CCS#2 submission as well as additional data provided to EPA (2022), and is included for completeness. Refer to previous applications for additional detailed information. The information presented herein extends to the CCS#5, CCS#6, and CCS#7 location.

**Geologic Name(s) of Injection Zone:** The proposed injection zone is the Cambrian-age Mt. Simon Sandstone. $CO_2$ injected through the well will be contained in the injection zone and will flow into the Mt. Simon at the injection interval. The injection interval is a portion of the Mt. Simon where the injection well is perforated, i.e., the Lower Mt. Simon A and Mt. Simon B.

**Depth Interval of Injection Zone Beneath Land Surface.**
Sensitive, Confidential, or Privileged Information

**Characteristics of the Injection Zone:** Sensitive, Confidential, or Privileged Information

EPA (2022) requested additional information regarding the clay content within the injection zone as it relates to pore filling and cementation and potential impact on injectivity at CCS#1 and CCS#2. Numerous studies have been done to understand the mineralogy of Mt. Simon Sandstone (Carroll et al., 2013; Freiburg et al., 2014; Yoksoulian et al., 2014; Davila et al., 2019; Shao et al., 2020). Sensitive, Confidential, or Privileged Information

Batch reactor experiments conducted with Mt. Simon Sandstone generally have indicated limited dissolution of rock minerals by $CO_2$ (Carroll et al., 2013; Yoksoulian et al., 2014; Shao et al., 2020). In addition, results from ISGS mineralogical analyses indicated the bulk mineral composition remained unchanged for all sandstone samples after reaction (1-4 months), indicating that the influence of rock-brine-$CO_2$ interaction on bulk rock composition was negligible.

These studies and analyses indicate very little likely impact on injectivity at CCS#1 or CCS#2 due to K-Feldspar or the dissolution of other minerals. Operational data indicate that injectivity may be more significantly related to other factors such as inclusion of compression oils in the injectate and condition of the formation resulting from well construction, perforation, and maintenance.

**Geologic Name(s) of Confining Zone:** The primary confining zone (seal) is the Cambrian-age Eau Claire Formation. Sensitive, Confidential, or Privileged Information [redacted]

**Depth Interval of Upper Confining Zone Beneath Land Surface**
Sensitive, Confidential, or Privileged Information [redacted]

**Characteristics of Confining Zone:** Sensitive, Confidential, or Privileged Information [redacted]

As indicated above, site injection zone and confining zone characteristics were verified and augmented by ADM's collection of log and core data at existing wells CCS#1, CCS#2, VW #1, and VW#2 that included individual permeability and porosity data. These data are presented on well logs included in Attachment A. Provided well logs also verify the regional and local thickness of the injection and confining zones.

Figure 3.3-1 is the ADM $CO_2$ Storage Site Cross Sectional Log. This log presentation is an amalgamation of the information developed during well construction; i.e., mud logs, open hole logs, and analysis of well cores. The petrophysical information presented in this log is consistent with and was used in the development of the Petrel static model used to characterize the $CO_2$ storage site.

Sensitive, Confidential, or Privileged Information



**Figure 3.3-1:** ADM $CO_2$ Storage Site Cross Sectional Log, Existing Wells

### 3.3.1 Variogram Analysis

The Mt. Simon extends laterally across the entire AoR. Porosity and permeability distributions were originally developed using a process described by Senel (et.al, 2013) that was updated in 2015; a summary of the original and updated modeling is presented in Attachment A. Modeling conducted to support the CCS#5, CCS#6, and CCS#7 permit application included geophysical logs and data from nearby ADM wells CCS#1, CCS#2, VW #1 and VW#2. The porosity logs acquired from these four wells used in modeling provided relatively high vertical resolution regarding effective porosity at each well and the formation characteristics allowed for correlation of layers between wells; however, without using other data, less was known about the porosity values of the rock present between the wells. To complete geological modeling, it was necessary to interpolate the data from the wells into the interwell space in a way that represented the geological setting. Variogram analysis was used to evaluate the geological setting, and it was also used to interpolate the effective porosity of the formations in the interwell space based on the measured log data. Variograms are often determined from well data; however, due to the limited number of well logs available at the site, this analysis could not be completed in a statistically valid way with only four well data set. Therefore, to complete the modeling, variogram analysis was completed based on the upscaled 2019 Porosity Cube (Figure 3.3-2) because it has a high horizontal sampling rate. The upscaling process used an averaging algorithm to define one porosity cube value for each model cell. This provided a way to calculate a series of zone-specific parameters, which included a variogram map, major azimuth, range, sill, nugget, and function types (Figures 3.3-2 and 3.3-3**Figure 3.3-**). The 2019 Porosity Cube was only processed for the Eau Claire Shale down to the upper section of the Precambrian. The quantified variogram parameters that were generated for each formation are explained below and are shown in **Error! Reference source not found.**:

**Table 3.3-1.** Variogram parameters extracted from the 2019 Porosity Cube and well logs

Sensitive, Confidential, or Privileged Information



- **Variogram map**: In variogram analysis, determining the direction of the variogram is one of the first decisions that must be made and was completed using variogram maps (Figure 3.3-3). Theoretically, the direction of maximum continuity (major direction) and direction of minimum continuity (minor direction) are found after the variograms are calculated in all possible directions (from 0 degree to 359°). The directions that show minimum and maximum range are selected as the variograms that represent the minor and major directions.
    - The major direction defines the direction where the sample points have the strongest correlation. The azimuth angle of this major direction can be changed interactively by editing the direction in the search cone. Azimuth angle is specified as the clockwise angle from the north (in degrees).
    - The minor search direction is perpendicular to the major direction.
- **Range**: The range describes where the variogram model reaches its plateau (i.e., the separation distance where there is no longer any change in the degree of correlation between pairs of data values). The range is specific in each direction for the model variogram. A large range means greater continuity and a small range means less continuity. The larger the range, the smaller the heterogeneity. Major and minor ranges were extracted from the highly horizontal sampled 2019 Porosity Cube, and the vertical range was taken from the well log analyses.
- **Sill:** The sill is the semi-variance where the separation distance is greater than the range (on the plateau). This describes the variation between two unrelated samples.
- **Nugget:** The nugget is the semi-variance where the separation distance is zero.
- **Variogram types**: Different methods (variogram types) exist. The types used in this project were:
    - Spherical: The curve is linear at shorter distances and then makes a sharp transition to a flat sill.
    - Exponential: The curve has an exponential behavior, with a rapid variation at shorter distances.
- **Mt. Simon Information**: The Mt. Simon properties were generated using the original variogram parameters from the 2020 simulation grid, which were interpreted using a porosity cube. The facies model used an isotropic distribution of 10,000 x 10,000ft. For the porosity and permeability models,

anisotropic variograms with a major direction of 127 degrees were used with major and minor ranges varying per zone. The major and minor ranges were as follows: for the Mt. Simon B – 2,669.664 x 1,937.288ft, Mt. Simon A Upper – 2,349.249 x 2,175.311ft, and the Mt. Simon Lower – 2,294.321 x 2,120.382ft.





**Figure 3.3-2**. Steps used to generate the mini grid for geostatistical extraction.

Sensitive, Confidential, or Privileged Information



**Figure 3.3-3**. Variogram maps extracted from the 2019 Porosity Cube.

### 3.3.2 Petrophysical Modeling of Effective Porosity and Permeability Interpolation

The effective porosity logs from the four wells used in modeling (i.e., CCS#1, CCS#2, VW#1, VW#2) provided high vertical resolution at each well; however, other than the fact that correlations could be made between the wells, little was known about the porosity values between the wells. Using the variogram analysis described in Section 3.3.1, the 2019 Porosity Cube was used to guide the petrophysical modeling of effective porosity to define lateral and vertical extent formation porosity. This method was used because seismic inversion properties (porosity and acoustic impedance, AI) can be correlated with the well log properties (porosity and AI); seismic inversion requires a relationship to be defined between the AI observed in the 3D seismic survey and the total porosity in the well logs. Once defined, this relationship is then used to transform the 3D seismic acoustic impedance (AI) volume into a porosity volume (2019 Porosity Cube). A reliable correlation between the porosity well log and the 2019 Porosity Cube was found.

Effective porosity and permeability were interpolated using the above-described geostatistics. Because of the presence of reservoir and non-reservoir facies types, the porosity and permeability were modeled separately within each zone and facies type. Cokriging was used to take advantage of the covariance between the effective porosity logs and the 2019 Porosity Cube. This method is appropriate because the primary data (effective porosity logs) has high vertical resolution but is not present between wells; the related secondary data (2019 Porosity Cube) lacks high vertical resolution but has abundant horizontal sampling between the wells. Using this relationship, in 2020, a more-reliable reservoir model was developed because it capitalizes on the strengths of both the high vertical resolution well log with the higher horizontal sampling seismic data. A plot of the upscaled porosity versus the porosity cube is shown to have a reasonable correlation coefficient of 0.81; therefore, the porosity cube can be used as a reliable cokriging variable (Figure 3.3-4. Using the geostatistics from each formation from the variogram analysis, permeability was cokriged using Gaussian random function simulation (GRFS) against the effective porosity property (Figure 3.3-4). Cokriging was used to take advantage of the known covariance between effective porosity and permeability.





**Figure 3.3-4.** Property model workflow.

As presented in Section 3.2, modeling was updated in 2023 to expand the model area and more accurately simulate the proposed CCS#5-7 area. In addition to providing more structural information pertinent to the CCS #5-7 area, as the lateral extent of the modeled area was increased, the facies and petrophysical properties were rerun using the original variogram parameters to propagate the entire model. The original values in the 9.7-mile x 9.3-mile area were preserved to honor the history matching work done previously. As a result, upscaled and calibrated porosity and permeability profiles were developed that extended through the CCS# 5-7 area, as shown in Figures 3.3-5, 3.3-6, 3.3-7, 3.3-8 and 3.3-9. Attachment A includes additional porosity and permeability profile cross sections. Synthetic logs were extracted from the geocellular model at the proposed CCS#5, CCS #6, and CCS #7 well locations (Figure 3.3-10). Increased porosity and permeability are predicted in the Mt. Simon A Upper and Lower formations.





**Figure 3.3-5.** Location of Injection and Verification Wells, CCS#5-7 Area and Cross Section locations.





**Figure 3.3-6**. Upscaled and calibrated porosity profiles along the cross-section A-A' and B-B'. Vertical exaggeration is 5x.




**Figure 3.3-7** Upscaled and calibrated Upscaled and calibrated permeability profiles along the cross-section A-A' and B-B'. Vertical exaggeration is 5x.




**Figure 3.3-8**. Upscaled and calibrated porosity profiles along the cross-section C-C' and A-A'. Vertical exaggeration is 5x.




**Figure 3.3-9.** Upscaled and calibrated permeability profiles along the cross-section B-B' and C-C'. Vertical exaggeration is 5x.




**Figure 3.3-10.** Synthetic facies, porosity, and permeability at the proposed CCS#5, CCS #6 and CCS #7 well locations extracted from the 3D model.

**References**

Carroll, S., McNab, W., Dai, Z. and Torres, S. (2013) Reactivity of Mt. Simon sandstone and the Eau Claire shale under $CO_2$ storage conditions. Environ. Sci. Technol. 47, 252-261.

Dávila, G., Dalton, L., Crandall, D.M., Garing, C., Werth, C.J. and Druhan, J.L. (2020) Reactive alteration of a Mt. Simon Sandstone due to $CO_2$-rich brine displacement. Geochimica et Cosmochimica Acta 271, 227-247.

Frommelt, D., 2010. Letter to the Illinois Environmental Protection Agency, Subject: CCS Well #1 Completion Report, Archer Daniels Midland Company – UIC Permit UIC-012-ADM, dated May 5, 2010.

Medina, C. R., & Rupp, A. J. (2012). Reservoir characterization and lithostratigraphic division of the Mount Simon Sandstone (Cambrian): Implications for estimations of geologic sequestration storage capacity. Environmental Geosciences, 1-15.

Shao, H., Freiburg, J.T., Berger, P.M., Taylor, A.H., Cohen, H.F. and Locke, R.A. (2020) Mobilization of trace metals from caprock and formation rocks at the Illinois Basin – Decatur Project demonstration site under geological carbon dioxide sequestration conditions. Chemical Geology 550, 119758.

Yoksoulian, L., Berger, P.M., Freiburg, J.T., and Butler, S.M, 2014. Geochemical investigations of $CO_2$ - Brine - rock interactions of the Knox Group in the Illinois Basin, U.S. Department of Energy, Topical Report DOE/FE0002068 - 10, 58p.

## 3.4 Hydrologic and hydrogeologic Information

As with the currently permitted CCS#1, CCS#2 and proposed CCS#3 and CCS#4 Class VI injection wells, the CCS#5, CCS#6 and CCS #7 Class VI well targets an injection zone in the Cambrian Mt. Simon Sandstone of the Illinois Basin (see coordinates above under Section 2.1). Core data, as well as geologic and hydrologic information from the injection and confining zones was collected during the drilling and testing of the nearby injection wells CCS#1 and CCS#2, as well as the two deep monitoring wells VW#1 and VW#2. Data from an ISGS database of core sample data and additional core sample analyses from sites within approximately 30–80 miles of the injection wells were also used. Specifically, information used to help guide the geologic model were obtained from core and geophysical logging data from a stratigraphic well in the Mt. Auburn area that was installed by Podolsky Soil Company, the McMillen, T.R. Well No. 1 (API number 120212565000). Wireline log results from CCS#2 and VW#2 and core analyses from VW#2 were compared to data collected from CCS#1 and the ISGS database. The results show good agreement with respect to porosity, permeability, lithology, thickness, and other geologic characteristics, validating the local site geology and hydrogeology. Regarding the formations of interest, Table 3.4-1 details thickness and formation top information collected during the construction of the sites four current deep wells.

Sensitive, Confidential, or Privileged Information

[redacted]

The following present elevation information for existing CCS, VW, and GM wells. Ground Elevation, Rig Kelly Bushing (RKB) height, and Kelly Bushing Elevation (KBE) for each well is presented. Note that depths are generally measured from the Rig Kelly Bushing Elevation.

Sensitive, Confidential, or Privileged Information

[redacted]

## Because the specific rig to be used for drilling and testing the CCS #5, #6 and #7 wells has not been identified yet, the exact RKB is still unknown [redacted]

The Mt. Simon Sandstone is the first formally recognized sedimentary unit overlying the Precambrian granitic basement rock. [redacted]

Directly overlying the Mt. Simon Sandstone is the Cambrian Eau Claire Formation. [redacted]. Two other regional shale units are identified as secondary and tertiary confining zones are the Ordovician Maquoketa Formation and the Devonian New Albany Shale, respectively. Although these units protect the locally used sources of underground drinking water, they lie above the designated lowermost USDW.

Only limited data and modeling results are available for characterizing ground water flow in the deep Illinois Basin. Based on modeling results from Gupta and Bair (1997), flow patterns in the Mt. Simon are “influenced by the geologic structure with flow away from arches such as the Kankakee Arch and toward the deeper parts of the Illinois Basin.” In the model, an initial fluid pressure of 3,205 psi (at elevation -6,345 ft MSL), an initial temperature of 112ºF (at elevation - 5,365 ft MSL; gradient 1ºF/ft), and an initial salinity of 200,000 ppm were used. MSL is defined as mean sea level. Like other areas with humid climates (Freeze and Cherry, 1979), the water table in central Illinois is expected to generally reflect the elevation of the land surface. Steady-state ground water flow modeling for the IBDP site indicates that shallow ground water flows toward the east and southeast toward the Sangamon River and Lake Decatur. Figure 3.4-1 is a map of the observed head in the Mt Simon and details the location of the proposed injection well.





**Figure 3.4-1**. Observed head in the Mt. Simon Sandstone. The red dot represents the location of the Decatur IL $CO_2$ storage site (potentiometric surface = 76 m/249 ft above mean sea level).

The lowermost USDW in the AoR is the Ordovician St. Peter Sandstone. Sensitive, Confidential, or Privileged Information Because of the formation depth and high TDS, the St. Peter is not currently exploited as a local source of drinking water.

### 3.4.1 Water quality data

Based on ISGS data from eight shallow compliance wells monitored from 2010 to 2022, TDS values in Quaternary strata have ranged from about 300 to 700 mg/L, and TDS values in Pennsylvanian strata have ranged from about 600 to 1,400 mg/L. See Figure 3.4-2 that presents the TDS values from the eight shallow compliance wells since monitoring began.

Further, other shallow (non-compliance) wells were monitored by the ISGS from 2008 to 2017. Data from those wells verify that TDS values from Quaternary strata were in the range of 200-2,000mg/L, and TDS values from Pennsylvanian strata were in the range of 700-4,000 mg/L.

Sensitive, Confidential, or Privileged Information




**Figure 3.4-2.** Total Dissolved Solids concentrations in shallow groundwater compliance wells from 2010 to 2022.

Sampling of the St. Peter Sandstone has occurred in GM2 from 2015 to 2022. Results from sampling are provided in the table below and show a range of TDS values in the St. Peter Sandstone of 4,200 to 5,200 mg/L.

**Table 3.4-2.** Total Dissolved Solids concentrations in ISGS St. Peter Sandstone samples from well GM2 (2015 to 2022).

Sensitive, Confidential, or Privileged Information

The Table 3.4-3 presents TDS concentration of fluid samples collected from the Mt. Simon for the CCS#1 well:

**Table 3.4-3.** Mt. Simon Total Dissolved Solids Data, CCS#1 (Frommelt, 2010 and ADM, 2010)

Sensitive, Confidential, or Privileged Information

**References**

Frommelt, D., 2010. Letter to the Illinois Environmental Protection Agency, Subject: CCS Well #1 Completion Report, Archer Daniels Midland Company – UIC Permit UIC-012-ADM, dated May 5, 2010.

Freiburg, J. T. (2014). A Depositional and Diagenetic Characterization of the Mt . Simon Sandstone at the Illinois

Basin - Decatur Project Carbon Capture and Storage Site. Decatur, Illinois, USA.

Gupta, N. & Bair, E.S. (1997). Variable-density flow in the mid-continent Basins and Arches region of the United States. *Water Resources Research,* v. 33, n. 8.

Freeze, R. A. and Cherry, J. A. (1979). Groundwater. *Prentice-Hall.*

## 3.5 Geochemical Data and Compatibility of $CO_2$

The Mt. Simon formation water is dominated by Na-Ca-Cl type chemistry and has total dissolved solids (TDS) concentration of approximately 195 g/L (Labotka et al, 2015). Geochemical modeling was used to predict the effects of the geochemical reactions of supercritical $CO_2$ with Mt. Simon Sandstone and the formation water (Berger et al., 2009). It was predicted that illite and glauconite would dissolve initially, followed by precipitation of kaolinite and smectite. The study concluded that the volume of pore space would not be significantly altered (Berger et al., 2009) and no compatibility problems, such as a major reduction in injection-formation permeability resulting from chemical precipitates, are expected.

Carroll et al. (2013) conducted a combined experimental and modeling study using Mt. Simon Sandstone and Eau Claire Shale samples under $CO_2$ storage conditions. The study showed that dissolution of illitic clays and K-feldspar, and precipitation of montmorillonite, amorphous silica, and kaolinite, are the major reaction paths initiated by addition of $CO_2$. Significant increase in Fe concentration was noticed after $CO_2$ is introduced, with iron-bearing clays interpreted to be the source of Fe release. The authors suggest that these reactions could alter reservoir and seal permeability by clogging pores and fracture networks. However, the effects of dissolution and precipitation on petrophysics are two sided. Dissolution of the iron clays could increase porosity and permeability locally and promote long-term mineral trapping of $CO_2$ as Fe carbonates, while precipitation of Fe-carbonates, clays and hydroxides could reduce reservoir and seal permeability by clogging pores and fracture networks.

Monitoring data indicate that $CO_2$ injected to date has been contained within the Mt. Simon Sandstone, especially the lower Mt. Simon Sandstone, and has not been in contact with the Eau Claire Formation. Therefore, dissolution of minerals within the Eau Claire Formation should not be occurring. Also, laboratory experiments have been conducted to understand the general behavior of Eau Claire Formation samples when exposed to $CO_2$ in a batch reactor (Carroll et al., 2013; Shao et al., 2020). While the Eau Claire samples did chemically interact with $CO_2$ in the laboratory experiments, those experiments are not accurate analogs for in situ conditions. For example, the Eau Claire Formation is a highly laminated, fissile shale to silty shale with the shaliest section directly overlying the Mt. Simon Sandstone. Roy et al (2014) noted that the advective flow from the Mt. Simon Sandstone, as well as ionic diffusion, into the Eau Claire is expected to be insignificant.

A recent flow-through experiment study (Dávila, et al., 2020) using a Mt. Simon core sample from the site coupled with reactive transport modeling also showed changes in flow properties induced by mineral reactions. Rock-water reactions similar to those identified by Carroll, et.al, are documented, including dissolution of K-feldspar, calcite, minor illite and pyrite combined with the precipitation of montmorillonite, mesolite, muscovite, and alunite. Particularly, calcite dissolution at the inlet of the core sample was clearly noted, leading to increased porosity at the inlet. However, overall permeability of the core sample decreased at the end of the flow experiment.

Attachment A includes a document entitled "CCS $CO_2$ Storage Behavior" containing plots and the raw data that show how the current $CO_2$ is captured subsurface. These plots show the mass of $CO_2$ that is mobile, immobile, and dissolved in water as a function of time. The attachment contains the following:

1) The injection simulation results for operating CCS#1, CCS#2, and CCS#3 that were used to submit the original permit. An error regarding how vertical flow was treated as occurring through the injection zone was identified in these simulation results that has been corrected in newer versions of the modeling predictions. These results are being provided nonetheless as they were the basis of the original application and because they continue to be valid illustrations of the mechanisms that capture the injected $CO_2$ in the subsurface.

2) The updated injection simulation results for operating CCS#1, CCS#2, CCS#3 CCS#4, CCS#5, CCS#6, and CCS#7, which include the more robust treatment of vertical movement within the injection zone, also show that injected $CO_2$ will be captured in the subsurface.

In summary, results show that the $CO_2$ mobile in the gas phase decreases over time, while the $CO_2$ trapped in a gas phase increases and the $CO_2$ dissolved in the water phase tends to slightly increase over time.

Overall, these site-specific studies as well as those by Shao et. al (2020) and Yoksoulian et. al. (2014) show similar geochemical reaction pathways to the previous studies from other sedimentary reservoirs and seals. The effects on rock properties, though somewhat varied at the core scale, do not show significant differences from previous studies. Therefore, because previous and current (2020) studies are in general agreement, it is not expected that injection of $CO_2$ into the proposed CCS#5, CCS#6 and CCS#7 wells would lead to drastic geochemical reactions within the reservoir and seal that compromise injectivity and long-term security.

**References:**

Berger, P.M., Mehnert, E., & Roy, W.R., 2009, Geochemical modeling of carbon sequestration in the Mt. Simon Sandstone. In *Abstracts with Programs - Geological Society of America, v. 4*1, pp. 4, Geological Society of America (GSA), Boulder, CO, United States (USA).

Carroll, S.A., McNab, W.W., Dai, Z., & Torres, S.C., 2013. Reactivity of Mount Simon Sandstone and the Eau Claire Shale Under $CO_2$ Storage Conditions. Environmental Science & Technology, v. 47, p. 252-261.

Dávila, G., Dalton, L., Crandall, D.M., & Garing, C., Werth, C.J., & Druhan, J.L., 2020, Reactive alteration of a Mt. Simon Sandstone due to $CO_2$-rich brine displacement. Geochimica et Cosmochimica Acta, v. 271, p. 227-247.

Labotka, D. M., Panno, S. V., Locke, R. A., & Freiburg, J. T. (2015). Isotopic and geochemical characterization of fossil brines of the Cambrian Mt. Simon Sandstone and Ironton-Galesville Formation from the Illinois Basin, USA. *Geochimica et Cosmochimica Acta*, v. *165*, p.342-360. https://doi.org/10.1016/j.gca.2015.06.013

Shao, H., Freiburg, J.T., Berger, P.M., Taylor, A.H., Cohen, H.F. and Locke, R.A. (2020) Mobilization of trace metals from caprock and formation rocks at the Illinois Basin – Decatur Project demonstration site under geological carbon dioxide sequestration conditions. Chemical Geology 550, 119758.

Yoksoulian, L., Berger, P.M., Freiburg, J.T., and Butler, S.M, 2014. Geochemical investigations of $CO_2$-Brine-rock interactions of the Knox Group in the Illinois Basin, U.S. Department of Energy, Topical Report DOE/FE0002068-10, 58p.

## 3.6 Geomechanical and Petrophysical Information

### 3.6.1 Formation Pressure

Mt. Simon fluid sampling and testing were conducted in August 2015 in the VW#2. These tests included in-situ measurements of formation pressure and temperature, and the collection of eight fluid samples at five depths. A temperature log was run in the CCS#2 in 2015. Sensitive, Confidential, or Privileged Information [redacted] In this permit application, the original formation pressure gradient for CCS#5, CCS#6 and CCS#7 was assumed to be the same based on the proposed completion of the well within the same injection zone. Note that no formation pressure data were collected at the existing CCS #1 and CCS #2 locations for the Eau Claire.

As conducted for previously drilled and tested CCS and VM wells, injection zone characteristics and confirmation of confining zone integrity via site-specific measurements will be obtained during drilling of injection well CCS#5, CCS#6 and CCS#7 (including capillary pressure; information on fractures, stress, ductility, rock strength, elastic properties; and in situ fluid pressures). The following tests/ measurements will be performed/collected for the CCS#5, CCS#6, and CCS#7 wells, within the limits of technical feasibility and recovered core quality: capillary pressure, fracture pressure information on fractures, stress, ductility, rock strength, elastic properties; and in situ fluid pressures. In addition, these data will be correlated with the existing well and core data from the project.

### 3.6.2 Rock Strength

A 1-dimensional (1D) mechanical earth model (MEM) has been created using log data, core data, pressure, and stress measurements to calibrate a model of the rock properties and stresses at the wellbore (Plumb, et al, 2000). Due to the abundance of data acquired for this project, the 1D MEM properties were well constrained. Data from Three wells, CCS#1, VM#1, VM#2, were evaluated using the 1D MEM workflow (Lee et al., 2014). [redacted]

### 3.6.3 In-Situ Stress

In-situ stress fields consist of three stress components: vertical, minimum horizontal, and maximum horizontal. The overburden/vertical stress is determined by integrating the density of the rock with depth. The horizontal stresses are estimated using the poro-elastic stress model which assumes that the rocks are a semi-infinite poro-elastic medium subjected to overburden and horizontal strain loadings (Higgins et al., 2008). The Mt. Simon and Eau Claire in-situ stress field results are summarized in Table 3.6-1. The stress regime is strike-slip ($\sigma_{Hmax} > \sigma_V > \sigma_{hmin}$) with localized normal faulting ($\sigma_V > \sigma_{Hmax} > \sigma_{hmin}$) for intervals with relatively low elastic moduli. This is consistent with earthquake source mechanisms in other parts of Illinois which indicates dominate strike slip stress regime (Lahann et al., 2017). The maximum horizontal stress direction is N68$^{o}$E based on the drilling induced fractures and breakout orientation. This direction is also consistent with the fast shear azimuth from the dipole shear log.

**Table 3.6-1.** In-situ stress from 1D MEMs – CCS#1, VM#1, VM#2 (Lee et al., 2014)

Sensitive, Confidential, or Privileged Information

### 3.6.4 Confining Zone Integrity

Caprock integrity was examined using the in-situ stress and rock mechanical properties from the 1D MEMs for CCS#1, VM#1, and VM#2. The formation was assumed to be intact since no faults within the confining zone were interpreted from 2D and 3D seismic data. Using the geomechanical properties as described above, stress state in the Eau Claire Shale is below the Coulomb failure line both at the initial state and after $CO_2$ injection (Figure 3.6-1). The stress path moves toward the shear failure line after $CO_2$ injection, but the magnitude of stress change is small and the caprock is still within the stable region with minimum risk of shear failure. A pore pressure increase of 650 psi was assumed in this analysis, which represents the highest pressure increase that will be possible directly below Eau Claire Shale from reservoir simulation. Poroelasticity was not accounted for in this analysis. Both assumptions make this analysis more conservative for shear failure evaluation. No tensile failure is expected in the caprock as well due to the high fracture gradient in Eau Claire Shale. A more detailed analysis on the caprock integrity can be performed if small-scale fractures or faults below the current seismic resolution are identified in the future.

Confining zone integrity with respect to occurrence of microseismic events was also examined. Analysis of the available seismic event catalog as well as re-processing using advanced processing techniques (such as double-difference techniques) provide evidence that few, if any events occurred at depths shallower than the lower Mt. Simon Formation (Dando et al., 2021). Refer to Fig 3.2-3 in section 3.2.2 for visual confirmation. These observations also provide evidence that the confining zone integrity remains intact.




**Figure 3.6-1.** Stress state in the Eau Claire Shale is below the Coulomb failure line both at the initial state (black dots) and after $CO_2$ injection (grey dots). p' – effective mean stress, q – deviatoric stress. Dark black line represents in failure line using rock strength properties from core analysis in Eau Claire Shale as described in previous section. Two light-colored lines represent failure lines using p10 and p90 rock strength values from log analysis. Poroelasticity was not accounted for, and thus this represents a more conservative evaluation.

### 3.6.5 Fracture/Fault Stability Analysis

Clusters of microseismic events were observed in pre-Cambrian, Argenta and lowest units of the Mt. Simon away from the wellbores during and after of the CCS#1 and CCS#2 injection periods. Based on the working assumption that microseismic events are caused by incremental failure along pre-existing critically stressed zones of weakness, a total of 12 zones of discontinuity were identified and modeled as fault planes (Lee et al., 2014). These pre-existing weakness zones exist near or at their critical stress rate, and a small variation in injection pressure can result in strain relief along these zones. The finite element model (FEM) combines previous model properties to determine rock strain change with associated change in pressure and generates synthetic microseismic events. These synthetic events compared well with the measured microseismic events for both location and occurrence (Figure 3.6-2). The use of seismic moment to estimate the length of seismogenic slip planes in the local subsurface suggests that faults large enough to produce felt seismicity are unlikely to be present at or near the Decatur site. (Williams-Stroud et.al., 2020).





**Figure 3.6-2.** Location of modelled microseismic events (yellow) and measured microseismic events (red). (Lee et al., 2014)

**References**

Dando, B.D.E, B. P. Goertz-Allmann, D. Kuhn, N. Langet, A. M. Dichiarante, V. Oye. 2021. Relocating microseismicity from downhole monitoring of the Decatur CCS site using a modified double-difference algorithm. Geophys J. Int., 227, 1094-1122.

Higgins, S.M., Goodwin, S. A,, Donald, A., Bratton, T.R., and George W.T., 2008, Anisotropic stress models improve completion design in the Baxter Shale, Paper SPE Annual Technical Conference and Exhibition, Denver, Colorado, USA, September 2008, doi: https://doi.org/10.2118/115736-MS

Lahann, R. W., Rupp, J. A., Medina, C. R., Carlson, G., and Johnson, K. M., 2017, State of stress in the Illinois Basin and constraints on inducing failure. Environmental Geosciences, 24(3), p. 123-150.

Lee, D. W., Mohamed, F., Will, R., Bauer, R., and Shelander, D., 2014, Integrating mechanical earth models, surface seismic, and microseismic field observations at the Illinois Basin-Decatur Project, Energy Procedia, 63, p. 3347-3356.

Plumb, R., Edwards, S., Pidcock, G., Lee, D., and Stacey, B., 2000, The mechanical earth model concept and its application to high-risk well construction projects, IADC/SPE Drilling Conference, New Orleans, Louisiana, February 23 – 25, 2000, doi: https://doi.org/10.2118/59128-MS

Williams-Stroud, S., Bauer, R., Leetaru, H., Oye, V., Stanek, F., Greenberg, S., and Langet, N. 2020, Analysis of microseismicity and reactivated fault size to assess the potential for felt events by $CO_2$ injection in the Illinois Basin. Bulletin of the Seismological Society of America, 110(5), p. 2188-2204.

## 3.7 Injection & confining zone mineralogy, petrology, and lithology

### 3.7.1 Mt Simon Sandstone

The Cambrian Mt. Simon Sandstone is a transgressive terrestrial to shallow marine sequence deposited in the proto-Illinois and Illinois basins, and the Michigan and Appalachian basins (Kolata and Nelson, 1990). Depositional environments in the Mt. Simon are highly variable; the numerous interpretations include shallow-marine, deltaic, fluvial, eolian, sabkha, and coastal (Driese et al., 1981; Hagadorn et al., 2002; Fischietto, 2009; Bowen et al., 2011; Freiburg et al., 2014). At the storage site, the Mt Simon Sandstone is over 457 m (1500 ft thick) and can be divided into an upper, middle, and lower unit. The formation consists of well sorted, fine- to coarse-grained sandstone, poorly sorted conglomerates, and minor siltstones and mudstones.

Stratigraphic and petrographic analysis of the whole cores and sidewall cores from three project wells, CCS#1, VW#1, and VW#2, provides detailed site-specific data (Leetaru & Freiburg, 2014; Freiburg et al., 2014). The Lower Mt. Simon contains four major facies originating in various depositional environments that include subaqueous coast, subaerial coast, lagoon, river, plain, and eolian plain (Leetaru & Freiburg, 2014; Freiburg et al., 2016). Major lithologies include fine- to coarse-grained sandstone and granule to pebble conglomerates that are interbedded with low- porosity and permeability, siltstones and mudstones.

The Middle Mt Simon exhibits two distinct lithofacies. The lower facies is composed dominantly of maroon to dark brown subarkose arenite and quartz arenite, interbedded with thin mudstones and wackes (sandstones with clay matrix). This facies also contains planar to cross-bedded coarse-grained poorly sorted sandstones and granule to pebble conglomerates with trace amounts of lithics and clay minerals. The upper facies consists dominantly of quartz arenite and lesser amounts of quartz wacke and occasional thin laminae of allogenic green clay. Hematite cements, in the form of Leisigang bands, are common in both the top and bottom facies (Leetaru & Freiburg, 2014).

The upper Mt Simon Sandstone comprises two interbedded lithofacies (Leetaru & Freiburg, 2014). The first facies is composed of mudstones and pink arkose wacke and subarkose arenites. Sandstones are commonly well cemented with clay and authigenic feldspar. The second facies is comprised of tan to white quartz arenites which are commonly mottled, homogenous, planar, or crossbedded. XRD data show the predominate mineral phase in the Mt Simon sandstone is quartz, generally over 70%, followed by minor amounts of potassium feldspar (up to 20%) and clay (up to 15%), and small to trace amounts of plagioclase, calcite, siderite, ankerite, dolomite, pyrite, barite, fluorapatite, and hematite. (Freiburg et al., 2014). The most common clays within the Mt. Simon are illite and mixed layered illite-smectite, with small fractions of chlorite and kaolinite (Freiburg et al., 2014). Clay occurs as grain coatings on both quartz and feldspar grains, as pore filling and cement, and as bedded detrital laminae. Iron oxides, primarily hematite and goethite, commonly occur as grain coats, Liesegang bands, residues in stylolites, and at unconformity surfaces within the Mt. Simon (Bowen et al., 2011; Freiburg et al., 2014). Authigenic clays appear most commonly near weathered feldspar grains and casts of dissolved feldspar grains, indicating that the feldspars may be one possible source of the authigenic clays (Bowen et al., 2011).

The highest reservoir quality occurs in the unconsolidated to partially consolidated, coarser grained quartz arenite and subarkosic sandstone in the Lower Mt. Simon, which exhibits preserved, excellent, primary porosity. Porosity is further enhanced by secondary porosity derived from feldspar dissolution. Some mineral grains are coated by thin layer of clay which prevents quartz overgrowths. Authigenic quartz is the most common cement in

the Mt. Simon and is the most significant factor of porosity reduction, along with consolidation (Freiburg et al., 2014).

### 3.7.2 Eau Claire Shale

The primary seal for the Mt Simon carbon sequestration reservoir is the overlying Eau Claire formation which is approximately 244 m (800 ft) thick at the storage site (CCS#5, CCS #6 and CCS#7). Within the Eau Claire Formation is deposited within a tidally influenced, shallow marine depositional environment with four major facies, including (Unit A) intertidal mixed sand/mud flats and tidal channels of the foreshore environment; (Unit B) subtidal deposits of the offshore transition zone; (Unit C) subtidal deposits of the upper shoreface environment; and (Unit D) subtidal mixed carbonate/siliciclastic deposits (Palkovic, 2015). At the proposed site, the lower part of the Eau Claire formation consists of gray to dark gray, highly laminated, fissile shale to silty shale with abundant siltstone beds. The upper part consists of very fine-grained dolomitic limestone interbedded with thin siltstone layers (Leetaru & Freiburg, 2014).

The mineralogy varies widely throughout the Eau Claire. Quartz, K-feldspar, and clays are the most common minerals and comprises the majority of the mineral makeup for most lithologies. Small amounts of plagioclase, calcite, siderite, ankerite, dolomite, and pyrite are commonly present (Palkovic, 2015). The predominant clay minerals are mixed layered illite/smectitie, illite, with small amounts of kaolinite and chlorite. Glauconite is also detected (Leetaru & Freiburg, 2014; Palkovic, 2015).

The mineral phases in the reservoir and seal are all common minerals found in sedimentary rocks. Their reactivity with $CO_2$-rich formation water has been extensively examined by rock-water- $CO_2$ reaction experiments and geochemical simulation. Additionally, a number of field projects of large-scale $CO_2$ injection into sedimentary rock formations with similar mineral compositions have been conducted during the last decades. Due to the relatively low mineral reaction kinetics, no drastic rock-water- $CO_2$ interactions which could pose threats to the viability of the injection projects have been documented. Therefore, we do not expect compatibility issues with the mineral composition at the proposed injection site.

**References:**

Bowen, B.B., Ochoa, R.I., Wilkens, N.D., Brophy, J., Lovell, T.R., Fischietto, N., Medina, C.R., & Rupp, J.A., 2011, Depositional and diagenetic variability within the Cambrian Mount Simon Sandstone: Implications for carbon dioxide sequestration. Environmental Geosciences, v. 18, p. 69–89.

Driese, S. G., Byers, C. W., and Dott, R. H., Jr., 1981, Tidal deposition in the basal upper Cambrian Mt. Simon Formation in Wisconsin: Journal of Sedimentary Petrology, v. 51, no. 2, p. 367–381.

Fischietto, N.E.1, Bowen, B.B.1, and Rupp, J.A., Facies analysis and Reservoir Characterization of the Cambrian Mount Simon Formation in the Illinois Basin: Implications for $CO_2$ Sequestration and Storage Earth and Atmospheric Sciences, Purdue University, 550 Stadium Mall Drive, West Lafayette, IN, 47907

Freiburg, J.T., D.G. Morse, H.E. Leetaru, R.P. Hoss, and Q. Yan, 2014, A depositional and diagenetic characterization of the Mt. Simon Sandstone at the Illinois Basin - Decatur Project carbon capture and storage site, Decatur, Illinois, USA: Illinois State Geological Survey, Circular 583, 59 p. and 3 digital appendices.

Freiburg, J.T., Ritzi, R.W., & Kehoe, K.S., 2016. Depositional and diagenetic controls on anomalously high porosity within a deeply buried $CO_2$ storage reservoir–The Cambrian Mt. Simon Sandstone, Illinois Basin, USA. International Journal Greenhouse Gas Control 55, 42−54.

Leetaru, H.E., & Freiburg, J.T., 2014, Litho-facies and reservoir characterization of the Mt Simon Sandstone at the Illinois Basin – Decatur Project. GHG Greenhouse gases Science and Technology, Greenhouse Gas Science & Technology, v. p. 580–595.

Palkovic, M. J., 2015, Depositional characterization of the Eau Claire Formation at the Illinois Basin – Decatur Project: facies, mineralogy and geochemistry. Thesis for degree of Master of Science in Geology, University of Illinois at Urbana-Champaign, 2015.

## 3.8 Seismic history, seismic sources, and seismic risk

While injection at CCS#1 from 2012-2014 was associated with clear induced microseismic activity (Section 3.2.2), injection at CCS#2 has not resulted in any increase in activity despite no significant change in the scale and quality of active receiver networks used (Dando, et.al., 2021). Monitoring began 18 months prior to injection at CCS#2 to record background microseismicity, during this period only 8 local events were detected that were not associated with anthropogenic activity. These eight events ranged in magnitude from -2.16 to -1.52 (Bauer, et.al., 2016).

Injection at CCS#1 began in 2011 and 4,747 microseismic events occurred between 2011 and the end of 2014 (Bauer, et.al, 2016). Induced microseismicity at CCS#1 started two months after injection began, and by 6 months post injection the activity decreased from around 50-200 events per month to around 20 per month – see Figure 3.8-1(a). Ninety-four percent of the events prior to 2016 were less than magnitude 0, and only two events were above magnitude 1 at 1.07 and 1.17 prior to 2016 (Bauer, et.al., 2016). Approximately half of the microseismic events were in the Precambrian basement with the rest in the Mt. Simon and Argenta. Events were grouped into four clusters that tended to follow a northeasterly trend or nearly the direction of $S_{HMax}$. Microseismic events were not considered large enough to endanger caprock integrity (Bauer, et.al., 2016).

Injection began at CCS#2 in April 2017, and through November 2019 there were only 220 microseismic events located during the injection period, even though $CO_2$ was being injected at 1.7 times the CCS#1 injection rate (Stanek, et.al., 2020) (Figure 3.8-1. The reduction in event rate is credited with a shallower injection interval depth, further from the crystalline Precambrian basement and the deepest Mt. Simon that accommodated a significant portion of microseismic events during CCS#1 injection. Induced microseismicity was not considered significant for CCS#2 because many of the injection events were in the same cluster locations as for CCS#1, and the rate of events detected did not change from the period between CCS#1 and CCS#2 injection, and after injection began at CCS#2.

Sensitive, Confidential, or Privileged Information



**Figure 3.8-1** - Event count timeline (a) and magnitude histogram (b) of all events (Stanek, et.al., 2020; Dando, et.al., 2021). From the timeline, the events (mainly occurring in the Precambrian basement) dropped off significantly after injection ceased at CCS#1. The number of events did not noticeably increase with the commencement of injection at CCS#2.

Figure 3.8-2 shows the microseismic events recorded at the IDBP site through June 2018. The events tend to lie in well-defined clusters, and the moment magnitudes for these events are all below the threshold where an event can be felt at the surface. The cross section shown in Figure 3.8-3 shows all recorded events and well locations along a direction perpendicular to $S_{HMax.}$ The events fall almost exclusively in the Precambrian basement, with some events also occurring in the lower Mt. Simon and Argenta formations.

Sensitive, Confidential, or Privileged Information




**Figure 3.8-2.** Locations of 5037 microseismic events recorded during injection period of CCS#1 and CCS#2 (December 2011 – June 2018). The events are colored by Moment Magnitude. The blue line represents the position of the cross section in Figure 3.8-3.

Sensitive, Confidential, or Privileged Information




**Figure 3.8-3.** Cross section with all wells and microseismic events projected to the plane (shown in blue in Figure 3.8-2). Note most of the events are in the Precambrian basement.

Historically, ADM mitigated known risks by applying the information obtained from the previous wells to the subsequent well design and operations. With respect to microseismic events within the basement rock, ADM increased the standoff between the basement and the injection zone for CCS#2, which greatly decreased the number of recorded microseismic events. That information has been leveraged in the design of the CCS#5, CCS#6 and CCS#7wells, and via the recompletion of CCS#1 to mitigate microseismic risk by duplicating the CCS#2 standoff between the basement and the proposed injection zone for CCS#3, CCS#4, CCS#5, CCS#6 and CCS#7.

In addition, ADM will maintain a robust monitoring program (Section 9.4.3), as provided in the AoR and Corrective Action Plan (Section 4.4.), and the Emergency and Remedial Response Plan. Table F-2a in the ERRP outlines the actions to be implemented in each seismic risk case wherein the response actions for progressively serious operating states (i.e., green, yellow, orange, and magenta) as will be implemented based on seismic threshold conditions.

As indicated in Section 3.6.3, the local stress regime is assumed to be strike-slip with regard to in-situ stress analyses. Although the stress regime in the area is strike-slip, and this is the mechanism for earthquakes observed in other parts of Illinois, Section 3.6.4 outlines that there are no observable faults that penetrate to the Eau Claire. In addition, geomechanical testing shows that the rock in the Eau Claire is below Coulomb failure both initially and after injection. With respect to the injection zone, per Lee, et al. (2014), microseismic events associated with the CCS#1 well were clustered in areas showing higher curvature at the Precambrian Basement, with some in the Argenta and the lowest Mt. Simon. These areas were not noted to be associated with any

observable faults, and this was confirmed by the low correlation between the possible interpreted faults from the reprocessed seismic seen and noted in Figure 3.2-2. In addition, work by Williams-Stroud et al. (2020) indicates that the use of seismic moment to estimate the length of seismogenic slip planes in the local subsurface suggests that faults large enough to produce felt seismicity are unlikely to be present at or near the Decatur site. (Williams-Stroud et al., 2020). Considered together, this evidence indicates that strike-slip conditions within the county will not have adverse effects on the confining and injection zones.

### 3.8.1 Injection Pressure and Microseismicity

Data also indicate that the additional injection pressures from CCS#5, CCS#6 and CCS#7 will not increase microseismicity in basement rock. Based on observed historic microseismicity within the basement rocks associated with the CCS#1 and CCS#2 injection wells, the largest magnitude events within the Precambrian strata have been limited to below Mw 1.0. Based on microseismic event distributions, various zones of discontinuity were identified at the site [Section 3.6.5]. Slip plane dimensions (as calculated from observed seismic moments from existing catalog) suggest that faults large enough to produce felt seismicity are unlikely at this site (Williams-Stroud et.al., 2020).

Empirical data from the VW1 monitored zone below CCS2 injection interval shows that the pressure increased is less than 40 psi after 4 years of CCS2 injection. Injection modeling studies indicate that the pressure perturbation within the basement at the end of injection period based on the proposed injection plan will stay at or below 600-700 psi (see Figure 3.8-4).





**Figure 3.8-4.** Example Pressure Perturbation across CCS#5-CCS#7 injection zone at year 2038 (end of injection) 95 MT

In addition, lab studies and failure analysis using Precambrian samples from IBDP project have shown that the basement rock is highly stable and the necessary change in pore pressure needed to cause failure of basement rock is more than 2400 psi (17 MPa) (see Figure 3.8-5). From injection modeling studies, the maximum pressure change within the basement at the end of injection are estimated to be at or below 600-700 psi (4.8 MPa). This suggests that even with the maximum pressure perturbation estimated during the life of these new wells, we expect to stay below the Mohr-Coulomb failure envelop. Therefore, modeling, theoretical, experimental, and empirical data support the conclusion that higher magnitude microseismicity is unlikely to increase due to CCS#5, CCS #6, or CCS #7 injection.

Sensitive, Confidential, or Privileged Information




**Figure 3.8-5.** Mohr-Coulomb failure envelope constructed for the basement rock assuming zero cohesion on preexisting weak planes. Orange envelop shows the initial state prior to any injection. [Makhnenko et al. 2020].

As discussed in Section 3.1, CCS#1 will be recompleted using the Mt Simon B/A-Upper as the injection interval. Figure 3.8-6 shows the petrophysical properties for the 4 completed deep wells at the Decatur $CO_2$ storage site. The figure details the low porosity and permeability layers and provides interpretation of low vertical permeability baffle facies. Examination of the Mt Simon A-lower indicates the presence of four (4) low permeability baffles within this zone. These facies appear in all four wells and are considered to be spatially extensive within the AoR. These baffles facies will prevent the injection pressure from being transmitted to the Precambrian basement. During construction of the proposed injection wells, interpretation of the logs and testing of the core samples will guide the well's final completion.

Based on this information, increased risk of microseismicity is not expected due to injection activities at CCS #5, CCS#6 or CCS #7.

Sensitive, Confidential, or Privileged Information



**Figure 3.8-6.** Petrophysics, completions, and baffle facies interpretation on low-porosity and low-permeability layers.

**References**

Bauer, R., Carney, M., and Finley, R.,. "Overview of microseismic response to $CO_2$ injection into the Mt.Simon saline reservoir at the Illinois Basin-Decatur Project." *International Journal of Greenhouse Gas Control* (2016): 378-388.

Dando, B.D.E., et al. "Relocating microseismicity from downhole monitoring of the Decatur CCS site using a modified double-difference algorithm." *Geophysical Journal International* (2021): 1094-1122.
Lee, D. W., Mohamed, F., Will, R., Bauer, R., and Shelander, D., 2014, Integrating mechanical earth models, surface seismic, and microseismic field observations at the Illinois Basin-Decatur Project, Energy Procedia, 63, p. 3347-3356.

Makhnenko, R. Y., Bondarenko, N. B., Kim, K., Whittaker, S. 2020. Laboratory Modeling of Induced Microseismicity in the Illinois Basin. Paper presented at the 54th U.S. Rock Mechanics/ Geomechanics Symposium (ARMA-2020-2040).

Stanek, Frantisek, Sherilyn Williams-Stroud and Robert Bauer. "Importance of monitoring seismicity induced by $CO_2$ sequestration at Illinois Basin – Decatur." *SEG International Exposition and 90th Annual Meeting*. Society of Exploration Geophysicists, 2020. 2226-2230.

## 3.9 Air and Soil Gas Monitoring

At the Decatur CCS site, $CO_2$ air monitoring is conducted at any well that penetrates the Eu Claire seal formation. Currently CCS#1, CCS#2, VW#1, and VW#2, have $CO_2$ air monitoring at the well site. $CO_2$ air monitoring will be conducted at proposed CCS#3, CCS#4, CCS#5, CCS#6, CCS#7 and proposed VW#3, VW#4 and VW #5. Because there are no other wells within the AoR that penetrate the injection zone seal formation, no additional air monitoring is planned.

Soil gas and flux monitoring networks were initiated for the Decatur CCS project site in 2009 for the IBDP Project (CCS#1) and 2012 for the IL-ICCS Project (CCS#2). The soil flux monitoring network consisted of approximately 70 soil flux collars installed within the project area and were co-located with approximately 50 soil gas nests. Monitoring of these networks continued through 2015 collecting about six years of background and operational data (during CCS#1 injection period 2011-2014).

Soil $CO_2$ flux was measured on a monthly basis. Soil gas was sampled on a quarterly basis and analyzed using gas chromatography for $CO_2$, N2, O2 and light hydrocarbons (C1 to C6). In addition, selected samples were be analyzed for isotope composition δ13C, δ18O and radiocarbon (Δ14C) of $CO_2$ to help determine the source of $CO_2$ in the soil. In addition, background concentrations were measured to determine statistical variations of $CO_2$ with respect to sample temperature, seasonal variations, diurnal variations and other factors. Soil gas samples were initially collected on a monthly basis and were reduced to quarterly after sufficient baseline information was collected to characterize the seasonal variability in gas composition and isotopic signatures. All analytical results have been archived and are available to the USEPA upon request.

Because sufficient baseline and operational data has been generated for the Decatur CCS Site and no statistical changes were observed during the injection period for CCS#1 and the pre-injection period for CCS#2, no further soil gas or flux monitoring is planned at this time.

## 3.10 Facies changes in the injection or confining zone

Reservoir simulation modeling brought forward challenges between observed and simulated data. When the reservoir simulations began in 2008, there were challenges with history matching between the observed data and the simulation results. The history matching helped refine the geomodel by using the discrepancies between the observed and the simulated $CO_2$ migration to highlight regions of the geomodel that required modification. These model modifications were changes to structure and property distribution (porosity and permeability) that were not clear or had been uncertain earlier.

In the 2018 model update, adding baffle facies layers became necessary for history matching. These baffle facies layers are areas of relatively lower porosity and relatively lower permeability barriers identified on well logs, which were interpreted litho-facies or facies changes within the Mt. Simon Formation. When the reservoir simulations were run, the baffle layers were used as discontinuous barriers to $CO_2$ and pressure migration. From this log interpretation, the baffles were not always continuous between wells (dark green baffles with yellow reservoir on track 6 of Figure 3.10-1). Some baffles could be correlated from well to well and some could not. The justification for adding these baffle facies into the model was as follows:

- The first recognized influence of layered baffles was the pressure reactions at VW#1 during the CCS#1 injection, with the highest formation pressure increases of about 5.1% in the lowest three gauges, highs of only about 1.7% increase in gauge 4, and less formation pressure increases in upper gauges. Also, $CO_2$ was detected in VW#1 at Zone 3 and lower, but not at Zone 4 and higher.

- When CCS#2 injection began in the lowest perforation, a higher-pressure response occurred at the CCS#1 injection interval than was modeled. This indicates there may be a preferential pathway from CCS#2 to CCS#1; however, a similar high-pressure response at VW#1 compared to the previous modeled response did not occur, suggesting a different degree of connection between CCS#2 to CCS#1 and CCS#2 to VW#1. A directional preferential pathway was seen by CCS#2, as the pressure response first arrived at VW#1 far before VW#2, the later of which is closer to CCS#2.
- The pressure response at VW#2 (Zone 2) indicated that reservoir interval including VW#2 (Zone 2) and CCS#2 might be locally confined by the low-permeability baffles.
- Although the Mt. Simon A-Lower was believed to be undifferentiated, repeat pulsed neutron logs at VW#1 show that high-permeability sand packages and interlayered low-porosity and low-permeability layers (baffles) strongly control vertical $CO_2$ plume geometry at distance from the injector.
- These observed preferential pathways/flow barriers suggested that strong heterogeneity (porosity and permeability) exists in the reservoir. Adding the baffle facies allowed for better history matching results in all the simulation scenarios.






**Figure 3.10-1.** Petrophysics, completions, and baffle facies interpretation on low-porosity and low-permeability layers.

## 3.11 Injection zone storage capacity

For the injection scenarios lateral extent of plumes are mapped and area of plume calculated at year 2038 (end of injection) and fifty year after injection stops in year 2088. Figure 3.11-1 show the plume for each case superimposed on satellite image.




Yr. 2038 Yr. 2088

**Figure 3.11-1.** 95Mt injection. Image on the left represents the plume extent at the end of injection in year 2038. Image on the right represents the plume extent in year 2088. The CCS#5-CCS#7 plume covers an area of 5,519 acres and 6,874 acres, respectively.

Sensitive, Confidential, or Privileged Information

[redacted]

The current simulation presented in Figure 3.11-1 accounts for pressure front interactions at all seven injection wells. The modeled $CO_2$ plumes and resulting pressure front considers the total formation storage capacity, and accounts for the total $CO_2$ injection volume from CCS#1, CCS#2, CCS#3, CCS#4, CCS#5, CCS#6 and CCS#7.




**Figure 3.11-3.** Reproduced layers of the geologic model and average porosity/permeability values, as identified by ADM based on log analysis, along with the approximate screened intervals of CCS #1 and CCS #2.

## 3.12 Confining zone integrity

The median porosity of the Eau Claire Formation is 4.7%, based on information from an ISGS database of UIC well core samples. Pre-injection testing in CCS#2 and VW#2 indicated very small pore sizes based on CMR data, resulting in generally very low permeability. During pre-operational testing, ADM collected 33 horizontal and 3 vertical whole core samples, and 2 rotary sidewall core samples, all from VW#2. Three hundred fifty-one (351) core plugs were drilled from the whole core collected from VW#2 and were suitable for routine core property measurements. The rock properties derived from these samples were primarily used to validate and calibrate the ELAN petrophysical model based on well logs. While no core samples were taken from the shale zone of the Eau Claire A at VW#2, 36 plugs of the upper interval Eau Claire C (very fine sandstone, microcrystalline limestone, and siltstone) were available for testing. Sensitive, Confidential, or Privileged Information

ADM also cited a median permeability value of 0.000026 mD from the ISGS UIC core database. In addition, based on a set of core samples from a site approximately 80 miles to the north of the proposed Class VI location, of the 110 analyses conducted, most were in the range of < 0.001 to 0.001 mD, with five in the range of 0.100 to 0.871 mD (the maximum value in the data set). This indicates that even the more permeable beds in the Eau Claire Formation are expected to be relatively tight and tend to act as sealing lithologies.

A “mini-frac” field test was used to determine in-situ fracture pressure in the confining zone. Sensitive, Confidential, or Privileged Information As maximum injection pressure is limited at 90% of the fracture pressure gradient at Mt Simon formation, Eau Claire will not be exposed to pressures which could create induced fractures.

As presented in previous sections, microseismicity events have occurred, primarily in association with CCS#1 injection. However, analysis of the available catalog as well as re-processing using advanced processing techniques (such as double-difference techniques) provide evidence that few, if any events occurred at depths shallower than the lower Mt. Simon Formation (Dando et al., 2021). Refer to Figure 3.2-5 in section 3.2.2 for additional information. These observations also provide evidence that the confining zone integrity remains intact although microseismic events occurred.

Additionally, modeling results with respect to cumulative pressure and potential occurrence of seismic events indicate that injection into CCS#5, CCS#6, and CCS#7 will not impact the confining capabilities of the Eau Claire. Modeling results have shown limited plume height growth within the Mt. Simon Formation indicating no breach within the Primary seal (Eau Claire) as shown in Figures 3.12-1, 3.12-2 and 3.12-3, below.





**Figure 3.12-1.** $CO_2$ Pressure Jan 2038 (end of Injection) along CCS#5-CCS#7 cross section (95Mt).





**Figure 3.12-2.** $CO_2$ saturation along CCS#5-CCS#6 cross section (95Mt injection case). See section 4.





**Figure 3.12-3.** $CO_2$ saturation along CCS#5-CCS#7 cross section (95Mt injection case).

Moreover, as discussed in Section 4.1 (simulation results), the modeling study conducted used the maximum injection rate as the primary constraint to define projections. The maximum rate was reduced if necessary by a secondary constraint such that the maximum allowable injection pressure (90% of the fracturing pressure of the Mt. Simon) was not exceeded. The Mt. Simon injection zone is as per the identified fracture gradients (0.715 psi/ft) from step rate tests at CCS#1. The fracture pressure from these four CCS#1 tests ranged from 5,078 to 5,324 psig, corresponding to a fracture gradient ranging from 0.93 to 0.98 psi/ft in the Eau Claire shale. This provides basis for the expectation of seal containment for the new CCS#5, CCS#6, and CCS#7 wells. Refer to operational plan limits (Section 8).

In addition, the absence of evidence of interpreted faults from the 2D and 3D seismic data as outlined in section 3.6.4., indicates that the Eau Claire Formation is regionally intact as a seal. The stress state for the Eau Claire

resides below coulomb failure, both pre-and post-injection, and the risk of breaching the failure envelope is minimal based on limiting the injection pressures to 90% of the fracturing pressure of the Mt. Simon.

Finally, Table F-2a in the Emergency and Remedial Response Plan, which outlines the risks and mitigations associated with seismic activity, along with the monitoring program (Section 8), will inform future operational conditions. Accordingly, the available evidence shows that bringing a third and fourth injection well online will not contribute to cumulative pressure or seismic events that have the potential to impact the confining zone

**References**

Dando, B.D.E., et al. "Relocating microseismicity from downhole monitoring of the Decatur CCS site using a modified double-difference algorithm." *Geophysical Journal International* (2021): 1094-1122.

# 4. Area of Review (AoR) Delineation and Corrective Action Plan

## 4.1 Conceptual site model

The Midwest Geological Sequestration Consortium's (MGSC) Illinois Basin-Decatur Project (IBDP) started injecting $CO_2$ through CCS#1 injector well in lower sections of Mt. Simon sandstone formation in November 2011. In November 2014, IBDP reached its goal of injecting one million metric tons of $CO_2$. The Illinois Industrial Carbon Capture and Storage (ICCS), led by ADM, expanded the site's $CO_2$ injection and storage capability with the objective to inject up to one million metric tons per year through CCS#2 injector well.

During the course of both projects, in addition to the data acquired during drilling and completion, an extensive data set was also established through various monitoring activities. The data obtained includes but is not exclusive of injection wells bottomhole pressures (BHP), multi-zone pressure data from in-zone verification wells VW#1 and VW#2, spinner data to quantify flow-splits, i.e., injection profile logs and reservoir saturation tools (RST) from both injectors. These datasets allowed calibration of various reservoir parameters including intrinsic permeabilities, relative permeabilities, wellbore skin values, vertical to horizontal permeability ratios, and rock compressibility. These calibrations allow the model to be updated periodically to improve the accuracy between the model predictions versus the actual result.

The previous studies compiled by Zaluski & Lee (2018, 2020) described the steps taken to create the history matched (calibrated) model of $CO_2$ injection into the wells at the site. The calibrated model includes the injection data acquired until June 2021. The dynamic model includes the entire Mt. Simon and the overlying seal (the Eau Claire), spanning a 38 × 47 mile area. The final reservoir model was represented by a 348 × 532 × 110 grid in a Cartesian system with 348 grid points in the x-direction, 532 grid points in the y- direction, and 110 grid points in the z-direction, for a total of 20,364,960 grid points.

**Description of Software**

ECLIPSE 300 is a compositional finite-difference solver that is commonly used to simulate hydrocarbon production and has various other applications including carbon capture and storage modeling. The $CO_2$ STORE module of the simulator can be used to account for the thermodynamic interactions between three phases: an H2O-rich phase (i.e., 'liquid'), a $CO_2$-rich phase (i.e., 'gas'), and a solid phase, which is limited to several common salt compounds (e.g., NaCl, CaCl2, and CaCO3). Mutual solubilities and physical properties (e.g., density, viscosity, enthalpy, etc.) of the H2O and $CO_2$ phases are calculated to match experimental results through a range of typical storage reservoir conditions, including temperature ranges between 12°C-100°C and pressures up to 60 MPa. Details of this method can be found in Spycher & Pruess (2005). Additional assumptions governing the phase interactions throughout the simulations are as follows:

- The salt components may exist in both the liquid and solid phases.
- The $CO_2$-rich phase (i.e., 'gas') density is obtained by using the Redlich-Kwong equation of state. The model was accurately tuned and modified as further described below (Redlich and Kwong, 1949).
- The brine density is first approximated as pure water then corrected for salt and $CO_2$ concentration by using Ezrokhi's method (Zaytsev & Aseyev, 1992).
- The $CO_2$ gas viscosity is calculated per the methods described by Vesovic et al. (1990) and Fenghour et al. (1998).

The gas density was obtained using a modified Redlich-Kwong equation of state following a method developed by Spycher and Pruess (2005, 2009), where the attraction parameter is made temperature dependent.

The transition between liquid $CO_2$ and gaseous $CO_2$ can lead to rapid density changes of the gas phase; the simulator uses a narrow transition interval between the liquid and gaseous density to represent the two-phase $CO_2$ region. The effects of $CO_2$ solubility in water are captured in the simulator. The simulator follows the Spycher and Pruess procedure for fugacity equilibration between water and free $CO_2$. Water fugacity is obtained by Henry's law and $CO_2$ fugacity is calculated using a modified Redlich-Kwong equation of state.

Because the compression facility controls the $CO_2$ delivery temperature to the injection well to remain between 80°F and 120°F, the temperature of the injectate will be comparable to the reservoir formation temperature within the injection interval. Therefore, the simulations were carried out based on isothermal operating conditions. With respect to time step selection, the software algorithm optimizes the time step duration based on specific convergence criteria designed to minimize numerical artifacts. For these simulations, time step size ranged from 8.64x101 to 8.64x105 seconds or 0.001 to 10 days. In all cases, the maximum solution change over a time step is monitored and compared with the specified target. Convergence is achieved once the model reaches the maximum tolerance where small changes of temperature and pressure calculation results occur on successive iterations. New time steps are chosen so that the predicted solution change is less than a specified target.




**Figure 4.1-1.** CCS #5-#7 injector and verification well locations.

The injection intervals for each well can be seen in Figure 4.1-2. All the new proposed injection intervals in CCS #5-7 remain deeper than the CCS #2 injection interval. In addition, the base of the USDW in the vicinity of the CCS # 5-7 wells is shallower than exists at the CCS #2 location. Therefore, the critical-pressure threshold of 62.2 psi which was used for CCS #2 permitting is still valid for AoR identification and will be further explained in Section 4.2.

Sensitive, Confidential, or Privileged Information




**Figure 4.1-2.** Proposed injection intervals for CCS #5-7.

**Simulation Results**

In the simulation, the primary constraint on maximum injection rate is defined by the lower of either the assigned rate or reduced such that the maximum allowable injection pressure controls flow rate. A step rate test at CCS#1, in the interval of -7,025 ft KB to -7,050 ft KB was conducted to estimate the fracture pressure of the injection zone. The result from the uppermost perforation of CCS#1 (-7,025 ft KB) was that a pressure sensitive threshold is reached at approximately 5,024 psig, corresponding to a fracture gradient of 0.715 psi/ft. A value of 90% of this fracturing pressure was calculated at the top of the shallowest perforated interval and used in the simulations as the maximum allowable injection pressure. The final constraint to the injection scenarios is applied at the field level. Each scenario has a target field injection rate over the injection period. For second and third cases the target field injection rate is smaller than the sum of the maximum allowed injection rate defined at well level. This configuration allows wells to compensate for each other within the allowable rate and pressure constraints.

As can be seen in Figure 4.1-3, CCS #5-7 are all able to maintain the base-case target injection rate without reaching maximum allowable injection pressure. Over the projected operational life of the project, approximately 13.2 million tons will be injected into each of the three wells. The total cumulative volumes may vary for each well depending upon injection start dates.





**Figure 4.1-3.** CCS #5-7 bottomhole pressure and injection rates vs time for 40-million-ton injection scenario.

## References

Zaluski & Lee. (2018). IBDP/ICCS Static Geological Model Development and Dynamic Modelling Updates, Schlumberger

Zaluski & Lee. (2020). IBDP Final Static Geological Model Development and Dynamic Modelling, Schlumberger

Spycher, N. and Pruess, K. (2005). "$CO_2$-H2O mixtures in the geological sequestration of $CO_2$.II. Partitioning in chloride brines at 12-100 C and up to 600 bar," Geochimica et Cosmochimica Act, 69, No. 13, 3309-3320

Spycher, N. and Pruess, K. (2009). "A Phase-Partitioning Model for $CO_2$-Brine Mixtures at Elevated Temperatures and Pressures: Application to $CO_2$-Enhanced Geothermal Systems," Transport Porous Media, 82, No. 1, 173-196.

Zaytsev, I.D. and Aseyev, G.G. (1992). Properties of Aqueous Solutions of Electrolytes. Boca Raton, Florida, USA CRC Press.

Vesovic, V., Wakeham, W. A., Olchowy, G.A., Sengers, J.V., Watson, J.T.R. and Millat, J. (1990). "The Transport Properties of Carbon Dioxide," Journal of Physical and Chemical Reference Data. 19, No.3, 763.

Fenghour, A., Wakeham, W.A., and Vesovic, V. (1998). "The Viscosity of Carbon Dioxide," Journal of Physical and Chemical Reference Data. 27, No.1, 31-44.

## 4.2 Computational AoR delineation model

### 4.2.1 Pressure Delineation Model

To delineate the pressure front, the minimum or critical pressure (Pi,f) necessary to potentially cause flow to be possible from the injection zone into the lowermost USDW must be calculated.

Based on the Method 1 provided in the May 2013 UIC Program Class VI Well Area of Review and Evaluation and Corrective Action Guidance document, the increase in pressure that may be sustained in the injection zone without allowing upward cross flow into the USDW is given by:

$$\Delta P_{if} = P_u + \rho_i g \cdot (z_u - z_i) - P_i$$

Pi = is the initial pressure in the injection zone,

Pu = initial pressure of the lowermost USDW,

ρi = fluid density of the injection zone,

ρu = fluid density of the lowermost USDW, g = acceleration due to gravity,

zu = elevation of the lowermost USDW and

zi = elevation of the injection zone.

The values that were used in the calculations can be found in the Table 4.2-1. The pressure of St. Peter formation (lowermost USDW) are site specific and were obtained from the ground water monitoring well GM#2 downhole pressure gauge. The zone two downhole pressure gauge at VW#2 was used to determine initial Mt. Simon reservoir pressure. Original connate fluid densities in the Mt. Simon and St. Peter were obtained from ground water samples from VW#2 and GM#2 respectively. Formation depths used in the critical pressure rise calculation remain based on the CCS#2 injector since the shallowest injection interval at either of the ADM sites is located in this well. In addition, the base of the USDW in the vicinity of the CCS #5-7 wells is shallower than exists at the CCS #2 location. These assumptions provide a conservative basis for calculation of the critical pressure for the CCS #5-7 site.

**Table 4.2-1.** Parameter space and values that were used to calculate critical pressure which is used to identify pressure induced Area of Review, per May 2013 UIC Program Class VI Well Area of Review and Evaluation and Corrective Action Guidance document.

| Units | Description (units) | CCS#2 |
|---|---|---|
| $P_u$ | Pressure in the St Peter USDW (Pa) | Sensitive, Confidential, or Privileged Information [redacted] |
| $P_u$ | St Peter Fluid head (m) | |
| | St Peter Level of Fluid (m) | |
| $P_i$ | Pressure in the Mt Simon (Pa) | |
| $P_i$ | Mt Simon Fluid head (m) | |
| | Mt Simon Level of Fluid (m) | |
| $p_{i\ brine}$ | Mt Simon brine density (kg/m3) | |
| $p_{u\ water}$ | St Peter water density (kg/m3) | |
| g | gravity (m/s2) | |
| **$z_u$** | **St Peter Depth (ft)** | |
| $z_u$ | St Peter Depth (m) | |
| **$z_i$** | **Mt Simon Reference Depth (ft)** | |
| $z_i$ | Mt Simon Reference Depth (m) | |

The corresponding Pi,f value is calculated as negative 28.2 psi and indicates that Mt. Simon is naturally over pressured with respect to St. Peter formation, which is the deepest USDW in the region. Therefore, as suggested in the guidance document, Method 2 was used to estimate pressure front based on the displacing fluid initially present in the borehole, assuming (1) hydrostatic conditions and (2) initially linearly varying densities in the borehole and constant density once the injection zone fluid is lifted to the top of the borehole (i.e., uniform density approach). The threshold pressure increase (ΔPc) may be calculated by:

$$\Delta P_c = \frac{1}{2} \cdot g \cdot \xi \cdot (z_u - z_i)^2$$

Where $\xi$ is a linear coefficient defined by;

$$\xi = \frac{\rho_i - \rho_u}{z_u - z_i}$$

The corresponding critical pressure value calculated to be 90.4 psi. As suggested in the UIC Program Class VI Well Area of Review and Evaluation and Corrective Action Guidance document, some over-pressurization within the injection zone may be allowable without causing sustained fluid leakage, owing to the density differential between the injection zone and USDW. If the value of ΔPc using Method 2 is greater than the absolute value of ΔPi,f using Method 1, the difference in magnitude between the two is used as an estimate of the allowable pressure increase. Hence, using this approach allows for a 62.2 psi pressure increase in the injection interval and any area projected to have a pressure rise of more than this value is included within the area of review.

### 4.2.2 Reservoir Modeling Results

The area defined by the 62.2 psi pressure front was extracted from the simulation results for the three volumetric sensitivity cases discussed further in Section 4.2.3. Simulation results were evaluated on a yearly basis during the injection period and every 5 years thereafter. In all scenarios, the 62.2 psi pressure front reaches its maximum extent approximately ten years post-injection in 2048. Figure 4.2.2-1 illustrates the maximum extent of the 40 Mt case pressure projection wherein a 62.2 psi pressure front is predicted to extend to a radius of approximately 13.8 miles.





**Figure 4.2.2-1.** Maximum extent of the 62.2 psi pressure front for the 40-million-ton injection scenario with an equivalent radius of 13.8 miles. 40 million tons is the planned injection scenario.

### 4.2.3 Sensitivity Discussion

To determine the sensitivity of model projections of plume size and reservoir pressure rise to input parameters, analyses were conducted to determine plume size and pressure rise as a function of total injected volume.

Figures 4.2.3-1 through 4.2.3-3 present modeled $CO_2$ plumes corresponding to total injected volumes of 40, 45 and 49 million tons during the projected operational lifetime. As summarized in Table 4.2.3-2, a 23% increase in injected volume results in an approximate 4% increase in equivalent plume radius.





**Figure 4.2.3-1.** Case 1 – 40Mt injection. Image on the left represents the plume extent at the end of injection in year 2038. Image on the right represents the plume extent in year 2088. The CCS #5-7 plume covers an area of 8.62 and 10.74 square miles, respectively.





**Figure 4.2.3-2.** Case 2 – 45Mt injection. Image on the left represents the plume extent at the end of injection in year 2038. Image on the right represents the plume extent in year 2088. The CCS #5-7 plume covers an area of 8.90 and 11.34 square miles, respectively.





**Figure 4.2.3-3.** Case 3 – 49Mt injection. Image on the left represents the plume extent at the end of injection in year 2038. Image on the right represents the plume extent in year 2088. The CCS #5-7 plume covers an area of 9.32 and 11.89 square miles, respectively.

**Table 4.2.3-1.** Plume Area

| Year | Plume Area ($mi^2$) | | |
|---|---|---|---|
| | 40MT | 45MT | 49MT |
| **2038** | 8.62 | 8.90 | 9.32 |
| **2088** | 10.74 | 11.34 | 11.89 |

**Table 4.2.3-2.** Equivalent Plume Radii

| Year | Equivalent Plume Radius (mi) | | |
|---|---|---|---|
| | 40MT | 45MT | 49MT |
| **2038** | 1.66 | 1.68 | 1.72 |
| **2088** | 1.85 | 1.90 | 1.95 |

Predicted pressure-rise demonstrates similar sensitivity to injected volume. In all injection cases, the 62.2 psi pressure front reaches its maximum extent approximately ten years post-injection in 2048. Figure 4.3.2-4 presents the 62.2-psi AoR boundaries for the same 3 cases of projected rate. As shown, a 23% increase in injected volume will extend the equivalent AoR radius by approximately 2.4%. Post-injection pressure behavior is similar for all rate assumptions, with the cone of influence predicted for each of the 3 sensitivity cases reducing to less than 50% of its maximum size over a 50-year post-injection timeframe.





**Figure 4.2.3-4.** AoR Boundary vs Total Injected Volume

In addition, variations in primary reservoir parameters (permeability and thickness) have similar impacts on projected plume behavior as changes in rate. Based on supplementary modeling, increasing the thickness by a factor of 50% reduces plume radius by approximately 20% while permeability has a much smaller effect.

Relatively large changes to major model input parameters result in limited changes to predictions. In fact, the level of characterization for the site and for the probable injection rates/volumes is more accurate than these very generalized sensitivity examples that have been presented for illustration purposes. The proposed testing and monitoring program will allow for comparison and tracking of plume and pressure development throughout the life of the project.

Bottomhole Pressure and Rate vs Time – 45-Million-ton Scenario

In the 45 Mt sensitivity scenario, the maximum assigned rate can be injected into all wells without encountering maximum pressure limitations. In this case, approximately 15 million tons are injected into each of the three wells.






**Figure 4.2.3-5.** Injector bottomhole pressure and injection rate profiles for 45-million-ton injection scenario.

Bottomhole Pressure and Rate vs Time – 49-Million-ton Scenario

In the 49 Mt scenario, CCS #6 reaches its maximum bottomhole pressure constraint and its rate is scaled down to avoid exceeding the maximum allowable pressure. In this case, the cumulative injection volumes for CCS#5, CCS#6 and CCS#7 are 16.8, 15.1 and 16.8 million tonnes, respectively.








**Figure 4.2.3-6.** Injector bottomhole pressure and injection rate profiles for 49-million-ton injection scenario.

The table below summarizes the injection rate, simulated maximum injection pressure, maximum allowable pressure for each well and each case.

**Table 4.2.3-3.** Maximum simulated bottomhole injection pressures for each well and scenario and maximum allowed bottomhole pressures for each well

| Well | Max Simulated Pressure (psi) | | | Max Allowed Injection Pressure |
|---|---|---|---|---|
| | 40MT | 45MT | 49MT | |
| CCS5 | 4,093 | 4,280 | 4,375 | 4,439 |
| CCS6 | 4,199 | 4,331 | 4,337 | 4,337 |
| CCS7 | 4,105 | 4,214 | 4,295 | 4,404 |

## 4.3 Artificial penetrations within the AoR

The AoR is presented in Figures B.1 and B.2 in Appendix B. This AoR was calculated based on the pressure impacts generated by the combined operation of existing wells CCS#1 and CCS#2 and proposed wells CCS#3, CCS#4, CCS#5, CCS#6, and CCS#7 as presented in Section 4.1 and 4.2. Based on publicly available information from the Illinois State Geological Survey (ISGS) and the Illinois State Water Survey (ISWS) gathered in December 2022, ADM identified a total of 3,630 wells (821 oil/gas wells and 2,809 water wells) within the AoR. Except for the ADM CCS related wells [i.e., those associated with the Illinois Basin Decatur Project (IBDP) and Illinois Industrial Carbon Capture and Storage (IL-ICCS) projects, as described below], no wells were identified from public records that penetrate the confining zone within the AoR.

### 4.3.1 Tabulation of Wells within the AoR

Wells within the AoR

The only known wells within the AoR which currently penetrate the caprock (Eau Claire Formation) are wells associated with the IBDP and IL-ICCS projects:

- The IBDP injection well, CCS#1 (which is currently permitted as a Class VI well in its post-injection phase and will be used as a monitoring well during the IL-ICCS project).
- The IBDP verification well, VW#1 (which will continue to be used as a monitoring well during the IL-ICCS project).
- The IL-ICCS injection well, CCS#2.
- The IL-ICCS verification well, VW#2.

Tables B.1 and B.2 in Appendix B present a tabulation of publicly available data for oil and gas and water wells within the AoR, respectively. Figures B.1 and B.2 in Appendix B present the location of these oil and gas and water wells within the AoR, respectively. Available records for each well without a listed total depth were evaluated. The information gathered indicates none of the oil/gas or water wells with available data penetrate the confining zone. Based on the similar age, locations, and likely targets of the wells with less complete data, a reasonable assumption has been made that wells without a listed total depth are consistent with local wells and also do not penetrate the confining zone. This approach is consistent with the approach approved for the prior CCS#1 and CCS#2 permits. Sensitive, Confidential, or Privileged Information [redacted] As part of the original permit application, all wells within the 4 townships-area of the injection well site were also identified (total of 3,761

wells at that time), and includes wells outside of the AoR. Information regarding these wells was provided as a supplement to the previous permit application.

There are four oil and gas wells located within approximately 2.4 km (1.5 miles) of the CCS #5-7 proposed well locations centroid. The closest well to centroid is located in Section 32, T18N, R2E (API number 121152293100), was drilled in 2001, and was -640 m (-2,100 ft KB) deep. The well was determined to be a dry hole and was subsequently plugged and abandoned. The other three (3) oil and gas wells are located in Section 33, T18N, R2E or Section 5, T17N, R2E. The deepest of these oil wells is API number 121152292300, located in Section 5. This well was drilled into the Silurian and was -642 m KB (-2,106 ft KB) deep. In summary, four oil and gas wells occur within 1.5 miles of the CCS #5-#7 proposed well locations centroid, but none penetrate the confining zone. Therefore, none of these wells have any potential to be a vertical pathway for fluid movement out of the permitted injection zone.

Wells Penetrating the Confining Zone

With the exception of the injection and verification wells previously detailed in this Section, there are no other known wells within the area of review that penetrate deeper than -1,169 m KB (-3,835 ft KB). The depth to the top of the upper confining zone (Eau Claire Formation) at CCS #1 is -1,538 m KB (-5,047 ft KB), and depths ranging from approximately -1,419 to -1,438 m KB (-4,656 to -4,717 ft KB) are expected at CCS#5-7. Therefore, there are only four known wells that currently penetrate into the uppermost confining zone within the AoR: the IBDP wells CCS#1 and VW#1, and the IL-ICCS wells CCS#2 and VW#2. These wells are currently constructed and monitored to satisfactory standards such that they are not potential vertical pathways for fluid movement out of the permitted injection zone.

If any of these deeper wells that penetrate through the confining zone are taken out of service during the life of the project, ADM will provide information to EPA to confirm that they have been properly plugged to ensure USDW protection pursuant to requirements at 40 CFR Part 146. If any additional wells that penetrate the confining zone are identified (e.g., if the AoR is re-delineated to cover a larger area as the result of an AoR reevaluation), ADM will evaluate these wells for potential risk and complete corrective action as needed pursuant to 40 CFR 146.84(d).

### 4.3.2 Plan for Site Access

This is not applicable because no corrective action is required at this time.

### 4.3.3 Justification of Phased Corrective Action

This is not applicable because no corrective action is required at this time.

## 4.4 AoR and Corrective Action Plan

ADM will take the following steps to evaluate project data and, if necessary, reevaluate the AoR. Future AoR reevaluations will be performed during the injection and post-injection phases. ADM will:

1. Review available monitoring data and compare it to the model predictions of plume size and pressure increase projected for the injection interval. ADM will analyze monitoring and operational data from the injection well (CCS#2), proposed injection wells (CCS#5, CCS#6 and CCS#7), the monitoring and geophysical wells, other surrounding wells, and other sources to assess whether the predicted $CO_2$ plume migration and pressure impacts are consistent with predicted behavior. Monitoring activities to be conducted are described in the Testing and Monitoring Plan (Section 9 of this permit application) and the PISC and Closure Plan (Section 11 of this permit application). Specific steps of this review include:

a. Review available data regarding the position of the $CO_2$ plume and pressure front (including pressure and temperature monitoring data and RST saturation and seismic survey data). Specific activities will include:

    i. Correlate data from time-lapse RST logs, time-lapse VSP surveys (if conducted since the last review), and other seismic methods (e.g., 3D surveys) to locate and track the movement of the $CO_2$ plume. A good correlation between the data sets will provide strong evidence for the continued validation of the model representation of the storage system. Also, as may be practical, 2D and 3D seismic surveys will be employed to determine the plume location as described in the Testing and Monitoring Plan and/or the PISC and Site Closure Plan (as applicable).

    ii. Review downhole reservoir pressure data collected from various locations and intervals using a combination of surface and downhole pressure gauges.

b. Review ground water chemistry monitoring data acquired from the shallow (i.e., in Quaternary and/or Pennsylvanian strata) monitoring wells, the St. Peter, and the Ironton-Galesville to verify that there is no evidence of excursion of carbon dioxide or brines that represent an endangerment to any USDWs.

c. Review operational data, e.g., regarding injection rates and pressures, and verifying that it is consistent with the inputs used in the most recent modeling effort.

d. Review any geologic data acquired since the last modeling effort, (e.g., additional site characterization performed, if any), updates of petrophysical properties from core analysis, etc. Identifying whether any new data materially differ from modeling inputs/assumptions.

2. Compare the results of reservoir modeling used for AoR delineation to the pressure and saturation data collected. Monitoring data will be used to show that the model accurately represents the storage site and can be used as a proxy to determine the properties and size of the plume. ADM will demonstrate the degree of accuracy by comparing monitoring data against the model predictions (i.e., plume location, rate of movement, and pressure decay). Statistical methods will be employed to correlate the data and confirm the ability of the model to accurately represent the storage site.

3. If the information reviewed is consistent with, or is unchanged from, the most recent modeling assumptions or confirms modeled predictions about the maximum extent of plume and pressure front movement, ADM will prepare a report demonstrating that, based on the monitoring and operating data, no reevaluation of the AoR is needed. The report will include the data and results demonstrating that no changes are necessary.

4. If material changes have occurred (e.g., in the behavior of the plume and pressure front, operations, or site conditions) such that the actual plume or pressure front may extend beyond the previously modeled plume and pressure front such that the basis of the approvals change, ADM will re-delineate the AoR. The following steps will be taken:

    a. Revising the site conceptual model based on new site characterization, operational, or monitoring data.

    b. Calibrating the model in order to minimize the differences between monitoring data and model simulations.

c. Performing the AoR delineation as described in the Computational Modeling Section of this AoR and Corrective Action Plan.

5. Review wells in any newly identified areas of the AoR and apply corrective action to deficient wells, if necessary. Specific steps include:
    a. Identifying any additional wells within the expanded AoR that penetrate the confining zone and provide a description of each well type, construction, date drilled, location, depth, record of plugging and/or completion.
    b. Determining which abandoned wells in the newly delineated AoR have been plugged in a manner that prevents the movement of carbon dioxide or other fluids that may endanger USDWs.
    c. Performing corrective action on all deficient wells in the AoR using methods designed to prevent the movement of fluid into or between USDWs, including the use of materials compatible with carbon dioxide.

6. Prepare a report documenting the AoR reevaluation process, data evaluated, any corrective actions determined to be necessary, and the status of corrective action or a schedule for any corrective actions to be performed. The report will be submitted to EPA within one year of the reevaluation. The report will include maps that highlight similarities and differences in comparison with previous AoR delineations.

7. Update the AoR and Corrective Action Plan to reflect the revised AoR, along with other related project plans, as needed.

### 4.4.1 AoR Reevaluation Cycle

ADM will reevaluate the above described AoR every five years during the injection and post-injection phases.

In addition, monitoring and operational data will be reviewed periodically by ADM during the injection and post-injection phases. The reservoir flow model will be history matched against the observed parameters measured at the monitoring wells. Pressure will be monitored as described in the Testing and Monitoring Plan. The time lapse pressure monitoring data will be compared to the model predicted time lapse pressure profiles. ADM will provide a review of this data in the semi-annual report.

If data suggest that a significant change in the size or shape of the actual $CO_2$ plume as compared to the predicted $CO_2$ plume and/or pressure front is occurring or there are deviations from modeled predictions such that the actual plume or pressure front may extend vertically or horizontally beyond the modeled plume and pressure front, ADM will initiate an AoR reevaluation prior to the next scheduled reevaluation. Such deviations may be evidenced by the results of direct or indirect monitoring activities including MIT failures or loss of MI; observed pressure and saturation profiles; changes in the physical or chemical characteristics of the $CO_2$; any detection of $CO_2$ above the confining zone (e.g., based on hydro chemical/physical parameters); micro seismic data indicating slippage in or near the confining zone or micro seismic data within the injection zone that indicates slippage and propagation into the confining zone; or arrival of the $CO_2$ plume and/or pressure front at certain monitoring locations that diverges from expectations, as described below.

### 4.4.2 Trigger for AoR Reevaluations Prior to the Next Scheduled Reevaluation

Unscheduled reevaluation of the AoR will be based on quantitative changes of the monitoring parameters in the deep monitoring wells, including unexpected changes in the following parameters: pressure, temperature, neutron saturation, and the deep ground water (> 3,000 ft below KB) constituent concentrations indicating that

the actual plume or pressure front may extend beyond the modeled plume and pressure front. These changes include:

- *Pressure:* Changes in pressure that are unexpected and outside three (3) standard deviations from the average will trigger a new evaluation of the AoR.
- *Temperature*: Changes in temperature that are unexpected and outside three (3) standard deviations from the average will trigger a new evaluation of the AoR.
- *RST Saturation:* Increases in $CO_2$ saturation that indicate the movement of $CO_2$ into or above the confining zone will trigger a new evaluation of the AoR unless the changes are found to be related to the well integrity. (Any well integrity issues will be investigated and addressed.)
- *Deep ground water constituent concentrations*: Unexpected changes in fluid constituent concentrations that indicate movement of $CO_2$ or brines into or above the confining zone will trigger a new evaluation of the AoR unless the changes are found to be related to the well integrity. (Any well integrity issues will be investigated and addressed.)
- *Exceeding Fracture Pressure Conditions*: Pressure in any of the injection or monitoring wells exceeding 90 percent of the formation fracture pressure established for the point of measurement. This would be a violation of the permit conditions. The Testing and Monitoring Plan (Section 9 of this permit application) and the operating procedures in Section 8 of this permit application provides discussion of pressure monitoring and specific procedures that will be completed during the injection start-up period.
- *Exceeding Established Baseline Hydro chemical/Physical Parameter Patterns:* A statistically significant difference between observed and baseline hydro chemical/physical parameter patterns (e.g., fluid conductivity, pressure, temperature) immediately above the confining zone. The Testing and Monitoring Plan (Section 8 of this permit application) provides extended information regarding how pressure, temperature, and fluid conductivity will be monitored.
- *Compromise in Injection Well Mechanical Integrity*: A significant change in pressure within the protective annular pressurization system surrounding each injection well that indicates a loss of mechanical integrity at an injection well.
- *Seismic Monitoring Identification of Subsurface Structural Features*: Seismic monitoring data that indicates the presence of a fault or fracture in or near the confining zone or a fault or fracture within the injection zone that indicates propagation into the confining zone. The Testing and Monitoring Plan provides extended information about the micro seismic monitoring network.

An unscheduled AoR reevaluation may also be needed if it is likely that the actual plume or pressure front may extend beyond the modeled plume and pressure front because any of the following has occurred:

- Seismic event greater than M3.5 within eight (8) miles of the injection wells;
- If there is an exceedance of any Class VI operating permit condition (e.g., exceeding the permitted volumes of carbon dioxide injected); or
- If new site characterization data changes the computational model to such an extent that the predicted plume or pressure front extends vertically or horizontally beyond the predicted AoR.

ADM will discuss any such events with the UIC Program Director to determine if an AoR reevaluation is required.

If an unscheduled reevaluation is triggered, ADM will perform the steps described at the beginning of this section of this Plan.

# 5. Financial Responsibility Plan

Cost estimates for financial assurance associated with the proposed ADM CCS #5-7 wells are generated based on prices incurred for similar work and reflect the current pricing environment. The cost summary presented in Section 5.6 applies both inflation and cost discounting assumptions based on the expected project timeline. See Appendix A for Financial Responsibility documentation.

## 5.1 Area of Review and Corrective Action Cost Estimate

As outlined in Appendix B of the permit application, the area of review (AoR) refers to the maximum area extent of the effected injection reservoir in which Mt. Simon pressure will exceed a critical pressure and have the potential to hypothetically drive fluids upwards into the lowermost USDW (St. Peter formation) if a vertical pathway is present. The AoR is based on results from current numerical modeling including all proposed wells at the site (including CCS #1-7) and is subject to change if operational measurements deviate significantly from modeled predictions. However, no known deep penetrating wells were found to exist within the AoR. Based on this review, no cost has been assigned for corrective action since no pathways for hypothetical leakage were found to exist.

## 5.2 Injection Well Plugging and Site Reclamation Estimate

Plugging costs for the three injection wells (CCS#5, CCS#6, and CCS#7) will be incurred at the end of their respective operational periods. A series of cement plugs will be placed to seal the entire wellbore, and each well will be capped and covered below ground level. Table 5.2-1 presents an approximate breakdown of total estimated cost based on the procedures provided in Section 10.

**TABLE 5.2-1.** Cost Summary for Injection Well Plugging/Site Reclamation

| Activity | No. Wells | Cost/Well | Subtotal |
|---|---|---|---|
| Sensitive, Confidential, or Privileged Information | | | |
| **Total Estimated Cost for P&A / Site Reclamation:** | | | **$2,325,000** |

## 5.3 Post-Injection Site Care Cost Estimate

Post-injection monitoring extends the use of the verification wells (VWs) and geophysical monitoring wells (MWs) by means of the operational testing and monitoring plan described in Section 9 of the permit application. Monitoring activities, locations and frequencies are summarized in Table 5.3-1. Monitoring costs assume that VW #4 and VW#5 will be installed as a single wellbore with multi-zone sampling capacity.

**TABLE 5.3-1.** Cost Summary for Post-Injection Monitoring

| Activity | Tested Wells | Frequency | Cost/Test | Total No. of Tests | Subtotal (10-yr) |
|---|---|---|---|---|---|
| Sensitive, Confidential, or Privileged Information | | | | | |
| **Total Estimated Cost for Post-Injection Monitoring:** | | | | | **$2,250,000** |

## 5.4 Site Closure Cost Estimate

The site closure costs summarized in Table 5.4-1 include plugging and reclamation activities for all VWs and MWs (the procedure is identical to that described in Section 5.2 for injection wells). The VWs extend to the approximate depth of injection wells but have a smaller diameter, which significantly reduces the volume of cement and time required for plugging. The GWs are installed to the base of the St. Peter formation, which is approximately half the depth of injection and verification wells. Site closure estimates assume VW #4 and #5 exist as single wellbores; multiple, smaller-diameter wellbores would likely incur the same total plugging cost.

**TABLE 5.4-1.** Cost Summary for Site Closure

| Activity | No. Wells | Cost/Well | Subtotal |
|---|---|---|---|
| Sensitive, Confidential, or Privileged Information | | | |
| **Total Estimated Cost for Site Closure:** | | | **$2,335,000** |

## 5.5 Emergency and Remedial Response Cost Estimate

The primary sources of risk evaluated in the current plan are similar to the risk categories utilized in the previously approved CCS#1 and #2 permits, and CCS#3 and CCS#4 permit applications. For the current evaluation, additional consideration was given to surface equipment and to the slight changes to some FEP probabilities impacted by the presence of the additional wells and the increased volume and pressure associated

with the incremental injection operations in the fourth site injector. In this site-wide financial risk assessment, Monte-Carlo analysis was used to calculate an expected present value (PV) of financial liability based on the probability and expected cost of risk events occurring over the 15-year operational and 10-year post operational periods. Probabilities for each event were assigned primarily based on a 2007 risk assessment report submitted as part of the FutureGen Environmental Impact Statement (FutureGen, Contract No. DE-AT26-06NT42921). Table 5.5-1 summarizes the range of probabilities estimated in the FutureGen report for each respective risk event and used as part of the input values for this evaluation.

**TABLE 5.5-1.** Annual Probabilities of Relevant CCS Risk Events

| Risk Event | Event Description | Annual Frequency of Failure (Single Item) | |
|---|---|---|---|
| | | Low Estimate | High Estimate |
| 1 | Pipeline Rupture | Sensitive, Confidential, or Privileged Information | |
| 2 | Pipeline Puncture | | |
| 3 | Wellhead Equipment Rupture | | |
| 4 | Upward rapid leakage through $CO_2$ injection well | | |
| 5 | Upward slow leakage through $CO_2$ injection well | | |
| 6 | Upward rapid leakage through deep oil & gas wells | | |
| 7 | Upward slow leakage through deep oil & gas wells | | |
| 8 | Upward rapid leakage through caprock | | |
| 9 | Upward slow leakage through caprock | | |
| 10 | Release through existing faults | | |
| 11 | Release through induced faults | | |
| 12 | Leaks due to undocumented deep wells, high rate | | |
| 13 | Leaks due to undocumented deep wells, low rate | | |

Each Monte-Carlo simulation observation assigns random event probabilities using uniform distributions based on the respective low and high estimates shown in Table 5.5-1. The resulting probabilities are then multiplied by the number of relevant items: events 1-5 apply to three $CO_2$ injection wells, events 6-7 are applied to approximately 100 oil and gas wells within the project's area-of review (AoR), and the remaining events are interpreted as project-wide risks with a multiplier of 1.

If an event occurs in a particular Monte-Carlo realization based on the probability distribution and the multiplier for the potential number of events from the process described above, it is then assigned a cost based on a triangular distribution. Most-likely costs assigned for events 4-13 are volume-based remediation estimates based on the magnitude of potential leakage (Appendix 8 provides additional information on the methodology of cost assignments). Table 5.5-2 summarizes the distribution parameters used for each risk event (low, most-likely, and high estimates).

**TABLE 5.5-2.** Remediation Cost Parameters for Risk Events

| Event | Event Description | Event Cost (Triangular Distribution) | | |
|---|---|---|---|---|
| | | Low | Most Likely | High |
| 1 | Pipeline Rupture | Sensitive, Confidential, or Privileged Information | | |
| 2 | Pipeline Puncture | | | |
| 3 | Wellhead Equipment Rupture | | | |
| 4 | Upward rapid leakage through $CO_2$ injection well | | | |
| 5 | Upward slow leakage through $CO_2$ injection well | | | |
| 6 | Upward rapid leakage through deep oil & gas wells | | | |
| 7 | Upward slow leakage through deep oil & gas wells | | | |
| 8 | Upward rapid leakage through caprock | | | |
| 9 | Upward slow leakage through caprock | | | |
| 10 | Release through existing faults | | | |
| 11 | Release through induced faults | | | |
| 12 | Leaks due to undocumented deep wells, high rate | | | |
| 13 | Leaks due to undocumented deep wells, low rate | | | |

Using the defined probability and cost distributions, the Monte-Carlo simulation creates thousands of viable scenarios that project annual liability costs over a 25-year timeframe (15 years operational and 10 post-operational). Future payments are discounted at a rate of 2.0% and incorporate an annual inflation rate of 2.75%. Figure 5.5-1 illustrates the final distribution of total project liability based on the aggregate results of 100,000 simulations. The Monte Carlo analysis was used to generate an expected value of $4.47 million based on the results from all modeled outcomes.





**Figure 5.5-1.** Distribution of Emergency and Remedial Response Net Present Value

## 5.6 Cost Summary

Cost estimates detailed in Sections 5.1 through 5.5 were adjusted to present values using the same method described in the emergency and remedial response section (future costs were inflated assuming an annual inflation rate of 2.75% and discounted at a rate of 2.0%). Table 5.6-1 summarizes the pre-adjusted and adjusted cost totals for the five cost categories.

**TABLE 5.6-1.** Financial Assurance Cost Summary, CCS #5, CCS #6 and CCS #7

| Category | Pre-adjusted | Adjusted NPV |
|---|---|---|
| Sensitive, Confidential, or Privileged Information | | |
| **Total Financial Assurance Required:** | | **$13,220,000** |

# 6. Well Construction Details

## 6.1 Well Hole Diameters and Injection Intervals

The approximate open hole diameters and injection intervals for CCS#5-7 are described below in Tables 6.1-1, 6.1-2, and 6.1-3.

**Table 6.1-1.** CCS#5 preliminary open hole diameters and depth intervals

| Name of Interval | Approximate Depth Interval (feet) | Open Hole Diameter (inches) | Comment |
|---|---|---|---|
| Surface | Sensitive, Confidential, or Privileged Information | | To bedrock |
| Intermediate | | | To primary seal |
| Long | | | To total depth |

**Table 6.1-2.** CCS#6 preliminary open hole diameters and depth intervals

| Name of Interval | Approximate Depth Interval (feet) | Open Hole Diameter (inches) | Comment |
|---|---|---|---|
| Surface | Sensitive, Confidential, or Privileged Information | | To bedrock |
| Intermediate | | | To primary seal |
| Long | | | To total depth |

**Table 6.1-3.** CCS#7 preliminary open hole diameters and depth intervals

| Name of Interval | Approximate Depth Interval (feet) | Open Hole Diameter (inches) | Comment |
|---|---|---|---|
| Surface | Sensitive, Confidential, or Privileged Information | | To bedrock |
| Intermediate | | | To primary seal |
| Long | | | To total depth |

## 6.2 Casing Specifications

The casing specifications for CCS#5-7 are described below in Tables 6.2-1, 6.2-2, and 6.2-3.

**Table 6.2-1.** CCS#5 preliminary casing specifications

| Name of Interval | Approximate Depth Interval (feet) | Outside Diameter (inches) | Inside Diameter (inches) | Weight (lb/ft) | Grade (API) | Design Coupling (Short or Long Threaded) | Thermal Conductivity @ 77°F (BTU/ft.hr. °F) |
|---|---|---|---|---|---|---|---|
| Surface[1] | Sensitive, Confidential, or Privileged Information | | | | | | |
| Intermediate[2] | | | | | | | |
| Long[3] (carbon) | | | | | | | |
| Long[3] (chrome) | | | | | | | |

**Table 6.2-2.** CCS#6 preliminary casing specifications

| Name of Interval | Approximate Depth Interval (feet) | Outside Diameter (inches) | Inside Diameter (inches) | Weight (lb/ft) | Grade (API) | Design Coupling (Short or Long Threaded) | Thermal Conductivity @ 77°F (BTU/ft.hr. °F) |
|---|---|---|---|---|---|---|---|
| Surface[1] | Sensitive, Confidential, or Privileged Information | | | | | | |
| Intermediate[2] | | | | | | | |
| Long[3] (carbon) | | | | | | | |
| Long[3] (chrome) | | | | | | | |

**Table 6.2-3.** CCS#7 preliminary casing specifications

| Name of Interval | Approximate Depth Interval (feet) | Outside Diameter (inches) | Inside Diameter (inches) | Weight (lb/ft) | Grade (API) | Design Coupling (Short or Long Threaded) | Thermal Conductivity @ 77°F (BTU/ft.hr. °F) |
|---|---|---|---|---|---|---|---|
| Surface[1] | Sensitive, Confidential, or Privileged Information | | | | | | |
| Intermediate[2] | | | | | | | |
| Long[3] (carbon) | | | | | | | |
| Long[3] (chrome) | | | | | | | |

Note 1: Surface casing will be 350 ft of 20-inch casing for all three wells. After drilling a 26-inch hole to approximately 350 ft true vertical depth (TVD) or at least 50 ft into the bedrock below the shallow groundwater, 20-inch, 94 ppf, H40, short thread and coupling (STC) casing will be set and cemented to surface. Coupling outside diameter is ~21 inches.

Note 2: Intermediate casing will be at least 5,600 ft of 13.375-inch casing for all three wells. After a shoe test or formation integrity test (FIT) is performed, a 17.5-inch hole will be drilled to approximately 5,600 ft TVD or approximately 50 ft into the Eau Claire Shale (primary seal formation). The 13.375-inch-long thread and coupling (LTC) or buttress thread and coupling (BTC) casing will be set and cemented to surface. Coupling outside diameter is ~14.375-inches.

Note 3: Long string casing for all three wells consists of two sections: 1 ) 9.625-inch, API CS casing and 2) 9.625-inch, API 13Cr alloy casing. After a shoe test is performed and the integrity of the casing is tested, a 12.25-inch hole will be drilled to approximately 7,700 ft – 7,900 ft TVD or through the Mt. Simon, where the long string casing will be set and cemented in two stages using $CO_2$ resistant cement in the bottom (tail) section. The upper 9.625-inch depths will be approximately 5,200 ft TVD for all three wells. Coupling outside diameter is ~10.625-inches for the upper CS section and ~10.485-inches for the lower 13Cr section.

## 6.3 Tubing Specifications

The tubing specifications for CCS#5-7 are described below in Tables 6.3-1, 6.3-2, and 6.3-3.

**Table 6.3-1.** CCS#5 Preliminary tubing Specifications

| Name | Depth Interval (feet)[1] | Outside Diameter (inches) | Inside Diameter (inches) | Weight (lb/ft) | Grade (API) | Design Coupling (Short or Long Threaded | Burst strength (psi) | Collapse strength (psi) |
|---|---|---|---|---|---|---|---|---|
| Injection tubing[2,3,4] | Sensitive, Confidential, or Privileged Information | | | | | | | |

**Table 6.3-2.** CCS#6 Preliminary tubing Specifications

| Name | Depth Interval (feet)[1] | Outside Diameter (inches) | Inside Diameter (inches) | Weight (lb/ft) | Grade (API) | Design Coupling (Short or Long Threaded | Burst strength (psi) | Collapse strength (psi) |
|---|---|---|---|---|---|---|---|---|
| Injection tubing[2,3,4] | Sensitive, Confidential, or Privileged Information | | | | | | | |

**Table 6.3-3.** CCS#7 Preliminary tubing Specifications

| Name | Depth Interval (feet)[1] | Outside Diameter (inches) | Inside Diameter (inches) | Weight (lb/ft) | Grade (API) | Design Coupling (Short or Long Threaded | Burst strength (psi) | Collapse strength (psi) |
|---|---|---|---|---|---|---|---|---|
| Injection tubing[2,3,4] | Sensitive, Confidential, or Privileged Information | | | | | | | |

Note 1: The tubing length will be finalized after the location of the perforations are selected and the packer location determined. The final tubing design may change subject to availability and/or pending results of reservoir analysis. The well casing design does allow for a larger tubing than 5 ½" if required.

Note 2: Maximum allowable suspended weight based on joint strength of injection tubing. Specified yield strength (weakest point) on tubular and connection is 306,000 lbs.

Note 3: Weight of expected injection tubing string (axial load) in air (dead weight) will be 122,500 lbs., 120,100 lbs.., and 120,900 lbs. for CC#5, CCS#6, and CCS#7 respectively.

Note 4: Thermal conductivity of tubing @ 77°F will be 16 BTU / ft.hr.°F.

The wells will be plugged back from the bottom with at least 80 feet of cement or with a sufficient volume to prevent the injection fluid from coming directly in contact with the Precambrian granite basement through the

wellbore. Figures 6.3-1, 6.3-2, and 6.3-3 display wellbore schematics showing surface and subsurface well details for all three wells.

**CCS#5 Well Schematic**





**Figure 6.3-1.** CCS#5 Well Schematic

**CCS#6 Well Schematic**





**Figure 6.3-2.** CCS#6 Well Schematic

**CCS#7 Well Schematic**





**Figure 6.3-3.** CCS#7 Well Schematic

## 6.4 Tubing and Packer Pressure Gauge and Compatibility

The pressure and temperature gauge will be installed at the packer at approximate depth of 6,750 ft. for all three wells. Tubing and packer materials will be compatible with fluids with which the materials may be expected to come into contact and will meet or exceed standards developed for such materials by the American Petroleum Institute, ASTM International, or comparable standards acceptable to the Director.

# 7. Pre-Injection/Operational Testing Plan

The testing activities at CCS#5, CCS#6 and CCS#7 described in this Section are restricted to the pre-injection phase. Testing and monitoring activities during the injection and post-injection phases are described in the Testing and Monitoring Plan, along with other non-well related pre-injection baseline activities such as geochemical monitoring.

The pre-injection operational testing plan presented herein addresses the requirements of 40 CFR Section 146.87 (a-f):

- Deviation checks during drilling (a)(1)
- Logging required before installation of surface casing and long string casing (a)(2)(3)
- Tests to demonstrate internal and external mechanical integrity (a)(4)(5)
- Proposed coring program (b)
- Proposed fluid sampling program, including those to assess the chemical characteristics of the injection and confining zones (c)(d)
- Tests to verify hydrogeologic conditions in the injection and confining zone and determine fracture pressure(d)(e)

## 7.1 Tests during well drilling/construction

ADM will perform logging, surveys and tests to determine or verify the depth, thickness, porosity, permeability, lithology, and formation fluid salinity in all relevant geologic formations. These tests shall include:

- Deviation checks that meet the requirements of 40 CFR 146.87(a)(1);
- Logs and tests before and upon installation of the surface casing that meet the requirements of 40 CFR 146.87(a)(2);
- Logs and tests before and upon installation of the long-string casing that meet the requirements of 40 CFR 146.87(a)(3);
- Tests to demonstrate internal and external mechanical integrity that meet the requirements of 40 CFR 146.87(a)(4); and
- Any alternative methods that are required by and/or approved by the Director pursuant to 40 CFR 146.87(a)(5).

### 7.1.1 Deviation Checks and casing design

The subsurface and surface design (casing, cement, and wellhead designs) meets the requirements to appropriately manage $CO_2$, the preserve mechanical integrity during injection operations and to sustain the integrity of the caprock to ensure $CO_2$ remains in the Mt. Simon. For reasons such as equipment or supply availability, or changes to the supplemental monitoring program, the final well design may vary but will meet or exceed requirements in terms of strength and $CO_2$ compatibility. See Appendix G for well cement information.

The injection well is planned to be drilled vertically with an inclination of 5° degrees or less. During drilling, the wellbore trajectory will be tracked and surveyed every 1,000 feet to reduce the risk of interception with adjacent wellbores. In the event that a deviation exceeds 5° degrees due to a well kick off or directional drilling to facilitate the construction and operation of the well. The permittee will notify the agency within 7 calendar days.

### 7.1.2 Mechanical Integrity Testing and Logging During and after Casing Installation

Wireline logging is an important tool that will be used to identify many characteristics of the formations encountered during drilling and for demonstrating mechanical integrity of the well. The logs discussed in this section were conducted on CCS#1-2 and VW#1-2 and are summarized in Table 7.1.2-1. The logging program for CCS#5, CCS#6 and CCS#7 will be comparable but may differ from the previous well logging programs. Logs for the proposed injection wells are presented in Section 7.1.2.2 and 7.1.2.3, and are summarized in Table 7.1.2-2.

Mechanical integrity testing and logging are described in Section 7.1.2.3 and proposed testing is summarized in Table 7.1.2-3. ADM will provide a schedule for all testing and logging to the permitting agency at least 30 days in advance of conducting the first such tests and/or logs.

#### 7.1.2.1 Historic Logs

Table 7.1.2-1 presents a summary of the previous geophysical logs collected in the existing CCS and VW wells. The logging programs for the two active CCS wells were similar. CCS#1 had triple combo logs (gamma ray, spontaneous potential, caliper, resistivity, bulk density, and neutron porosity) performed on all sections of each well. All casing strings had either a cement bond log (CBL) or ultrasonic CBL to confirm the condition of cement between the casing and reservoir. The intermediate and long string sections of the wells had open hole logging programs that included triple combo, dipole sonic, formation micro-imaging (fracture finder), spectral gamma ray, and nuclear magnetic resonance logs as part of the suite of open hole logs. The long string logs on CCS#1 included a modular dynamics tester and a versatile seismic imager. The long string on CCS#2 also included a Litho-Scanner (Lithology Scanner). Triple combo, modular dynamics tester, Pressure Express Tool (XPT) and pulse neutron logs were performed in VW#1-2. The logging suite performed on the CCS wells presents a comprehensive geophysical analysis of the injection zone, confining zone, and overlying formations. A summary of the geologic characterization is provided in Section 3. Site Geologic Characterization of this application document.

**Table 7.1.2-1.** Log Summary: Existing Site Wells

| Well Name | Log Vendor | Log Title | Date Run | Depth Interval (MD ft. KB ) |
|---|---|---|---|---|
| Sensitive, Confidential, or Privileged Information | | GR, CAL, SP, Resistivity, RHOB, NPHI | 3/9/2009 | Sensitive, Confidential, or Privileged Information |
| | | Variable Density CBL | | |
| | | GR, CAL, SP, Resistivity, RHOB, NPHI | 4/5/2009 | |
| | | Sonic Scanner and FMI | 4/5/2009 | |
| | | CMR, ECS, HNGS | 4/5/2009 | |
| | | MSCT | 4/5/2009 | |
| | | Ultrasonic Cement Imaging | | |
| | | GR, CAL, SP, Resistivity, RHOB, NPHI | 4/26/2009 | |
| | | Sonic Scanner and FMI | 4/26/2009 | |
| | | CMR, ECS, HNGS | 4/26/2009 | |
| | | MSCT | 4/26/2009 | |
| | | MDT | 4/26/2009 | |
| | | VSIT | 4/26/2009 | |
| | | Ultrasonic Cement Imaging | | |
| | | Variable Density CBL | | |
| | | Pressure/Temperature Log | | |
| | | Thermal Neutron Decay (Formation Sigma) Log | | |
| | | Multi-Finger Caliper Log | | |
| | | CCL and Perforation Record | | |
| | | Injection Fullbore Spinner Logs | | |
| | | | | |
| | | GR, Resistivity, NPHI, SlimPulse | 1/12/2015 | |
| | | CAL, DSLT, GPIT | 1/12/2015 | |
| | | CBL | 1/16/2015 | |
| | | GR, CAL, SP, Resistivity, RHOB, NPHI | 5/3/2015 | |
| | | Sonic Scanner, FMI, CAL, GPIT | 5/3/2015 | |
| | | ECS, HNGS | 5/3/2015 | |
| | | Variable Density CBL | 5/31/2015 | |
| | | Isolation Scanner Cement Evaluation | 5/31/2015 | |
| | | Isolation Scanner Casing Integrity | 5/31/2015 | |
| | | GR, CAL, SP, Resistivity, RHOB, NPHI | 5/29/2015 | |
| | | Sonic Scanner, FMI, CAL, GPIT | 5/29/2015 | |
| | | CMR, Litho Scanner, HNGS | 5/29/2015 | |
| | | MSCT | 5/29/2015 | |
| | | Multi-finger Imaging Tool | 6/10/2015 | |
| | | Variable Density CBL | 6/10/2015 | |
| | | Isolation Scanner Cement Evaluation | 6/10/2015 | |

| Well Name | Log Vendor | Log Title | Date Run | Depth Interval (MD ft. KB ) |
|---|---|---|---|---|
| Sensitive, Confidential, or Privileged Information | | Isolation Scanner Third Interface Echo | 6/10/2015 | Sensitive, Confidential, or Privileged Information |
| | | | | |
| | | GR, SP, Resistivity, RHOB, NPHI, Sonic | | |
| | | CBL and/or Cement Imaging | | |
| | | GR, CAL, Resistivity, RHOB, NPHI | | |
| | | Sonic Scanner | | |
| | | GR, CAL, Resistivity, RHOB, NPHI | | |
| | | Sonic Scanner | | |
| | | MDT | 10/25/2010 | |
| | | XPT (Pressure Express Tool) | 11/17/2010 | |
| | | | | |
| | | GR, CAL, Resistivity, RHOB, NPHI | 10/8/2012 | |
| | | Sonic Scanner | 10/8/2012 | |
| | | GR, CAL, Resistivity, RHOB, NPHI | 10/31/2012 | |
| | | Sonic Scanner | 10/31/2012 | |
| | | XPT (Pressure Express Tool) | 10/31/2012 | |
| | | RST | | |

7.1.2.2 Proposed CCS#5, CCS#6 and CCS#7 Logs

Table 7.1.2-2 presents the proposed log suite for CCS#5, CCS#6 and CCS#7. Each open hole section (prior to setting each casing string) will be logged with multiple suites to fully characterize the geologic formations (reservoirs and seals). The logging program will include resistivity, spontaneous potential (SP), gamma ray (GR), cement bond, and caliper logs.

**Table 7.1.2-2.** Proposed Logging CCS#5, CCS#6 and CCS#7

| Log Type (Open Hole or Cased Hole) | Log Run Title | Hole Section |
|---|---|---|
| Open Hole | GR, SP, Resistivity, Caliper | Surface |
| Cased Hole | Radial Cement Bond Log | Surface |
| Cased Hole | Temperature Log | Surface |
| Open Hole | GR, SP, Resistivity, Caliper | Intermediate |
| Open Hole | Bulk Density, Neutron Porosity | Intermediate |
| Open Hole | Sonic | Intermediate |
| Cased Hole | Radial Cement Bond Log or Ultrasonic Cement Bond Log | Intermediate |
| Cased Hole | Temperature Log | Intermediate |
| Open Hole | Spectral GR, SP, Resistivity, Caliper | Long String |
| Open Hole | Bulk Density, Neutron Porosity | Long String |
| Open Hole | Sonic | Long String |
| Open Hole | Nuclear Magnetic Resonance | Long String |
| Open Hole | Fracture Finder | Long String |
| Cased Hole | Radial Cement Bond Log or Ultrasonic Cement Bond Log | Long String |
| Cased Hole | Temperature Log | Long String |

With the exception of the 20" conductor casing, a cement bond log (CBL) with radial capability and/or ultrasonic cement imaging logs will be run on all casing strings. In addition to cement evaluation data, ultrasonic imaging and/or multi-finger caliper (MFC) logs will provide baseline casing thickness and/or internal radius measurements. Follow-up MFC logs will be performed in the event the injection tubing is removed during a well recompletion or workover.

Regarding the conductor casing, due to the large casing size, a cement bond log with radial imaging is not practical and when performed typically yield ambiguous results. To achieve good cement mechanical integrity, the best practice indicators are returning excess clean cement to the surface during cement displacement, having minimal cement fallback after completing cement displacement, and successfully passing a casing shoe test.

Based on previous experience with CCS#1 and CCS#2, hydraulic stimulation of the injection zone is not expected but an acid matrix stimulation to reduce perforation skin damage may be necessary. To reduce the risk of formation damage during well perforation, the operator will employ a static or dynamic underbalanced techniques.

After the well is cased, pre-injection testing will be performed to provide well specific data for the reservoir model. During these tests, P/T gauges will be deployed near the perforated interval while the pressure fall-off and step rate tests are performed. The final perforating scheme will be based on interpretation of the test results.

After installation of the 5-1/2" injection tubing, a baseline temperature and pulse neutron (PN) log will be performed. These logs will be compared to subsequent timelapse logs to inform the operator about the accumulation and movement of $CO_2$ behind the wellbore and the state of the well's mechanical integrity. The PN logs will provided information about the location and vertical movement of $CO_2$ near the wellbore. This allows the operator to monitor the movement of $CO_2$ within the injection zone and above the seal formation. Both logging techniques will be used to demonstrate the mechanical integrity of the well.

7.1.2.3 Proposed Mechanical Integrity Testing

After setting and cementing the casing, a radially capable cement imaging log and casing inspection log will be run to evaluate the cement bond between the casing and the reservoir and to provide a baseline casing inspection log. Next, the casing string will undergo a one-hour pressure test at 750 psig and will pass if the pressure loss is less than 3%. After passing these tests, the well will be perforated and completed with 5.5-inch tubing and packer assembly. After well completion, the tubing/casing annulus will undergo a one-hour pressure test. As mentioned above, a baseline pulse neutron log will be run. Repeat PN logs can be run if anomalous temperature data indicates a need for further analysis. Monitoring the distributed temperature system (DTS) data across the top of the Mt. Simon Sandstone formation, as well as the porous zones above the seal, will be used to validate the integrity of the completion. Table 7.1.2-3 below is a summary of the pre-injection testing program.

**Table 7.1.2-3** Summary of MITs and Pressure Fall-Off Test to be Performed Prior to Injection

| Class VI Rule Citation | Rule Description | Test Description | Program Period |
|---|---|---|---|
| [40 CFR 146.89(a)(1)] | MIT – Internal | Annulus Pressure Test | Prior to Operation |
| [40 CFR 146.87(a)(4)] | MIT – External | OA or Temperature Log | Prior to Operation |
| [40 CFR 146.87(e)(1)] | Testing prior to operating | Pressure Fall-off Test | Prior to Operation |

## 7.2 Injection zone characterization and core sampling

ADM will provide the agency 30 days notification for the planned CCS#5, CCS#6, CCW#7, VW#4 and VW#5 coring events and/or reservoir fluid sampling. Because the permittee has a significant data set from previously obtained whole core samples, the permittee may only obtain sidewall cores from the new wells.

### 7.2.1 Historic injection zone fluid characterization and core sampling

The following information provides a review of the historic coring and fluid sampling programs. This dataset supports the basis of the proposed coring and reservoir fluid sampling programs for CCS#5, CCS#6 and CCS#7.

7.2.1.1 Historic Fluid Sampling

This section discusses the historic fluid sampling that has been conducted in CCS#1 and CCS#2 to characterize the Eau Claire (confining zone) and Mt. Simon (injection zone). The previous sampling and analysis of the fluid of the injection zone included fluid temperature, pH, conductivity, reservoir pressure, and static fluid level. In addition, total dissolved solids (TDS), fluid chemistry, density, and viscosity of the fluid in the injection zone were performed. The fluid samples were collected using Schlumberger's Modular Formation Dynamics Tester (MDT). Sampling of CCS#1 and CCS#2 were completed using the MDT tool at several depths within the Mt. Simon. Average fluid parameters of the injection zone are included in Table 7.2.1-1. These were collected using the MDT at multiple points in the injection zone. Using the fluid parameters from Table 7.2.1-1 , an estimated static fluid level for the injection reservoir was calculated to be 249.5 feet above mean sea level (AMSL). Explanation

of the historical analyses and results are discussed in more detail in previous permit applications and completion reports.

**Table 7.2.1-1.** Average Injection Zone Fluid Parameters

Sensitive, Confidential, or Privileged Information


Historic information pertaining to physical characteristics of the injection and confining zone can be derived from log and core data and are discussed below.

7.2.1.2 Historic Well Coring Programs

Thorough coring programs, utilizing both conventional whole core and rotary sidewall core and including wide-ranging analytical suites, were performed at CCS#1, CCS#2, VW#1, VW#2, and GM#2. While the focus on coring and analysis was the confining and injection zones in VW#2 and CCS#2, core-related information on overlying formations was also gathered in VW#1, CCS#1, and GM#2. A total of approximately 1,268 feet of whole core was recovered between the five wells, the bulk of which was captured in VW#1 (700 feet) and VW#2 (392 feet). Recovered sidewall core samples from the two injection wells and two verification wells totaled 400 samples. Of these 400 samples, 174 sidewalls were from VW#1, 62 sidewalls were from CCS#1, 69 sidewalls were from VW#2, and 95 sidewalls were from CCS#2. A summary of the core collected in these wells is presented in Appendix D and is discussed in more detail below.

Sensitive, Confidential, or Privileged Information

Sensitive, Confidential, or Privileged Information



### 7.2.2 Proposed Coring and Fluid Sampling Program

This section addresses the pre-operational sampling proposed by ADM to ensure that sufficient characterization of the subsurface at CCS#5, CCS #6 and CCS #7 is performed in addition to satisfying Class VI regulations. These requirements include injection and confining zone physical and chemical characteristics including coring and formation fluid sampling. Subpart (f) of §146.87 requires 30-day notice of any logging or testing of the Class VI well to the Director so that the Director has the opportunity to witness well activities.

7.2.2.1 Proposed Coring Program

The coring program and analysis that ADM performed at CCS#1, CCS#2, VW#1, and VW#2 provides extensive characterization of various formations, particularly the confining zone and injection zone, as described in Section 7.2.1. Appendix D provides more detail on the core data collected in these wells. The data provided from the site wells included both whole core and sidewall core focusing on the confining zone and injection zone. The testing in the existing core included routine core analysis (porosity, permeability, grain density, fluid saturations, and lithology descriptions), mercury injection capillary pressure, geomechanics, x-ray diffraction, quantitative evaluation of minerals by scanning electron microscopy, focused ion beam electron microscopy, tight rock analysis, total organic carbon content, nuclear magnetic resonance, pulse decay permeability, laser grain size analysis, CT scanning, and thin sections.

The coring program for CCS#5, CCS#6 and CCS#7 may include whole core within the confining zone (Eau Claire) and injection zone (Mt. Simon), as well as potential sidewall coring within select formations, as necessary based on open hole logging results. Routine core and geomechanical analysis will be performed on recovered core, as applicable. Data will be correlated with openhole geophysical well logs from the wells, and compared to core sample results obtained from previous wells.

7.2.2.2 Proposed Fluid Sampling Program

Although sufficient data has been acquired from the reservoir from the two injectors already installed and tested at the site, prior to any well testing in a newly drilled well a sample of the formation fluid from the injection zone will be collected to measure the pH, conductivity, physical, chemical, static fluid level and other characteristics to satisfy §146.87 (c) and (d)(3), and to determine whether the $CO_2$ plume has reached any newly drilled injector (CCS#5, CCS#6 and CCS#7) during the time of completion. These data are also important in the analysis of the initial pressure falloff test. Collection of these data, and previous reservoir sampling in combination with temperature and pressure logs noted in Section 7.4 Injection and confining zone formation testing , will satisfy §146.87 (c).

Well sampling will be conducted to satisfy regulations stated in Section 7.2. While a similar method of sample collection via wireline used to sample CCS#1 and CCS#2 is expected, the detailed procedure will depend on borehole conditions encountered during operations, as well as equipment and personnel availability experienced near the time of completion of the well. Detailed procedures outlining the expected sampling and subsequent analysis will be submitted in accordance with federal regulations and guidance prior to implementing a specific sampling procedure in the field.

## 7.3 Fracture pressure and downhole hydrogeologic testing of conditions

Specific regulatory requirements exist as permitting standards for testing and data collection associated with new wells. As presented at 40 CFR §146.82 (c), (d) and (e), the following are among the data that must be acquired for any new Class VI Injection well:

(c) The owner or operator must record the fluid temperature, pH, conductivity, reservoir pressure, and static fluid level of the injection zone(s).

(d) At a minimum, the owner or operator must determine or calculate the following information concerning the injection and confining zone(s):

(1) Fracture pressure

(e) Upon completion, but prior to operation, the owner or operator must conduct the following tests to verify hydrogeologic characteristics of the injection zone(s):

(1) A pressure fall-off test; and

(2) A pump test; or

(3) Injectivity tests.

CCS#5, CCS#6 and CCS#7 are new wells that may be installed at the site in the future and hence must comply with requirements at 40 CFR §146.87 (c), (d) and (e) (see Section 7.2 for the proposed fluid sampling and coring program). Data obtained as part of previous injection and monitoring requirements at the site are relevant to data acquisition to be collected from any new site wells. Historic activities are summarized in Section 7.3.1, which supports the proposed data collection activities presented in Section 7.3.2.

### 7.3.1 Historic testing

This section discusses the historic testing that has been conducted in CCS#1 and CCS#2 to characterize the Eau Claire (confining zone) and Mt. Simon (injection zone).

The well testing performed in both injection wells at the ADM site consisted of a pressure build-up falloff test (FOT) and a step rate test (SRT). The well testing performed in CCS#1 and CCS#2 are presented in Table 7.3-1. As presented in previous and forthcoming sections, historical sampling and testing activities conducted to characterize the subsurface at the site were comprehensive. No pressure transient testing was conducted in the VM wells.

#### 7.3.1.2 Historic Reservoir Testing

Well testing in the two injection wells CCS#1 and CCS#2 included an initial FOT and an SRT. A description of tests performed at each injection well is discussed in greater detail below and summarized in Table 7.3-1.

**Table 7.3-1.** Testing Summary: Existing Site Wells

| Activity | Well | Formation | Depth (feet KB) | Comment |
|---|---|---|---|---|
| Pressure of Reservoir | Sensitive, Confidential, or Privileged Information | | | |
| Pressure Step Rate | | | | |
| Pressure Falloff | | | | |

#### CCS 1 Test History

Three FOTs of varying duration were conducted in September and October 2009 as part of the initial completion of CCS#1. FOT involve two parts. During the first portion of the falloff tests, the reservoir was stressed by injecting fluid at a (traditionally) relatively stabilized rate, causing an increase in reservoir pressure. During the second portion of the test, injection was stopped and the well shut-in while the reservoir pressure monitored as it decayed and approached near-static condition.

The initial perforations in the CCS#1 injection interval were from 7,025 to 7,050 feet KB. To conduct initial reservoir testing, water, treated with a clay-stabilizing potassium chloride (KCl) substitute, was injected at rates of between 1.5 to 2.0 barrels per minute (bpm) (63 to 84 gallons per minute [gpm]) for approximately two hours. A 19.5-hour pressure falloff period followed this injection period.

After this test, the perforations were acidized and an SRT was conducted by pumping at increasing rate steps to observe a change of the well injectivity. Following the SRT, treated water was injected at a rate of 3.1 bpm (130 gpm) for five hours. After this period of relatively stable injection, the well was shut in and pressure was monitored for approximately 45 hours as a second FOT.

A third FOT was conducted after additional perforations were made in the well and subsequently stimulated with acid. These additional perforations, totaling 30 feet, were from 6,982 to 7,012 feet KB. The perforated zone received a second acid treatment. For the third FOT, treated water was injected at an increasing rate of 3.1 to 4.2 bpm (130 to 176 gpm) over 6.5 hours and then at 4.2 bpm (176 gpm) for an additional 6.5 hours. After this 13-hour period of injection, the well was shut in and pressure was monitored for 105 hours.

Analysis of the pressure transient data using analytical simulations was performed by Schlumberger. These analyses resulted in a projected reservoir permeability-thickness of 13,875 md-ft. Based on an average effective injection zone thickness of 75 feet, a permeability of 185 millidarcies (md) was calculated.

Analysis of the SRT, performed by Schlumberger, estimated a fracture propagation pressure of 4,966 psi at the bottomhole gauge depth of 6,891 feet KB resulting in a gradient of 0.72 psi/ft. This analysis was performed graphically by plotting the pressure at the end of each step versus rate. The intersection of lines before and after a pressure sensitive threshold was used to estimate the fracture pressure. This approach is an industry standard method for estimating conservative values.

Copies of the pressure transient data and analyses were presented to EPA in previous reports and are available upon request.

The confining zone testing included a “mini-frac” using Schlumberger’s MDT tool across a 2.8-foot interval of the Eau Claire centered on 5,435 feet KB. The fracture pressure measured from the tool ranged from 5,078 to 5,324 psig, which corresponds to fracture gradients of 0.93 to 0.98 psi/ft for the Eau Claire (confining zone).

<u>CCS#2 Test History</u>
An SRT and two FOTs were performed in July 2015 as part of the initial completion of CCS#2.
The SRT was performed following the perforation of four separate intervals (6,630 to 6,670 ft KB, 6,680 to 6,725 ft KB, 6,735 to 6,775 ft KB, and 6,787 to 6,825 ft KB) at a density of 4 shots per foot (SPF) for a total perforation interval of 163 feet. The initial injection period consisted of multiple increasing injection rates from 2 bpm to 8 bpm (6.28 hours), followed by a 16.3-hour falloff, then an injection period of 6 bpm for 8.4 hours prior to a final 157-hour falloff period. The fluid injected was 8.33 ppg water.

This data was analyzed by Schlumberger and was reported in an Injection-Falloff Analysis dated August 24, 2015. Schlumberger’s Report Summary stated:

Sensitive, Confidential, or Privileged Information

Sensitive, Confidential, or Privileged Information

The FOT and spinner log data from the long-term injection test at the end of the pressure transient sequence were collected and analyzed. Spinner log data from Schlumberger's Production Log Advisor report dated August 12, 2015 showed that during the long-term injection test, a total of 47.1 feet of the perforations were taking fluid in the upper 34 feet of the Mt. Simon, with 59% of the flow (and the lowermost 8.6 feet) taking 35% of the flow. The pressure falloff test analysis indicated a permeability thickness of 19,118 md-feet.

Copies of the pressure transient data and analyses were presented to EPA in previous reports and are available upon request.

### 7.3.2 Proposed CCS#5, CCS#6 and CCS#7 testing program

This section addresses the pre-operational testing proposed by ADM to ensure that sufficient characterization of the subsurface at CCS#5, CCS#6 and CCS#7 is performed and to satisfy Class VI regulations. These requirements include those addressed in Section 7.2 (e.g., injection and confining zone physical, chemical, and fluid characteristics) as well as fracture pressure determination and well testing located in §146.87(d)(1) and (e). ADM will provide 30-day notice of any logging or testing of the Class VI well to the Director so that the Director in order to provide the Agency the opportunity to witness such activities.

#### 7.3.2.1 Well Testing - Injection Zone

After CCS#5, CCS #6 and CCS#7 are cased, perforated, and fluid sampling has been complete, an SRT will be performed to obtain a confirmatory estimate of the fracture pressure of the injection zone. Subsequent wells will not be subjected to an SRT upon completion unless irregular data is obtained from the third injection well. It is noted that the existing Class VI program offers the following discussion regarding the use of additional site SRT data, and similar practices are proposed for new injectors:

Sensitive, Confidential, or Privileged Information

#### 7.3.2.2 Well Testing - Confining Zone

As discussed in Section 7.3.2.2, a "mini-frac" using the MDT tool was used to estimate the fracture gradient of the confining zone in CCS#1 and CCS#2. In addition, dipole sonic data are available through the confining zone to estimate the geomechanics. If the results of CCS#5, CCS#6 and CCS#7 geophysical well logging conducted through the confining zone indicate that conditions are similar to the results found using previous logging conducted at CCS#1 and CCS#2, then no additional testing of the confining zone is proposed for CCS#5, CCS #6 and/or CCS #7. Dipole sonic logs will be correlated to existing well logs with similar results and can also be used to infer the representativeness of the CCS#1 and CCS#2 MDT "mini-frac" results.

## 7.4 Injection and confining zone formation testing

CCS#5, CCS #6 and CCS #7 are new wells that may be installed at the site in the future and hence must comply with requirements at 40 CFR §146.87 (a), (b) and (e). Data obtained as part of previous injection and monitoring requirements at the site are relevant to data acquisition to be collected from any new site wells and are summarized in Tables 7.1.2-1, 7.1.2-2, and 7.1.2-3. Historic activities are summarized in Section 7.3.1, which supports the proposed data collection activities presented in Section 7.3.2 because a significant quantity of data has already been obtained to characterize the site during previous testing that supports the proposed CCS#5, CCS#6 and CCS#7 program.

## 7.5 Quality Assurance Surveillance Plan (QASP)

The QASP is provided in APPENDIX C: Quality Assurance and Surveillance Plan which meets relevant requirements under 40 CFR 146.90

# 8. Site Operating Plan

## 8.1 Injection rate

The CCS#5, CCS#6 and CCS#7 injection wells will be operated at rates that will result in an annual average injection rate of approximately 1.1 million MT/year per well. Injection is projected to begin in February, 2026.

The injection wells are intended to be operated continuously (24 hour per day, 7 days a week, and 365 days per year). The injection rate will vary between 0 and 3,050 MT for each well per day and may vary due to equipment maintenance, mechanical inspection, and testing subject to § 146.89 and § 146.90.

## 8.2 Maximum injection pressure

Except during stimulation, ADM will ensure that injection pressure does not exceed 90 percent of the fracture pressure of the injection zone(s) so as to ensure that the injection does not initiate new fractures or propagate existing fractures in the injection zone(s). In no case shall injection pressure initiate fractures or propagate existing fractures in the confining zone or cause the movement of injection or formation fluids into a USDW. The maximum injection pressure is included in Table 8.2-1 below.

**Table 8.2-1.** Well Operating Conditions

| PARAMETER/CONDITION | LIMITATION | UNIT |
|---|---|---|
| Maximum Injection Pressure - Surface | * | psig |
| Minimum Annulus Pressure | 100 | psig |
| Minimum Annulus Pressure/Tubing Differential (directly above and across packer) | 100 | psig |

*To be determined based on 0.6435 psi/ft multiplied by as-built depth.

The operational injection pressure is estimated to be between 2,100 and 2,300 psi. The higher pressure would be a result of lower Mt. Simon injectivity parameters. These pressure estimates are based on the design surface compression capacity of 3,050 MT per day/well.

## 8.3 $CO_2$ volume

The proposed sequestration site at the ADM facility will be supplied with $CO_2$ from ADM or 3rd party carbon capture systems, including but not limited to:

- Pre-combustion systems
- Oxy-combustion systems
- Post combustion systems
- $CO_2$ from ADM's various ethanol and cogeneration facilities, including but not limited to Decatur, IL; Clinton, IA; and Cedar Rapids, IA

The details of these $CO_2$ streams are presented in Section 8.6, $CO_2$ stream characteristics.

The CCS#5, CCS#6 and CCS#7 wells will be operated at a maximum daily injection rate of 3,050 MT/day per well and injection will result in an average annual average injection rate of approximately 1.1 million MT/year per well

from the above combined sources. Injection is expected to begin in February, 2026. The total injection volume over the life of CCS#5, CCS#6 and CCS#7 is expected to be at least 13.2 million MT/well.

## 8.4 Annulus pressure

### 8.4.1 Regulatory Requirements

Except during workovers or times of annulus maintenance, ADM will maintain on the annulus a pressure that exceeds the operating injection pressure as specified in 40 CFR 146.88(c), unless the Director determines that such requirement might harm the integrity of the well or endanger USDWs.

ADM will fill the annulus between the tubing and the long string casing in a liquid-filled condition using a non-corrosive fluid approved by the Director. As previously discussed in this document, an inhibited brine is to be used as the annulus fluid for the CCS#5, CCS#6, and CCS#7wells.

### 8.4.2 Casing, Tubing, Annulus Pressure, Average and Maximum

Because the injection tubing will be set in a packer above the injection interval within the Mt. Simon, the casing-tubing annulus space above the packer will be isolated from the $CO_2$ stream. A constant surface annulus pressure of 400 to 500 psig and at least 100 psig across the packer will be utilized during injection. The average and maximum annulus pressure are anticipated being about the same; however, fluctuations in pressure are anticipated from changes in ambient surface temperature and injection tubing pressure.

All other annulus spaces (one between surface casing and intermediate casing, and one between intermediate casing and long string casing) will have cement to surface. Consequently, the pressures of these annular spaces will be at atmospheric pressure at surface and will not be monitored.

## 8.5 Well stimulation procedures

### 8.5.1 Regulatory Requirements

This section is intended to address the standards presented in cited materials as follows:

“If well stimulation is planned, describe the stimulation fluids and procedures to ensure that stimulation will not fracture the confining zone, affect well integrity, or otherwise allow injection of formation fluids to endanger USDWs”. EPA Guidance “Underground Injection Control (UIC) Program Class VI Well Construction Guidance”, Section 4.1, provides supporting information.

- § Part 146.82(a)(9): [the owner or operator shall submit pursuant to §146.91(e), and the director shall consider the following:] Proposed stimulation program, a description of stimulation fluids to be used and a determination that stimulation will not interfere with containment.
- § 146.88 (a): Except during stimulation, the owner or operator must ensure that injection pressure does not exceed 90 percent of the fracture pressure of the injection zone(s) so as to ensure that the injection does not initiate new fractures or propagate existing fractures in the injection zones(s). In no case may injection pressure initiate fractures in the confining zones(s) or cause movement of injection or formation fluids that endangers a USDW.
- § 146.91 (d) (2) and (e): [Owners or operators must notify the director in writing 30 days in advance of]: Any planned stimulation activities, other than stimulation for formation testing conducted under § 146.82. (e): regardless of whether a state has primary enforcement responsibility, owners or operators

must submit all required reports, submittals, and notifications under subpart h of this part to EPA in an electronic format approved by EPA.

The purpose of this Section is to satisfy applicable regulatory requirements presented in § 146.82(a)(9), 146.88(a), and 146.91(d)(2). More specifically, the Section addresses a description of the proposed stimulation programs that may be implemented, a description of stimulation fluids that may be used, and a determination that stimulation plans will not interfere with containment. Because flexibility is required to ensure that the owner/operator may select an appropriate stimulation approach depending on conditions that may develop in the future and because EPA is required to review and approve these approaches prior to implementation, this plan includes multiple methodologies for EPA review and approval. The mandatory 30-day notice that will be provided by the operator in an electronic format and may include any of the described methods, depending upon circumstances, that would produce the desired outcome. By providing details about potential stimulation options as part of the permit application in a single plan, EPA is informed of the possible proposed approaches, and may review and approve them as part of the permit authorization, well in advance of any specific stimulation program proposal.

The purpose of any stimulation treatment is to enhance injectivity that is observed at initial conditions or remediate injection capacity restrictions that develop after a well is placed in service. Impediments to optimum injection capacity can be associated with native and induced flow path restricting materials, such as: clay fragments, mineral scales, metallic sulfide or oxide particulates, relative permeability blockages, oil emulsions, and other materials carried into the injection intervals or induced by the injected $CO_2$ or formed as a result of reactions within the formation.

Prior to completion of any new well or implementation of stimulation on an existing well, ADM will provide a 30-day notice of the specific stimulation methods proposed for completion of the new well based on conditions encountered during drilling and testing. After completion, if injection monitoring or analyses indicate a flow restriction that is either within the well bore or in the near well bore injection formation interval(s), ADM will provide specific proposed remedial stimulation actions with at least 30-days prior notice. The notifications will include the proposed operational tasks and method(s) that will be implemented to conduct stimulation, and the detailed chemical formulation (final selections and volumes) for stimulation when chemical stimulation is proposed.

### 8.5.2 Stimulation Programs or Methods and Description of Stimulation Fluids

#### 8.5.2.1 Chemical Stimulation Methods

Chemical stimulation methods can involve injection of fluids with no fluid recovery (i.e., Bullhead Stimulation), matrix treatment with fluid recovery, or direct chemical injection with the carbon dioxide injectate. The following sections describe these methods and present fluids that may be used as part of the described methods.

Bullhead Stimulation

Bullhead Stimulation is a stimulation method whereby fluids are injected to enhance injectivity or solubilize flow restrictions, with no fluid recovery. It can be accomplished in injection wells by pumping treatment fluids into an injection formation and ultimately displacing the treatment fluids or flushing them out of the wellbore and into the formation with no recovery back to surface. The chemical stimulant may be preceded by volumes of treated water or other fluids and subsequently followed by enough treated water to displace the stimulation chemicals into the injection zone. For the purpose of these proposed methods, treatment is conducted below the permitted bottom hole pressure for well operations so that no new fractures are created. The displacement may be in stages to allow the stimulation chemicals time to soak at the targeted depth. Variations for delivering the chemical treatment to the targeted intervals include:

- Pumping the chemicals and stimulants down the injection tubing. Site equipment or temporary pumping equipment may be used for injection.
- Placing the chemicals and stimulants at or near the targeted interval(s) by running coiled tubing inside of the injection tubing and pumping the chemicals through the coiled tubing. This option may also include using various nozzles on the coiled tubing string to jet water or chemicals at specific perforated intervals to enhance the chemical contact and mechanical washing.
- Pulling the injection tubing and running a work string or coiled tubing string to pump the chemicals to the targeted interval(s). This placement method may also include running isolation packers to focus the chemical injection on specific intervals.

Matrix Treatment with Fluid Recovery

Matrix treatment stimulation involves the injection of fluids to solubilize flow restrictions, as well as with reverse flow to recover spent chemicals and solubilized fines and other materials. Chemicals are pumped into the formation with all or partial recovery by flowing fluids back out of the well bore. This method is preferred when the treatment is expected to mobilize significant mass of particulates or solid materials that need to be removed from the formation porosity to optimize injection. The chemicals may be preceded by volumes of treated water and may be followed by additional volumes of treated water. In some cases where significant solids are present, initial treatment steps may involve attempts to recover solids from the well and near wellbore porosity by backflowing, jetting with coiled tubing, swabbing, or otherwise producing the well so that less treatment chemical is then required to address immobile plugging materials.

The same methods of placement listed in the bullets, above, under Bullhead Stimulation would be options for Matrix Treatment with fluid recovery. The principal recovery method would be to utilize the previously injected carbon dioxide as the media to flow the spent chemicals and flush water back out of the well. This would require installing temporary separation equipment at surface to flow the well back under controlled conditions and remove the particulate laden spent treatment fluids prior to venting the carbon dioxide.
If extensive fluid volumes are used, the well may be amenable to recovering fluid by:

- Swabbing of the well to recover the fluids that have been pumped down the injection string or a work string of jointed pipe.
- Jetting fluids out with nitrogen gas or carbon dioxide gas when working with coiled tubing or a work string.

Direct Chemical Injection with the Carbon Dioxide Injection

The introduction of solubilizing or scale prevention agents in a fluid system carried by the carbon dioxide injection fluid may be used to solubilize or prevent formation of materials that would impede injection flow paths. This method could be implemented on either a continuous or batch basis.
Direct chemical injection with carbon dioxide injection would be appropriate when it is necessary to dissolve minor amounts of particulates or to introduce scale inhibitors into the injection intervals. Chemicals are typically not recovered.

Description of Fluid System Components that may be Proposed for Chemical Stimulation.

Proposed chemical stimulation formulations may contain a variety of primary fluids and additives to address various conditions that might be encountered. When new well completion or remediation requirements are identified and vendors are selected, specific fluid details, including concentrations and volumes, will be provided

with the 30-day notice. Treatment chemicals and additives would be expected to include one or more of the following chemical agents or categories, or suitable equivalents:

1. Inorganic acid solutions such as:
    - hydrochloric acid
    - hydrofluoric acid in combination with hydrochloric acid

2. Inorganic basic solutions such as:
    - sodium hydroxide
    - ammonium solutions and conjugal salts there of
    - sodium hypochlorite solutions and conjugal salts there of

3. Oxidizing agents such as:
    - Sodium hypochlorite solutions
    - Chlorine dioxide solutions
    - Sodium chlorite solutions
    - Sodium chlorate solutions

4. Organic acids such as
    - Citric acid
    - Acetic acid
    - Formic acid
    - Sulfamic acid

5. Combinations of inorganic and organic acids as listed in 1. Inorganic acid solutions and 4. Organic acids

6. Alternating stages of acids listed in 1. Inorganic acid solutions or 4. Organic acids or both with oxidizers listed in 3. Oxidizing agents.

7. Chelating agents, as a direct treatment chemical or in combination with acids listed in 1. Inorganic acid solutions and/or 4. Organic acids, such as:
    - Citric acid and salts thereof
    - Acetic acid and salts thereof
    - Nitrilotriacetic acid (NTA)
    - Ethylene diamine tetra-acetic acid, EDTA
    - Hydroxyl ethylene diamine triacetic acid, HEDTA
    - Glutamic acid-N,N-diacetic acid, GLDA
    - Tetrakis(hydroxymethyl)phosphonium sulfate, THPS

8. Acid inhibitors, particularly in common with acids listed in 1. Inorganic acid solutions. There are numerous commonly utilized chemical additives applied to minimize the corrosion of metal well components. Some general categories are:
    - Quaternary amine compounds
    - Imadazoline compounds
    - Pyridine compounds
    - And many others
9. Surfactants, in common with acids listed in 1. Inorganic acid solutions, bases listed in 2. Inorganic basic solutions, and organic acids listed in 4. Organic acids.
10. Organic solvents to mitigate hydrocarbon contamination that could inhibit acid penetration, such as:
    - Xylene
    - Toluene
    - Naphtha
    - Terpenes
11. Mutual solvents to enhance the dispersion and effectiveness of any organic solvents that are applied, such as
    - Ethylene Glycol MonoButyl Ether, EGMBE
    - Various alcohols
12. Scale inhibitors to reduce scale formation from reactions with the fluids introduced during the stimulation or from the subsequent $CO_2$ injection. There are many specifically designed scale inhibitor chemistry formulations that might be applied depending on the expected scaling potential. The two primary general categories are:
    - Polymeric – typically long chain polymers with carboxylic or acrylic functional groups
    - Phosphonate - organic phosphorous bearing compounds that are specifically designed and fabricated to prevent scale formation
13. Clay stabilizers – salts or chemicals specifically applied to prevent the native clays in the formation from fragmenting and releasing pore blocking particulates. Examples include:
    - Inorganic salts, particularly potassium chloride, sodium chloride, calcium chloride, ammonium chloride, and magnesium chloride; but other salts might be used.
    - Temporary clay stabilizers; typically, organic amine type compounds with relatively low molecular weight intended to bind with ion-exchange sites on the clays to prevent the clays from fragmenting. Examples include:
        - Tetramethylammonium chloride, TMAC
        - Choline chloride

  - Other substances that are utilized to stabilize clays to prevent damage through ion-exchange induced clay fragmentation

- Permanent clay stabilizers; typically, long chain cationic or nonionic polymers that bridge across multiple ion-exchange sites on the clay structure to provide longer term fragmentation prevention. There are many polymeric chemistries applied for this purpose, with polyamines being one common example.

14. Diverting agents – materials used to temporarily block off intervals that retain high injectivity so that stimulation chemicals are focused into intervals that are less permeable or more impaired. These might include:

    - Rock salt; conveyed into the well bore as a slurry with the salt crystals suspended in salt brine. The salt brine may be treated with gelling agents such as guar polymer or xanthan gum to produce higher viscosity and salt carrying capacity.
    - Water soluble solids with low acid solubility, such as benzoic acid flakes, encapsulated citric acid, or other bridging agents that can be dissolved after stimulation chemical placement is completed by flushing with water or injected carbon dioxide.
    - Soluble ball sealers that are made of materials that will dissolve over time in carbon dioxide solution or injected water and/or brine.
    - Insoluble rubber ball sealers that would need to be removed from the well through flow back or other mechanical methods for recovery.
    - Polymeric substances that are formulated to provide temporary restrictions and then “break down” or dissolve with time and temperature.

15. Biologic control agents, or biocides. When large volumes of flush water are used before or after a chemical stimulation, treatment of the fluids to prevent contaminating the well bore with undesirable microbes may be appropriate. Numerous chemical alternatives are available as EPA registered biocides and may be used as additives to reduce undesirable biological activity. A few examples are:

    - Quaternary amine compounds,
    - Sodium hypochlorite,
    - Chlorine dioxide,
    - Dazomet, and
    - Other alternatives, depending on the anticipated microbial control requirement and confirmation that the biocidal agent(s) are compatible with the proposed chemical stimulation.

8.5.2.2 Mechanical Stimulation Methods

In addition to chemical stimulation, mechanical stimulation of the well may be pursued independently, or in concert with the chemical methods described earlier in this section. Mechanical methods that might be used include perforation, propellant stimulant, and backflow methods as described below.

Perforation

Perforation or re-perforation, with or without supplemental propellant assistance may be proposed during initial completion and remedial stimulation operations. Initial well completions will commonly incorporate perforations to connect the well bore to the targeted injection intervals. In some cases, ADM may propose to utilize

propellant assisted perforating tools to enhance the connectivity through the steel casing and cement sheath to the formation. Analytical data may indicate near-wellbore flow restrictions that are best remediated with mechanical penetration. Any re-perforating, with or without propellant assistance, will be proposed to EPA with detailed procedures in the 30-day advance notification.

Propellant assistance is accomplished by various suppliers using slightly different methods to obtain the same basic objective, i.e., to provide a short duration, high energy gas pulse to further extend the perforation tunnels created by the shape charges. (Enhanced Energetics Kraken-enhanced Perforating Flow Performance Tests, API RP19B Section 4 Test Results – 2020, Appendix E).

Propellant Stimulation

Propellant stimulation may be used to induce or enhance flow paths in the injection zone, with flow paths confined to approximately the height of the propellant gun. Direct propellant stimulation may be proposed to create flow paths through the damaged or restricted formation sections. This may be particularly effective when analytical data indicate that flow restriction extends past the wellbore face or the initial perforation channel to moderate depths into the formation, (i.e.,5 to 15 feet). Various studies and modeling efforts have been performed by private and governmental agencies to confirm that propellant stimulations create or stimulate flow paths into the targeted formation intervals with nominal vertical growth; verifying that there is no risk of confinement layer breach when guns depths are restricted to appropriate distances below the top of the injection zone. (Appendix E: SPE 8934 1980; Enhanced Energetics – Gas Gun – Vertical Containment, (undated); Letter of Determination, Natural Resources Agency of California Department of Conservation, Division of Oil, Gas, & Geothermal Resources, Dated 4/12/2019).

Deployment for initial perforation, re-perforation, re-perforation with propellant assistance, or propellant stimulation alone is commonly done with conventional electric line, coiled tubing e-line, and/or jointed tubing conveyed methods. Any of these methods might be proposed depending upon the scope of the stimulation and well operating conditions. When performing remedial work, the stimulation might be performed with the well full of liquid kill weight fluid or with the well full of injected carbon dioxide.

Backflow

Fluids can be produced from an injection well by backflow (also referred to as flow back), used to reverse the direction of flow, thereby mobilizing fines that are plugging near wellbore pore spaces and perforation channels. This material can then settle into the rathole below the completion, or some minor smaller particulate may be produced back to surface if sufficient energy is available to overcome well hydrostatics and friction to sustain velocity needed to carry solids back to the surface.

To backflow a $CO_2$ injector, safety issues associated with a controlled $CO_2$ release from the wellhead to the atmosphere will be addressed and the wellhead area prepared for operations. Preparations will include assessment of: wellhead temperature and pressure, weather, and air quality monitoring; communications; PPE; and suitable exclusion areas. After equipment is tested and necessary monitoring is enabled, valves at the wellhead are opened to allow $CO_2$ to be produced from the well, thereby reversing flow direction from the injection reservoir downhole. Controlled $CO_2$ production will be monitored to ensure safe production operations and to allow the calculation of the volume of $CO_2$ produced. At the end of the proscribed production period (15 to 30 minutes), valves will be closed slowly in stages to manage temperature effects and minimize the potential for shocks to the well from instantaneous shut-in.

An example well flow back procedure maintenance that has previously been provided by ADM to EPA is attached in Appendix E. This is provided as an example only and will be customized for each proposed flow back operation or use of flow back in conjunction with other stimulation methods. Other types of stimulation notices will include similar detailed plans for the proposed activities.

Well flowback operations may be followed by mechanical methods of solids removal from the rathole, such as jetting with coiled tubing, that will also be detailed in the 30- day notification to EPA.

Other Activities

All the above methods may be proposed to enhance original injectivity upon the initial well completion and may also be used to remediate injectivity restrictions. When injection rates vs injection pressure is below expectations, EPA will be notified when the operator proposes to investigate injection restrictions using common physical and analytical methods such as:

- Collecting bottom hole samples with sampling equipment conveyed into the well bore by wireline, slickline, or coiled tubing, with follow up analytical testing as appropriate for the sample and treatments under consideration,
- Performing injection profile logging activities with thermal measurement instruments, acoustic measurements instruments, or mechanical spinner tools to pinpoint the focus intervals for the stimulation, and
- Injection and fall-off testing to assess overall skin damage.

Standard procedures will be followed with respect to job safety and monitoring for all field operations. The 30-day notice to EPA for proposed operations will include:

- Listing of pre-job planning and assignments,
- Methods and practices for well control to prevent uncontrolled emissions or loss of well control,
- Methods for estimating, recording, and reporting any controlled emissions,
- When the proposed action involves ceasing injection and performing maintenance activities, the detailed work procedures will include:
  - approaches for shutting-in and securing the well for the proposed activities
  - specific actions to be performed
  - detail of all chemicals and concentrations that will be applied
  - detail for all tools, such as propellant enhanced perforating guns, coiled tubing equipment with jetting type wash nozzle, etc. that may be utilized
  - procedures to secure the well after stimulation activities
  - any post stimulation evaluation procedures that are proposed
  - procedures to return the well to injection service after stimulation
- When stimulation is proposed while the well is still injecting, the notice will include
  - detail for all chemicals and concentrations that will be applied
  - monitoring and control mechanisms that will be utilized to perform the chemical injection

  - methods to evaluate the chemical performance and adjust chemical dosing, as appropriate and,
- Job specific personnel training requirements.

The flow back maintenance procedure in Appendix E provides an example of the prior planning, well control procedures, and other job specific safety and environmental protection control practices that will be detailed and employed with all stimulation activities. Such safety plans are not considered UIC permit requirements, but are provided herein for general informational purposes. These procedures are subject to change without advanced notice based on vendors selected to complete various field operations, the type of field actions undertaken to accomplish well stimulation, and the nature of potential chemical and physical hazards identified for personnel.

### 8.5.3 Determination that Stimulation will not Interfere with Containment

Stimulation of the permitted injection interval will take place at depths below the top of the permitted injection interval and are not projected to have an impact on the confining layer. Mechanical operations such as perforating will be vertically separated from the casing at the top of the permitted injection zone by a minimum of 10 feet. Chemical additives will be injected into perforations below the base of the confining zone and will not be in contact with the rock matrix above the base of the confining zone formations. This will be accomplished by injecting limited treatment volumes at controlled pressures.

Routine chemical stimulation will be conducted at sustained bottom hole pressures that remain below 90% of the established fracture initiation pressures for the well/interval being stimulated. This practice will satisfy the requirement that “In no case may injection pressure initiate fractures in the confining zones(s) or cause movement of injection or formation fluids that endangers an Underground Source of Drinking Water USDW” [40 CFR Part 146.88(a)].

Stimulation chemical treatments will be conducted in a manner to ensure that chemical treatments are isolated to the injection interval. For example:

- When treating through either the injection tubulars or a work string, the annular pressure will be monitored to confirm that chemicals are contained below the upper packer or other down hole isolation tools.

- All chemical treatments will be selected for chemical compatibility with the placement method. For example, mineral acids will be treated with chemical inhibitors to prevent any significant corrosion damage to the tubing string that conveys the chemical. In addition, chemical systems will be selected to avoid damage to the down hole packer sealing elements and other seals within the injection system that might be exposed to the chemicals.

Propellant stimulations will only be utilized well below the top of the injection zone. Established studies indicate that propellant stimulations have only nominal height growth above the propellant tool depth so restricting the use of propellant well below the top of the injection interval will assure that no fractures are created into the confining layer.

## 8.6 $CO_2$ stream characteristics

The injection stream is high purity $CO_2$ with trace levels of other constituents. The details of these $CO_2$ streams are presented in the tables below.

**Table 8.6-1.** $CO_2$ Stream Characteristics

| Component | Wt. % |
|---|---|
| Carbon Dioxide | > 93.8% |
| Nitrogen | < 4.0% |
| Oxygen | < 1.0% |
| Water | < 250 ppmw |
| Hydrocarbons | < 5.0% |
| Sulfur Species | Report |

The $CO_2$ streams included in this application are typically greater than 95.0% pure $CO_2$. It is saturated with water vapor at 100°F and at slightly greater than atmospheric pressure. Common impurities (in amounts typically less than 200 ppm by volume) are carbon monoxide, methanol, ethanol, acetaldehyde, oxides of nitrogen, and hydrogen sulfide.

## 8.7 Injection Well Operating Requirements

ADM will install, continuously operate, and maintain an automatic alarm and an automatic shut-off system or, at the discretion of the Director, down-hole shut- off systems, or other mechanical devices that provide equivalent protection; and successfully demonstrate the functionality of the alarm system and shut-off system prior to the Director authorizing injection, and at a minimum of once every twelfth month after the last approved demonstration.

Testing to demonstrate functionality will involve subjecting the system to simulated failure conditions. ADM will provide notice in an electronic format 30 days prior to running the test and will provide the Director or their representative the opportunity to attend. The test will be documented using either a mechanical or digital device which records the value of the parameter of interest, or by a service company job record. A final report including any additional interpretation necessary for evaluation of the testing will be submitted.

The injection well operating requirements are previously covered in Sections 8.1, 8.2, and 8.4.

### 8.7.1 Precautions to Prevent Well Blowouts

ADM will maintain on the well a pressure which will prevent the return of the injection fluid as specified in Section 8.4 to the surface. The well bore will be filled with a high specific gravity fluid during workovers to maintain a positive (downward) gradient and/or a plug shall be installed which can resist the pressure differential. A blowout preventer will be installed and kept in proper operational condition whenever the wellhead is removed to work on the well. ADM will follow procedures such as those below to assure that a backflow or blowout does not occur:

- Limit the temperature and/or corrosivity of the injectate; and
- Develop procedures necessary to assure that pressure imbalances do not occur.

### 8.7.2 Circumstances Under Which Injection Must Cease

Injection will cease when any of the following circumstances arises:

1. Failure of the well to pass a mechanical integrity test;

2. A loss of mechanical integrity during operation;

3. The automatic alarm or automatic shut-off system is triggered;

4. A significant unexpected change in the annulus or injection pressure;

5. The Director determines that the well lacks mechanical integrity; or

6. ADM is unable to maintain compliance with any permit condition or regulatory requirement and the Director determines that injection should cease.

If any of the above circumstances arise, ADM will immediately cease injection and shut-in the well as outlined in Section 12. Emergency and Remedial Response Plan.

# 9. Testing and Monitoring Plan

This Testing and Monitoring Plan describes how ADM will monitor the CCS#1- CCS#7 site pursuant to 40 CFR 146.90. In addition to demonstrating that the well is operating as planned, the carbon dioxide plume and pressure front are moving as predicted, and that there is no endangerment to USDWs, the testing and monitoring data will be used to validate and adjust the geological models used to predict the distribution of the $CO_2$ within the storage zone to support AoR reevaluations and a non-endangerment demonstration to support closure.

## 9.1 $CO_2$ stream analysis

ADM will analyze the $CO_2$ stream during the operation period to yield data representative of its chemical and physical characteristics and to meet the requirements of 40 CFR 146.90(a). Sampling will take place each calendar quarter. ADM will analyze each $CO_2$ gas stream for the constituents identified in Table 9.1-1 using the methods listed.

**Table 9.1-1.** Summary of analytical parameters for $CO_2$ gas streams

| Parameters | Analytical Methods (1) |
|---|---|
| **Oxygen** | ISBT 4.0 (GC/DID)<br>GC/TCD |
| **Nitrogen** | ISBT 4.0 GC/DID<br>GC/TCD |
| **Carbon Monoxide** | ISBT 5.0 Colorimetric<br>ISBT 4.0 (GC/DID) |
| **Oxides of Nitrogen** | ISBT 7.0 Colorimetric |
| **Total Hydrocarbons** | ISBT 10.0 THA (FID) |
| **Methane** | ISBT 10.1 GC/FID) |
| **Acetaldehyde** | ISBT 11.0 (GC/FID) |
| **Sulfur Dioxide** | ISBT 14.0 (GC/SCD) |
| **Hydrogen Sulfide** | ISBT 14.0 (GC/SCD) |
| **Ethanol** | ISBT 11.0 (GC/FID) |
| **Carbon Dioxide** | ISBT 2.0 Caustic absorption Zahm-Nagel<br>ALI method SAM 4.1 subtraction method (GC/DID)<br>GC/TCD |

### 9.1.1 Sampling Methods

$CO_2$ stream sampling will occur in the compressor building after the last stage of compression and prior to flowline conveyance to the injection wellhead. A sampling station will be installed with the ability to purge and collect samples into a container that will be sealed and sent to the authorized laboratory.

All sample containers will be labeled with durable labels and indelible markings. A unique sample identification number and sampling date will be recorded on the sample containers.

### 9.1.2 Laboratory to be Used/Chain of Custody Procedures

Samples will be analyzed by a third-party laboratory using standardized procedures for gas chromatography, mass spectrometry, detector tubes, and photo ionization. The sample chain-of- custody procedures described in Section B.3 of the QASP will be employed.

## 9.2 Mechanical integrity and corrosion testing

To meet the requirements of 40 CFR 146.90(c), ADM will monitor well materials during the operation period for loss of mass, thickness, cracking, pitting, and other signs of corrosion at surface to ensure that the well components meet the minimum standards for material strength and performance. This monitoring will occur once per calendar quarter. ADM will monitor corrosion using the corrosion coupon method and collect samples according to the description below.

### 9.2.1 Sample Description

Samples of material used in the construction of the compression equipment, pipeline and injection well which come into contact with the $CO_2$ stream will be included in the corrosion monitoring program either by using actual material and/or conventional corrosion coupons. The samples consist of those items listed in Table 9.2.1-1 below. Each coupon will be weighed, measured, and photographed prior to initial exposure (see "Sample Handling and Monitoring" below).

**Table 9.2.1-1.** List of Equipment Coupon with Material of Construction.

| Equipment Coupon | Material of Construction |
|---|---|
| Pipeline | CS A106B |
| Long String Casing (Surface - 4,800') | Carbon Steel |
| Long String Casing (4,800' – TD) | Chrome Alloy |
| Injection Tubing | Chrome alloy |
| Wellhead | Chrome alloy |
| Packers 1 | Chrome alloy |

### 9.2.2 Sample Exposure

Each sample will be attached to an individual holder (Figure 1a) and then inserted in a flow- through pipe arrangement (Figure 1b). The corrosion monitoring system will be located downstream of all process compression/dehydration/pumping equipment (i.e., at the beginning of the pipeline to the wellhead). To accomplish this, a parallel stream of high-pressure $CO_2$ will be routed from the pipeline through the corrosion monitoring system and then back into a lower pressure point upstream in the compression system. This loop will operate any time injection is occurring. No other equipment will act on the $CO_2$ past this point; therefore this location will provide sufficiently representative exposures of the samples to the $CO_2$ composition, temperature, and pressures that will be seen at the wellhead and injection tubing. The holders and location of the system will be included in the pipeline design and will allow for continuation of injection during sample removal.



**Figure 1a.** Coupon Holder




**Figure 1b.** Flow-through Pipe Arrangement.

### 9.2.3 Sample Handling and Monitoring

The coupons will be handled and assessed for corrosion using the American Society for Testing and Materials (ASTM) G1-03, Standard Practice for Preparing, Cleaning, and Evaluating Corrosion Test Specimens (ASTM 2011). The coupons will be photographed, visually inspected with a minimum of 10x power, dimensionally measured (to within 0.0001 inch), and weighed (to within 0.0001 gm).

### 9.2.4 Mechanical Integrity Testing

Mechanical integrity testing will be conducted consistent with requirements at 40 CFR 146.90(e) and 146.89(c), which state that once per year until CCS#5, CCS#6 and CCS#7 are plugged, the operator will perform an approved tracer survey such as an oxygen-activation log or a temperature or noise log. In addition, these regulations discuss casing inspection logs to be performed if required by the Director at a frequency specified in the Testing and Monitoring Plan. Casing inspection logs are proposed to be run during a well workover when the tubing is pulled from the well. Annual external mechanical integrity testing will be consistent with methods described in Section 7.1.2.3 and Table 7.1.2-3.

## 9.3 Pressure fall-off testing

ADM will perform pressure fall-off tests during the injection phase as described below to meet the requirements of 40 CFR 146.90(f).

At a minimum, pressure fall-off testing will be performed:

- During injection in year 5 of operation; and
- At least every 5 years during the remainder of the injection period.

ADM will conduct pressure fall-off testing according to the procedures below.

### 9.3.1 Pressure Fall-off Test Procedure

Each pressure falloff test will include a period of injection followed by a period of no-injection or shut-in. Normal injection using the stream of $CO_2$ captured from the ADM facility will be used during the injection period preceding the shut-in portion of the falloff tests. The normal injection rate is estimated to be maximum 3,050 MT/day for wells CCS#5, CCS#6 and CCS#7. Prior to the falloff test, a constant rate will be maintained. If this rate causes relatively large changes in bottomhole pressure, the rate may be decreased. Injection will have occurred

at previously approved, neighboring CCS wells for multiple years prior to this test, but there may have been injection interruptions due to operations or testing. At a minimum, one week of relatively continuous injection will precede the shut-in portion of the falloff test; however, several months of injection prior to the falloff will likely be part of the pre- shut-in injection period and subsequent analysis. This data will be measured using a surface readout downhole gauge so a final decision on test duration can be made after preliminary evaluation of the data takes place. The gauges may be those used for day-to-day data acquisition or a pressure gauge will be conveyed via electric line (e-line).

To reduce the wellbore storage effects attributable to the pipeline and surface equipment, the well will be shut-in at the wellhead nearly instantaneously with direct coordination with the injection compression facility/pipeline operator. Because surface readout will be used and downhole recording memory restrictions will be eliminated, data will be collected at five second intervals or more frequently for the entire test. The shut-in period of the falloff test will be at least 48 hours or longer until adequate pressure transient data are collected to allow meaningful interpretation of the data. Because surface readout gauges will be used, the shut-in duration can be determined in real-time. A report containing the pressure falloff data and interpretation of the reservoir ambient pressure will be submitted to the permitting agency within 30 days of the test. Pressure sensors used for this test will be the wellhead sensors and a downhole gauge for the pressure falloff test. Each gauge will be of a type that meets or exceeds ASME B 40.1 Class 2A (0.5% accuracy across full range). Wellhead pressure gauge range will be 0-4,000 psi. Downhole gauge range will be 0-10,000 psi.

## 9.4 Groundwater quality monitoring

The purpose of the groundwater monitoring plan is to evaluate potential carbon dioxide ($CO_2$) migration and/or native fluid displacement from the injection zone or other water quality changes that may lead to endangerment of USDWs. ADM will monitor three separate zones during operation to meet the requirements of 40 CFR 146.90(d).

### 9.4.1 Identification of Monitored Intervals

The groundwater monitoring plan for the CCS#1-CCS#7 area focuses on the following zones:

- Quaternary and/or Pennsylvanian strata – the source of local drinking water.
- The St. Peter Formation – the lowermost USDW.
- The Ironton-Galesville Sandstone – the zone above the Eau Claire confining zone.

The above zones shall be monitored in conjunction with approved Testing and Monitoring Plans for CCS#1, CCS#2, and proposed CCS#3, CCS#4, CCS#5, CCS#6 and CCS#7. Of the above listed formations, the St. Peter Formation and Ironton-Galesville Sandstone will be monitored at CCS#5, CCS#6 and CCS#7. ADM operates four shallow monitoring wells, two geophysical monitoring wells, and two injection zone verification wells in association with CCS#1 and CCS#2. These wells were included in the approved testing and monitoring program for completeness. Additional geophysical monitoring and additional verification wells are proposed in association with CCS #3, CCS #4, CCS#5, CCS #6 and CCS #7. Additional verification wells VW#4 and VW#5 are proposed in association with the CCS#5, CCS#6 and CCS#7 area. All geophysical monitoring (GM) wells will be located approximately 150-200 feet from the proposed injection wells. All of the existing and proposed monitoring locations are located on ADM property, or property leased by ADM.

Table 9.4.2-1 and Table 9.4.3-1 show the planned direct and indirect monitoring methods, locations, and frequencies for groundwater quality monitoring above the confining zone. ADM will also monitor in the Mt. Simon

Sandstone (the injection zone). Monitoring in this layer will be to track the $CO_2$ plume and is described in Section 9.5.

### 9.4.2 Direct Monitoring Methods

ADM will employ direct monitoring methods such as pressure and temperature monitoring and fluid sampling on a monthly or annual basis. Table 9.4.2-1 summarizes the planned locations and frequencies of all applicable direct monitoring methods. Note that the depths presented are estimates of depth below mean sea level (presented as positive values) and will be revised to reflect actual formation depths upon drilling.

**Table 9.4.2-1.** Summary of Direct Monitoring Methods

| Target Formation | Monitoring Activity | Monitoring Location(s) | Spatial Coverage | Frequency |
|---|---|---|---|---|
| Sensitive, Confidential, or Privileged Information | Fluid Sampling | Sensitive, Confidential, or Privileged Information | | Baseline; Quarterly during Year 1 & 2; Semi-annual thereafter |
| | Temperature Monitoring (DTS) | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | Fluid Sampling | | | |
| | | | | Baseline; Annual |
| | | | | Baseline; Annual |
| | | | | Baseline; Annual |
| | | | | Baseline; Annual |
| | | | | Baseline; Annual |
| | | | | Baseline; Annual |
| | | | | Monthly |
| | | | | Monthly |

| Target Formation | Monitoring Activity | Monitoring Location(s) | Spatial Coverage | Frequency |
|---|---|---|---|---|
| Sensitive, Confidential, or Privileged Information | | Sensitive, Confidential, or Privileged Information | | Monthly |
| | | | | Monthly |
| | | | | Monthly |
| | | | | Monthly |
| | Temperature Monitoring (DTS) | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | Pressure Monitoring | | | Monthly |
| | | | | Monthly |
| | | | | Monthly |
| | | | | Monthly |
| | | | | Monthly |
| | Temperature Monitoring (DTS) | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | Fluid Sampling | | | Baseline; Annual |
| | | | | Baseline; Annual |
| | | | | Baseline; Annual |
| | | | | Baseline; Annual |
| | | | | Baseline; Annual |

Notes:

* indicates applicable if the proposed well is drilled in the future. Sample location is to be considered only an estimate at this time based on general offset information, and is highly likely subject to change after drilling.
**Continuous temperature and pressure monitoring (DTS) will be satisfied with a minimum 5-minute sampling and at least hourly recording. If the continuous monitoring is unavailable, the well can continue to operate by performing pressure and temperature monitoring every 4 hours.

### 9.4.3 Indirect Monitoring Methods

ADM will continue to employ indirect monitoring methods such as wireline logging and seismic monitoring. Table 9.4.3-1 summarizes the planned locations and frequencies of all applicable indirect monitoring methods.

**Table 9.4.3-1.** Summary of Indirect Monitoring Methods

| Target Formation | Monitoring Activity | Monitoring Location(s) | Spatial Coverage | Frequency |
|---|---|---|---|---|
| Sensitive, Confidential, or Privileged Information | Pulse Neutron/RST Logging | Sensitive, Confidential, or Privileged Information | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | Pulse Neutron/RST Logging | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | Pulse Neutron/RST Logging | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |

| Target Formation | Monitoring Activity | Monitoring Location(s) | Spatial Coverage | Frequency |
|---|---|---|---|---|
| | | Sensitive, Confidential, or Privileged Information | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | | | | Baseline, Bi-Annual |
| | Passive seismic | | | Continuous**; processed monthly |
| | Time-lapse 3D surface seismic | | | 5-Year |

Notes:
* indicates applicable if the proposed well is drilled in the future. Sample location has been estimated based off offset information and is subject to change after drilling
**Continuous recording of passive seismic data is processed on a monthly basis to determine if seismic events over M1.0 occurred within the AoR. The passive seismic monitoring system at borehole and surface seismic stations is owned and operated by USGS.

### 9.4.4 Analytical and Field Parameters for Groundwater Samples

Sampling will be performed as described in Section B.2 of the Quality Assurance Sampling Plan (QASP); this section of the QASP describes the groundwater sampling methods to be employed, including sampling SOPs (Section B.2.a/b), and sample preservation (Section B.2.g). Sample handling and custody will be performed as described in Section B.3 of the QASP. Quality control will be ensured using the methods described in Section B.5 of the QASP. Table 9.4.4-1 presents a summary of analytical parameters and proposed analytical methods.

**Table 9.4.4-1.** Summary of Fluid Sampling Constituents and Analytical Methods

| Target Formation | Parameters | Analytical Methods [1] |
|---|---|---|
| Sensitive, Confidential, or Privileged Information | **Cations:** Ca, Fe, K, Mg, Na, and Si | ICP-OES, EPA Method 6010B |
| | **Anions:** Br, Cl, F, NO3, and SO4 | Ion Chromatography, EPA Method 300.0 |
| | **Dissolved $CO_2$** | Coulometric titration, ASTM D513-11 |
| | **Total Dissolved Solids** | Gravimetry; APHA 2540C |
| | **Alkalinity** | APHA 2320B |
| | **pH (field)** | EPA 150.1 |
| | **Specific conductance (field)** | APHA 2510 |
| | **Temperature (field)** | Thermocouple |
| | **Cations:** Ca, Fe, K, Mg, Na, and Si | ICP-OES, EPA Method 6010B |
| | **Anions:** Br, Cl, F, NO3, and SO4 | Ion Chromatography, EPA Method 300.0 |
| | **Dissolved $CO_2$** | Coulometric titration, ASTM D513-11 |
| | **Isotopes:** δ13C of DIC | Isotope ratio mass spectrometry |
| | **Total Dissolved Solids** | Gravimetry; APHA 2540C |
| | **Water Density (field)** | Oscillating body method |
| | **Alkalinity** | APHA 2320B |
| | **pH (field)** | EPA 150.1 |
| | **Specific conductance (field)** | APHA 2510 |
| | **Temperature (field)** | Thermocouple |
| | **Cations:** Ca, Fe, K, Mg, Na, and Si | ICP-OES, EPA Method 6010B |
| | **Anions:** Br, Cl, F, NO3, and SO4 | Ion Chromatography, EPA Method 300.0 |
| | **Dissolved $CO_2$** | Coulometric titration, ASTM D513-11 |
| | **Isotopes:** δ13C of DIC | Isotope ratio mass spectrometry |
| | **Total Dissolved Solids** | Gravimetry; APHA 2540C |
| | **Water Density (field)** | Oscillating body method |
| | **Alkalinity** | APHA 2320B |
| | **pH (field)** | EPA 150.1 |
| | **Specific conductance (field)** | APHA 2510 |
| | **Temperature (field)** | Thermocouple |

Note 1: ICP = inductively coupled plasma; MS = mass spectrometry; OES = optical emission spectrometry; GC-P = gas chromatography - pyrolysis. An equivalent method may be employed with the prior approval of the UIC Program Director.

## 9.5 $CO_2$ plume and pressure front tracking

### 9.5.1 Direct Monitoring Methods

Monitoring of Temperature and Pressure

In-situ pressure measurements will be recorded in all active injection wells. Pressure data will be collected via downhole pressure gauges located near the base of the Eau Claire Formation (the confining zone) in addition to the Ironton-Galesville Sandstone located directly above the Eau Claire formation. Temperature will be monitored in all active injection wells throughout each wellbore. This monitoring will be conducted for as long as remains practical utilizing a fiber-optic, dynamic temperature survey (DTS) to be installed during the installation of each well.

Significant variance between actual measured and predicted pressure/temperature (P/T) data will indicate that a re-calibration of the numerical model is warranted. Review and revisions to the model and subsequently the area of review (AoR) and the monitoring program supported by simulations generated with the model will be conducted on a minimum frequency of once every 5-years during operations to incorporate any subsequent changes in model predictions.

Justification for the Verification Well Program

Figure 9.5.1-1 presents the proposed CCS #5-#7 monitoring locations relative to the projected plume boundary of the CCS #5-7 system. Figure 9.5.1-2 shows the wells superimposed on a satellite image for reference. The locations of VW#4 and VW #5 were selected based on the regulatory guidelines described below.

1. With regard to up-gradient orientation, current modeling indicates that up-gradient gravity effects are not significant enough to meaningfully influence plume drift during the operational period (Figure 9.5.1-3 presents the extent of the $CO_2$ plume growth at specified time horizons). Direct monitoring in VW#4 and VW #5, in addition to the proposed indirect seismic methods, should provide sufficient verification of plume behavior in directions that are not directly monitored via fluid sampling.

2. Based on Figure 9.5.1-3, the $CO_2$ plume is predicted to eclipse the proposed VW #4 and VW #5 locations late in the operational period. Pressure impacts will be measurable much earlier than any groundwater concentration changes, and collection of both pressure and sampling data will enable the initial model to be calibrated over the course of operations to conform with direct monitoring measurements.

3. The current orientation of VW #4 and VW #5 allow for direct monitoring along an approximate SW-NE axis. Due to the radial behavior of the $CO_2$ plume, arrival in VW #4 and VW #5 at close to the same point time extends a high degree of confidence to modeled plume behavior along a NW-SE azimuth.

In addition to satisfying general regulatory guidelines and technical objectives, the selected locations of VW#4 and VW#5 offer suitable surface access for drilling, testing and future maintenance/workover operations. Based on the limited extent of post-operational plume migration, the proposed 2-well VW network will provide both spatial and temporal confirmation of plume and pressure development within the CCS #5-7 system.





**Figure 9.5.1-1.** Orientation of ADM Injection and Monitoring Wells (Coordinate View)




**Figure 9.5.1-2.** Orientation of ADM Injection and Monitoring Wells (Surface View)





**Figure 9.5.1-3**. Proposed Verification Well Proximity to Projected Plume Arrival

Annual Fluid Sampling

Following baseline fluid sampling and analysis, fluid sampling will be conducted on an annual basis in all monitoring-verification wells. Initial samples will be taken via packer-isolated sliding sleeves located adjacent to the Ironton-Galesville Sandstone or suitable equivalent method if complications are encountered with the equipment and within the Mt. Simon Formation below the lower-most packer. Each sample interval will be analyzed for the constituents listed in Table 9.5.2-1 to document baseline fluid chemistry and to detect changes in fluid chemistry that could result from the movement of brine or $CO_2$ from the storage interval through the overlying confining zone and other formation.

**Table 9.5.2-1**. Summary of Fluid Sampling Constituents and Analytical Methods

| Parameters | Analytical Methods [(1)] |
|---|---|
| **Cations:**<br>Ca, Fe, K, Mg, Na, and Si | ICP-OES,<br>EPA Method 6010B |
| **Anions:**<br>Br, Cl, F, NO3, and SO4 | Ion Chromatography,<br>EPA Method 300.0 |

| | |
|---|---|
| **Dissolved $CO_2$** | Coulometric titration, ASTM D513-11 |
| **Isotopes:** δ13C of DIC | Isotope ratio mass spectrometry |
| **Total Dissolved Solids** | Gravimetry; APHA 2540C |
| **Water Density (field)** | Oscillating body method |
| **Alkalinity** | APHA 2320B |
| **pH (field)** | EPA 150.1 |
| **Specific conductance (field)** | APHA 2510 |
| **Temperature (field)** | Thermocouple |

By conducting the planned sampling initially and at specified monitoring frequencies, it is expected that baseline conditions can be documented, natural variability in conditions can be characterized, and unintended brine or $CO_2$ migration could be detected if it occurred. Sufficient data will be collected to demonstrate that the effects of $CO_2$ injection are limited to the permitted injection zone comprised of the Mt. Simon formation. Table 9.5.2-2 summarizes the planned locations and frequencies of all applicable direct monitoring methods.

**Table 9.5.2-2.** Summary of Direct Monitoring Methods

| Target Formation | Monitoring Activity | Monitoring Location(s) | Spatial Coverage | Frequency |
|---|---|---|---|---|
| Sensitive, Confidential, or Privileged Information | Pressure Monitoring | Sensitive, Confidential, or Privileged Information | Sensitive, Confidential, or Privileged Information | Continuous**; recorded hourly |
| | Temperature Monitoring | | | Continuous**; recorded hourly |
| | Fluid Sampling | | | Baseline; Annual |
| | Pressure Monitoring | | | Monthly |
| | | | | Monthly |
| | | | | Monthly |
| | | | | Monthly |
| | | | | Monthly |
| | Temperature Monitoring (DTS) | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | | | | Continuous**; recorded hourly |
| | Fluid Sampling | | | Baseline; Annual |
| | | | | Baseline; Annual |
| | | | | Baseline; Annual |
| | | | | Baseline; Annual |
| | | | | Baseline; Annual |

Sensitive, Confidential, or Privileged Information

| Target Formation | Monitoring Activity | Frequency |
|---|---|---|
| [redacted] | Pressure Monitoring | Continuous**; recorded hourly |
| | | Continuous**; recorded hourly |
| | | Continuous**; recorded hourly |
| | | Continuous**; recorded hourly |
| | | Continuous**; recorded hourly |
| | | Continuous**; recorded hourly |
| | | Continuous**; recorded hourly |
| | | Monthly |
| | | Monthly |
| | | Monthly |
| | | Monthly |
| | Temperature Monitoring (DTS) | Continuous**; recorded hourly |
| | | Continuous**; recorded hourly |
| | | Continuous**; recorded hourly |
| | | Continuous**; recorded hourly |
| | | Continuous**; recorded hourly |
| | | Continuous**; recorded hourly |
| | | Continuous**; recorded hourly |
| | Fluid Sampling | Baseline; Annual |
| | | Baseline; Annual |
| | | Baseline; Annual |
| | | Baseline; Annual |
| | | Baseline; Annual |

Note:
* indicates applicable if the proposed well is drilled in the future. Sample location is to be considered only an estimate at this time based on general offset information, and is highly likely subject to change after drilling

**Continuous temperature and pressure monitoring (DTS) will be satisfied with a minimum 5-minute sampling and at least hourly recording. If the continuous monitoring is unavailable, the well can continue to operate by performing pressure and temperature monitoring every 4 hours.

### 9.5.2 Indirect Monitoring Methods

Wireline Logging

Both pulse-neutron and reservoir-saturation logs will be conducted initially and once every two years in all active injection and verification wells so long as wireline logging equipment can be safely run into each well. Baseline conditions will be established in any new wells drilled by conducting initial logging as part of new well completions. At a minimum, initial logging will be conducted from surface to TD and subsequent logging will be conducted over intervals sufficient to establish changing conditions. Analysis of logging data will provide a means to complement and verify the results obtained from the fluid sampling program, specifically regarding any potential migration of $CO_2$ into and/or above the confining zone.

Seismic Monitoring

Time-lapse seismic surveys will be conducted at 5-year intervals during the operational period and used as a broad-scale means to attempt to track the migration of the subsurface $CO_2$ plume. Data collection has previously been conducted at the site outside any potential plume boundary. In the future, similar areas will be surveyed and the area expanded if reservoir modeling data and verification well monitoring indicate a need for expanded data acquisition to ascertain the leading edge of the plume. Analysis of subsequent seismic survey data will be conducted and if results are favorable, will be used to provide a supplemental method for assisting with validating the numerical model forecasts as they pertain to maximum plume extent and distribution. In addition, ADM will continue to operate its current passive-seismic monitoring system or a suitable equivalent replacement system, with the ability to detect seismic events exceeding M1.0 within the AoR. Table 9.5.2-1 summarizes the methods and locations of the planned indirect monitoring program.

**Table 9.5.2-1.** Summary of Indirect Monitoring Methods

| Monitoring Activity | Sensitive, Confidential, or Privileged Information | Frequency |
|---|---|---|
| Pulse Neutron/RST Logging | | Baseline, Bi-Annual |
| | | Baseline, Bi-Annual |
| | | Baseline, Bi-Annual |
| | | Baseline, Bi-Annual |
| | | Baseline, Bi-Annual |
| | | Baseline, Bi-Annual |
| | | Baseline, Bi-Annual |
| | | Baseline, Bi-Annual |
| | | Baseline, Bi-Annual |
| | | Baseline, Bi-Annual |
| | | Baseline, Bi-Annual |
| | | Baseline, Bi-Annual |
| Passive seismic | | Continuous**; recorded monthly |
| Time-lapse 3D surface seismic | | 5-Year |

Note: * indicates applicable if the proposed well is drilled in the future
**Continuous recording of passive seismic data is processed on a monthly basis to determine if seismic events over M1.0 occurred within the AoR. The passive seismic monitoring system at borehole and surface seismic stations is owned and operated by USGS.

## 9.6 Testing and monitoring plan QASP

A quality assurance and surveillance plan (QASP) for all testing and monitoring activities pursuant to 40 CFR 146.90(k) is provided in APPENDIX C: Quality Assurance and Surveillance Plan.

## 9.7 Reporting Requirements

The following details the reporting and recordkeeping requirements as it relates to CCS#5, CCS#6, and CC#7.

### 9.7.1 Electronic Reporting

Electronic reports, submittals, notifications and records made and maintained by the permittee under this permit will be in an electronic format approved by EPA. The permittee will electronically submit all required reports to the Director at the following website or via a suitable alternative method as may be instructed by EPA: *https://gsdt.pnnl.gov/*

### 9.7.2 Semi-Annual Reports

ADM will submit semi-annual reports containing:

(a) Any significant changes to the physical, chemical, and other relevant characteristics of the carbon dioxide stream from the proposed operating data;

(b) Monthly average, maximum, and minimum values for injection pressure, flow rate and daily volume, temperature, and annular pressure;

(c) A description of any event that exceeds operating parameters for annulus pressure or injection pressure specified in the permit;

(d) A description of any event which triggers the shut-off systems based on permit operational alarm value setpoints required pursuant to 40 CFR 146.88(e), and the response taken;

(e) The monthly volume and/or mass of the carbon dioxide stream injected over the reporting period and the volume and/or mass injected cumulatively over the life of the project;

(f) Monthly annulus fluid volume added or produced; and

(g) Results of the monitoring required in the Testing and Monitoring Plan, including:

(i) A tabulation of: (1) daily maximum injection pressure, (2) daily minimum annulus pressure, (3) daily minimum value of the difference between simultaneous measurements of annulus and injection pressure, (4) daily volume, (5) daily maximum flow rate, and (6) average annulus tank fluid level; and

(ii) Graph(s) of the monitoring as required, or of daily average values of these parameters. The injection pressure, injection volume and flow rate, annulus fluid level, annulus pressure, and temperature shall be submitted on one or more graphs, using contrasting symbols or colors, or in another manner approved by the Director; and

(h) Results of any additional monitoring identified in the Testing and Monitoring Plan.

### 9.7.3 24-Hour Reporting

ADM will report to the Director any permit noncompliance which may endanger human health or the environment and/or any events that require implementation of actions in the Emergency and Remedial Response Plan. Any information shall be provided orally within 24 hours from the time the permittee becomes aware of the circumstances. Such verbal reports shall include, but not be limited to the following information:

- Any evidence that the injected carbon dioxide stream or associated pressure front may cause an endangerment to a USDW, or any monitoring or other information which indicates that any contaminant may cause endangerment to a USDW;
- Any noncompliance with a permit condition, or malfunction of the injection system, which may cause fluid migration into or between USDWs;
- Any triggering of the shut-off system required (i.e., down-hole or at the surface);
- Any failure to maintain mechanical integrity;
- Pursuant to compliance with the requirement at 40 CFR 146.90(h) for surface air/soil gas monitoring or other monitoring technologies, if required by the Director, any release of carbon dioxide to the atmosphere or biosphere; and
- Actions taken to implement appropriate protocols outlined in the Emergency and Remedial Response Plan.

A written submission to document any required 24-hour reporting shall be provided to the Director in an electronic format within five days of the time the permittee becomes aware of the circumstances described

in Section 9.7.3. The submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and, if the noncompliance has not been corrected, the anticipated time it is expected to continue as well as actions taken to implement appropriate protocols outlined in the Emergency and Remedial Response Plan; and steps taken or planned to reduce, eliminate and prevent recurrence of the noncompliance.

### 9.7.4 Reports on Well Tests and Workovers

Report, within 30 days, the results of:

- Periodic tests of mechanical integrity;
- Any well workover or stimulation;
- Any other test of the injection well conducted by the permittee if required by the Director; and
- Any test of any monitoring well required by this permit.

### 9.7.5 Advance Notice Reporting

- Well Tests – ADM will give at least 30 days advance written notice to the Director in an electronic format of any planned workover, stimulation, or other welltest.
- Planned Changes – ADM will give written notice to the Director in an electronic format, as soon as practical, of any planned physical alterations or additions to the permitted injection facility other than minor repair/replacement or maintenance activities. An analysis of any new injection fluid shall be submitted to the Director for review and written approval at least 30 days prior to injection; this approval may result in a permit modification.
- Anticipated Noncompliance – ADM will give advanced written notice to the Director in an electronic format of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements.

### 9.7.6 Additional Reports

- Compliance Schedules – Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of this permit will be submitted in an electronic format by ADM no later than 30 days following each schedule date.
- Transfer of Permits – This permit is not transferable to any person except after notice is sent to the Director in an electronic format at least 30 days prior to transfer and the requirements of 40 CFR 144.38(a) have been met. Pursuant to requirements at 40 CFR 144.38(a), the Director will require modification or revocation and reissuance of the permit to change the name of the permittee and incorporate such other requirements as may be necessary under the SDWA.
- Other Noncompliance – ADM will report in an electronic format all other instances of noncompliance not otherwise reported with the next monitoring report. The reports shall contain the information listed in Section 9.7.3 above.
- Other Information – When ADM becomes aware of failure to submit any relevant facts in the permit application or that incorrect information was submitted in a permit application or in any report to the Director, ADM will submit such facts or corrected information in an electronic format within 10 days in accordance with 40 CFR 144.51(l)(8).

- Report on Permit Review – Within 30 days of receipt of this permit, ADM will certify to the Director in an electronic format that he or she has read and is personally familiar with all terms and conditions of this permit.

### 9.7.7 Records

ADM will retain records and all monitoring information, including all calibration and maintenance records and all original chart recordings for continuous monitoring instrumentation and copies of all reports required by this permit (including records from pre-injection, active injection, and post-injection phases) for a period ofat least 10 years from collection.

ADM will maintain records of all data required to complete the permit application form for this permit and any supplemental information (e.g. modeling inputs for AoR delineations and reevaluations, plan modifications) submitted under 40 CFR 144.27, 144.31, 144.39, and 144.41; information used to develop the demonstration of the alternative post-injection site care timeframe; and the site closure report for a period of at least 10 years after site closure.

ADM will retain records concerning the nature and composition of all injected fluids until 10 years after site closure.
Records of monitoring information shall include:

- The date, exact place, and time of sampling or measurements;
- The name(s) of the individual(s) who performed the sampling ormeasurements;
- A precise description of both sampling methodology and the handling ofsamples;
- The date(s) analyses were performed;
- The name(s) of the individual(s) who performed the analyses;
- The analytical techniques or methods used; and
- The results of such analyses.

# 10. Well Plugging Plan

## 10.1 Facility Information

Facility Name: Archer Daniels Midland
CCS#1 Permit: IL-115-6A-0002
CCS#2 Permit: IL-115-6A-0001
CCS#3 Permit: TBD
CCS#4 Permit: TBD
CCS#5 Permit: TBD
CCS#6 Permit: TBD
CCS#7 Permit: TBD

Facility Contact: Mr. Doug Kirk, Plant Manager
4666 Faries Parkway, Decatur, IL
(217) 454-4577, douglas.kirk@adm.com

Well Location: Decatur, Macon County, IL;
CCS#5 (Proposed): N39° 57’ 47.32”, W89° 00’ 44.33”
CCS#6 (Proposed): N39° 57’ 48.15”, W88° 58’ 48.70”
CCS#7 (Proposed): N39° 56' 54.21'', W88° 59' 36.19”

Injection well plugging will be conducted according to the procedures provided in this section, which are consistent with previously approved procedures and submittals provided to US EPA Region 5 by ADM in May of 2016.

Upon completion of the active injection phase of the project, or at the end of the life of the respective CCS injection well, the well will be plugged and abandoned to meet the requirements of 40 CFR 146.92. The plugging procedure and materials are designed and will be implemented to prevent any unwanted fluid movement, to resist the corrosive aspects of carbon dioxide/water mixtures, and to protect any USDWs. Annual testing or information derived during plugging operations may indicate the need for revisions to this plugging plan. Significant revisions will be submitted to the UIC Program Director.

## 10.2 Summary

After injection has ceased, the well to be plugged will be flushed with a kill weight brine fluid. A minimum of three tubing volumes will be injected without exceeding maximum bottomhole injection pressure specified by permit. Bottom hole pressure measurements will be made using wireline or slickline conveyed tools and the well will be logged and pressure tested to evaluate Part I mechanical integrity (inside) and Part II external mechanical integrity (outside) of the casing prior to plugging. If a loss of mechanical integrity is discovered, the agency will be consulted regarding findings, and the well will be repaired as necessary to allow plugging consistent with regulatory requirements prior to proceeding with the plugging operations.

A detailed plugging procedure is provided below. Well construction and completion activities are designed to bring cement to surface on all casing strings. It is not anticipated that any of the casing will be retrieved at plugging.

After injection is terminated permanently, the injection tubing and packer will be removed. After the tubing and packer are removed, the casing will be circulated clean, or fluids displaced into the injection interval, and the balanced-plug placement method will be used to plug the well by cementing the long-string casing to surface. If, after flushing, the tubing and packer cannot be released, a tubing cutter will be used to cut off the tubing above the packer and the packer will be left in the well, the well will be flushed, and the cement retainer method will be used for plugging the injection formation below the packer.

All of the casing strings will be cut off at least 4 feet below the surface, below the plow line. A blanking plate with the required permit information will be welded to the top of the cutoff casing at the conclusion of the plugging process.

## 10.3 Planned Tests or Measures to Determine Bottom-hole Reservoir Pressure

ADM will record static bottom hole formation pressure using a down hole pressure gauge and calculate kill fluid density based on final ambient monitoring pressure measurements.

## 10.4 Planned External Mechanical Integrity Test(s)

ADM will conduct at least one of the tests in Table 10.2-1 to verify external MI prior to plugging the injection well as required in 40 CFR 146.92(a).

**Table 10.2-1**. External MIT Methods

| Test Type | Means of Testing |
|---|---|
| Temperature Log | Along wellbore using DTS or wireline well log |
| Noise Log | Wireline Well Log |
| Oxygen Activation Log | Wireline Well Log |

## 10.5 Information on Cement Plugs

The cement(s) formulated for plugging will be compatible with the carbon dioxide stream that has historically been injected into the well at the conclusion of the well life. The cement formulation and required certification documents will be submitted to the agency with the final well plugging plan to be submitted with the notice to plug the well. The operator will report the wet density of the cement and will retain duplicate samples of the cement used for each plug. Figures 10.5-1, 10.5-2, and 10.5-3 present plugging schematics for the CCS#5, CCS#6, and CCS#7 wells, respectively. Tables 10.5-2, 10.5-3, and 10.5-4 present the details of the cement volumes for all three wells.





**Figure 10.5-1**. Proposed CCS#5 Plugging Schematic





**Figure 10.5-2.** Proposed CCS#6 Plugging Schematic





**Figure 10.5-3. Proposed CCS#7 Plugging Schematic**

**Table 10.5-2.** CCS#5 Cement Plug Details

| | Plug #1 | Plug #2 |
|---|---|---|
| **Inner Diameter of Casing in Which Plug Will be Placed (in)** | Sensitive, Confidential, or Privileged Information | |
| **Depth to Bottom of Tubing or Drill Pipe (ft)** | | |
| **Slurry Volume to be Plumped ($ft^3$)** | | |
| **Sacks of Cement to be Used (per plug)** | | |
| **Slurry Weight (lb/gal)** | | |
| **Calculated Top of Plug (ft)** | | |
| **Bottom of Plug (ft)** | | |
| **Type of Cement** | | |
| **Method of Emplacement** | | |

**Table 10.5-3.** CCS#6 Cement Plug Details

| | Plug #1 | Plug #2 |
|---|---|---|
| **Inner Diameter of Casing in Which Plug Will be Placed (in)** | Sensitive, Confidential, or Privileged Information | |
| **Depth to Bottom of Tubing or Drill Pipe (ft)** | | |
| **Slurry Volume to be Plumped ($ft^3$)** | | |
| **Sacks of Cement to be Used (per plug)** | | |
| **Slurry Weight (lb/gal)** | | |
| **Calculated Top of Plug (ft)** | | |
| **Bottom of Plug (ft)** | | |
| **Type of Cement** | | |
| **Method of Emplacement** | | |

**Table 10.5-4.** CCS#7 Cement Plug Details

| | Plug #1 | Plug #2 |
|---|---|---|
| **Inner Diameter of Casing in Which Plug Will be Placed (in)** | Sensitive, Confidential, or Privileged Information | |
| **Depth to Bottom of Tubing or Drill Pipe (ft)** | | |
| **Slurry Volume to be Plumped ($ft^3$)** | | |
| **Sacks of Cement to be Used (per plug)** | | |
| **Slurry Weight (lb/gal)** | | |
| **Calculated Top of Plug (ft)** | | |
| **Bottom of Plug (ft)** | | |
| **Type of Cement** | | |
| **Method of Emplacement** | | |

The first 500' plug placed in each well may include 20% excess in the volume to accommodate any issues with perforations. Tables 10.5-2, 10.5-3, and 10.5-4 all account for the 20% excess.

## 10.3 Narrative Description of Plugging Procedures

In compliance with 40 CFR 146.92(c), ADM will do the following:

1. Notify the regulatory agency at least 60 days before plugging the well and provide updated plugging plan, if applicable.

2. Confirm the mechanical integrity of the well by performing one of the permitted external mechanical integrity tests presented in the table under "Planned External Mechanical Integrity Test(s)" above.

3. Move-in Rig onto well and rig up (RU). All $CO_2$ pipelines will be marked and noted with rig supervisor prior to field work.

4. Conduct and document a safety meeting specifying requirements based on conditions noted at the well prior to plugging mobilization.

5. RU wireline or slickline equipment and required pressure control and run-in well to datum depth or suitable equivalent to record bottom hole pressure using down hole gauge. RD slickline. Calculate required kill fluid density.

6. Check pressures on the vertical run of the tree to verify wellhead equipment is sufficient for plugging activities.

7. Test the pump and lines to a minimum of 2,500 psi. Fill tubing with kill weight brine (minimum 9.5 ppg or greater, as determined by bottom hole pressure measurement). Bleeding off occasionally may be necessary to remove all gas from the system. Test casing annulus to a minimum of 1,000 psi and monitor as in annual MIT. If there is pressure remaining on tubing, rig-up equipment to pump down tubing and inject minimum of two tubing volumes of kill weight brine. Monitor tubing and casing pressure for 1 hour. If both casing and tubing are dead then nipple up (install) blowout preventers (NU BOPs). Monitor casing and tubing pressures.

8. If the well is not dead or the pressure cannot be bled off of tubing, RU slickline and set plug in lower profile nipple below packer. Circulate tubing and annulus with kill weight fluid until well is dead. After well is dead, nipple down (ND) tree, NU BOPs, and perform a function test. BOP's should have appropriately sized single pipe rams on top and blind rams in the bottom ram for tubing. Test pipe rams and blind rams to 250 psi low, 3,000 psi high. Test annular preventer to 250 psi low and 3,000 psi high. Test all TIW valves (pressure control valve), BOP choke and kill lines, and choke manifold to 250 psi low and 3,000 psi high. NOTE: Make sure casing valve is open during all BOP tests.

9. After testing BOPs pick up tubing string and unlatch seal assembly from seal bore. Rig slick line and lubricator back to well and remove X- plug from well. Rig to pump via lubricator and circulate until well is dead. During this process, annulus fluid may be bullheaded into the formation or circulated out of the well.

10. Pull out of hole with tubing laying it down. NOTE: Ensure that the well is over-balanced and add kill brine as needed to maintain fluid-filled well.

11. Pull seal assembly, pick up workstring, and trip in hole (TIH) with the packer retrieving tools. Latch onto the packer and pull out of hole laying down same.

    **Contingency:** If unable to pull seal assembly, RU electric line and make cut on tubing string just above packer. Note: Cut must be made above packer at least 5-10 ft MD. If unable to pull the packer, pull the work string out of hole and proceed to next step. If problems are noted, update cement remediation plan (if needed) and execute prior to plugging operations.

12. TIH with work string to tagged total depth (TD). Note that the tagged TD might be shallower than the original TD due to fill. The work string should be worked as deep as safely possible. Keep the hole full at all times. Circulate the well with fluid of sufficient weight to maintain static equilibrium and prepare for cement plugging operations.

13. The lower section of the well from the top of the confining zone to the bottom of the plug will be plugged using $CO_2$ resistant cement (Schlumberger Evercrete or suitable equivalent) which is expected to be from TD to a depth approximately 1,000 ft above the top of the Eau Claire formation (at approximately 4,300 ft KB). This initial stage of plugging will be accomplished by placing consecutive 500-foot balanced plugs in the casing using a cement slurry with a density of 15.9 ppg and a yield of 1.11 cubic feet per sack of cement. Note that the values used in these calculations are derived from Schlumberger's Evercrete mix. Actual cement volume will depend upon plug back total depth and wellbore fill that determine total plug length. It is anticipated that seven to eight plugs will be necessary to complete the first stage. The top depth of the plug will be verified by setting the work string down onto the plug. No more than two plugs will be set before cement is allowed to develop sufficient compressive strength (per data from testing on the specific cement blend).

14. Circulate the well and ensure it is in balance. Wait on cement for a minimum of 20 hours prior to proceeding with second stage of plugging above the confining zone to surface. Tag cement to verify depth and place work string just above the top of cement.

15. The upper section of the well from the top of the confining zone to surface will be plugged using Class A/H cement (or suitable equivalent) with a density of 15.9 ppg and a yield of 1.18 cubic feet per sack of cement. Note that the values used in these calculations are derived from Schlumberger's Class A/H blends. This stage of plugging will be accomplished by placing consecutive 500-foot balanced plugs in the casing. Actual cement volume will depend upon the top of the plug placed in the lower section of the well. It is anticipated that eight to nine plugs will be necessary to complete the second stage.

16. After each plug is set, pull out of plug and reverse circulate the work string. Repeat this operation until all the plugs have been set. If plugs are well balanced, then the reverse circulation step can be omitted until after every third plug. Lay down work string while pulling from well.

17. After the penultimate plug has been set, pull the work string from well and shut in for 12 hours.

18. Trip in hole with work string and tag cement top. Calculate volume for final plug. Pull work string back out of well.

19. ND BOPs and cut all casing strings below plow line (minimum four (4) feet below ground level or per local policies/standards and ADM requirements).

20. Lay down all work string, etc. Rig down all equipment and move out. Clean cellar to where a plate can be welded onto casing stub with well name onto lowest casing string at 4 feet, or as per permitting agency directive.

The procedures described above are subject to modification during execution, as necessary, to ensure implementation of a plugging operation that protects worker safety and effectively protects USDWs. Any significant modifications due to unforeseen circumstances will be reported to the agency during field operations and documented in the plugging report. Completed plugging forms, records and lab information will be supplied to the regulatory agency as required by permit. The plugging report will be certified as accurate by ADM and the plugging contractor, and shall be submitted to the agency within 60 days after plugging is completed.

# 11. Post-Injection Site Care and Site Closure Plan

This Post-Injection Site Care and Site Closure (PISC) plan describes the activities that ADM will perform to meet the requirements of 40 CFR 146.93. ADM will monitor groundwater quality and track the position of the carbon dioxide plume and pressure front for 10 years after the cessation of injection. ADM will not cease post-injection monitoring in accordance with the approved PISC Plan until site closure has been authorized by the Director pursuant to 40 CFR 146.93(b)(3). Following authorization for site closure, ADM will plug all monitoring wells, restore the site to its original condition, and submit a Site Closure report and associated documentation.

## 11.1 Pressure differential and position of the $CO_2$ plume and pressure front

Figure 11.1-1 represents the predicted extent of the pressure front that defines the AoR at the end of operation, 5-years post-injection and at the end of the 10-year PISC timeframe. This map is a summary of the AoR delineation modeling results submitted in Section 4 of this application per 40 CFR 146.84. At the onset of the post-injection period, it is expected that the $CO_2$ plume will continue to expand to a small degree as the system reaches pressure equilibrium, with marginal $CO_2$ plume expansion occurring after approximately 10-years post-injection. Similarly, as shown in Figure 11.1-1, the AoR is also predicted to expand for several years post-injection as equilibrium is reached. By 2048, the pressure-induced cone of influence (the pressure change that defines the permit AoR) is projected to reach its maximum size, eventually reducing to less than 50% of its maximum size by 2088.





**Figure 11.1-1.** Modeled Extent of $CO_2$ Pressure Induced Cone of Influence

Figure 11.1-2 is a summary of modeling results presented in Section 4 of this document. It depicts the modeled extent of the plume boundary at the end of operation, the end of the 10-year PISC timeframe and for comparison purposes also shows the minimal changes that occur at 50-years post injection as compared with the end of the PISC period. Based on modeling results, minimal post-operational plume drift is expected and the plume is predicted to reach its near-maximum size by the end of the 10-year PISC period, with the rate of expansion decreasing and becoming negligible by 50 years post-injection.





**Figure 11.1-2**. Modeled Extent of $CO_2$ Plume (End of Operation, 10-Years and 50-Years Post-Injection)

## 11.2 Post-injection phase monitoring plan

### 11.2.1 Groundwater Quality Monitoring

Tables 11.2.1-1 and 11.2.1-2 present the direct and indirect monitoring methods, locations, and frequencies planned for monitoring groundwater quality associated with CCS #5, CCS #6 and CCS #7 installation and operation. Monitoring above the confining zone in the lowermost USDW in the AoR, the St. Peter Formation, and for the Ironton-Galesville Sandstone will take place as part of the CCS #5-#7 program. Monitoring of the Quaternary and/or Pennsylvanian strata will take place in association with other injectors as required by permit. All of the existing and proposed monitoring wells are located on ADM property. Table 11.2.1-3 identifies the parameters to be monitored and the analytical methods ADM will employ.

Fluid sampling will provide direct evidence regarding the presence or absence of $CO_2$ and/or altered geochemistry that is associated with $CO_2$ movement. Temperature monitoring will provide evidence to determine if fluid passing a monitored location has changed the original temperature of the monitored interval and pressure monitoring will provide evidence if sufficient fluid movement has occurred into a deep strata that has resulted in an induced pressure gradient at the monitored location.

**Table 11.2.1-1.** Post-Injection Phase Direct Groundwater Monitoring Above Confining Zone

| Target Formation | Monitoring Activity | Monitoring Location | Frequency: Year 1 | Frequency: Years 2-3 | Frequency: Years 4-9 | Frequency: Year 10 |
|---|---|---|---|---|---|---|
| Sensitive, Confidential, or Privileged Informa | Fluid Sampling | Sensitive, Confidential, or Privileged Informa | Annual | Annual | Annual | Annual |
| | Distributed Temperature Sensing (DTS) | | Monthly | None | None | None |
| | Fluid Sampling | | Annual | Annual | Annual | Annual |
| | Pressure/Temperature Monitoring | | Monthly | Monthly | Annual | Annual |
| | DTS | | Monthly | None | None | None |

**Table 11.2.1-2.** Post-Injection Phase Indirect Groundwater Monitoring Above Confining Zone

| Target Formation | Monitoring Activity | Monitoring Location | Frequency to Year 10 |
|---|---|---|---|
| Sensitive, Confidential, or Privileged Information | Pulse-Neutron/RST Logging | Sensitive, Confidential, or Privileged Information | Years 1,3,5,7, and 10 |
| | Pulse-Neutron/RST Logging | | Years 1,3,5,7, and 10 |
| | Pulse-Neutron/RST Logging | | Years 1,3,5,7, and 10 |

**Table 11.2.1-3.** Summary of Analytical and Field Parameters for Groundwater Samples [(1)]

| Parameters | Analytical Methods |
|---|---|
| ***Quaternary/Pennsylvanian*** | |
| **Cations:** Ca, Fe, K, Mg, Na, and Si | ICP-OES EPA Method 6010B |
| **Anions:** Br, Cl, F, $NO_3$, and $SO_4$ | Ion Chromatography EPA Method 300.0 |
| **Dissolved $CO_2$** | Coulometric titration, ASTM D513-11 |
| **Total Dissolved Solids** | Gravimetry; APHA 2540C |
| **Alkalinity** | APHA 2320B |
| **pH (field)** | EPA 150.1 |
| **Specific conductance (field)** | APHA 2510 |
| **Temperature (field)** | Thermocouple |
| ***St. Peter*** | |
| **Cations:** Ca, Fe, K, Mg, Na, and Si | ICP-OES EPA Method 6010B |
| **Anions:** Br, Cl, F, $NO_3$, and $SO_4$ | Ion Chromatography EPA Method 300.0 |
| **Dissolved $CO_2$** | Coulometric titration, ASTM D513-11 |
| **Isotopes: $\delta^{13}C$ of DIC** | Isotope ratio mass spectrometry |
| **Total Dissolved Solids** | Gravimetry; APHA 2540C |
| **Water Density (field)** | Oscillating body method |
| **Alkalinity** | APHA 2320B |
| **pH (field)** | EPA 150.1 |
| **Specific conductance (field)** | APHA 2510 |
| **Temperature (field)** | Thermocouple |
| ***Ironton-Galesville*** | |
| **Cations:** Ca, Fe, K, Mg, Na, and Si | ICP-OES EPA Method 6010B |
| **Anions:** Br, Cl, F, $NO_3$, and $SO_4$ | Ion Chromatography EPA Method 300.0 |
| **Dissolved $CO_2$** | Coulometric titration, ASTM D513-11 |
| **Isotopes: $\delta^{13}C$ of DIC** | Isotope ratio mass spectrometry |
| **Total Dissolved Solids** | Gravimetry; APHA 2540C |
| **Water Density (field)** | Oscillating body method |
| **Alkalinity** | APHA 2320B |
| **pH (field)** | EPA 150.1 |
| **Specific conductance (field)** | APHA 2510 |
| **Temperature (field)** | Thermocouple |

Note 1: ICP = inductively coupled plasma; MS = mass spectrometry; OES = optical emission spectrometry; GC-P = gas chromatography - pyrolysis. An equivalent method may be employed with prior approval of the Director.

As applicable to the plan presented in this section, sampling will be performed as described in section B.2 of the QASP; this section of the QASP describes the groundwater sampling methods to be employed, including sampling SOPs (section B.2.a/b), and sample preservation (section B.2.g).

- Sample handling and custody will be performed as described in section B.3 of the QASP.
- Quality control will be ensured using the methods described in section B.5 of the QASP.

### 11.2.2 Carbon Dioxide Plume and Pressure Front Tracking

ADM will employ direct and indirect methods to track the extent of the carbon dioxide plume and the presence or absence of elevated pressure within the injection formation as specified. Table 11.2.2-1 presents the direct and indirect methods that will be used to monitor the $CO_2$ plume evolution in the injection zone, including the activities, locations, and frequencies ADM will employ. ADM will conduct fluid sampling and analysis to detect changes in groundwater in order to directly monitor the presence or absence of the carbon dioxide plume at a monitored location. Arrival time of the plume and concentrations detected will be compared to simulations to validate the model projections. The parameters to be analyzed as part of fluid sampling in the Mt. Simon (and associated analytical methods) are presented in Table 11.2.2-2. Sufficient changes in chemical constituents will be analyzed to determine if they provide evidence of plume location. Indirect plume monitoring will be employed using pulsed neutron capture/reservoir saturation tool (RST) logs to monitor $CO_2$ saturation and these data will be integrated with 3D surface seismic surveys as practical to determine if changing density results in sufficient seismic signatures to track plume movement in the subsurface. Quality assurance procedures for seismic monitoring methods are presented in Section B.9 of the QASP.

**Table 11.2.2-1**. Post-Injection Phase Plume Monitoring [1,2]

| Target Formation | Monitoring Activity | Monitoring Location | Frequency to Year 10 |
|---|---|---|---|
| ***Direct Plume Monitoring*** | | | |
| Sensitive, Confidential, or Privileged Information | Fluid Sampling | Sensitive, Confidential, or Privileged Information | Annual |
| ***Indirect Plume Monitoring*** | | | |
| Sensitive, Confidential, or Privileged Information | | | |
| | Pulse-Neutron/RST Logging | | Years 1,3,5,7 and 10 |
| | 3D Seismic Survey | | Year 10 |

**Table 11.2.2-2.** Summary of analytical and field parameters for fluid sampling in the Mt. Simon

| Parameters | Analytical Methods [1] |
|---|---|
| **Water Density (field)** | Oscillating body method |
| **Alkalinity** | APHA 2320B |
| **pH (field)** | EPA 150.1 |
| **Specific conductance (field)** | APHA 2510 |
| **Temperature (field)** | Thermocouple |
| ***Mt. Simon*** | |
| **Cations:**<br>Ca, Fe, K, Mg, Na, and Si | ICP-OES<br>EPA Method 6010B |
| **Anions:**<br>Br, Cl, F, $NO_3$, and $SO_4$ | Ion Chromatography<br>EPA Method 300.0 |
| **Dissolved $CO_2$** | Coulometric titration, ASTM D513-11 |
| **Isotopes: $\delta^{13}C$ of DIC** | Isotope ratio mass spectrometry |
| **Total Dissolved Solids** | Gravimetry; APHA 2540C |
| **Water Density (field)** | Oscillating body method |
| **Alkalinity** | APHA 2320B |
| **pH (field)** | EPA 150.1 |
| **Specific conductance (field)** | APHA 2510 |
| **Temperature (field)** | Thermocouple |

Note 1: ICP = inductively coupled plasma; MS = mass spectrometry; OES = optical emission spectrometry; GC-P = gas chromatography - pyrolysis. An equivalent method may be employed with the prior approval of the Director.

Table 11.2.2-3 presents the direct and indirect methods that ADM will use to monitor the pressure front, including the activities, locations, and frequencies ADM will employ during the post-operational period. ADM will deploy pressure/temperature monitors and distributed temperature sensors to directly monitor the position of the pressure front. Passive seismic monitoring using a combination of borehole and surface seismic stations to detect local events over M1.0 within the AoR will also be performed.

**Table 11.2.2-3.** Post-Injection Phase Pressure Front Monitoring

| Target Formation | Monitoring Activity | Monitoring Location | Frequency: Year 1 | Frequency: Years 2-3 | Frequency: Years 4-9 | Frequency: Year 10 |
|---|---|---|---|---|---|---|
| ***Direct Pressure-front Monitoring*** | | | | | | |
| [redacted] | Pressure/Temperature Monitoring | [redacted] | Monthly | Monthly | Monthly | Monthly |
| | Pressure/Temperature Monitoring | | Monthly | Monthly | Annual | Annual |
| | DTS | | Monthly | None | None | None |
| ***Other Monitoring*** | | | | | | |
| [redacted] | Passive Seismic | | Continuous**; processed monthly | Continuous**; processed monthly | Continuous**; processed monthly | Continuous**; processed monthly |

**Continuous recording of passive seismic data is processed on a monthly basis to determine if seismic events over M1.0 occurred within the AoR. The current passive seismic monitoring system at borehole and surface seismic stations is owned and operated by USGS. ADM reserves the right to supplement or replace such monitoring with a suitable equivalent if necessary.

## 11.3 Alternative PISC timeframe

ADM will conduct post-injection monitoring for 10 years following the cessation of injection operations in CCS#5-7, consistent with the previously demonstrated and approved alternative timeframe pursuant to 40 CFR 146.93(c)(1), for CCS#1-4. ADM requests a 10-year alternative post-injection care time period for CCS#5-7 based on the computational modeling conducted to delineate the AoR; predictions of plume migration, pressure decline once injection stops, and carbon dioxide trapping; site-specific geology; well construction; and the distance between the injection zone and the nearest USDWs. Modeling results are summarized in previous portions of this section and described in more detail in Section 4 of this application. Site specific conditions that satisfy the alternative timeframe requirements listed in § 146.93(c)(1) and (2) are described in the following paragraphs. Note that the specific section for each criterion in the CFR is listed in square brackets, [ ].

- [§146.93(c)(1)(i)] The results of computational modeling of the project (Section 4 of this application) show that the sequestered $CO_2$ will not migrate above the Mt. Simon Sandstone.
- [§146.93(c)(1)(ii)] The modeling demonstrates that formation fluids will not be forced into any USDWs; and/or the timeframe for pressure decline to pre-injection pressures. Consistent with the map presented in Figure 11.1-1, Figure 11.3-1 presents the modeled bottomhole pressures projected over time for the CCS #5-7 locations. Pressure values are normalized to a depth of 6,000' SSTVD. Figure 11.3-1 illustrates that bottomhole pressures are projected to decline significantly over the first several years post-injection. At the end of the 10-year PISC timeframe, approximately 90% of the total pressure decline is observed.





**Figure 11.3-1.** Modeled Extent of Bottom Hole Pressure to 50 Years Post-Injection

- [§146.93(c)(1)(ii)] The hydrogeologic and seismic characterization for the project site indicates that the Eau Claire Formation, the primary seal above the Mt. Simon, does not contain any faults and has permeability sufficiently low to impede $CO_2$ migration to overlying formations.

- [§146.93(c)(1)(iii), the predicted rate of carbon dioxide plume migration within the injection zone after cessation of injection is addressed in Section 4 of this application. Based on the modeled plume areas summarized in Figure 11.1-2, the equivalent plume radius (assuming circular areas and no initial plume) grows at an average of approximately 730 ft/year during injection operations. During the initial ten years of post-injection equilibration, the rate of plume expansion slows to an average of approximately 50 ft/year. With each passing year, post-operation, "residual" reservoir pressure and migration velocities decline. Following the 10-year PISC timeframe, the rate of expansion continues to decrease and becomes negligible by 50 years post-injection.
- [146.93(c)(1)(iv-vi) addresses the description of processes that result in carbon dioxide trapping including immobilization by capillary trapping, dissolution and mineralization and the predicted rate of trapping, as well as the site-specific studies supporting these mechanisms. Section 3.11 addressed expected mineralogical reactions and associated studies associated with $CO_2$ injection into the Mt. Simon reservoir system. The section concludes that it is not expected "that injection of $CO_2$ into the proposed well would lead to drastic geochemical reactions within the reservoir and seal that compromise injectivity and long-term security", and does not call for $CO_2$ immobilization as a trapping mechanism. The alternative timeframe is well justified by modeled pressure decline. As indicated above and shown in Figure 11.3-1, at the end of the 10-year PISC timeframe, more than 90% of the pressure decline that will occur is observed in the wells. Pressure rise in the injection zone has dissipated significantly by the end of the 10-year PISC period.
- [§146.93(c)(1)(viii) and (ix)] Potential conduits for hypothetical $CO_2$ migration above the Mt. Simon are limited to the ADM injection and verification wells, all of which will be constructed, monitored, and ultimately plugged in a manner that will minimize the potential for any such migration and meet the requirements of 40 CFR Part 146. There are no other potential vertical pathways out of the Mt. Simon injection zone within the AoR at the end of the operating life and pressures at the injection wells are projected to have declined to within approximately 10% of the maximum pressure rise experienced during operations by the end of the 10-year PISC period.
- [§146.93(c)(1)(x)] The St Peter Sandstone is the lowermost USDW at the Decatur $CO_2$ storage site. The injection interval is approximately 3,000 ft below this aquifer but is not used as a local source of drinking water. The local source of drinking water is Lake Decatur and well water from the Quaternary and Pennsylvanian strata. The injection intervals for the three wells are approximately 6,500 ft below the local source of drinking water. There are three confining formations (New Albany Shale, Maquoketa Formation, Eau Claire Formation) between the injection zone and the lowermost USDW. If, based on results of operational monitoring the EPA requires post-injection monitoring beyond the ten-year timeframe outlined in this plan, the operator will work with the Director to establish the monitoring activities, frequency, and duration of the PISC period.
- Sections 3 and 4 present the information that satisfies the requirements set forth in §146.93(c)(2) regarding predictive models used, methods used to determine input parameters including analyses, tests, and estimation techniques, model calibration, modeling assumptions, and modeling uncertainty. The same parameters, modeling techniques, and geologic characterization were presented to support approval of the alternative 10-year PISC time period for CCS #1-4.

ADM will conduct the monitoring described under "Groundwater Quality Monitoring" and "Carbon Dioxide Plume and Pressure Front Tracking" sections presented above and report the results as described under the "Schedule for Submitting Post-Injection Monitoring Results." This will continue until ADM demonstrates, based on monitoring and other site-specific data, that no additional monitoring is needed to ensure that the project

does not pose an endangerment to any USDWs, per the requirements at 40 CFR 146.93(b)(2) or (3).

If any of the information upon which this demonstration was based changes or the measured behavior of the system varies significantly from modeled predictions in a way that would negatively impact the permitting criteria, e.g., as a result of increased projections of pressure an expanded AoR requires reevaluation, ADM may update this PISC and Site Closure Plan pursuant to 40 CFR 146.93(a)(4). ADM will update the PISC and Site Closure Plan, within six months of ceasing injection or demonstrate that no update is needed and as necessary during the duration of the PISC timeframe.

## 11.4 Non-endangerment demonstration criteria

Prior to authorization of site closure, ADM will submit a demonstration of non-endangerment of USDWs to the Director, per 40 CFR 146.93(b)(2) or (3).

To make the non-endangerment demonstration, ADM will issue a report to the Director. This report will make a demonstration of USDW non-endangerment based on the evaluation of the site monitoring data used in conjunction with the project computational model. The report will detail how the non-endangerment demonstration uses site-specific conditions to confirm and demonstrate non-endangerment. The report will include (or appropriately reference): all relevant monitoring data and interpretations upon which the non-endangerment demonstration is based, model documentation and all supporting data, and any other information necessary for the Director to review the analysis. The report will include the following components. These components are identical to those presented in the pending CCS #3 and CCS #4 applications, and will also apply to CCS #5-7:

Summary of Existing Monitoring Data

A summary of all previous monitoring data collected at the site, pursuant to the Testing and Monitoring Plan (Section 9 of this application) and this PISC and Site Closure Plan, including data collected during the injection and PISC phases of the project, will be submitted to help demonstrate non-endangerment. Data submittals will be in a format acceptable to the Director [40 CFR 146.91(e)], and will include a narrative explanation of monitoring activities, including the dates of all monitoring events, changes to the monitoring program over time, and an explanation of all monitoring infrastructure that has existed at the site. Data will be compared with baseline data collected during site characterization [40 CFR 146.82(a)(6) and 146.87(d)(3)].

Comparison of Monitoring Data and Model Predictions and Model Documentation

The results of computational modeling used for AoR delineation and for demonstration of the alternative PISC timeframe will be compared to monitoring data collected during the operational and the PISC periods. The data will include the results of time-lapse temperature and pressure monitoring, groundwater quality analysis, passive seismic monitoring, and geophysical surveys (i.e., logging, operating-phase VSP, and 3D surface seismic surveys) used to update the computational reservoir model and to monitor the site. Data generated during the PISC period will be used to show that the computational model accurately represents the storage site and can be used as a proxy to determine the properties of the plume including the plume size. ADM will demonstrate that the accuracy of the model is sufficient by comparing the monitoring data obtained during the PISC period against the performance of the system as predicted by the model (i.e., plume location, rate of movement, and pressure decay). Statistical methods will be employed to correlate the data and confirm the capability of the model to accurately represent the storage site. The validation of the computational model with the significant set of monitoring data will be a significant element to support the non-endangerment demonstration. Justification that the conclusions of the model are meaningful will be presented based on the validation efforts. Further, the validation of the model over the areas, and at the points, where direct data collection has taken place will help to ensure confidence in the model for those areas where surface infrastructure preclude geophysical data collection

and where direct observation wells cannot be placed.

*Evaluation of Carbon Dioxide Plume*

ADM may use a combination of fluid sampling data, time-lapse RST logs, time-lapse VSP surveys, and other seismic methods (2D or 3D surveys) to locate and track the extent of the $CO_2$ plume. Figures 11.4-1 through 11.4-3 present examples of how the data may be correlated against the model prediction. In Figure 11.4-1, a series of RST logs are compared against the plume vertical extent predicted by the model at a specific point location at a specified time interval. If a good correlation between the two data sets can be established it will be used to provide validation of the model's ability to represent the storage system. Similarly, Figure 11.4-2 illustrates an example of how the time-lapse VSPs can be compared against the predicted spatial extent of the plume at a specified time interval. Limited 2D and 3D seismic surveys will be employed to attempt a determination of the plume location at specific times. As practical, based on the data collected, the information generated from these activities will be compared against the model using statistical methods to validate the ability of the model to accurately represent the storage site. Figure 11.4-3 presents an example of how the data from time-lapse 3D seismic surveys may be correlated against model predictions.




**Figure 11.4-1.** Comparison of the time-lapse RST logs against the predicted vertical extent of the plume at a specific time interval during the operational and PISC timeframes.




**Figure 11.4-2.** Comparison of the time-lapse VSPs against the predicted spatial extent of the plume at specific time intervals during the operational and PISC timeframes.

Sensitive, Confidential, or Privileged Information



**Figure 11.4-3.** Comparison of the time-lapse surface 3D against the predicted spatial extent of the plume at specific time intervals during the operational and PISC timeframes.

*Evaluation of Mobilized Fluids*

In addition to carbon dioxide, mobilized fluids may pose a risk to USDWs. These include native fluids that are high in TDS and therefore may impair a USDW, and fluids containing mobilized drinking water contaminants (e.g., arsenic, mercury, hydrogen sulfide). The geochemical data collected from monitoring wells will be used to demonstrate that no mobilized fluids have moved above the confining formations that act as the seal or caprock. If no such fluids are detected during the PISC period, declining pressure gradients will further limit the potential for movement of such fluids as pressures are coming to equilibrium by the end of the PISC; therefore, such fluids would not pose a risk to USDWs. In order to demonstrate non-endangerment, ADM will compare the operational and PISC period samples from layers above the injection zone, including the lowermost USDW, against the pre-injection baseline samples. This comparison will support a demonstration that no significant changes in the fluid properties of the overlying formations have occurred and that no mobilized formation fluids have moved through the sealing formation. This validation of seal integrity will help demonstrate that the injectate and/or mobilized fluids would not represent an endangerment to any USDWs. Additionally, RST logs will be used to monitor the concentrations of the reservoir fluids in the observation zone above the primary overlying Eau Claire Formation Shale seal.

*Evaluation of Reservoir Pressure*

ADM will also support the demonstration of non-endangerment to USDWs by showing that, during the PISC period, the pressure within the Mt. Simon has rapidly decreased toward pre-injection static reservoir pressure values. Because the increased pressure during injection is the primary driving force for fluid movement that may endanger a USDW, the decay in the pressure differentials will provide strong justification that the injectate does not pose a risk to any USDWs.

ADM will monitor the downhole reservoir pressure at various locations and intervals using a combination of surface and downhole pressure gauges. The measured pressure at a specific depth interval will be compared against the pressure predicted by the computational model. Agreement between the actual and the predicted values will help validate the accuracy of the model and further demonstrate non-endangerment.

*Evaluation of Passive Seismic Data*

Finally, passive seismic monitoring will be used to help further demonstrate seal formation integrity. ADM will provide seismic monitoring data showing that no seismic events have occurred that would indicate fracturing or fault activation near or through the seal formation. Combined with the AoR evaluation to assess the presence of other deep wells into the injection zone or lack thereof, this validation of seal integrity will provide further support for a demonstration that the $CO_2$ plume is no longer capable of posing endangerment to any USDWs. Figure 11.4-4 illustrates how these data could be presented. This figure shows a subset of locatable microseismic events occurring during part of the IBDP project operational period. This figure shows that a majority of the microseismic events measured occurred below the Eau Claire seal formation indicating that no fracturing or fault activation was possible within this formation. This provided additional verification of the Eau Claire formation integrity and indicates that to date the response to the imposed fluid pressures due to injection are confined to the vicinity of the injection zone and below.





**Figure 11.4-4.** Visual representation showing the microseismic activity occurring during the injection and post-injection periods (figure provided by IBDP project)

## 11.5 Monitoring well plugging and site closure plan

ADM will conduct site closure activities to meet the requirements of 40 CFR 146.93(e), as described below. ADM will submit a final Site Closure Plan and notify the permitting agency at least 120 days prior of its intent to close the site. Once the permitting agency has authorized closure of the site, ADM will: plug the injection well(s),

monitoring and verification well(s), and geophysical well(s); restore the site and move out all equipment; and submit a site closure report to the Director. The activities, as described below, present the planned activities consistent with the approved PISC for CCS#2 and proposed CCS #3. The 3-well system proposed for verification monitoring at the site is to be applicable to all 4 CCS injectors at the site. The information below pertaining to verification well plugging pertains to VW #2, and VW #3 as presented in the CCS# 2 permit and CCS #3 permit application, and is presented below for completeness purposes. A final Site Closure Plan will be submitted to the Director for approval with the notification of the intent to close the site. Details regarding plugging of the CCS#5, CCS#6, and CCS#7 injection wells are included in Section 10.

### 11.5.1 Plugging the Verification Monitor Wells

A detailed verification well plugging procedure is provided below. All casing strings in these wells are designed to be cemented to surface and no casing is planned to be retrieved at plugging.

Type and Quantity of Plugging Materials, Depth Intervals

The cements used for plugging will be tested in a lab prior to plug placement and both wet and dry samples will be collected during plugging for each plug to ensure quality of the plugs. All of the casing strings will be cut off at least 4 feet below the surface, below the plow line. A blanking plate with the required permit information will be welded to the top of the cutoff casing at the end of the plugging process.

Volume Calculations

Volumes will be calculated for each wellbore environment at the time of plugging based on desired plug diameter and length required. The methodology employed will be to:

1. Choose the following:
    a. Length of the cement plug desired.
    b. Desired setting depth of base of plug.
    c. Amount of spacer to be pumped ahead of the slurry.

2. Determine the following:
    a. Number of sacks of cement required.
    b. Volume of spacer to be pumped behind the slurry to balance the plug.
    c. Plug length before the pipe is withdrawn.
    d. Length of mud freefall in drill pipe.
    e. Displacement volume required to spot the plug.

Plugging Procedure

At the end of the serviceable life of a verification well, or when it is determined that plugging is appropriate, the well will be plugged and abandoned. In summary, the plugging procedure will consist of flushing the well with a kill weight brine fluid, conducting a final external MIT, removing all components of the completion system and then placing cement plugs along the entire length of the well. Prior to placing the cement plugs, the final MIT will consist of running casing inspection and temperature logs or suitable equivalents to confirm external mechanical integrity. If a loss of integrity is discovered, then a plan to repair using the cement squeeze method will be prepared and submitted to the agency for review and approval.

The following is an example of a detailed plugging procedure provided for VW#2 in the previously approved CCS#2 PISC, noting that all depths, cement volumes/sacks and other well-specific data are provided by example and will be modified to reflect actual well conditions. The same approved procedures are proposed for each of the VW wells at the site including the proposed and not yet installed VW#3.

1. Move in workover unit with pump and tank.

2. Record bottom hole pressure using down hole instrumentation and calculate kill fluid density. Pressure test annulus as per historic annual mechanical integrity testing (MIT) requirements.

3. Fill both tubing strings with kill weight brine as calculated from bottomhole pressure measurement (expected approximately 9.5 ppg).

4. Nipple down well head and nipple up blow-out preventers (BOPs).

5. Remove completion equipment from well. If the packer cannot be removed from the well, modify plans to cut off tubing and plug through the packer.

6. Keep hole full with workover brine of sufficient density to maintain well control.

7. Log well with cement bond log (CBL), temperature, and casing inspection log or suitable equivalent techniques to confirm external mechanical integrity.

8. Pick up work string and trip in hole to PBTD.

9. Circulate two wellbore volumes to ensure that uniform density fluid is in the well.

10. The lower section of the well will be plugged using $CO_2$ resistant cement from TD at approximately 7,150 feet to approximately 800 feet above the top of the Eau Claire formation (to approximately 4,200 ft). This will be accomplished by placing plugs in 500-foot increments. Using a density of 15.9 ppg slurry with a yield of 1.11 cf/sk, approximately 347 sacks of cement will be required (to incorporate a safety factor, 416 sacks are assumed: 2,950 ft X .1305 cu ft/ft x 1.2 excess / 1.11 cf/sk = 416 sacks). Actual cement volume will depend upon actual weight of the casing within the plugged zone. This will require at least six plugs of 500 feet in length. No more than two plugs will be set before cement is allowed to set and plug depths will be verified by setting work string down onto the plug.

11. Pull approximately ten stands of tubing (~600 ft) out and shut down overnight to wait on cement curing.

12. After appropriate wait on cement period based on hole conditions, trip in hole and tag the plug. Resume plugging procedure as before and continue placing plugs until the last plug reaches the surface.

13. Nipple down BOPs.

14. Remove all well head components and cut off all casings below the plow line.

15. Finish filling well with cement from the surface if needed. Total of approximately 465 sacks total cement used in all remaining plugs above 4,200 feet (4200 ft X .1305 cu ft/ft /1.18 cu ft/sk = 465 sks). Cement calculations based on using Class A cement from 4200 ft back to surface with a density of 15.6 ppg and a yield of 1.18 cu ft /sk. Lay down all work string, etc. Clean cellar to where a plate can be welded with well

name onto lowest casing string at least 4 feet below ground level, or as per permitting agency directive.

16. If required, install permanent marker back to surface on which all pertinent well information is inscribed.

17. Backfill cellar.

18. Rig down workover unit and move out all equipment. Haul off all workover fluids for proper disposal.

19. Reclaim surface to normal grade and reseed location.

20. Complete plugging forms and send in with charts and all lab information to the regulatory agency. Plugging report shall be certified as accurate by ADM and shall be submitted within 60 days after plugging is completed.

Note: 7,150 ft of 5 ½" 17 #/ft (7,150 ft X 0.1305 cu ft/ft = 933 cu ft) casing requires an estimated 933 cubic feet of cement to fill 14 plugs. An excess factor of 20% is to be used, as practical, for plugging the lowermost 3,000 ft of the wellbore to account for cement that might be lost to the formation, so total material used would be 423 sacks of EverCRETE $CO_2$ resistant cement (or equivalent) and 442 sack Class A/H cement.

Figure 11.5.1-1 presents an example well plugging schematic prepared for VW#2, which would be generally applicable to VW#3 noting that final plugging design will be dependent upon local geologic and other conditions at the time of plugging.





**Figure 11.5.1-1.** Generic Plugging Schematic – Verification Well Based on VW#2

### 11.5.2 Plugging the Geophysical Well(s)

At the end of the serviceable life of the well, or when plugging is determined to be appropriate, the geophysical well(s) will be plugged and abandoned. The following is an example of a detailed plugging procedure provided for GM#2 in the CCS#2 approved PISC and will generically apply to GM #4 to be installed in association with CCS #4, noting that all depths, cement volumes/sacks and other well-specific data are provided by example and will be modified to reflect actual well conditions:

1. Notify the permitting agency at least 60 days prior to plugging the well.

2. Remove monitoring equipment from well bore. Well will contain fresh water or a mixture of fresh water and native St. Peter formation water.

3. Nipple down well head and connect cement pump truck to casing. Establish injection rate with fresh water. Mix and pump 247 sacks Class A cement (15.9 ppg). Slow injection rate to ½ bbl/min as cement starts to enter St. Peter perforations. Continue squeezing cement into formation until a squeeze pressure of 500 psi is obtained. Monitor static cement level in casing for 12 hours and fill with cement if needed to top out. Plan to have 50 sacks additional cement above calculated volume on location to top out if needed. (To incorporate a safety factor, 255 sacks are assumed: 3,450 ft X 0.0873 cu ft/ft /1.18 cu ft/sk = 255 sacks.)

4. After cement cures, cut off all well head components and cut off all casings at least 4 feet below ground surface (below the plow line).

5. Install permanent marker at surface, or as required by the permitting agency.

6. Reclaim surface to normal grade and reseed location.

Figure 11.5.2-1 presents a generalized GM#4 plugging schematic based on GM#2, noting that the specific depths, formation tops, etc., will be specific to the GM#4 location and conditions encountered at the time of plugging.





**Figure 11.5.2-1.** Generic Plugging Schematic- Geophysical Monitoring Wells based on GM #2

### 11.5.3 Planned Remedial/Site Restoration Activities

To restore the site to its pre-injection condition following site closure, ADM will be guided by the state rules for plugging of wells located on leased property under The Illinois Oil and Gas Act: Title 62: Mining Chapter I: Department of Natural Resources - Part 240, Section 240.1170 - Plugging Fluid Waste Disposal and Well Site Restoration.

The following steps will be taken:

1. The free liquid fraction of the plugging fluid waste will be removed from any pits and disposed of in accordance with state and federal regulations (e.g., injection or in above ground tanks or containers pending disposal) prior to restoration. The remaining plugging fluid wastes shall be disposed of by on-site burial.

2. All plugging pits shall be filled and leveled in a manner that allows the site to be returned to original use with no subsidence or leakage of fluids, and where applicable, with sufficient compaction to support farm machinery.

3. All drilling and production equipment, machinery, and equipment debris shall be removed from the site.

4. Casing shall be cut off at least four (4) feet below the surface of the ground, and a steel plate welded on the casing or a mushroomed cap of cement approximately one (1) foot in thickness shall be placed over the casing so that the top of the cap is at least three (3) feet below ground level.

5. Any drilling rat holes shall be filled with cement to no lower than four (4) feet and no higher than three (3) feet below ground level.

6. The well site and all excavations, holes and pits shall be filled and the surface leveled.

*Site Closure Report*

A site closure report will be prepared and submitted within 90 days following site closure, documenting the following:

- Plugging of the verification and geophysical wells (and the injection well if it has not previously been plugged) as specified at 40 CFR 146.92,
- Location of any sealed injection well on a plat of survey that has been submitted to the local zoning authority, with a copy of the plat provided to the Regional Administrator of EPA Region 5,
- Notifications to state and local authorities as required at 40 CFR 146.93(f)(2),
- Records regarding the nature, composition, and volume of the injected $CO_2$, and
- Post-injection monitoring records.

ADM will record a notation to the property deed on which the injection well was located that will indicate the following:

- That the property was used for carbon dioxide sequestration,
- The name of the local agency to which a plat of survey with injection well location was submitted, as well

as the EPA Region Office to which is was submitted

- The volume of fluid injected,
- The formation(s) into which the fluid was injected, and
- The period over which the injection occurred.

The site closure report will be submitted to the permitting agency and maintained by the operator for a period of 10 years following site closure. Additionally, the operator will maintain the records collected during the PISC period for a period of 10 years after which these records will be delivered to the Director.

## 11.6 Quality Assurance and Surveillance Plan (QASP)

The Quality Assurance and Surveillance Plan is presented in Appendix C.

# 12. Emergency and Remedial Response Plan

ADM has prepared an Emergency and Remedial Response Plan (ERRP) in accordance with 40 CFR 146.94. This ERRP is being updated to include the proposed CCS#5, CCS#6 and CCS #7 locations, and updated AoR. It is being submitted as a separate attachment in the GSDT tool.

# APPENDICIES

# APPENDIX A: Financial Responsibility Documents

## 8.0 APPENDIX

To assess the financial assurance requirements[1] associated with the ADM Decatur CCS development, Petrotek combined UIC subject matter expertise with Monte Carlo modeling. The utility of a Monte Carlo approach is that it eliminates reliance on a deterministic value for future events as well as the implied certainty of those events occurring, no matter their likelihood. As has been established from prior evaluations used to assess risks associated with Class I Hazardous Injection wells, occurrence of failures is extremely rare[2,3]. Accounting for both random occurrence and stringent well construction criteria mandated by the US Environmental Protection Agency (EPA), along with using available data regarding occurrences of failure and their mechanisms, the ability to produce a single estimate of the probability of an event occurring is impractical and is likely to be erroneous[2]. Therefore, a statistical method rather than a deterministic method has been used in this evaluation to assign probabilities of outcomes that could result in costs that require financial assurance.

Monte Carlo evaluation involves stochastic modeling to define the probable liability; rather than determining a value from a single future event, Monte Carlo models thousands of discrete scenarios, each regarding a possible circumstance at any point in the future.

Monte Carlo modeling has been used for decades with wide applicability, including the evaluation environmental risk[4], with extension to CCS[5]. Monte Carlo methods have also been used extensively to provide risk estimates for the EPA[2]. The Monte Carlo method being used for the Decatur project in particular follows methodologies similar to those that have been used in the past[6,7], and also adheres to EPA guidance[8].

For the purposes of this assessment, the Monte Carlo analysis was conducted in a step-wise manner. A list of risk event groups was generated, along with their individual probability of occurrence, distribution of costs if the event occurred, and a specified time frame. For each discrete scenario, the Monte Carlo model assigns a random probability for each risk event, within each event's provided range, for each year. The cost of each risk event for each year would then be determined from its cost distribution. Total cost would then be determined by summing the costs of each individual risk event for every year, then adjusting subsequent years to a present value. The process would be repeated 100,000 times to simulate a large set of outcomes. From the 100,000 different scenarios, a distribution of possible costs is generated, from which an expected value of the liability cost can be ascertained.

### 8.1 Risk Scenario Identification

Multiple frameworks exist to identify the potential risks and hazards from the operation of a CCS project[9], most with a global perspective. The potential risks collated for the Decatur CCS project were identified using multiple, specific sources[10,11,12,13,14,15]. However, for relevancy each risk is required to be discrete and independent unto itself, as well as

relevant to ADM's project and the area in and around Decatur. For example, Quintessa Ltd., a UK based consultancy with sponsorship from the EU, generated a thorough list of over 140 different possible features, events, and processes (FEP) to assess the specific risk and performance of CCS projects[10]. This list was consulted to determine the potential relevancy and applicability of a FEP to the ADM CCS operation.

Cross-referencing was then completed with the dataset of risks provided in the environmental impact statement (EIS) created for the FutureGen CCS project[11]. FutureGen was a consortium of entities with the bulk of funding from the Department of Energy (DOE). The list of risks provided by the FutureGen EIS were generated through research of historical oil, gas, and pipeline operations throughout the United States with relevancy to handling CO2. This list of applicable risk factors was then compared with risk factors previously used to quantify the financial assurance for the ADM CCS-2 well in previously approved submittals. The final list of risks, based on this review, was then utilized for the Decatur Monte Carlo analysis:

1. **Pipeline Rupture**. Encompasses the total rupture of a pipeline due to accidental causes or intentional sabotage, during which CO2 will be released in the area local to the project as well as the surrounding vicinity.

2. **Pipeline Puncture**. Encompasses a range of scenarios to describe a hole in the pipeline, most of which are a low level of risk and cost and are easy to repair but which would cause the release of CO2 at surface. Includes a wide range of the rate of leakage, the causes of which could be due to accident or intentional sabotage.

3. **Wellhead Equipment Failure (either slow or catastrophic)**. Encompasses the accidental or intentional sabotage of a wellhead used for the injection or monitoring purposes of the project but which would allow the release of CO2 at surface. Causes are found at the extremes, through either slow corrosion or the catastrophic failure of an accidental nature or from impact, such as from a vehicle or airplane.

4. **Leakage (rapid and slow) through installed wells (injection, monitor)**. Encompasses the leakage of CO2 through loss of integrity of installed wells. Causes are wide, but inclusive of improper initial installation or through continuous physical or chemical processes. The assumption with this risk is that eventually CO2 or other fluids would escape the injection zone by means of these wells.

5. **Leakage (rapid and slow) through currently existing wells that transect through the injection of confining zone, either active or plugged**. Encompasses artificial penetrations within the areal extent of the CO2 plume. Includes historical oil and gas wells with a wide range of installation or plugging practices, some of which may be unable to withstand the elevated pressure within the plume or contact with the injected CO2 and would subsequently allow CO2 or other fluids to escape the injection zone.

6. **Leakage (rapid and slow) through undocumented wells which may transect through the injection or confining zone**. Similar to the risk event associated with

existing wells that transect the injection or confining zone, this risk event assumes that there may be wells that transect either zone, but which are unaccounted for and will be in contact with the elevated pressure of the plume or injected CO2 at some point in the future and would allow the leakage of CO2 or other fluids into adjacent strata.

7. **Leakage (rapid and slow) through the seal(s) adjacent to the injection zone through means other than existing or created wells, faults, or fractures**. Encompasses those risks which would cause injected CO2 or other fluids to leak through the caprock and into adjacent strata. The range is large, but includes a combination of elevated pressures beyond the mechanical strength of the rock coupled with thermal changes, physical changes and chemical changes which would allow the CO2 to escape. Also includes those risks associated with a seismic event not associated with the injection of CO2.

8. **Leakage through existing and assessed faults**. The risk scenario in which injected CO2 or other fluids would escape the injection zone through existing faults, whether they are open or sealed.

9. **Leakage through induced faults**. The risk scenario in which CO2 or other fluids escape the injection zone through pressure induced faulting or seismic events associated with the injection of the CO2.

The list provided in the financial assurance discussion includes the same nine risks, albeit in discrete form, such that rapid and slow leaking scenarios are differentiated for each risk, so that there are 13 total risk factors indicated[13] and used as model input.

It should be noted that each of the assumed risks will incorporate different time frames. Risks associated with surface equipment will be no longer be a relevant factor once the injection period is complete. Additionally, after injection has stopped and associated wells are plugged to regulatory standards, by definition they will no longer be a factor contributing to ongoing risk. Within the injection zone, the induced pressure caused by the injection of the CO2 into the Mt. Simon will dissipate over time; it will be the highest at the point that injection is ceased and will be the highest proximal to the injection wellbores. Over time, as the pressure dissipates, the risk of a pressure-induced leak or failure decreases as well.

The rapid and slow leakage qualifiers denote the rate at which CO2 would hypothetically have the potential to leak from the injection zone into adjacent strata, with the possibility of continuing into overlying aquifers or underground sources of drinking water (USDW). A slow leak includes scenarios wherein transfer of a given volume of CO2 may take a longer period of time to occur, whereas a rapid leak indicates the loss of a given volume extremely quickly if not catastrophically.

## 8.2 Risk Scenario Probability of Occurrence

Each identified risk was individually assigned a distribution of annual probability of occurrence. Since the outcome of the analysis is highly dependent on the probability of each risk scenario occurring, a deterministic probability would introduce bias into the analysis, whereas using a distribution for the probability alleviated this bias. Likewise, although the EPA stipulates criteria for the proper construction of injection wells which are intended to reduce the probability of a risk event occurring[3], such standards and practices do not completely eliminate all risk and low probabilities still exist of an event occurring. Additionally, each risk can have any form of causation, and a distribution of probability of occurrence can take this into account. For modeling purposes, risk causation scenarios are innumerable, so professional judgement must be utilized to provide a range of probabilities for each scenario[16].

As previously indicated, research has been done to investigate potential failure mechanisms (observed to date) for some of the limited number of Class I Hazardous Injection Wells and carbon sequestration projects located in the US and throughout the world. This work provides useful and relevant information regarding the probability distributions for different risk scenarios below ground (regarding injection and monitor well failures, leakage, and faulting)[2,3,11,12,17]. Above ground, pipeline and treatment equipment data sets exist for probability estimation within the United States and elsewhere[18,19,20,21,22,23].

For the risk scenarios previously collated and identified as relevant to the Decatur facility, the assumed probabilities of occurrence for each are noted in Table 1.

**Table 1. Risk Event Probabilities of Occurrence.**

| Risk Event | Event Description | Annual Frequency of Failure (Single Item) | |
|---|---|---|---|
| | | Low Estimate | High Estimate |
| 1 | Pipeline Rupture | Sensitive, Confidential, or Privileged Information | |
| 2 | Pipeline Puncture | | |
| 3 | Wellhead Equipment Failure | | |
| 4 | Upward rapid leakage through Installed well | | |
| 5 | Upward slow leakage through Installed well | | |
| 6 | Upward rapid leakage through deep transecting wells | | |
| 7 | Upward slow leakage through deep transecting wells | | |
| 8 | Leaks due to undocumented deep wells, high rate | | |
| 9 | Leaks due to undocumented deep wells, low rate | | |
| 10 | Upward rapid leakage through caprock | | |
| 11 | Upward slow leakage through caprock | | |
| 12 | Release through existing faults | | |
| 13 | Release through induced faults | | |

These probabilities mirror those found in the FutureGen EIS, but also incorporate a distribution instead of a deterministic forecast of probability.

For some of the risk scenarios, the probability of occurrence is only inclusive of installed equipment, such as the pipeline or an injection well; for the remainder, the risk is relevant to the whole project and is impacted by the volume of CO2 injected, any stray constituents, the increase in pressure caused by injection, and the reservoir area over which the pressure will be increased compared to in-situ conditions. For the latter case, risks are modeled for the volume of CO2 injected, the leakage mechanism, and the volume of leakage as well as impacted strata or leakage effects on the surface, human, wildlife, or environment. For those which encompass individual components such as injection or monitor wells, the risks must be multiplied by the number of wells, installed or previously existing[24,25]. Table 2 outlines the number of items for each risk category relevant to the Decatur site and project.

**Table 2. Number of Items per Risk Scenario.**

| Risk Event | Event Description | Number of Items |
|---|---|---|
| 1 | Pipeline Rupture | 3 |
| 2 | Pipeline Puncture | 3 |
| 3 | Wellhead Equipment Failure | 9 |
| 4 | Upward rapid leakage through Installed well | 9 |
| 5 | Upward slow leakage through Installed well | 9 |
| 6 | Upward rapid leakage through deep transecting wells | 100 |
| 7 | Upward slow leakage through deep transecting wells | 100 |
| 8 | Leaks due to undocumented deep wells, high rate | 1 |
| 9 | Leaks due to undocumented deep wells, low rate | 1 |
| 10 | Upward rapid leakage through caprock | 1 |
| 11 | Upward slow leakage through caprock | 1 |
| 12 | Release through existing faults | 1 |
| 13 | Release through induced faults | 1 |

## 8.3 Risk Scenario Cost Distribution

Each risk scenario identified as relevant was assigned a triangular distribution of representative costs in the event that the risk scenario occurred. Because each risk event has a range of probability of occurrence, the severity of the effects when the risk event occurs is also modeled with a distribution. As such, for each risk scenario, a minimum cost, maximum cost, and most likely cost was stipulated to generate the triangular distribution of the severity.

From the stipulated triangular distribution for a risk event, the probability density and cumulative density functions can be generated. In the event that the risk scenario occurs, the probability of occurrence would then directly translate to the associated cost of that

occurrence. Likewise, the lower the probability of the risk scenario, the lower the resulting damages in the event the scenario occurs. Triangular distributions also follow guidance from the EPA in cases for which data is infrequent and professional judgement must be used[26], such as the case with CCS within the US.

Table 3 demonstrates the distributions for each of the risk scenarios identified.

**Table 3. Triangle Distributions for Each Risk Scenario.**

| Risk Event | Event Description | Cost Estimates (Triangular Distribution) | | |
|---|---|---|---|---|
| | | Low | Most Likely | High |
| 1 | Pipeline Rupture | Sensitive, Confidential, or Privileged Information | | |
| 2 | Pipeline Puncture | | | |
| 3 | Wellhead Equipment Failure | | | |
| 4 | Upward rapid leakage through Installed well | | | |
| 5 | Upward slow leakage through Installed well | | | |
| 6 | Upward rapid leakage through transecting wells | | | |
| 7 | Upward slow leakage through transecting wells | | | |
| 8 | Leaks from undocumented deep wells, high rate | | | |
| 9 | Leaks from undocumented deep wells, low rate | | | |
| 10 | Upward rapid leakage through caprock | | | |
| 11 | Upward slow leakage through caprock | | | |
| 12 | Release through existing faults | | | |
| 13 | Release through induced faults | | | |

For each of the risk scenarios presented in Table 3, the cost distributions estimate the likely range of severity and the associated costs. In the event of a risk scenario occurring, the costs include the consequences of:

- Impacts to human and wildlife health and life within the modeled region of the Decatur project;
- Impacts to plant life and environment within proximity of the Decatur site;
- Impacts to bodies of water within proximity of the Decatur site;
- Impacts to air quality;
- Impacts to soils and sediments within the modeled region of the Decatur project;
- Impacts to groundwater or other aquifers whether actively used or under consideration.

The severity of impacts in the event of a risk scenario occurring are largely estimated from the FutureGen EIS[11] while adjusting the costs for specificity to the Decatur project site. The categories also incorporated the demographics in and around the Decatur area[27].


Costs associated with repair of equipment on surface (risk scenarios 1 - 3) are estimated from the Office of Pipeline Safety[18,19,20,21] and professional judgment. Cost estimates for

remediation of leakage (risk scenarios 4 – 13) are estimated from similar studies[11,28] and professional judgment. Due to the lack of particular CCS risk events occurring, and associated cost data, confidence in the costs is assumed by using a 100x multiplier when necessary between the low cost estimate and the high cost estimate. The multiplier, when used, is applied uniformly.

## 8.4 Monte Carlo Modeling

To demonstrate how the Monte Carlo model generates a scenario, Figure 1 represents the triangular distribution of a hypothetical risk scenario which has minimum estimate of $100,000, a most-likely estimate of $500,000 and a maximum estimate of $2,500,000. The resulting cumulative distribution function (CDF) curve is shown as the solid black line. For each scenario generated in a Monte Carlo simulation, a value between 0 and 1 would be randomly assigned (as seen on the y-axis of the CDF). Using the random value, the representative cost is then determined (as reflected on the x-axis of the CDF). Figure 1 illustrates the results from three random successive cases where this particular event was assumed to take place (65%, 39%, and 21%) and the random probability represented by the CDF curve was then used by the model to assign a cost value for that case.

**Figure 1. Monte-Carlo Method Using Random Probabilities**




This process is conducted for each risk scenario for the stipulated number of trials. The more trials that are conducted, the smoother the resulting probability distribution function (PDF) becomes. As can be seen in Figure 2, as the number of trials is increased for a hypothetical triangular distribution, the PDF curve of the distribution becomes more defined. However, although the number of trials increases the definition of the distribution,

the change in the CDF becomes smaller and smaller, so the efficiency of the Monte Carlo begins to drop, as shown in Table 4. As such, the number of trials best utilized for the Monte Carlo analysis resides in the window of good distribution definition and at the point of minimal decrease in efficiency.

**Figure 2. Triangular Distribution Definition vs Number of Trials Conducted**





**Table 4. Generated Mean from Increasing Trial Counts**

| Trial Count | Mean |
|---|---|
| 1,000 | $0.959 Million |
| 10,000 | $0.947 Million |
| 100,000 | $0.951 Million |
| 1,000,000 | $0.950 Million |

For the Decatur project, 100,000 trials were utilized for the Monte Carlo analysis. For each risk scenario, random probabilities were assigned for each year of injection as well as the 10 years of post-injection monitoring and site care. Costs for each year were adjusted upward assuming that future inflation is projected based on an average historical rate of inflation (based on the Consumer Price Index)[29]. The costs for each risk scenario in each year were then totaled to create the total liability cost for that given year; afterward, the cost for that year was adjusted to present value using a long-term bond rate, such as the 10-year or 20-year treasury bond, that best matches the duration of the cashflows from

the project[30]. The present values from all 100,000 trials of the Decatur project are shown in Figure 3, and the cumulative distribution of the trials is shown in Figure 4.

**Figure 3. Probability Distribution of the Present Values from the Monte Carlo Analysis**






**Figure 4. Cumulative Distribution of the Monte Carlo Analysis**



To obtain the probable liability cost from the calculated distribution shown in Figure 4, the expected value needs to be determined. The expected value is the weighted average of the liability costs using the probability of occurrence of each cost for weighting[31]. The expected value also corresponds to the mean value of a distribution. The expected value of the Monte Carlo analysis generated for the Decatur project is approximately $5,530,000.

In addition to the expected value, the generated distribution also provides quantitative insight into the statistical “tails” of the distribution. In this case, roughly 10% of the distribution incurs $0 cost, whereas beyond three standard deviations from the mean, the distribution is fairly flat; this long “tail” is associated with those costs which are significant, but that are extremely unlikely to occur. This agrees with the probabilities presented in section 8.2, such that some of the probabilities of an event occurring are so unlikely that the practical cost is $0 almost 100% of the time. For example, risk scenario 10 (rapid leakage through caprock) has a probable occurrence of only 3 in 100,000,000. This also mirrors a similar analysis of Class I Hazardous Injection Wells which found low probabilities for occurrences of such events that ranged from 1 in 1,000,000 and 1 in 10 quadrillion[2].

For these reasons, the expected value of the distribution works well for a practical cost of liability. Beyond that, costs may become larger, but they also have a larger chance of not occurring than actually occurring. The expected value thus strikes a balance of matching the appropriate cost with the actual probable risk of occurrence.

**References:**

1. US EPA. Preamble: Federal Requirements Under the Underground Injection Control (UIC) Program for Carbon Dioxide (CO2) Geologic Sequestration (GS) Wells; Final Rule.
2. Rish, William R. A probabilistic Risk Assessment of Class I Hazardous Waste Injection Wells.
3. US EPA. Class I Underground Injection Control Program: Study of the Risks Associated with Class I Underground Injection Wells.
4. Poulter, Susan; et al. Monte Carlo Simulation In Environmental Risk Assessment--Science, Policy And Legal Issues.
5. Trabucchi, Chiara; et al. Application of a Risk-Based Probabilistic Model (CCSvt Model) to Value Potential Risks Arising from Carbon Capture and Storage.
6. Trabucchi, Chiara; et al. A multi-disciplinary framework to monetize financial consequences arising from CCS projects and motivate effective financial responsibility.
7. Trabucchi, Chiara; et al. Valuation of Potential Risks Arising from a Model, Commercial-Scale CCS Project Site.
8. US EPA. Guiding Principles For Monte Carlo Analysis document.
9. Pawar, R; et al. Recent Advances In Risk Assessment And Risk Management Of Geologic CO2 Storage.
10. Quintessa Limited. Features, Events, and Processes Database. https://www.quintessa.org/co2fepdb/v2.0.0/
11. FutureGen EIS.
12. Shi, Ji-Quan; et al. A Methodology For CO2 Storage System Risk And Uncertainty Assessment.
13. Price, P.N. Carbon Sequestration Risks and Risk Management.
14. US EPA. Vulnerability Evaluation Framework For Geologic Sequestration Of Carbon Dioxide.
15. US EPA. Cost Analysis for the Federal Requirements Under the Underground Injection Control Program for Carbon Dioxide Geologic Sequestration Wells (Final GS Rule).
16. Hoffman, F.O.; et al. An Introductory Guide To Uncertainty Analysis In Environmental And Health Risk Assessment.
17. Jewell, Stephen. CO2 Storage Liabilities In The North Sea An Assessment Of Risks And Financial Consequences.
18. Pipeline and Hazardous Materials Safety Administration. Distribution, Transmission & Gathering, LNG, and Liquid Accident and Incident Data. Hazardous Liquid Accident Data – Pre 1986 Data Set. https://www.phmsa.dot.gov/data-and-

statistics/pipeline/distribution-transmission-gathering-lng-and-liquid-accident-and-incident-data

19. Pipeline and Hazardous Materials Safety Administration. Distribution, Transmission & Gathering, LNG, and Liquid Accident and Incident Data. Hazardous Liquid Accident Data – 1986 to January 2002 Data Set. https://www.phmsa.dot.gov/data-and-statistics/pipeline/distribution-transmission-gathering-lng-and-liquid-accident-and-incident-data
20. Pipeline and Hazardous Materials Safety Administration. Distribution, Transmission & Gathering, LNG, and Liquid Accident and Incident Data. Hazardous Liquid Accident Data – January 2002 to December 2009 Data Set. https://www.phmsa.dot.gov/data-and-statistics/pipeline/distribution-transmission-gathering-lng-and-liquid-accident-and-incident-data
21. Pipeline and Hazardous Materials Safety Administration. Distribution, Transmission & Gathering, LNG, and Liquid Accident and Incident Data. Hazardous Liquid Accident Data – January 2010 to Present Data Set. https://www.phmsa.dot.gov/data-and-statistics/pipeline/distribution-transmission-gathering-lng-and-liquid-accident-and-incident-data
22. Nussey, Clive. Failure frequencies for major failures of high pressure storage vessels at COMAH sites: A comparison of data used by HSE and the Netherlands.
23. Harper, Peter; et al. Assessment of the major hazard potential of carbon dioxide (CO2).
24. Illinois Oil and Gas Resources Interactive Map. https://isgs.illinois.edu/illinois-oil-and-gas-resources-interactive-map
25. Illinois Water Well Interactive Map. https://isgs.illinois.edu/ilwater
26. US EPA. Use of Monte Carlo Simulation in Risk Assessments. https://www.epa.gov/risk/use-monte-carlo-simulation-risk-assessments
27. Decatur Illinois 2019 Census. https://datacommons.org/place/geoId/1718823
28. Lee, Yong-Gyo; et al. Ultimate Costs of the Disaster: Seven Years after the Deepwater Horizon Oil Spill.
29. Bureau of Labor Statistics CPI Database. https://www.bls.gov/cpi/
30. United States Treasury. https://home.treasury.gov/resource-center/data-chart-center/interest-rates/TextView?type=daily_treasury_yield_curve&field_tdr_date_value=2022
31. Anderson, David R.; et al. Modern Business Statistics. Cengage Learning. 2008.

# APPENDIX B: Area of Review Well Database

**FIGURES**

**Figure B.1** – Oil and Gas Wells Within the AoR
**Figure B.2** – Water Wells Within the AoR

**TABLES**

**Table B.1** – Oil and Gas Wells Within the AoR
**Table B.2** – Water Wells Within the AoR

Sensitive, Confidential, or Privileged Information

Sensitive, Confidential, or Privileged Information

[redacted]

XY Coordinate System: NAD 1983 StatePlane Illinois East FIPS 1201 Feet

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | 120390010700 | 345 | -89.03011700 | 40.07681700 | 25-19N-1E | Myers, Theo | Fink | 1 | DAOP | 765 | Derrick Floor | 2,003 | Devonian - Siluria | 4/8/1952 |
| 2 | 120390010900 | | -88.96506400 | 40.07580600 | 27-19N-2E | Woollen Brothers | Marlow, Herbert | 2 | GAS | 731 | Digital Elevation Model | 83 | | |
| 3 | 121070003900 | | -89.15314500 | 39.93987200 | 12-17N-1W | Illinois Power Co. | | I-11 | STRUP | 592 | Ground level | 860 | | 5/31/1957 |
| 4 | 121070032000 | | -89.17030700 | 39.93174400 | 14-17N-1W | Sun Production Co (Sun Oil) | | LG-4-53 | STRUP | 596 | Ground level | 350 | | 5/26/1953 |
| 5 | 121070032100 | | -89.14420500 | 39.91750100 | 13-17N-1W | Sun Production Co (Sun Oil) | | LG-5-53 | STRUP | 601 | Ground level | 380 | No 5 Coal | 6/7/1953 |
| 6 | 121072289900 | 58031 | -89.17044600 | 39.92728400 | 14-17N-1W | Lockwood, Ronald G. | Schick | 1-L | DAP | 602 | Kelly Bushing | 1,765 | Silurian | 6/21/2006 |
| 7 | 121150000300 | | -88.99606600 | 39.87665000 | 32-17N-2E | Lincoln Oil&Gas Co | Parish | 1 | DA | 644 | Derrick Floor | 2,040 | | 12/31/1923 |
| 8 | 121150000400 | | -88.98442200 | 39.87683500 | 33-17N-2E | Meister Henry | Sticker | 1 | DA | 641 | Ground level | 2,092 | Niagaran | |
| 9 | 121150000500 | | -88.98216500 | 39.88415300 | 33-17N-2E | Wilson Syndicate | Wilson | 1 | DA | 627 | Ground level | 2,282 | Silurian | |
| 10 | 121150000600 | | -88.87796200 | 39.90209100 | 28-17N-3E | Eureka Oil Corp | Rhodes, Wm. | 1 | DA | 687 | Derrick Floor | 2,248 | Silurian | 12/31/1939 |
| 11 | 121150000800 | | -88.99519400 | 39.87128100 | 5-16N-2E | Lincoln Oil Well Serv Co | Powers, Caroline | 1 | DA | 620 | Ground level | 2,066 | Hunton | 12/31/1921 |
| 12 | 121150000900 | | -88.99848900 | 39.85232000 | 8-16N-2E | No Company | Powers, Geo. W. | 2 | UNK | 599 | Digital Elevation Model | 720 | | |
| 13 | 121150001300 | | -88.97989900 | 39.78329700 | 3-15N-2E | Werner Bros | Peterson | 1 | DA | 705 | Topographic map | 1,085 | | 12/31/1937 |
| 14 | 121150001400 | | -89.01205800 | 39.75048700 | 17-15N-2E | Williams J H | Cater, Lovina S. #1 | 1 | DA | 686 | Derrick Floor | 2,357 | Silurian | 1/2/1941 |
| 15 | 121150001500 | | -88.95379700 | 40.04293200 | 2-18N-2E | Alco Oil & Gas Corp. | Grady, T. C. | | UNK | 714 | Ground level | 626 | | |
| 16 | 121150001600 | | -88.97751100 | 39.88607200 | 33-17N-2E | Arcadia Refining Co. | Wilson | 1 | DA | 620 | Ground level | 1,862 | Fern Glen | |
| 17 | 121150001700 | | -88.82305900 | 39.85775400 | 11-16N-3E | Jarvis, S. D. etal | Veech, Sarah J. | 1 | DA | 693 | Rotary table | 2,366 | Devonian | 2/29/1940 |
| 18 | 121150001800 | | -88.99850800 | 39.86317200 | 5-16N-2E | Atlantic Oil & Gas | Bledsoe | 1 | DA | 614 | Ground level | 2,062 | | 12/31/1921 |
| 19 | 121150001900 | | -88.99755800 | 39.87482700 | 5-16N-2E | Powers G W | Pfeiffer | | DA | 667 | Ground level | 804 | | |
| 20 | 121150002000 | | -88.99749800 | 39.87124900 | 5-16N-2E | Lincoln Oil Well Serv Co | Powers, Caroline | 2 | DA | 629 | Ground level | 2,800 | Kimmswick | 12/31/1921 |
| 21 | 121150002400 | | -89.00193300 | 39.84227900 | 17-16N-2E | Unknown | Dipper, John | 1 | DA | 618 | Derrick Floor | 2,125 | Silurian | 4/6/1939 |
| 22 | 121150002600 | | -88.99022800 | 39.73378600 | 21-15N-2E | Decatur Oil & Gas Co | Cook, L. W. #1 | 1 | DAO | 731 | Derrick Floor | 3,175 | Galena | 12/31/1938 |
| 23 | 121150002800 | | -89.01951900 | 39.89805300 | 30-17N-2E | Sun Oil Company | Powers, J. | 1 | DA | 688 | Derrick Floor | 2,991 | St Peter | 12/31/1937 |
| 24 | 121150002900 | | -89.01840500 | 39.88445300 | 31-17N-2E | Powers, C. G., Etal | Stephenson | 1 | DA | 682 | Ground level | 2,109 | Silurian | 11/30/1924 |
| 25 | 121150003000 | | -88.98317700 | 39.73556200 | 21-15N-2E | Margrave Bros | Riley, Anna #1 | 1 | DA | 738 | Ground level | 1,330 | | 1/31/1942 |
| 26 | 121150003200 | | -89.04633300 | 39.78088400 | 1-15N-1E | Hoosier Drilling Company | Jockisch, David | 1 | DAOP | 675 | Ground level | 2,161 | Silurian | 7/31/1955 |
| 27 | 121150003300 | 2602 | -89.06288300 | 39.83537100 | 14-16N-1E | Cartmill, William | Gouge, Iva | 1 | OILP | 683 | Derrick Floor | 2,100 | Silurian | 6/30/1955 |
| 28 | 121150003600 | | -88.76819900 | 39.86617600 | 5-16N-4E | Paco Petroleum Corp. | Wagner, Lynn | 1 | DA | 730 | Derrick Floor | 2,445 | Silurian | 7/31/1955 |
| 29 | 121150003700 | | -88.82322900 | 39.86880100 | 2-16N-3E | Walker Lester | Chapman | 1 | OILP | 694 | Digital Elevation Model | 2,331 | Devonian | 7/31/1955 |
| 30 | 121150003800 | | -88.77290500 | 39.86618300 | 5-16N-4E | Carroll, Dell | Shirey, Bryce L. | 1 | DAP | 734 | Kelly Bushing | 2,422 | Silurian | 7/31/1955 |
| 31 | 121150003900 | 2835 | -88.76705900 | 39.85975100 | 8-16N-4E | Athene Development Company, Inc. | Vulgamott | 1 | DAP | 731 | Kelly Bushing | 2,444 | Silurian | 5/31/1955 |
| 32 | 121150004500 | | -88.84012900 | 39.86489200 | 2-16N-3E | Potsch, John P. Sr. | Shambaugh | 1 | DAP | 690 | Digital Elevation Model | 2,323 | Silurian | 1/31/1956 |
| 33 | 121150005000 | | -88.77290000 | 39.83696400 | 17-16N-4E | Engle, George S. | Krall, Clarence | 1-A | DAOP | 740 | Derrick Floor | 2,488 | Devonian | 8/13/1956 |
| 34 | 121150005100 | 1968 | -88.92851000 | 39.91287900 | 24-17N-2E | Mazzarino | Schwarz | 1 | DAP | 664 | Derrick Floor | 2,215 | Silurian | 6/22/1956 |
| 35 | 121150005101 | 1825 | -88.92851000 | 39.91287900 | 24-17N-2E | Atkins & Hale | Schwarze | 1 | OILP | 664 | Derrick Floor | 2,209 | | 11/14/1963 |
| 36 | 121150005200 | 1649 | -88.92609900 | 39.90745800 | 24-17N-2E | Atkins and Hale | Casey | 2 | DAP | 685 | Kelly Bushing | 2,184 | Silurian | 10/10/1964 |
| 37 | 121150005201 | 17334 | -88.92609900 | 39.90745800 | 24-17N-2E | Barger Engineering, Inc. | Fold, Baby | 3 | OIL | 665 | Kelly Bushing | 2,204 | Silurian | 10/13/1982 |
| 38 | 121150005300 | | -88.82086800 | 39.86885400 | 1-16N-3E | Walker Lester | Hawkins | 2 | OILP | 695 | Digital Elevation Model | 2,307 | Devonian | 6/30/1956 |
| 39 | 121150005400 | 3386 | -89.00323200 | 39.89461800 | 29-17N-2E | Richardson, M. H. | Troutman | 1 | DAP | 676 | Ground level | 2,625 | St Peter | 8/31/1956 |
| 40 | 121150005500 | 3537 | -89.02188800 | 39.91267700 | 19-17N-2E | Kewanee Oil Company | Powers | 1 | DAOP | 702 | Derrick Floor | 2,665 | St Peter | 9/30/1956 |
| 41 | 121150005600 | | -89.07308300 | 39.88667100 | 34-17N-1E | Cameron, W. A. | Troutman, Elizabeth | 1 | DAP | 677 | Derrick Floor | 2,073 | Silurian | 10/31/1956 |
| 42 | 121150005900 | | -88.79756600 | 39.97945600 | 31-18N-4E | Myers, Theodore F. | Ross, Charles M. | 1 | DAP | 637 | Derrick Floor | 2,130 | Silurian | 5/15/1957 |
| 43 | 121150006000 | 1075 | -89.05834800 | 39.83927900 | 14-16N-1E | Dell Carroll Oil Pro | Milnes, C. E. | 1 | OILP | 686 | Derrick Floor | 2,076 | Devonian | 7/15/1957 |
| 44 | 121150006100 | 1380 | -88.87834400 | 39.92533300 | 16-17N-3E | Engle, George S. | Hirsch-Babcock-I.C.R.R. Community | 1 | DAP | 684 | Derrick Floor | 2,266 | Silurian | 6/26/1957 |
| 45 | 121150006101 | 2062 | -88.87834400 | 39.92533300 | 16-17N-3E | Atkins & Hale | Hirsch Community | 1 | DAP | 684 | Derrick Floor | 2,270 | | 12/22/1963 |
| 46 | 121150006200 | 1815 | -89.05836800 | 39.84294200 | 14-16N-1E | Dell Carroll Oil Pro | Crabtree, Elva A. #1 | 1 | DAP | 681 | Ground level | 2,071 | Silurian | 7/31/1957 |
| 47 | 121150006500 | 2134 | -89.05606400 | 39.83749600 | 14-16N-1E | Dell Carroll Oil Pro | Krall, A. F. | 2 | OIL | 684 | Derrick Floor | 2,080 | Silurian | 8/31/1957 |
| 48 | 121150006700 | | -89.05600600 | 39.83017600 | 23-16N-1E | Dell Carroll Oil Pro | Schiwek-Albverson-Smith Com | 1 | OILP | 639 | Ground level | 2,053 | Silurian | 9/30/1957 |
| 49 | 121150007100 | | -88.77524300 | 39.86797700 | 5-16N-4E | Botts, Elton M. & Assoc. | Davis | 1 | DAOP | 730 | Kelly Bushing | 2,422 | Silurian | 9/30/1957 |
| 50 | 121150007300 | | -89.05838100 | 39.84656600 | 11-16N-1E | Carter E M | Crabtree, W. B. #1 | 1 | DA | 705 | Ground level | 2,105 | Devonian | 10/31/1957 |
| 51 | 121150007400 | 2848 | -89.06297400 | 39.83738400 | 14-16N-1E | Edwards, Ralph H. | Hanks & Warner Comm. #1 | 1 | OILP | 677 | Kelly Bushing | 2,060 | Silurian | 1/20/1958 |
| 52 | 121150007500 | 3015 | -89.05131400 | 39.83391400 | 14-16N-1E | Dell Carroll Oil Pro | Schiwek "B" Comm. #1 | 1 | DAP | 662 | Ground level | 2,089 | Devonian | 11/30/1957 |
| 53 | 121150007600 | 3088 | -89.05133800 | 39.83757100 | 14-16N-1E | Knierim, Donald P. | Joynt, R. O. #1 | 1 | DAP | 686 | Ground level | 2,107 | Devonian | 11/30/1957 |
| 54 | 121150007700 | | -89.05128400 | 39.83026000 | 23-16N-1E | Knierim, Donald P. | Hanks Comm | 1 | DAP | 645 | Ground level | 2,097 | Devonian | 10/31/1957 |
| 55 | 121150007800 | | -89.06057500 | 39.83009600 | 23-16N-1E | Warnick & Bennett | Vogel, Charles Comm | 1 | DA | 655 | Kelly Bushing | 2,059 | Silurian | 12/31/1957 |
| 56 | 121150008300 | 506 | -89.05824200 | 39.83563800 | 14-16N-1E | Dell Carroll Oil Pro | Krall, A. F. #3 | 3 | DAP | 691 | Rotary table | 2,095 | Silurian | 3/31/1958 |
| 57 | 121150008400 | | -89.05364900 | 39.85027100 | 11-16N-1E | Carroll, Dell | Jackson, James W. #1 | 1 | OILP | 691 | Derrick Floor | 2,096 | Silurian | 4/30/1958 |
| 58 | 121150008500 | 611 | -89.03455500 | 39.89255500 | 25-17N-1E | George, T. W. Trust | Parish, L. R. | 1 | DAP | 680 | Derrick Floor | 2,060 | Silurian | 4/30/1958 |
| 59 | 121150008600 | 507 | -89.05603900 | 39.84089000 | 14-16N-1E | Dell Carroll Oil Pro | Milnes, C. E. #2 | 2 | DAP | 689 | Digital Elevation Model | 2,089 | Silurian | 3/31/1958 |
| 60 | 121150008700 | 1215 | -89.07216600 | 39.83182000 | 15-16N-1E | Partlow & Cochonour | Webb-Davis #1 | 1 | DAP | 650 | Derrick Floor | 2,034 | Silurian | 6/30/1958 |
| 61 | 121150009800 | 2060 | -88.86758400 | 39.91999000 | 21-17N-3E | Atkins & Hale | Pujol - Cundiff | 1 | DAP | 683 | Kelly Bushing | 2,240 | Silurian | 11/25/1963 |
| 62 | 121150009900 | 681 | -89.03702700 | 39.78699700 | 1-15N-1E | Sun Production Co (Sun Oil) | Johner, Fred | 1 | DAO | 689 | Derrick Floor | 2,236 | Silurian | 5/3/1953 |
| 63 | 121150009901 | 42352 | -89.03702700 | 39.78699700 | 1-15N-1E | Watters Oil & Gas Co. | Brown, Elva W. | 1 | OILP | 693 | Kelly Bushing | 2,240 | Silurian | 9/20/1988 |
| 64 | 121150011600 | | -89.03686400 | 39.77100200 | 12-15N-1E | Alco Oil & Gas Corp. | Cobb | | DA | 699 | Digital Elevation Model | 1,936 | | 12/31/1921 |

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 65 | 121150011900 | | -88.99344800 | 39.76271000 | 9-15N-2E | Slagter, Arthur J., Jr. | Shively, C. B. #1 | 1 | DAP | 713 | Derrick Floor | 2,370 | Silurian | 7/31/1949 |
| 66 | 121150012100 | | -89.00942200 | 39.74139200 | 20-15N-2E | The Pure Oil Company | DeVore M. K. #1 | 1 | DAP | 706 | Derrick Floor | 2,452 | Silurian | 9/10/1951 |
| 67 | 121150012200 | | -88.99029000 | 39.73560800 | 21-15N-2E | Columbus Exploration | Hogan, R. #1 | 1 | DAP | 730 | Derrick Floor | 1,355 | | 9/30/1950 |
| 68 | 121150012300 | | -88.99752400 | 39.73746600 | 21-15N-2E | Hardin, C. G. | Hogan, Robert #1 | 1 | DAP | 730 | Ground level | 1,437 | | 2/28/1955 |
| 69 | 121150012400 | | -88.98807900 | 39.73923300 | 21-15N-2E | Columbus Exploration | Riley, Agnes et al #1 | 1 | DAP | 736 | Derrick Floor | 1,400 | Ste Genevieve | 2/28/1951 |
| 70 | 121150012900 | 2322 | -88.84756100 | 39.92765600 | 15-17N-3E | Atkins and Hale | Rowe | 1-A | DAOP | 690 | Kelly Bushing | 2,271 | Silurian | 12/13/1963 |
| 71 | 121150013000 | | -88.86420500 | 39.79022700 | 3-15N-3E | Bridges Basin Oil | Fryman, Leroy | 1 | DA | 636 | Digital Elevation Model | 1,385 | | 7/31/1949 |
| 72 | 121150015500 | | -89.12649000 | 39.85358400 | 7-16N-1E | McCumber, Don | Bruce #1 | 1 | DAP | 618 | Derrick Floor | 1,927 | Silurian | 10/31/1954 |
| 73 | 121150016900 | 2255 | -89.06061100 | 39.83742200 | 14-16N-1E | Dell Carroll Oil Pro | Krall, A. F. | 1 | OILP | 681 | Derrick Floor | 2,080 | Silurian | 7/31/1954 |
| 74 | 121150017000 | 2662 | -89.05136100 | 39.84122600 | 14-16N-1E | Dell Carroll Oil Pro | Watts, R. W. #1 | 1 | DAP | 690 | Ground level | 2,118 | Silurian | 9/30/1954 |
| 75 | 121150017600 | | -89.05341300 | 39.81578000 | 26-16N-1E | Keystone Oil Company | Rhoderick | 1 | DA | 601 | Ground level | 2,090 | Silurian | 9/30/1954 |
| 76 | 121150018000 | | -89.08147400 | 39.81006800 | 27-16N-1E | Shulman Bros & Ohio Oil | Scroggin-Matthews Comm. | 1 | DAOP | 591 | Derrick Floor | 2,010 | Silurian | 5/3/1954 |
| 77 | 121150018100 | | -89.00015100 | 39.74651700 | 17-15N-2E | | School | | GASP | 730 | Topographic map | 135 | | 1/1/1944 |
| 78 | 121150018400 | | -89.07907500 | 39.79181000 | 34-16N-1E | National Associated Petroleum Co. | Brown, Charles E. | 1 | DAP | 653 | Kelly Bushing | 2,085 | Silurian | 1/31/1955 |
| 79 | 121150018500 | | -88.98692500 | 39.78772700 | 4-15N-2E | Morris | Morris, M. E. | | GAS | 698 | Topographic map | 112 | | 12/31/1923 |
| 80 | 121150021600 | 2778 | -88.99759100 | 39.87481000 | 5-16N-2E | Richardson, M. H. | Hood, Paul | 1 | OILP | 620 | Ground level | 2,037 | Silurian | 10/8/1954 |
| 81 | 121150021700 | | -88.99295700 | 39.87306500 | 5-16N-2E | Welker Oil Co., Ltd. | Trump | 1 | OILP | 635 | Ground level | 2,052 | Silurian | 9/7/1953 |
| 82 | 121150026300 | | -89.02530000 | 39.81838000 | 19-16N-2E | Keystone Oil Company | Binkley | 1 | DAOP | 651 | Kelly Bushing | 2,115 | Silurian | 12/31/1954 |
| 83 | 121150031900 | | -88.99454300 | 39.81145900 | 29-16N-2E | Pulliam & Reed | Gammon, C. O. | | GAS | 667 | Topographic map | 180 | | 12/8/1948 |
| 84 | 121150032900 | | -88.81135000 | 39.87105300 | 1-16N-3E | Richey Ancil A | Blickenstaff, Cordia | 1 | OILP | 688 | Digital Elevation Model | 2,300 | Devonian | 10/31/1954 |
| 85 | 121150033000 | | -88.81841400 | 39.86517400 | 1-16N-3E | Walker Lester | Harrouff | 1 | OILP | 693 | Kelly Bushing | 2,281 | Devonian | 5/31/1954 |
| 86 | 121150033100 | | -88.81369400 | 39.86911300 | 1-16N-3E | Walker Lester | Hawkins | 1 | OILP | 685 | Ground level | 2,303 | Silurian | 4/1/1954 |
| 87 | 121150033200 | | -88.82317600 | 39.86501100 | 2-16N-3E | Walker Lester | Veech, Lewis | 1 | OILP | 693 | Ground level | 2,290 | Devonian | 5/26/1954 |
| 88 | 121150033300 | | -88.82336900 | 39.87835500 | 2-16N-3E | Walker Lester | Wheeler | 1 | DAOP | 688 | Derrick Floor | 2,328 | Silurian | 12/12/1953 |
| 89 | 121150033301 | | -88.82336900 | 39.87835500 | 2-16N-3E | Day R A | Ginder Comm. | 1 | OILP | 688 | Derrick Floor | 2,286 | | 11/8/1961 |
| 90 | 121150038000 | | -88.82078200 | 39.86325000 | 12-16N-3E | Runyon, Floyd L. | Veech, Otto | 1 | OILP | 697 | Kelly Bushing | 2,321 | Devonian | 5/31/1954 |
| 91 | 121150041400 | | -88.90060000 | 39.82196200 | 19-16N-3E | Bernard-Clink | Taylor, L. P. | 1 | GAS | 670 | Ground level | 65 | | 10/31/1954 |
| 92 | 121150041800 | | -88.81069600 | 39.81446400 | 25-16N-3E | Runyon, Floyd L. | Wilkerson, D. F. | 1 | DAOP | 708 | Derrick Floor | 2,523 | Silurian | 2/28/1951 |
| 93 | 121150042000 | | -88.88379400 | 39.80814600 | 29-16N-3E | Robinson, H. F., Inc. | Heckel | 1 | DAP | 650 | Derrick Floor | 2,417 | Devonian | 7/31/1951 |
| 94 | 121150043500 | | -88.80176600 | 39.86412700 | 7-16N-4E | Johnson, Sr., Morris H. C. | Sievers, Ray | 1 | DAP | 690 | Derrick Floor | 2,388 | Silurian | 6/30/1954 |
| 95 | 121150043600 | | -88.79204700 | 39.86425700 | 7-16N-4E | Stevens C | Wagner, W. H. | 1 | TAOP | 684 | Derrick Floor | 2,334 | Devonian | 1/24/1955 |
| 96 | 121150046700 | | -89.04667100 | 39.93230000 | 13-17N-1E | Nation Oil & Duncan | Brown, Robert | 1 | DAP | 694 | Derrick Floor | 2,098 | Silurian | 7/31/1954 |
| 97 | 121150047800 | | -89.08993000 | 39.89197300 | 28-17N-1E | Marathon Oil Company | Hamilton, M. C. et al | 1 | DAP | 664 | Ground level | 2,113 | Silurian | 9/30/1950 |
| 98 | 121150048200 | | -89.05626100 | 39.88863700 | 35-17N-1E | Welker Oil Co., Ltd. | Parish, L. R. | 1 | DAP | 677 | Ground level | 2,054 | Silurian | 8/31/1954 |
| 99 | 121150050100 | | -88.97551800 | 39.93180800 | 16-17N-2E | Proctor, Richard H. | Hamman, Esther | 1 | DAP | 654 | Ground level | 2,103 | Silurian | 8/31/1954 |
| 100 | 121150050400 | | -89.00090000 | 39.90558800 | 20-17N-2E | Richey Ancil A | Merryman, G. R. | 1 | DAP | 685 | Digital Elevation Model | 2,023 | Silurian | 10/31/1954 |
| 101 | 121150050900 | | -88.99158600 | 39.89121500 | 28-17N-2E | Richardson, M. H. | German, Blanche | 1 | DAP | 693 | Rotary table | 2,080 | Silurian | 11/30/1954 |
| 102 | 121150051100 | | -89.02312000 | 39.87800500 | 31-17N-2E | S & W Development Co | Moody-Friend Comm. | 1 | DAP | 677 | Ground level | 2,050 | Silurian | 8/31/1954 |
| 103 | 121150051200 | | -89.00077300 | 39.88018100 | 32-17N-2E | Runyon, Floyd L. | Daut, P. J. | 2 | OILP | 638 | Derrick Floor | 1,981 | Silurian | 10/31/1954 |
| 104 | 121150051300 | | -88.99609700 | 39.88027400 | 32-17N-2E | Runyon, Floyd L. | Duncan, D. | 1 | DAP | 643 | Ground level | 2,065 | Silurian | 8/31/1954 |
| 105 | 121150051400 | | -88.99605500 | 39.87665900 | 32-17N-2E | Runyon, Floyd L. | Lyster Comm | 1 | OILP | 649 | Kelly Bushing | 2,061 | Silurian | 8/31/1954 |
| 106 | 121150051500 | | -88.99852700 | 39.88564500 | 32-17N-2E | Richardson, M. H. | Trimby, Benjamin | 1 | OILP | 653 | Digital Elevation Model | 2,074 | Silurian | 9/30/1954 |
| 107 | 121150051600 | | -88.97983500 | 39.88965400 | 33-17N-2E | Richardson, M. H. | Duncan, Dora | 1 | DAOP | 282 | Derrick Floor | 2,106 | Silurian | 10/31/1954 |
| 108 | 121150051800 | | -88.98688700 | 39.88800100 | 33-17N-2E | Herring, Herman C. | Hays, T. E. | 1 | DAP | 677 | Derrick Floor | 2,101 | Silurian | 4/30/1952 |
| 109 | 121150052000 | | -88.97747000 | 39.88243700 | 33-17N-2E | Richardson, M. H. | Keller | 1 | DAP | 639 | Digital Elevation Model | 2,105 | Silurian | 9/30/1954 |
| 110 | 121150052100 | 109 | -88.99136600 | 39.87668300 | 33-17N-2E | Herring, Herman C. | Parish etal | 1 | DAP | 649 | Derrick Floor | 2,070 | Silurian | 1/31/1949 |
| 111 | 121150052101 | 1971 | -88.99136600 | 39.87668300 | 33-17N-2E | Runyon, Floyd L. | Parish, Ruth | 1 | OILP | 649 | Derrick Floor | 2,070 | | 8/7/1954 |
| 112 | 121150053500 | 1771 | -88.81883000 | 39.92448800 | 13-17N-3E | Unger, John | Blenz | 1 | DAP | 686 | Kelly Bushing | 2,315 | Silurian | 7/7/1954 |
| 113 | 121150053900 | 1528 | -88.88761700 | 39.90854000 | 20-17N-3E | Myers, Theodore F. | Kuny | 1 | DAP | 688 | Kelly Bushing | 2,226 | Silurian | 7/12/1954 |
| 114 | 121150054000 | | -88.88289100 | 39.91049900 | 20-17N-3E | Robinson, H. F., Inc. | Stout, Bertha | 1 | DAOP | 689 | Derrick Floor | 2,239 | Silurian | 1/31/1955 |
| 115 | 121150054300 | 1560 | -88.86877600 | 39.91815000 | 21-17N-3E | Breeze, F. E. | Phillips, Roy | 1 | DAP | 670 | Derrick Floor | 2,233 | Devonian | 8/5/1949 |
| 116 | 121150054301 | 2063 | -88.86877600 | 39.91815000 | 21-17N-3E | Atkins & Hale | Phillips, Roy | 1 | DAP | 670 | Derrick Floor | 2,275 | | 12/18/1963 |
| 117 | 121150054600 | 2230 | -88.84480100 | 39.89659600 | 27-17N-3E | Breeze, F. E. & Bayless | Hiser | 1 | DAP | 695 | Kelly Bushing | 2,308 | Silurian | 11/17/1948 |
| 118 | 121150054700 | | -88.87803700 | 39.90294700 | 28-17N-3E | Davis, C. G. | Clements, Belle | 1 | DAO | 678 | Derrick Floor | 2,344 | Devonian | 5/5/1947 |
| 119 | 121150054800 | | -88.88033900 | 39.89950900 | 29-17N-3E | Davis, C. G. | Boyd | 1 | DA | 686 | Derrick Floor | 2,282 | Silurian | 7/31/1946 |
| 120 | 121150054900 | | -88.89457800 | 39.90102100 | 29-17N-3E | Welker Oil Co., Ltd. | Boyd, A. T. | 1 | OILP | 680 | Ground level | 2,240 | Silurian | 3/31/1954 |
| 121 | 121150055000 | | -88.87986700 | 39.90595700 | 29-17N-3E | Costello Leonard J | McKee, John H., Sr. | 1 | DA | 685 | Digital Elevation Model | 2,251 | Devonian | 11/30/1946 |
| 122 | 121150055800 | | -88.86179800 | 39.87983000 | 33-17N-3E | Pearcy Ed B | Reas Bridge Park | 1 | UNK | 613 | Digital Elevation Model | 35 | | 12/31/1936 |
| 123 | 121150055900 | 225 | -88.81133700 | 39.88590300 | 36-17N-3E | National Associated Petroleum Co. | Nickey, William H. | 1 | DAP | 678 | Kelly Bushing | 2,331 | Silurian | 12/20/1954 |
| 124 | 121150056300 | | -88.75587600 | 39.91956700 | 21-17N-4E | Myers, Theo | McLaughlin | 1 | DAOP | 658 | Ground level | 2,292 | Silurian | 11/8/1954 |
| 125 | 121150056600 | | -88.76309600 | 39.88815600 | 33-17N-4E | Richardson, M. H. | Greenberg, Ike | 1 | DAOP | 686 | Ground level | 2,368 | Devonian | 11/1/1954 |
| 126 | 121150059000 | | -88.83551400 | 40.03174100 | 11-18N-3E | Richardson, M. H. | Wilson, C. A. | 1 | DAP | 695 | Derrick Floor | 2,069 | Silurian | 9/30/1954 |
| 127 | 121150060500 | | -88.99959800 | 39.77091200 | 5-15N-2E | Alco Oil & Gas Corp. | Miller, Carroll (Leland Bandy) | | GAS | 705 | Ground level | 1 | | |
| 128 | 121150060900 | 101 | -88.98254100 | 39.88363000 | 33-17N-2E | Roth, A. N. & Bartelmay, R. | Pollack, M. D. etal | 1 | DA | 648 | Derrick Floor | 2,176 | Silurian | 1/31/1949 |

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 129 | 121150061100 | 1540 | -89.06511900 | 39.81474200 | 26-16N-1E | Mansfield, Harold L. | Mathews, J. P. | 1 | DAP | 609 | Derrick Floor | 2,040 | Silurian | 7/31/1958 |
| 130 | 121150061200 | 2355 | -89.03221900 | 39.86885700 | 1-16N-1E | Knierim, Donald P. | Gulick, O. R. #1 | 1 | OILP | 680 | Kelly Bushing | 2,026 | Silurian | 3/9/1959 |
| 131 | 121150061800 | | -88.88278700 | 39.87749400 | 5-16N-3E | Burt, Luther R. | Rowe | | GAS | 675 | Ground level | 88 | | 12/31/1932 |
| 132 | 121150062000 | | -88.77289700 | 39.83691700 | 17-16N-4E | Engle, George S. | Krall, Clarence | 1 | JAP | 740 | Digital Elevation Model | 2,450 | Ste Genevieve | 5/31/1956 |
| 133 | 121150062700 | 2868 | -89.06964900 | 39.79735900 | 34-16N-1E | Reeter & Hirstein | Smith-Burns-Hobbs Comm. | 1 | DAP | 645 | Digital Elevation Model | 2,110 | Silurian | 11/30/1958 |
| 134 | 121150063400 | 550 | -88.77828600 | 39.76689100 | 8-15N-4E | Richardson, M. H. | Mills estate | 1 | DAOP | 722 | Ground level | 2,263 | Devonian | 5/25/1959 |
| 135 | 121150063500 | 70 | -89.04675000 | 39.85396800 | 12-16N-1E | Eager, Charles W. | Alsup #1 | 1 | OILP | 689 | Kelly Bushing | 2,070 | Silurian | 3/31/1959 |
| 136 | 121150063600 | 1033 | -89.04304600 | 39.85404200 | 12-16N-1E | Eager, Charles W. | Alsup #2 | 2 | OILP | 683 | Digital Elevation Model | 2,076 | Silurian | 5/31/1959 |
| 137 | 121150063900 | 1756 | -89.03467400 | 39.86748900 | 1-16N-1E | Carroll, Dell | Sawyer & Gulick Comm. | 1 | OIL | 690 | Kelly Bushing | 2,029 | | 9/14/1959 |
| 138 | 121150063901 | 20568 | -89.03467400 | 39.86748900 | 1-16N-1E | Carroll, Dell | Sawyer & Gulick Comm. | 1 | INJW | 690 | Kelly Bushing | 2,029 | Silurian | 9/6/1982 |
| 139 | 121150064200 | 1463 | -89.04675300 | 39.85120000 | 12-16N-1E | Dell Carroll Oil Pro | Travis, Ida M. #1 | 1 | OIL | 692 | Ground level | 2,081 | Silurian | 6/30/1960 |
| 140 | 121150064300 | 1464 | -89.05596500 | 39.83561000 | 14-16N-1E | Dell Carroll Oil Pro | Krall, A. F. #4 | 4 | DAP | 683 | Ground level | 2,117 | Silurian | 6/30/1960 |
| 141 | 121150064400 | 1752 | -89.09559500 | 39.81534800 | 28-16N-1E | Pure Oil Company | Whitley Consolidated | 1 | OILP | 628 | Derrick Floor | 2,002 | Silurian | 7/31/1960 |
| 142 | 121150064500 | 2080 | -89.07450900 | 39.81743700 | 22-16N-1E | Kaufman, E.H. | Mathews, J. D. | 1 | DAP | 591 | Derrick Floor | 2,016 | Silurian | 8/31/1960 |
| 143 | 121150064700 | | -89.04911900 | 39.85033100 | 11-16N-1E | Dell Carroll Oil Pro | Jackson, James W. #2 | 1 | DAP | 693 | Kelly Bushing | 2,089 | Silurian | 8/31/1960 |
| 144 | 121150064800 | 2002 | -89.10028600 | 39.81160500 | 28-16N-1E | Pure Oil Company | Whitley, Mabel | 1 | DAP | 623 | Derrick Floor | 1,995 | Silurian | 8/31/1960 |
| 145 | 121150064801 | 2068 | -89.10028600 | 39.81160500 | 28-16N-1E | Atkins and Hale | Whitley, Mabel | 3 | OILP | 623 | Derrick Floor | 2,022 | | 10/11/1962 |
| 146 | 121150064900 | 2110 | -89.09321800 | 39.81722000 | 21-16N-1E | Texaco, Inc. | Rothwell, E. K. | 1 | OIL | 632 | Derrick Floor | 2,000 | Silurian | 10/13/1960 |
| 147 | 121150064901 | 1912 | -89.09321800 | 39.81722000 | 21-16N-1E | Texaco, Inc. | Rothwell, E. K. | 1 | OILP | 632 | Derrick Floor | 2,064 | | 8/31/1962 |
| 148 | 121150065000 | | -89.16228000 | 39.88097000 | 35-17N-1W | Illinois Power Co. | | I-8 | STRUP | 600 | Ground level | 825 | | 5/31/1957 |
| 149 | 121150065300 | 2446 | -89.10538500 | 39.80607400 | 29-16N-1E | Cole, Clyde | Hall, Alonzo | 1 | DAP | 604 | Kelly Bushing | 1,980 | Silurian | 10/31/1960 |
| 150 | 121150065700 | 2856 | -88.79440900 | 39.86236900 | 7-16N-4E | Jordan, James | Sensebaugh | 1 | DA | 690 | Rotary table | 2,342 | Devonian | 3/31/1961 |
| 151 | 121150065800 | 70 | -89.10496500 | 39.81336300 | 29-16N-1E | Partlow & Cochonour | Alsup, R. D. | 1 | DAP | 621 | Kelly Bushing | 1,978 | Silurian | 12/31/1960 |
| 152 | 121150065801 | 1981 | -89.10496500 | 39.81336300 | 29-16N-1E | Collins Brothers Oil Company | Alsup, Raymond | 1 | DAP | 621 | Kelly Bushing | 2,024 | | 9/29/1962 |
| 153 | 121150065900 | 217 | -89.07404100 | 39.81011600 | 27-16N-1E | McKinney, Willard | Clifton | 1 | DAP | 595 | Ground level | 2,024 | Silurian | 1/31/1961 |
| 154 | 121150066300 | 1244 | -89.05374800 | 39.84484800 | 14-16N-1E | Dell Carroll Oil Pro | Milnes, C. E. "A Lease" #1 | 1 | DAP | 711 | Derrick Floor | 2,094 | Silurian | 6/30/1961 |
| 155 | 121150066500 | 1839 | -88.82097300 | 39.89681100 | 25-17N-3E | Myers, Theo | Bell, Glen | 1 | DAP | 688 | Derrick Floor | 2,296 | Devonian | 8/31/1961 |
| 156 | 121150066700 | 1899 | -88.80414900 | 39.86761600 | 1-16N-3E | Fawcett, John W. | McClure | 1 | OILP | 689 | Derrick Floor | 2,326 | Devonian | 8/31/1961 |
| 157 | 121150067100 | 2470 | -88.81605300 | 39.86527600 | 1-16N-3E | Hawkins Wm E | Harrouff, Emma | 1 | DAP | 691 | Kelly Bushing | 2,320 | Silurian | 10/31/1961 |
| 158 | 121150067900 | 1292 | -89.09558100 | 39.81717000 | 21-16N-1E | Atkins and Hale | Phillips | 1 | DAP | 623 | Derrick Floor | 1,987 | Silurian | 6/30/1962 |
| 159 | 121150067901 | 783 | -89.09558100 | 39.81717000 | 21-16N-1E | Badger, Floyd | Phillips | 1 | DAP | 623 | Derrick Floor | 2,050 | | 6/9/1963 |
| 160 | 121150067902 | 1526 | -89.09558100 | 39.81717000 | 21-16N-1E | Tully, Buddy | Phillips | 1 | DAP | 623 | Derrick Floor | 1,996 | | 9/27/1964 |
| 161 | 121150068000 | | -88.75166600 | 39.84625400 | 16-16N-4E | National Associated Petroleum Co. | Derr, Charles E. | 1 | DAP | 744 | Kelly Bushing | 2,496 | Devonian | 6/30/1962 |
| 162 | 121150068100 | | -89.09323200 | 39.81356200 | 28-16N-1E | Atkins and Hale | Dipper | 1 | OIL | 639 | Derrick Floor | 2,057 | Silurian | 7/31/1962 |
| 163 | 121150068300 | | -89.09559800 | 39.81169400 | 28-16N-1E | Atkins and Hale | Whitley | 1 | OILP | 627 | Kelly Bushing | 2,038 | Silurian | 7/31/1962 |
| 164 | 121150068400 | 1729 | -89.09205400 | 39.80810400 | 28-16N-1E | Atkins and Hale | Koonce, Clarence | 1 | OILP | 630 | Derrick Floor | 2,034 | Silurian | 8/31/1962 |
| 165 | 121150068500 | 1730 | -89.08729700 | 39.79174500 | 33-16N-1E | Atkins and Hale | Kraft | 1 | DAP | 638 | Kelly Bushing | 2,101 | Silurian | 8/31/1962 |
| 166 | 121150068600 | | -89.09091300 | 39.81360700 | 28-16N-1E | Atkins and Hale | Dipper | 2 | DAP | 643 | Kelly Bushing | 2,094 | Silurian | 8/31/1962 |
| 167 | 121150068700 | | -89.08153500 | 39.81558300 | 27-16N-1E | Mansfield, C. B. | Matthews Community | 1 | DAP | 631 | Derrick Floor | 2,043 | Silurian | 8/31/1962 |
| 168 | 121150068800 | 1828 | -89.08853900 | 39.81069800 | 28-16N-1E | Atkins & Hale | Dipper | 3 | OILP | 631 | Kelly Bushing | 2,051 | Silurian | 9/30/1962 |
| 169 | 121150068900 | 1943 | -89.07909000 | 39.82280000 | 22-16N-1E | H & J Dev. Co. | Hardy | 1 | DA | 651 | Derrick Floor | 2,042 | Silurian | 9/30/1962 |
| 170 | 121150069000 | 1798 | -89.09090500 | 39.81178500 | 28-16N-1E | The Texas Company | Dipper, D. D. | 1 | DAP | 637 | Derrick Floor | 2,162 | Silurian | 8/31/1962 |
| 171 | 121150069001 | 906 | -89.09090500 | 39.81178500 | 28-16N-1E | The Texas Company | Dipper, D. D. | 1 | SWDP | 637 | Derrick Floor | 2,160 | | 5/31/1963 |
| 172 | 121150069100 | 2010 | -89.02061200 | 39.86024000 | 7-16N-2E | Richardson, M. H. | Zarcone | 1 | DAP | 655 | Derrick Floor | 2,071 | Silurian | 9/30/1962 |
| 173 | 121150069200 | | -89.08131300 | 39.82461600 | 22-16N-1E | Mansfield, C. B. | Cooper | 1 | OILP | 653 | Ground level | 2,016 | Silurian | 10/13/1962 |
| 174 | 121150069300 | 1974 | -89.02759700 | 39.85143600 | 7-16N-2E | Dell Carroll Oil Pro | Troutman, C. S. Est | 1 | DAP | 684 | Kelly Bushing | 2,099 | Silurian | 10/9/1962 |
| 175 | 121150069400 | 1735 | -89.06282400 | 39.82297300 | 23-16N-1E | Lichtenberger, Robert | Allen, et al | 1 | DAP | 639 | Derrick Floor | 2,088 | Silurian | 9/30/1962 |
| 176 | 121150069500 | | -89.09323500 | 39.81174100 | 28-16N-1E | The Texas Company | Dipper, D. D. | 2 | OILP | 638 | Derrick Floor | 2,071 | Silurian | 10/31/1962 |
| 177 | 121150069600 | 2092 | -89.10030400 | 39.80795900 | 28-16N-1E | Atkins and Hale | Pure-Whitley | 1 | DAP | 620 | Derrick Floor | 2,004 | Silurian | 9/30/1962 |
| 178 | 121150069700 | 1973 | -89.06299800 | 39.84287100 | 14-16N-1E | Dell Carroll Oil Pro | Davis, Lucy K. #1 | 1 | OILP | 687 | Kelly Bushing | 2,075 | Silurian | 9/30/1962 |
| 179 | 121150069800 | 2148 | -89.06064200 | 39.84392700 | 14-16N-1E | Dell Carroll Oil Pro | Crabtree, Elva | 3 | DAP | 688 | Kelly Bushing | 2,089 | Silurian | 11/19/1962 |
| 180 | 121150069900 | 2271 | -89.09076000 | 39.82453100 | 21-16N-1E | Atkins and Hale | Roby #1 | 1 | DAP | 653 | Kelly Bushing | 2,030 | Silurian | 10/31/1962 |
| 181 | 121150070000 | 2290 | -89.09559400 | 39.81351500 | 28-16N-1E | Fulk Oil Company | Whitley Unit | 1-A | DAP | 630 | Derrick Floor | 2,003 | Silurian | 10/31/1962 |
| 182 | 121150070001 | 2 | -89.09559400 | 39.81351500 | 28-16N-1E | Fulk Oil Company | Whitley Unit | 1-A | OILP | 630 | Derrick Floor | 2,018 | | 1/31/1963 |
| 183 | 121150070100 | 2232 | -89.07441000 | 39.80829000 | 27-16N-1E | Law David | Clary | 1 | DAP | 624 | Kelly Bushing | 2,050 | Silurian | 11/7/1962 |
| 184 | 121150070200 | 2210 | -89.11205700 | 39.79873800 | 32-16N-1E | Buechler, Garold O. | Korenwald | 1 | OILP | 587 | Kelly Bushing | 1,967 | Silurian | 11/9/1962 |
| 185 | 121150070300 | 2304 | -89.10740700 | 39.79700300 | 32-16N-1E | Ware Watson | Millikin Est | 1 | OILP | 580 | Kelly Bushing | 1,962 | Silurian | 11/19/1962 |
| 186 | 121150070500 | 2640 | -89.05576700 | 39.81757200 | 23-16N-1E | Miller Marion | Bourne, Merle | 1 | DAP | 691 | Kelly Bushing | 2,065 | Silurian | 1/2/1963 |
| 187 | 121150070501 | 16402 | -89.05576700 | 39.81757200 | 23-16N-1E | Carter Oil Prop., Inc. | Bourne | 1 | OILP | 691 | Kelly Bushing | 2,065 | Silurian | 1/21/1985 |
| 188 | 121150070600 | 59 | -89.08720000 | 39.82549000 | 21-16N-1E | Atkins & Hale | Roby | 2 | DAP | 664 | Derrick Floor | 2,046 | Silurian | 1/20/1963 |
| 189 | 121150070601 | 1823 | -89.08719600 | 39.82546500 | 21-16N-1E | Centurian Oil, Inc. | Roby | 2 | OIL | 664 | Kelly Bushing | 2,046 | Silurian | 3/14/1967 |
| 190 | 121150070700 | | -89.10273800 | 39.79704000 | 33-16N-1E | McKinney, Etal | Swickard | 1 | DAP | 594 | Derrick Floor | 2,008 | Silurian | 1/20/1963 |
| 191 | 121150070800 | | -89.09559700 | 39.80804200 | 28-16N-1E | Atkins and Hale | Koonce-Whitley Community | 1 | DAP | 637 | Derrick Floor | 2,027 | Silurian | 1/31/1963 |
| 192 | 121150070900 | | -89.09018600 | 39.81728100 | 21-16N-1E | Mansfield, C. B. | Rothwell | 1 | DAP | 644 | Ground level | 2,072 | Silurian | 2/22/1963 |

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 193 | 121150071000 | 324 | -89.10034800 | 39.79888900 | 33-16N-1E | McKinney, Etal | Swickard | 2 | DAP | 590 | Derrick Floor | 1,999 | Silurian | 3/16/1963 |
| 194 | 121150071100 | 126 | -89.11213100 | 39.79297300 | 32-16N-1E | Lichtenberger, Robert | Kraft | 1 | OILP | 601 | Kelly Bushing | 1,995 | Silurian | 2/18/1963 |
| 195 | 121150071300 | | -89.10976900 | 39.79698900 | 32-16N-1E | Ware Watson | Millikin Estate | 2 | DAP | 587 | Kelly Bushing | 1,978 | Silurian | 5/9/1963 |
| 196 | 121150071400 | | -89.11208800 | 39.79631200 | 32-16N-1E | Ware Watson | Millikin Estate | 3 | DAP | 585 | Kelly Bushing | 1,970 | Silurian | 5/17/1963 |
| 197 | 121150071500 | 628 | -88.84275900 | 39.92405800 | 15-17N-3E | Atkins & Hale | Rowe | 1 | TAP | 689 | Kelly Bushing | 2,290 | Silurian | 5/20/1963 |
| 198 | 121150071501 | 979 | -88.84275900 | 39.92405800 | 15-17N-3E | Jarvis, Vernon D. | Rowe | 1 | DAP | 687 | Derrick Floor | 2,291 | | 7/15/1964 |
| 199 | 121150071600 | | -89.10977600 | 39.79636300 | 32-16N-1E | Ware Watson | Millikin Estate | 2-A | OILP | 583 | Kelly Bushing | 1,967 | Silurian | 5/25/1963 |
| 200 | 121150071700 | | -89.10739000 | 39.79882500 | 32-16N-1E | Ware Watson | Korenwald | 1 | OILP | 586 | Kelly Bushing | 1,977 | Silurian | 5/17/1963 |
| 201 | 121150071800 | 830 | -88.81136800 | 39.87291100 | 1-16N-3E | Atkins & Hale | Blickenstaff | 1 | DAP | 687 | Kelly Bushing | 2,335 | Silurian | 6/6/1963 |
| 202 | 121150071900 | 1028 | -89.02422200 | 39.90895000 | 19-17N-2E | HLN Oil Development | Powers, Jack H. | 1 | DAOP | 694 | Derrick Floor | 2,025 | Silurian | 5/31/1963 |
| 203 | 121150072000 | 954 | -88.84646500 | 39.91913200 | 22-17N-3E | Atkins & Hale | Spent Community | 1 | DAP | 681 | Kelly Bushing | 2,278 | Silurian | 6/15/1963 |
| 204 | 121150072400 | | -89.10512300 | 39.79342700 | 32-16N-1E | Funderburk, E. A. | Moffett, Warnick | 1 | DA | 597 | Ground level | 1,996 | Silurian | 8/15/1963 |
| 205 | 121150072500 | 1855 | -89.07441500 | 39.82642700 | 22-16N-1E | Dell Carroll Oil Pro | Cooper, Albert Estate | 2 | OILP | 650 | Kelly Bushing | 2,025 | Silurian | 10/29/1963 |
| 206 | 121150072600 | | -89.04676000 | 39.84677800 | 12-16N-1E | Dell Carroll Oil Pro | Travis, Ida M. #2 | 2 | DAP | 685 | Kelly Bushing | 2,100 | Silurian | 10/20/1963 |
| 207 | 121150072700 | 2059 | -88.93082700 | 39.90916200 | 24-17N-2E | Atkins and Hale | Schwarze | 2 | OILP | 687 | Kelly Bushing | 2,179 | Silurian | 11/4/1963 |
| 208 | 121150072800 | 1992 | -88.99708700 | 39.72654200 | 28-15N-2E | Atkins and Hale | Lash | 1 | DAOP | 727 | Kelly Bushing | 2,463 | Silurian | 11/16/1963 |
| 209 | 121150073000 | 2258 | -89.10981400 | 39.79271700 | 32-16N-1E | Ratliff Oil Prod., Inc. | Kraft | 1 | DAP | 604 | Kelly Bushing | 1,990 | Silurian | 12/7/1963 |
| 210 | 121150073200 | | -88.92498200 | 39.91480000 | 24-17N-2E | Atkins and Hale | Stroh Comm. | 1 | DAP | 687 | Kelly Bushing | 2,220 | Silurian | 3/21/1964 |
| 211 | 121150073800 | 1383 | -88.92377900 | 39.91117800 | 24-17N-2E | Atkins and Hale | Casey | 1 | DAP | 685 | Kelly Bushing | 2,193 | Silurian | 9/7/1964 |
| 212 | 121150073900 | 2061 | -88.88999200 | 39.91035700 | 20-17N-3E | Atkins and Hale | Roos-Kuny | 1 | DAP | 683 | Kelly Bushing | 2,229 | Silurian | 12/3/1963 |
| 213 | 121150074000 | 1567 | -88.99841900 | 39.87663600 | 32-17N-2E | Exploration & Development, Inc. | Nonneman | 1 | DAP | 634 | Kelly Bushing | 2,041 | Devonian | 9/28/1964 |
| 214 | 121150074001 | 31785 | -88.99841900 | 39.87663600 | 32-17N-2E | Barger Engineering, Inc. | Wright, A. | 1 | JAP | 634 | Kelly Bushing | 1,141 | Ste Genevieve | 9/19/1984 |
| 215 | 121150074800 | | -89.03839600 | 39.78782500 | 1-15N-1E | Sun Production Co (Sun Oil) | | M-35-53 | STRUP | 686 | Ground level | 260 | Shoal Creek | 2/19/1953 |
| 216 | 121150074900 | | -89.04803100 | 39.77989700 | 2-15N-1E | Sun Production Co (Sun Oil) | | M-11-53 | STRUP | 670 | Ground level | 232 | | 1/10/1953 |
| 217 | 121150075000 | | -89.06636500 | 39.78730000 | 3-15N-1E | Sun Production Co (Sun Oil) | | M-9-52 | STRUP | 658 | Ground level | 238 | Shoal Creek | 12/18/1952 |
| 218 | 121150075200 | | -89.08494000 | 39.78554000 | 4-15N-1E | Sun Production Co (Sun Oil) | | M-8-52 | STRUP | 627 | Ground level | 180 | Shoal Creek | 11/30/1952 |
| 219 | 121150075900 | | -89.06625500 | 39.77213800 | 11-15N-1E | Sun Production Co (Sun Oil) | | M-10-53 | STRUP | 630 | Ground level | 258 | | 1/4/1953 |
| 220 | 121150076000 | | -89.02875800 | 39.77168700 | 12-15N-1E | Sun Production Co (Sun Oil) | M-12-52 | | STRUP | 699 | Ground level | 306 | Shoal Creek | 1/14/1953 |
| 221 | 121150076500 | | -88.99991500 | 39.78025600 | 5-15N-2E | Sun Production Co (Sun Oil) | | M-49-53 | STRUP | 703 | Ground level | 280 | | 4/15/1953 |
| 222 | 121150076600 | | -88.99959800 | 39.76939100 | 8-15N-2E | Sun Production Co (Sun Oil) | | M-45-53 | STRUP | 703 | Ground level | 320 | | 3/25/1953 |
| 223 | 121150076700 | | -88.96157300 | 39.75549400 | 11-15N-2E | Sun Production Co (Sun Oil) | Jacobs, M. G. | 1 | STRUP | 710 | Ground level | 360 | | 1/15/1954 |
| 224 | 121150076800 | | -88.98015600 | 39.75628400 | 15-15N-2E | Sun Production Co (Sun Oil) | Graf, Frank H. | 1 | STRUP | 730 | Ground level | 377 | | 2/1/1954 |
| 225 | 121150076900 | | -88.96141200 | 39.74114000 | 22-15N-2E | Sun Production Co (Sun Oil) | Bollhorst, R. J. | 1 | STRUP | 718 | Ground level | 375 | Shoal Creek | 3/1/1954 |
| 226 | 121150077100 | | -88.97934800 | 39.72728500 | 28-15N-2E | Sun Production Co (Sun Oil) | Davis, R. B. | 1 | STRUP | 729 | Ground level | 360 | | 3/11/1954 |
| 227 | 121150077700 | | -88.89412500 | 39.75512700 | 8-15N-3E | Sun Production Co (Sun Oil) | Henry, R. | 1 | STRUP | 680 | Ground level | 420 | | 1/29/1954 |
| 228 | 121150077800 | | -88.81369000 | 39.76301200 | 12-15N-3E | Sun Production Co (Sun Oil) | McGaughey #1 | 1 | STRUP | 681 | Ground level | 271 | | 2/21/1954 |
| 229 | 121150077900 | | -88.92264900 | 39.72579700 | 19-15N-3E | Sun Production Co (Sun Oil) | Price, E. L. | 1 | STRUP | 711 | Ground level | 400 | | 1/26/1954 |
| 230 | 121150078000 | | -88.88801800 | 39.72597200 | 21-15N-3E | Sun Production Co (Sun Oil) | Boy's Home | 1 | STRUP | 703 | Ground level | 285 | | 2/16/1954 |
| 231 | 121150078100 | | -88.85039900 | 39.72667000 | 27-15N-3E | Sun Production Co (Sun Oil) | Smith, F. D. | 2 | STRUP | 708 | Ground level | 305 | | 2/14/1954 |
| 232 | 121150078400 | | -89.04783000 | 39.86028200 | 1-16N-1E | Sun Production Co (Sun Oil) | | M-30-53 | STRUP | 686 | Ground level | 270 | Shoal Creek | 2/10/1953 |
| 233 | 121150078500 | | -89.06668200 | 39.87490100 | 3-16N-1E | Sun Production Co (Sun Oil) | M-39-53 | | STRUP | 665 | Ground level | 240 | Shoal Creek | 2/8/1953 |
| 234 | 121150078600 | | -89.10377400 | 39.87423200 | 5-16N-1E | Sun Production Co (Sun Oil) | M-21-53 | | STRUP | 663 | Ground level | 230 | Shoal Creek | 2/6/1953 |
| 235 | 121150078700 | | -89.10372000 | 39.84634100 | 9-16N-1E | Sun Production Co (Sun Oil) | | M-18-53 | STRUP | 652 | Ground level | 200 | Shoal Creek | 2/4/1953 |
| 236 | 121150078800 | | -89.04301400 | 39.83313700 | 13-16N-1E | Sun Production Co (Sun Oil) | | M-29-53 | STRUP | 626 | Ground level | 230 | Shoal Creek | 2/12/1953 |
| 237 | 121150078900 | | -89.10414400 | 39.83084200 | 17-16N-1E | Sun Production Co (Sun Oil) | | M-17-53 | STRUP | 617 | Ground level | 190 | Shoal Creek | 2/3/1953 |
| 238 | 121150079000 | | -89.12253500 | 39.84457600 | 17-16N-1E | Sun Production Co (Sun Oil) | | M-24-53 | STRUP | 627 | Ground level | 200 | | 1/31/1953 |
| 239 | 121150079200 | | -89.05368600 | 39.80434900 | 26-16N-1E | Sun Production Co (Sun Oil) | | M-14-53 | STRUP | 657 | Ground level | 260 | Shoal Creek | 1/19/1953 |
| 240 | 121150079300 | | -89.10107300 | 39.81610100 | 28-16N-1E | Sun Production Co (Sun Oil) | | M-16-53 | STRUP | 613 | Ground level | 180 | Shoal Creek | 1/21/1953 |
| 241 | 121150079600 | | -89.09921900 | 39.79911200 | 33-16N-1E | Sun Production Co (Sun Oil) | | M-7-52 | STRUP | 584 | Ground level | 140 | | 12/13/1952 |
| 242 | 121150079700 | | -89.04743200 | 39.79515600 | 35-16N-1E | Sun Production Co (Sun Oil) | | M-1-57 | STRUP | 675 | Ground level | 225 | Shoal Creek | 4/15/1957 |
| 243 | 121150079800 | | -89.03792300 | 39.79503800 | 36-16N-1E | Sun Production Co (Sun Oil) | | M-13-53 | STRUP | 687 | Ground level | 300 | Shoal Creek | 1/14/1953 |
| 244 | 121150079900 | | -89.02884800 | 39.81758600 | 19-16N-2E | Sun Production Co (Sun Oil) | | M-36-53 | STRUP | 603 | Ground level | 220 | Shoal Creek | 2/13/1953 |
| 245 | 121150080000 | | -89.00512400 | 39.80971800 | 29-16N-2E | Sun Production Co (Sun Oil) | | M-37-53 | STRUP | 699 | Ground level | 290 | Shoal Creek | 2/23/1953 |
| 246 | 121150080100 | | -89.02724000 | 39.80651400 | 30-16N-2E | Sun Production Co (Sun Oil) | | M-38-53 | STRUP | 668 | Ground level | 260 | Shoal Creek | 1/31/1953 |
| 247 | 121150080300 | | -89.01906800 | 39.79645000 | 31-16N-2E | Sun Production Co (Sun Oil) | | M-42-53 | STRUP | 644 | Ground level | 240 | Shoal Creek | 3/8/1953 |
| 248 | 121150080400 | | -88.99068000 | 39.79281100 | 33-16N-2E | Sun Production Co (Sun Oil) | | M-43-53 | STRUP | 659 | Ground level | 260 | | 3/6/1953 |
| 249 | 121150080500 | | -88.96985300 | 39.80371000 | 34-16N-2E | Sun Production Co (Sun Oil) | | M-40-53 | STRUP | 687 | Ground level | 330 | Shoal Creek | 3/4/1953 |
| 250 | 121150080600 | | -89.16142700 | 39.87369800 | 2-16N-1W | Sun Production Co (Sun Oil) | | M-54-53 | STRUP | 601 | Ground level | 330 | | 5/19/1953 |
| 251 | 121150080800 | 490 | -89.03949400 | 39.99787600 | 24-18N-1E | Tabor Purvis | Patterson | 1 | DAP | 706 | Kelly Bushing | 1,955 | Silurian | 4/30/1965 |
| 252 | 121150080900 | | -89.09090200 | 39.81726700 | 21-16N-1E | Robison, H. F. | Rothwell | 1A | DAP | 642 | Kelly Bushing | 2,042 | Silurian | 3/23/1965 |
| 253 | 121150081600 | | -89.18039600 | 39.89535100 | 26-17N-1W | Sun Production Co (Sun Oil) | Knap, R. M-2-56 | 1 | STRUP | 597 | Ground level | 750 | | 7/17/1956 |
| 254 | 121150081700 | | -89.16246900 | 39.89617300 | 26-17N-1W | Sun Production Co (Sun Oil) | Campbell, Ellen B. | M-57-53 | STRUP | 599 | Ground level | 350 | No 5 Coal | 6/15/1953 |
| 255 | 121150082000 | | -89.18059800 | 39.89013000 | 27-17N-1W | Sun Production Co (Sun Oil) | | M-56-53 | STRUP | 601 | Ground level | 320 | No 5 Coal | 6/10/1953 |
| 256 | 121150082200 | 936 | -88.93076000 | 39.90460200 | 25-17N-2E | Atkins and Hale | Daniel | 1 | DAP | 685 | Kelly Bushing | 2,191 | Silurian | 8/1/1965 |

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 257 | 121150082300 | 863 | -88.98538600 | 39.97162300 | 33-18N-2E | Hill, A. G. | Haynes, Elwood | 1 | DAP | 694 | Kelly Bushing | 1,957 | Silurian | 7/12/1965 |
| 258 | 121150082500 | 1876 | -88.77050300 | 39.86982200 | 5-16N-4E | Richardson, M. H. | Shirey | 2 | DAP | 626 | Ground level | 2,383 | Silurian | 12/14/1965 |
| 259 | 121150082600 | 1861 | -89.07784100 | 39.82640300 | 22-16N-1E | Marquand, Boyd C. | Cooper-Pumphrey | 1 | OILP | 659 | Ground level | 2,068 | Silurian | 12/21/1965 |
| 260 | 121150082800 | 2006 | -89.12328900 | 39.94799100 | 5-17N-1E | Collins Brothers Oil Company | Brown, Helen E. et al | 1 | DAP | 601 | Derrick Floor | 1,926 | Silurian | 1/10/1966 |
| 261 | 121150083100 | 27 | -89.08126600 | 39.82640200 | 22-16N-1E | Marquand, Boyd C. | Cooper-Pumphrey | 2 | DAP | 653 | Kelly Bushing | 2,042 | Silurian | 2/9/1966 |
| 262 | 121150083300 | 1095 | -89.00790200 | 39.88372200 | 32-17N-2E | Kin-Ark Oil Co | Young, John E. | 1 | DAP | 651 | Kelly Bushing | 1,999 | Silurian | 7/29/1966 |
| 263 | 121150083400 |  | -88.92390800 | 39.75442600 | 13-15N-2E | Sun Production Co (Sun Oil) | Rowe, M. B. | 1 | STRUP | 703 | Ground level | 373 |  | 1/24/1954 |
| 264 | 121150083700 | 1589 | -88.85473900 | 39.93301400 | 15-17N-3E | Kin-Ark Oil Co | Kingdon, Albert | 1 | DAP | 689 | Kelly Bushing | 2,252 | Silurian | 10/22/1966 |
| 265 | 121150083701 | 336 | -88.85473900 | 39.93301400 | 15-17N-3E | Collins Assoc. Oil Co. | Kingdon, Albert | 1 | DAP | 689 | Kelly Bushing | 2,250 |  | 5/8/1969 |
| 266 | 121150083800 | 1989 | -88.93088300 | 39.91463200 | 24-17N-2E | Barra, Raymond P. | Stroh | 1A | OILP | 674 | Kelly Bushing | 2,138 | Silurian | 2/15/1967 |
| 267 | 121150083801 | 271 | -88.93088300 | 39.91463200 | 24-17N-2E | M. & N. Oil Company | Stroh | 1-A | OILP | 670 | Ground level | 2,139 | Silurian | 4/19/1972 |
| 268 | 121150083900 | 298 | -89.08832200 | 39.82818500 | 21-16N-1E | Centurian Oil, Inc. | Roby | 4 | OILP | 674 | Kelly Bushing | 2,054 | Silurian | 4/30/1967 |
| 269 | 121150084000 | 56 | -89.09072400 | 39.82634700 | 21-16N-1E | Centurian Oil, Inc. | Roby | 3 | OILP | 658 | Derrick Floor | 2,030 | Silurian | 2/24/1967 |
| 270 | 121150084100 |  | -89.00081700 | 39.88560800 | 32-17N-2E | Rand, Tim Oil Corp. | Wilder | 1 | DAP | 665 | Ground level | 2,031 | Silurian | 5/28/1967 |
| 271 | 121150084200 | 594 | -89.08590200 | 39.83000100 | 21-16N-1E | Centurian Oil, Inc. | Roby | 5 | OILP | 673 | Kelly Bushing | 2,075 | Silurian | 7/18/1967 |
| 272 | 121150084300 | 752 | -89.09064900 | 39.82997300 | 21-16N-1E | Centurian Oil, Inc. | Roby | 6 | OILP | 658 | Kelly Bushing | 2,044 | Silurian | 6/29/1967 |
| 273 | 121150084900 |  | -88.96123200 | 39.74117500 | 23-15N-2E | Phillips Petroleum, Co. |  |  | STRU | 717 | Ground level | 501 |  |  |
| 274 | 121150085000 |  | -88.84119600 | 39.74476200 | 14-15N-3E | Phillips Petroleum, Co. |  |  | STRU | 700 | Ground level | 623 |  |  |
| 275 | 121150085100 |  | -88.88859400 | 39.74065700 | 17-15N-3E | Phillips Petroleum, Co. |  |  | STRU | 693 | Ground level | 600 |  |  |
| 276 | 121150085200 |  | -88.76991500 | 39.76397400 | 9-15N-4E | Phillips Petroleum, Co. | Nov-38 |  | STRU | 726 | Ground level | 670 |  |  |
| 277 | 121150085300 |  | -88.93466000 | 39.80438200 | 35-16N-2E | Phillips Petroleum, Co. |  |  | STRU | 623 | Ground level | 410 |  |  |
| 278 | 121150085400 |  | -88.85789800 | 39.80849300 | 27-16N-3E | Phillips Petroleum, Co. |  |  | STRU | 667 | Ground level | 538 |  |  |
| 279 | 121150085500 | 1026 | -89.09303700 | 39.82995700 | 21-16N-1E | Centurian Oil, Inc. | Roby | 7 | DAP | 632 | Kelly Bushing | 1,984 | Silurian | 9/1/1967 |
| 280 | 121150086800 |  | -89.08613400 | 39.82097900 | 21-16N-1E | Aladdin Oil Dev. Co. | Rothwell | 1 | DAP | 652 | Kelly Bushing | 2,033 | Silurian | 12/13/1967 |
| 281 | 121150087900 |  | -89.09323200 | 39.81539500 | 28-16N-1E | Atkins and Hale | Dipper | 1-DH | DAP | 629 | Ground level | 2,050 | Silurian | 6/30/1968 |
| 282 | 121150088100 | 813 | -88.93090000 | 39.91646000 | 24-17N-2E | Mardi Oil Co. | Stroh | 2 | DAP | 681 | Kelly Bushing | 2,186 | Silurian | 8/17/1968 |
| 283 | 121150088200 |  | -89.10025900 | 39.81707000 | 21-16N-1E | Geo-Prospectors Inc | Beatty #1 | 1 | DAP | 615 | Kelly Bushing | 1,989 | Silurian | 9/16/1968 |
| 284 | 121150088300 |  | -89.07895000 | 39.83182500 | 15-16N-1E | Amgo, Inc. | Hoffman #1 | 1 | DAP | 667 | Kelly Bushing | 2,052 | Silurian | 10/8/1968 |
| 285 | 121150088400 | 1279 | -88.86185400 | 39.93472000 | 16-17N-3E | Collins Assoc. Oil Co. | Beadleston | 1 | DAP | 683 | Kelly Bushing | 2,246 | Silurian | 10/22/1968 |
| 286 | 121150091700 | 1469 | -88.92852800 | 39.91469800 | 24-17N-2E | Mardi Oil Co. | Stroh | 3 | OILP | 675 | Kelly Bushing | 2,147 | Silurian | 7/10/1969 |
| 287 | 121150099300 | 1162 | -88.93084500 | 39.91098900 | 24-17N-2E | Hale, Richard D. | Schwarze, Vivian | 3A | OILP | 681 | Kelly Bushing | 2,155 | Silurian | 4/25/1971 |
| 288 | 121150101600 |  | -89.09320600 | 39.81813000 | 21-16N-1E | Dodge, J. U. | Rothwell | 1-D | DAP | 637 | Kelly Bushing | 2,006 | Silurian | 6/6/1972 |
| 289 | 121150101700 |  | -88.93321000 | 39.91092300 | 24-17N-2E | Hale Oil Co. | Schwarze | 4 | JAP | 676 | Ground level | 2,154 | Silurian | 6/11/1972 |
| 290 | 121150101800 |  | -88.96925200 | 39.79753000 | 34-16N-2E | Hyde Park Corp. | Hyde Park Corp. | 1 | OBSO | 686 | Kelly Bushing | 3,440 | St Peter | 6/17/1972 |
| 291 | 121150102300 |  | -88.89115500 | 39.76191800 | 8-15N-3E | Carter Oil Co., The | Core Hole | 138 | UNK | 690 | Ground level | 530 |  | 12/31/1939 |
| 292 | 121150103400 |  | -88.75461500 | 39.84574500 | 16-16N-4E | Carter Oil Co., The | Core Hole | 197 | STRU | 742 | Ground level | 1,626 |  | 12/31/1939 |
| 293 | 121150104500 |  | -88.98171500 | 39.76638200 | 9-15N-2E | Alco Oil & Gas Corp. | Burt, J. W. |  | GASP | 722 | Digital Elevation Model | 148 |  |  |
| 294 | 121150104700 |  | -88.90854000 | 40.05329000 | 6-18N-3E | Pure Oil Co. | Core Prospect Ill. | A-10 | STRUP | 709 | Digital Elevation Model | 1,194 |  | 9/25/1940 |
| 295 | 121150104800 |  | -88.80365700 | 40.01735000 | 13-18N-3E | Pure Oil Co. | Illinois Prospect | A-3 | STRU | 660 | Digital Elevation Model | 1,225 |  | 6/30/1940 |
| 296 | 121150104900 |  | -88.79234100 | 40.01261000 | 18-18N-4E |  | Illinois Prospect | A-2 | STRU | 677 | Digital Elevation Model | 810 |  | 6/30/1940 |
| 297 | 121150105700 |  | -88.99762100 | 39.75022100 | 16-15N-2E | Baker, E. C. & Sons | Hogan, Terry |  | GAS | 718 | Topographic map | 131 |  | 6/20/1973 |
| 298 | 121150105800 |  | -88.83442000 | 39.90143100 | 26-17N-3E | Mashburn, Bruce | Maxey, C. E. |  | GAS | 702 | Ground level | 100 |  |  |
| 299 | 121152106000 |  | -88.82579100 | 39.87832700 | 2-16N-3E | Welker, Emerson | Flack-Brown Comm. | 1 | OILP | 692 | Kelly Bushing | 2,282 | Devonian | 6/12/1974 |
| 300 | 121152108100 |  | -89.09323500 | 39.80990500 | 28-16N-1E | Atkins and Hale | Dipper | 1-A | DAP | 634 | Kelly Bushing | 2,054 | Silurian | 5/8/1974 |
| 301 | 121152108200 |  | -88.93086600 | 39.91281100 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze | 1-A | OILP | 679 | Kelly Bushing | 2,142 | Silurian | 5/21/1974 |
| 302 | 121152108201 | 16743 | -88.93086600 | 39.91281100 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze | 1-A | OILP | 679 | Kelly Bushing | 2,142 | Silurian | 5/21/1974 |
| 303 | 121152108300 |  | -88.83772900 | 39.87819600 | 2-16N-3E | Welker, Emerson | King | 1 | DAOP | 688 | Kelly Bushing | 2,291 | Silurian | 4/20/1975 |
| 304 | 121152108400 | 718 | -88.83988500 | 39.88587800 | 35-17N-3E | Welker, Emerson | Sheffer | 1 | DAP | 674 | Kelly Bushing | 2,272 | Silurian | 8/8/1974 |
| 305 | 121152109000 |  | -89.08141100 | 39.82497500 | 22-16N-1E | Marquand, Boyd C. | Pumphrey-Cooper | 1 | OILP | 649 | Kelly Bushing | 2,044 | Silurian | 12/16/1974 |
| 306 | 121152109100 |  | -88.83844500 | 39.87818900 | 2-16N-3E | Welker, Emerson | King, Frank | 1A | DAP | 687 | Ground level | 2,292 | Devonian | 10/24/1974 |
| 307 | 121152109300 |  | -88.93322800 | 39.91274200 | 24-17N-2E | Triple G Oil Company Ltd. | SCHWARTZ | 2 | OIL | 681 | Kelly Bushing | 2,147 | Silurian | 2/2/1975 |
| 308 | 121152109400 |  | -89.07674200 | 39.83000100 | 22-16N-1E | Marquand, Boyd C. | Pumphrey-Cooper | 2-A | DAOP | 660 | Ground level | 2,090 | Silurian | 1/18/1975 |
| 309 | 121152109700 | 17 | -89.03948100 | 39.86690100 | 1-16N-1E | Northwestern Oil Co. | Roby & Miller | 1 | OILP | 675 | Ground level | 2,028 | Silurian | 7/3/1975 |
| 310 | 121152109800 | 125 | -88.93794600 | 39.91260700 | 23-17N-2E | Triple G Oil Company Ltd. | Phillips | 1 | OILP | 683 | Kelly Bushing | 2,155 | Silurian | 3/22/1975 |
| 311 | 121152110000 |  | -88.94024400 | 39.91162700 | 23-17N-2E | Triple G Oil Company Ltd. | Phillips | 2 | OIL | 678 | Kelly Bushing | 2,145 | Devonian | 10/24/1975 |
| 312 | 121152110100 | 485 | -89.03654700 | 39.78881700 | 36-16N-1E | Corley, W. A. | Hill, Howard | 1 | OILP | 691 | Kelly Bushing | 2,195 | Silurian | 8/7/1975 |
| 313 | 121152111000 | 1032 | -89.03182400 | 39.78886500 | 36-16N-1E | Corley, W. A. | Hill, Howard | 2 | DAP | 690 | Kelly Bushing | 2,167 | Silurian | 9/7/1975 |
| 314 | 121152111900 | 1901 | -89.02758300 | 39.77893000 | 6-15N-2E | Corley, W. A. | Brown, Carl S. #1 | 1 | DAP | 702 | Kelly Bushing | 2,216 | Silurian | 2/2/1976 |
| 315 | 121152112000 |  | -88.94261700 | 39.91246900 | 23-17N-2E | Triple G Oil Company Ltd. | Phillips | 3 | OILP | 677 | Kelly Bushing | 2,147 | Silurian | 7/1/1976 |
| 316 | 121152112100 | 485 | -89.03890500 | 39.78879300 | 36-16N-1E | Corley, W. A. | Hill, Allie R. | 1 | OILP | 690 | Kelly Bushing | 2,195 | Silurian | 5/19/1976 |
| 317 | 121152112200 | 2020 | -89.03938900 | 39.78697400 | 1-15N-1E | Corley, W. A. | Jockisch, Louis S. | 1 | DAOP | 685 | Ground level | 2,167 | Silurian | 3/15/1976 |
| 318 | 121152112700 | 2110 | -89.03895000 | 39.79061500 | 36-16N-1E | Corley, W. A. | Hill, Allie R. | 2 | DAP | 688 | Ground level | 2,163 | Silurian | 4/7/1976 |
| 319 | 121152112701 | 29961 | -89.03895000 | 39.79061500 | 36-16N-1E | Watters Oil & Gas Co. | Hill, Allie R. | 2 | OIL | 688 | Ground level | 2,193 | Silurian | 6/14/1984 |
| 320 | 121152112702 | 41494 | -89.03895000 | 39.79061500 | 36-16N-1E | Watters Oil & Gas Co. | Hill, Allie R. | 2 | INJW | 692 | Kelly Bushing | 2,193 | Silurian | 3/31/1988 |

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 321 | 121152113200 | 2454 | -89.06892000 | 39.82464000 | 22-16N-1E | Cooper, Carl E. | Cooper-Pumphrey | 1 | OILP | 640 | Ground level | 2,022 | Silurian | 11/21/1976 |
| 322 | 121152113400 | | -88.92702600 | 39.84930000 | 12-16N-2E | Staley, A. E. Manfct. Co | Waste Treatment Well | 1 | WASTE | 679 | Ground level | 504 | | 7/27/1976 |
| 323 | 121152113500 | 45678 | -88.96636300 | 39.80290800 | 34-16N-2E | Beasley | Edgecombe, Arthur | | INJT | 701 | Digital Elevation Model | 42 | | 5/9/1976 |
| 324 | 121152113800 | 2924 | -89.03433900 | 39.79637700 | 36-16N-1E | Corley, W. A. | Hill, Chester R. & Allie R. | 1 | OILP | 684 | Kelly Bushing | 2,201 | Silurian | 10/31/1976 |
| 325 | 121152113900 | 2997 | -89.04126600 | 39.78877200 | 36-16N-1E | Corley, W. A. | Hill, Allie | 3 | DAP | 686 | Ground level | 2,161 | Silurian | 9/24/1976 |
| 326 | 121152114300 | 3056 | -88.94263500 | 39.91428800 | 23-17N-2E | Triple G Oil Company Ltd. | Hockaday, Nola May | 1 | OILP | 678 | Kelly Bushing | 2,156 | Silurian | 5/8/1977 |
| 327 | 121152115000 | | -89.10622800 | 39.79972000 | 32-16N-1E | A. & H. Engineering Company | | 1 | STRU | | | 1,286 | | 12/31/1975 |
| 328 | 121152115100 | 3775 | -89.03453100 | 39.90167200 | 25-17N-1E | Bollenbacher Fam. Trst. | Flach | 1 | DAP | 690 | Ground level | 2,100 | Silurian | 3/24/1977 |
| 329 | 121152115200 | 3865 | -88.94259900 | 39.91064500 | 23-17N-2E | Triple G Oil Company Ltd. | Phillips | 4 | OIL | 686 | Kelly Bushing | 2,170 | Silurian | 2/15/1978 |
| 330 | 121152116500 | 4175 | -88.94264900 | 39.91611300 | 23-17N-2E | Triple G Oil Company Ltd. | Hockaday, Nola Mae | 2 | OILP | 681 | Kelly Bushing | 2,168 | Silurian | 1/2/1978 |
| 331 | 121152117100 | 58114 | -88.98550200 | 39.76511500 | 9-15N-2E | Baker, E. C. & Sons | Medusa Aggregates Co | | GAS | 724 | Topographic map | 140 | | 3/31/1977 |
| 332 | 121152117700 | 4892 | -88.94730300 | 39.91415300 | 23-17N-2E | Triple G Oil Company Ltd. | Hockaday Comm. | 3 | DAOP | 674 | Kelly Bushing | 2,144 | Silurian | 4/15/1978 |
| 333 | 121152117800 | 4959 | -89.03658800 | 39.79063900 | 36-16N-1E | Corley, W. Andrew | Hill, Howard | 3 | OIL | 693 | Kelly Bushing | 2,175 | Silurian | 5/11/1978 |
| 334 | 121152118200 | 5387 | -88.94496500 | 39.91786800 | 23-17N-2E | Triple G Oil Company Ltd. | Hockaday | 4 | OILP | 686 | Kelly Bushing | 2,155 | Silurian | 6/13/1978 |
| 335 | 121152118300 | 5433 | -89.03663000 | 39.79246100 | 36-16N-1E | Corley, W. A. | Hill, Allie Comm. | 1 | OILP | 691 | Kelly Bushing | 2,180 | Silurian | 4/3/1978 |
| 336 | 121152118400 | 5515 | -88.94266700 | 39.91793500 | 23-17N-2E | Triple G Oil Company Ltd. | Hockaday | 5 | OILP | 687 | Kelly Bushing | 2,160 | Silurian | 6/11/1980 |
| 337 | 121152118600 | 5714 | -89.05824800 | 39.83746000 | 14-16N-1E | Carroll, Dell | Krall | 5 | OIL | 691 | Kelly Bushing | 2,080 | Silurian | 7/31/1978 |
| 338 | 121152118700 | 5749 | -88.93791100 | 39.90937800 | 23-17N-2E | Triple G Oil Company Ltd. | Phillips | 5 | OIL | 690 | Kelly Bushing | 2,174 | Silurian | 12/2/1978 |
| 339 | 121152118800 | 5750 | -88.94026100 | 39.90810000 | 23-17N-2E | Triple G Oil Company Ltd. | Phillips | 6 | OIL | 683 | Kelly Bushing | 2,167 | Silurian | 11/17/1978 |
| 340 | 121152119200 | 6063 | -89.03426600 | 39.79345300 | 36-16N-1E | Corley, W. Andrew | Hill, Allie Comm. | 2 | DAOGP | 690 | Kelly Bushing | 2,203 | Silurian | 8/28/1978 |
| 341 | 121152119300 | 6064 | -89.03188100 | 39.79258800 | 36-16N-1E | Corley, W. Andrew | Hill, Howard | 6 | OIL | 689 | Ground level | 2,194 | Silurian | 10/9/1978 |
| 342 | 121152119400 | 6264 | -89.03422700 | 39.79066300 | 36-16N-1E | Corley, W. Andrew | Hill, Howard | 4 | DAP | 686 | Ground level | 2,160 | Silurian | 9/4/1978 |
| 343 | 121152119401 | 3742 | -89.03422700 | 39.79066300 | 36-16N-1E | Watters Oil & Gas Co. | Hill Unit | WS- 1 | WATRSP | 696 | Ground level | 2,000 | New Albany | 4/11/1988 |
| 344 | 121152119500 | 6288 | -89.03911700 | 39.79791900 | 36-16N-1E | Corley, W. A. | Hill, Howard & Christine | 1-C | DAOP | 684 | Ground level | 2,158 | Silurian | 9/19/1978 |
| 345 | 121152119600 | 6313 | -88.93560100 | 39.91449500 | 24-17N-2E | Triple G Oil Company Ltd. | Hubble | 1 | OILP | 693 | Kelly Bushing | 2,153 | Silurian | 12/26/1978 |
| 346 | 121152120101 | 8548 | -88.94732000 | 39.91779400 | 23-17N-2E | Triple G Oil Company Ltd. | Hockaday | 6 | OILP | 682 | Kelly Bushing | 2,144 | Silurian | 7/16/1980 |
| 347 | 121152120300 | 6523 | -88.94252300 | 39.90803400 | 23-17N-2E | Triple G Oil Company Ltd. | Phillips | 9 | OIL | 678 | Kelly Bushing | 2,150 | Silurian | 5/12/1979 |
| 348 | 121152120400 | 6527 | -88.93562600 | 39.91632500 | 24-17N-2E | Triple G Oil Company Ltd. | Hubble | 2 | OILP | 693 | Kelly Bushing | 2,150 | Silurian | 11/21/1979 |
| 349 | 121152120500 | 6526 | -88.93785700 | 39.90531800 | 26-17N-2E | Triple G Oil Company Ltd. | Phillips | 7 | OIL | 677 | Kelly Bushing | 2,159 | Silurian | 5/29/1979 |
| 350 | 121152120600 | 6525 | -88.94017700 | 39.90524900 | 26-17N-2E | Triple G Oil Company Ltd. | Phillips | 8 | OIL | 671 | Kelly Bushing | 2,144 | Silurian | 5/22/1979 |
| 351 | 121152127500 | 6811 | -89.02718500 | 39.79449600 | 31-16N-2E | Watters, Charles | Ellison, Ralph | 1 | DAOP | 679 | Kelly Bushing | 2,159 | Silurian | 1/9/1979 |
| 352 | 121152129000 | 7440 | -89.05557100 | 39.78852400 | 35-16N-1E | Carey, John Oil Co., Inc | Miller | 1 | DAOP | 680 | Kelly Bushing | 2,202 | Silurian | 6/12/1979 |
| 353 | 121152129300 | 7507 | -88.94253900 | 39.90518000 | 26-17N-2E | Triple G Oil Company Ltd. | Phillips | 10 | OIL | 673 | Kelly Bushing | 2,141 | Silurian | 8/25/1980 |
| 354 | 121152129400 | 7508 | -88.94250300 | 39.90335300 | 26-17N-2E | Triple G Oil Company Ltd. | Phillips | 11 | OIL | 680 | Kelly Bushing | 2,146 | Silurian | 8/25/1979 |
| 355 | 121152129500 | 7509 | -88.94488900 | 39.90796500 | 23-17N-2E | Triple G Oil Company Ltd. | Phillips | 12 | OIL | 678 | Kelly Bushing | 2,150 | Silurian | 11/12/1980 |
| 356 | 121152130200 | 7530 | -89.02245700 | 39.79268800 | 31-16N-2E | Watters, Charles | Price, Raymond Community | 1 | DAP | 667 | Ground level | 2,195 | Silurian | 6/25/1979 |
| 357 | 121152130300 | | -89.07904900 | 39.80093200 | 34-16N-1E | Watters, Charles | East, Earl Brown | 1 | DAOP | 649 | Ground level | 2,046 | Silurian | 7/13/1979 |
| 358 | 121152130500 | 7924 | -89.09323500 | 39.80625400 | 28-16N-1E | Watters, Charles | Johnston, Gary L. | 1 | OILP | 622 | Kelly Bushing | 2,158 | Silurian | 2/14/1979 |
| 359 | 121152130600 | 7927 | -89.02970000 | 39.79999600 | 36-16N-1E | Watters, Charles | Zindel, Royal Wesley | 1 | DAP | 686 | Kelly Bushing | 2,160 | Silurian | 8/28/1979 |
| 360 | 121152132500 | 8002 | -88.94034000 | 39.92165000 | 14-17N-2E | Triple G Oil Company Ltd. | Hubbel | 3 | OIL | 684 | Kelly Bushing | 2,137 | Silurian | 5/9/1980 |
| 361 | 121152132600 | 8050 | -88.93835700 | 39.89253300 | 26-17N-2E | Triple G Oil Company Ltd. | Snow | 1 | OILP | 663 | Kelly Bushing | 2,165 | Silurian | 4/3/1980 |
| 362 | 121152132700 | 8173 | -89.03945200 | 39.86872200 | 1-16N-1E | Comanche Oil (now Atlantic Energy) | Campbell #1 | 1 | OIL | 661 | Kelly Bushing | 2,048 | Silurian | 12/7/1979 |
| 363 | 121152132800 | 8172 | -89.04427100 | 39.86680900 | 1-16N-1E | Comanche Oil (now Atlantic Energy) | Roby-Miller #1-C | 1-C | OIL | 663 | Kelly Bushing | 2,042 | Silurian | 2/17/1980 |
| 364 | 121152132900 | 8562 | -89.09088400 | 39.80812500 | 28-16N-1E | Watters, Charles | Johnston, Gary et al | 2 | OILP | 634 | Kelly Bushing | 2,044 | Silurian | 1/29/1980 |
| 365 | 121152133000 | 8618 | -88.94725500 | 39.90789600 | 23-17N-2E | Triple G Oil Company Ltd. | Loeb-Phillips Comm. | 1 | OIL | 678 | Kelly Bushing | 2,150 | Silurian | 3/30/1980 |
| 366 | 121152133100 | 8773 | -88.93558000 | 39.91267600 | 24-17N-2E | Triple G Oil Company Ltd. | SCHWARZE TRUST | 1 | OIL | 692 | Kelly Bushing | 2,160 | Silurian | 2/6/1980 |
| 367 | 121152133200 | 8922 | -88.93564000 | 39.91814100 | 24-17N-2E | Triple G Oil Company Ltd. | Hubbel | 4 | OIL | 693 | Kelly Bushing | 2,141 | Silurian | 4/20/1980 |
| 368 | 121152133800 | 9057 | -88.89447500 | 39.86889400 | 5-16N-3E | Archer Daniels Midland | A.D.M. | 1 | DAOP | 682 | Kelly Bushing | 2,315 | Silurian | 2/18/1980 |
| 369 | 121152133900 | 9156 | -88.93095600 | 39.92193000 | 13-17N-2E | Triple G Oil Company Ltd. | Oldweiler, Eugenia | 1 | OILP | 684 | Kelly Bushing | 2,137 | Silurian | 7/4/1980 |
| 370 | 121152134000 | 9158 | -88.93566100 | 39.91996600 | 24-17N-2E | Triple G Oil Company Ltd. | Hubble | 5 | OIL | 685 | Kelly Bushing | 2,145 | Silurian | 6/14/1980 |
| 371 | 121152134100 | 9157 | -88.92144400 | 39.91490100 | 24-17N-2E | Triple G Oil Company Ltd. | Pense | 1 | OIL | 685 | Kelly Bushing | 2,170 | Silurian | 6/6/1980 |
| 372 | 121152134200 | 9154 | -88.94472900 | 39.89781800 | 26-17N-2E | Triple G Oil Company Ltd. | Cavender, Oma | 1 | OILP | 670 | Ground level | 2,150 | Silurian | 5/25/1980 |
| 373 | 121152134300 | 9155 | -88.94236700 | 39.89789000 | 26-17N-2E | Triple G Oil Company Ltd. | Cavender, Oma | 2 | OILP | 674 | Kelly Bushing | 2,152 | Silurian | 5/26/1980 |
| 374 | 121152135600 | | -89.08827600 | 39.83180600 | 16-16N-1E | Watters, Charles | Brown, Rex L. #1 | 1 | DAP | 668 | Ground level | 2,057 | Silurian | 4/27/1980 |
| 375 | 121152135800 | 9561 | -88.93316700 | 39.90830100 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze Childrens Trust | 3 | OIL | 673 | Kelly Bushing | 2,177 | Silurian | 9/25/1980 |
| 376 | 121152135900 | 9560 | -88.93083700 | 39.90837000 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze Childrens Trust | 4 | OIL | 673 | Kelly Bushing | 2,175 | Silurian | 9/25/1980 |
| 377 | 121152136000 | 9559 | -88.92846400 | 39.90846300 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze Childrens Trust | 5 | OIL | 673 | Kelly Bushing | 2,181 | Silurian | 9/25/1980 |
| 378 | 121152136100 | 9562 | -88.90952000 | 39.93737200 | 7-17N-3E | Triple G Oil Company Ltd. | Schwarze, Juanita | 1 | OILP | 684 | Kelly Bushing | 2,181 | Silurian | 1/14/1981 |
| 379 | 121152136200 | 9581 | -89.04908400 | 39.86301100 | 2-16N-1E | Watters, Charles | Dingman, Lyle D. Community #1 | 1 | OILP | 688 | Kelly Bushing | 2,054 | Silurian | 7/2/1980 |
| 380 | 121152136300 | 9602 | -88.92971100 | 39.91466500 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze, Vivian | 1 | OIL | 682 | Kelly Bushing | 2,150 | Silurian | 10/9/1980 |
| 381 | 121152136400 | 9688 | -89.03939500 | 39.87239300 | 1-16N-1E | Triple G Oil Company Ltd. | Bear Hybrid Corn Co. | 1 | OIL | 684 | Kelly Bushing | 2,035 | Silurian | 8/5/1980 |
| 382 | 121152136500 | 9689 | -88.93554500 | 39.90944700 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze Childrens Trust | 2 | OIL | 687 | Kelly Bushing | 2,179 | Silurian | 8/31/1980 |
| 383 | 121152136700 | 9998 | -89.04907200 | 39.86483200 | 2-16N-1E | Watters, Charles | Garver, Edward L. #1 | 1 | OILP | 681 | Ground level | 2,040 | Silurian | 7/17/1980 |
| 384 | 121152136800 | 10106 | -89.04197600 | 39.85948100 | 12-16N-1E | Watters, Charles | Davis, Virginia M. #1 | 1 | DAOP | 679 | Ground level | 2,049 | Silurian | 6/15/1980 |

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 385 | 121152137000 | 10172 | -89.02261700 | 39.80013300 | 31-16N-2E | Watters, Charles | Burt, Mary B. & Smith, Roberta etal | 1 | DAP | 645 | Ground level | 2,161 | Silurian | 12/29/1980 |
| 386 | 121152137100 | 10260 | -88.92623800 | 39.93658800 | 12-17N-2E | Triple G Oil Company Ltd. | McKinley | 1 | DAP | 684 | Kelly Bushing | 2,136 | Silurian | 4/29/1981 |
| 387 | 121152137200 | 10261 | -88.93568200 | 39.92178500 | 13-17N-2E | Triple G Oil Company Ltd. | Demange | 1 | DAP | 684 | Kelly Bushing | 2,170 | Silurian | 8/24/1980 |
| 388 | 121152137300 | 10263 | -88.92972500 | 39.91649500 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze, Vivian | 2 | OIL | 682 | Kelly Bushing | 2,155 | Silurian | 10/6/1980 |
| 389 | 121152137400 | 10290 | -88.93093500 | 39.92011100 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze, Vivian | 4 | OIL | 683 | Kelly Bushing | 2,151 | Silurian | 10/12/1980 |
| 390 | 121152137500 | 10291 | -88.93091800 | 39.91828100 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze, Vivian | 3 | OIL | 683 | Kelly Bushing | 2,155 | Silurian | 10/12/1980 |
| 391 | 121152137600 | 10264 | -88.93523400 | 39.89326300 | 25-17N-2E | Triple G Oil Company Ltd. | Henderson | 1 | OILP | 660 | Kelly Bushing | 2,178 | Silurian | 11/22/1980 |
| 392 | 121152137700 | 10262 | -88.91675500 | 39.92271100 | 18-17N-3E | Triple G Oil Company Ltd. | Fombelle, Hubert | 1 | OILP | 686 | Kelly Bushing | 2,174 | Silurian | 5/1/1981 |
| 393 | 121152137800 | 10332 | -88.93825100 | 39.93627300 | 11-17N-2E | Triple G Oil Company Ltd. | Chenoweth | 1 | DAP | 686 | Ground level | 2,143 | Silurian | 5/5/1981 |
| 394 | 121152138000 | 10464 | -89.05383200 | 39.85925000 | 11-16N-1E | Wycliff & Company | Mimms #1 | 1 | OILP | 594 | Kelly Bushing | 2,070 | Silurian | 2/3/1981 |
| 395 | 121152138100 | 10444 | -88.88046200 | 39.90625000 | 29-17N-3E | Davis, C. G. | French | 1 | DAP | 693 | Kelly Bushing | 2,294 | Devonian | 7/14/1980 |
| 396 | 121152138300 | 10963 | -88.99955300 | 39.86585100 | 5-16N-2E | Kaufman, E. H. | Shimer | 1 | DAOP | 672 | Kelly Bushing | 2,090 | Silurian | 8/29/1980 |
| 397 | 121152138400 | 11156 | -89.04670800 | 39.86494500 | 1-16N-1E | Comanche Oil (now Atlantic Energy) | Roby-Miller #2-C | 2-C | OIL | 686 | Kelly Bushing | 2,060 | Silurian | 10/7/1980 |
| 398 | 121152138500 | 11155 | -89.04435600 | 39.86305000 | 1-16N-1E | Comanche Oil (now Atlantic Energy) | Roby-Miller #3-C | 3-C | OIL | 685 | Kelly Bushing | 2,064 | Silurian | 10/1/1980 |
| 399 | 121152138600 | 11157 | -89.05365500 | 39.86669900 | 2-16N-1E | Comanche Oil (now Atlantic Energy) | Parish, Gerald | 1 | OILP | 697 | Kelly Bushing | 2,055 | Silurian | 10/19/1980 |
| 400 | 121152138800 | 11552 | -89.04186500 | 39.87049800 | 1-16N-1E | Comanche Oil (now Atlantic Energy) | Campbelll #2 | 2 | OIL | 686 | Kelly Bushing | 2,040 | Silurian | 11/25/1980 |
| 401 | 121152139000 | 11583 | -89.00427800 | 39.86573900 | 5-16N-2E | Kaufman, E.H. | Wilcox | 1 | DAP | 664 | Kelly Bushing | 2,061 | Silurian | 11/12/1980 |
| 402 | 121152139100 | 11674 | -89.04424800 | 39.86863300 | 1-16N-1E | Comanche Oil (now Atlantic Energy) | Campbell #3 | 3 | OIL | 681 | Ground level | 2,045 | Silurian | 1/12/1981 |
| 403 | 121152139200 | 11725 | -89.03709300 | 39.86512200 | 1-16N-1E | Carroll, Dell Oil Prop. | Sawyer & Gulick Comm. #2 | 2 | OIL | 690 | Kelly Bushing | 2,054 | Silurian | 12/19/1980 |
| 404 | 121152139300 | 11664 | -89.03935000 | 39.87606600 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Dingman | 1 | OIL | 685 | Kelly Bushing | 2,022 | Silurian | 12/14/1980 |
| 405 | 121152139400 | 11675 | -89.03225700 | 39.87611000 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Lehn | 1 | DAOP | 683 | Ground level | 1,988 | Silurian | 10/18/1980 |
| 406 | 121152139500 | 11831 | -89.02753700 | 39.86732300 | 6-16N-2E | Watters, Charles | Hayes, Wayne | 1 | OILP | 673 | Ground level | 2,060 | Silurian | 2/9/1981 |
| 407 | 121152139600 | 11837 | -88.94962600 | 39.91773000 | 23-17N-2E | Triple G Oil Company Ltd. | Hockaday | 7 | OILP | 680 | Kelly Bushing | 2,140 | Silurian | 1/1/1981 |
| 408 | 121152139700 | 11838 | -88.94731700 | 39.91597700 | 23-17N-2E | Triple G Oil Company Ltd. | Hockaday | 8 | OILP | 680 | Kelly Bushing | 2,146 | Silurian | 1/14/1981 |
| 409 | 121152139800 | 11813 | -88.94728800 | 39.91233100 | 23-17N-2E | Triple G Oil Company Ltd. | Loeb Phillips | 2 | OIL | 675 | Kelly Bushing | 2,155 | Silurian | 4/7/1981 |
| 410 | 121152139900 | 11814 | -88.94727400 | 39.91050700 | 23-17N-2E | Triple G Oil Company Ltd. | Loeb Phillips | 3 | OILP | 671 | Ground level | 2,155 | Silurian | 4/9/1981 |
| 411 | 121152140000 | 11834 | -88.92145700 | 39.91674200 | 24-17N-2E | Triple G Oil Company Ltd. | Pense | 2 | OIL | 682 | Ground level | 2,187 | Silurian | 8/25/1981 |
| 412 | 121152140100 | 11836 | -88.92147100 | 39.91856100 | 24-17N-2E | Triple G Oil Company Ltd. | Pense | 3 | OILP | 679 | Ground level | 2,180 | Silurian | 8/25/1981 |
| 413 | 121152140200 | 11833 | -88.92617900 | 39.91660200 | 24-17N-2E | Triple G Oil Company Ltd. | Schwartz, Vivian | 5 | OIL | 670 | Ground level | 2,170 | Silurian | 6/9/1981 |
| 414 | 121152140300 | 11839 | -88.92621000 | 39.92025700 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze, Vivian | 6 | OIL | 673 | Kelly Bushing | 2,160 | Silurian | 7/9/1981 |
| 415 | 121152140500 | 11906 | -89.04184600 | 39.87236400 | 1-16N-1E | Decatur Petroleum Co. | Bear Hybrid #1-A | 1-A | OIL | 680 | Ground level | 2,023 | Silurian | 6/13/1981 |
| 416 | 121152140600 | 11907 | -89.03702700 | 39.87242200 | 1-16N-1E | Decatur Petroleum Co. | Bear, R. #1 | 1 | OIL | 681 | Ground level | 2,030 | Silurian | 7/13/1981 |
| 417 | 121152140700 | 11910 | -88.87822100 | 39.91610300 | 21-17N-3E | Triple G Oil Company Ltd. | Hirsch, E. & P. | 1 | OIL | 669 | Ground level | 2,230 | | 5/30/1981 |
| 418 | 121152141200 | 12103 | -89.05838300 | 39.86666400 | 2-16N-1E | Carroll, Dell Oil Prop. | Gulick, Herb | 1 | TA | 691 | Kelly Bushing | 2,050 | Silurian | 9/8/1981 |
| 419 | 121152141300 | 12134 | -89.03698500 | 39.87607900 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Lehn | 2 | DAOP | 691 | Kelly Bushing | 2,025 | Silurian | 12/5/1980 |
| 420 | 121152141400 | 12220 | -89.04667200 | 39.87048100 | 1-16N-1E | Comanche Oil (now Atlantic Energy) | Campbell #4 | 4 | OIL | 680 | Kelly Bushing | 2,058 | Silurian | 3/17/1981 |
| 421 | 121152141500 | 12226 | -89.05839000 | 39.86848600 | 2-16N-1E | Pawnee Oil & Gas, Inc. | Dingman-Parish Community | 1 | OILP | 691 | Ground level | 2,038 | Silurian | 4/30/1981 |
| 422 | 121152141601 | 21950 | -89.05602600 | 39.86850500 | 2-16N-1E | Comanche Oil Corporation | Parish, G | 7 | OILP | 688 | Kelly Bushing | 2,050 | Silurian | 6/7/1983 |
| 423 | 121152141700 | 12333 | -89.05371700 | 39.86943200 | 2-16N-1E | Comanche Oil (now Atlantic Energy) | Parish, Gerald | 3 | OILP | 693 | Kelly Bushing | 2,055 | Silurian | 3/18/1981 |
| 424 | 121152141800 | 12334 | -89.05601900 | 39.86668300 | 2-16N-1E | Comanche Oil (now Atlantic Energy) | Parish, Gerald #2 | 4 | OILP | 696 | Kelly Bushing | 2,050 | Silurian | 3/25/1981 |
| 425 | 121152141801 | 26898 | -89.05601900 | 39.86668300 | 2-16N-1E | Comanche Oil (now Atlantic Energy) | Parish, Gerald | 2 | OIL | 696 | Kelly Bushing | 2,110 | Silurian | 3/25/1981 |
| 426 | 121152141900 | | -89.05135500 | 39.86853900 | 2-16N-1E | Pawnee Oil & Gas, Inc. | Parish, James | 1 | OIL | 691 | Ground level | 2,050 | Silurian | 1/14/1981 |
| 427 | 121152142000 | 12224 | -89.04901200 | 39.87418000 | 2-16N-1E | Pawnee Oil & Gas, Inc. | Parish, James | 2 | OILP | 681 | Ground level | 2,021 | Silurian | 4/24/1981 |
| 428 | 121152142100 | 12223 | -89.04417500 | 39.87603300 | 36-17N-1E | Pawnee Oil Corp. | Parish, James | 3 | OIL | 685 | Kelly Bushing | 2,040 | Silurian | 4/30/1981 |
| 429 | 121152142200 | 12221 | -89.04181100 | 39.87604800 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Dingman | 2 | OILP | 686 | Kelly Bushing | 2,050 | Silurian | 3/22/1981 |
| 430 | 121152142300 | 12219 | -89.03935100 | 39.87972300 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Dingman | 3 | OILP | 682 | Ground level | 2,040 | Silurian | 4/30/1981 |
| 431 | 121152142400 | 12321 | -88.94961500 | 39.91590800 | 23-17N-2E | Triple G Oil Company Ltd. | Hockaday | 9 | OILP | 677 | Ground level | 2,155 | Silurian | 4/4/1981 |
| 432 | 121152142500 | 12199 | -88.93797400 | 39.91533700 | 23-17N-2E | Barger Engineering, Inc. | Rohrkasse | 1 | OIL | 681 | Kelly Bushing | 2,175 | Silurian | 1/1/1981 |
| 433 | 121152142600 | 12198 | -88.94007300 | 39.89977500 | 26-17N-2E | Barger Engineering, Inc. | Casey | 1 | OIL | 675 | Ground level | 2,175 | Silurian | 4/30/1981 |
| 434 | 121152142700 | 7588 | -88.84163800 | 40.01083900 | 15-18N-3E | Hydrocarbon Survey, Inc. | Structure Test | 80-C-2 | CONF | | | | | |
| 435 | 121152142800 | 7589 | -88.85090000 | 40.01767100 | 15-18N-3E | Hydrocarbon Survey, Inc. | | 80-C-3 | CONF | | | | | |
| 436 | 121152142900 | 7587 | -88.86991000 | 40.01729700 | 16-18N-3E | Hydrocarbon Survey, Inc. | | 80-C-1 | CONF | | | | | |
| 437 | 121152143000 | 7591 | -88.87950500 | 40.00998200 | 16-18N-3E | Hydrocarbon Survey, Inc. | | 80-C-5 | CONF | | | | | |
| 438 | 121152143100 | 7590 | -88.85122400 | 40.00325300 | 22-18N-3E | Hydrocarbon Survey, Inc. | Structure Test | 80-C-4 | CONF | | | | | |
| 439 | 121152143200 | 7592 | -88.86065400 | 39.99552100 | 28-18N-3E | Hydrocarbon Survey, Inc. | 80-C-70 | | UNK | 689 | Digital Elevation Model | | | |
| 440 | 121152143300 | 12378 | -89.08290100 | 39.87199000 | 3-16N-1E | Comanche Oil (now Atlantic Energy) | Merriman #1 | 1 | DAP | 680 | Kelly Bushing | 2,015 | Devonian | 1/28/1981 |
| 441 | 121152143400 | 12376 | -89.09550300 | 39.82264600 | 21-16N-1E | Pawnee Oil Corp. | Beatty | 1 | OIL | 625 | Kelly Bushing | 2,035 | Silurian | 5/17/1981 |
| 442 | 121152143401 | 200819 | -89.09550300 | 39.82264600 | 21-16N-1E | Pawnee Oil Corp. | Pawnee-Beatty | 1 | TA | 625 | Kelly Bushing | 2,034 | Silurian | 6/4/1996 |
| 443 | 121152143402 | 55379 | -89.09550300 | 39.82264600 | 21-16N-1E | Pawnee Oil Corp. | Beatty | 1 | TA | 625 | Kelly Bushing | 2,034 | Silurian | 9/23/2001 |
| 444 | 121152143500 | 12380 | -89.04661400 | 39.88329800 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Parish, Gerald | 5 | DAP | 677 | Ground level | 2,026 | Devonian | 1/5/1981 |
| 445 | 121152143600 | 12453 | -89.05135600 | 39.86671800 | 2-16N-1E | Collins & Associates | Parish-Garver Comm. #1 | 1 | DAP | 692 | Ground level | 2,044 | Silurian | 12/29/1980 |
| 446 | 121152143601 | 28522 | -89.05135600 | 39.86671800 | 2-16N-1E | Collins & Associates | Parrish-Garver Comm. | 1 | OIL | 692 | Ground level | 2,140 | Silurian | 5/26/1984 |
| 447 | 121152143700 | 12452 | -89.01827500 | 39.86257600 | 6-16N-2E | Bianucci, Ray Management | Gaston | 1 | DAOP | 669 | Ground level | 2,080 | Silurian | 4/8/1981 |
| 448 | 121152143800 | 12417 | -88.94965100 | 39.92137600 | 14-17N-2E | Robertson, Harold | McKay | 1 | DAP | 682 | Kelly Bushing | 2,110 | Silurian | 12/20/1980 |

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 449 | 121152144000 | 12707 | -88.82083900 | 39.86703500 | 1-16N-3E | Randall, Russ, Inc. | Bartel | 1 | OIL | 696 | Kelly Bushing | 2,326 | Silurian | 4/18/1981 |
| 450 | 121152144100 | 12573 | -88.93331900 | 39.92185900 | 13-17N-2E | Triple G Oil Company Ltd. | Demange | 2 | OILP | 679 | Kelly Bushing | 2,166 | Silurian | 7/10/1981 |
| 451 | 121152144201 | 13365 | -88.92859700 | 39.92200400 | 13-17N-2E | Triple G Oil Company Ltd. | Oldweiler, E. | 2 | OILP | 684 | Ground level | 2,155 | Silurian | 9/25/1981 |
| 452 | 121152144300 | 12572 | -88.92382300 | 39.91667100 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze-Pense Comm. | 1 | OIL | 680 | Kelly Bushing | 2,183 | Trenton | 7/26/1981 |
| 453 | 121152144400 | 12571 | -88.92384300 | 39.92033400 | 24-17N-2E | Triple G Oil Company Ltd. | Schwarze-Pense Community | 2 | OIL | 680 | Kelly Bushing | 2,892 | Silurian | 9/27/1981 |
| 454 | 121152144500 | 12576 | -88.94225700 | 39.89060300 | 35-17N-2E | Triple G Oil Company Ltd. | Decatur Park District | 1 | OILP | 653 | Kelly Bushing | 2,175 | Silurian | 6/11/1981 |
| 455 | 121152144600 | 12599 | -88.85938600 | 40.00940200 | 22-18N-3E | Hydrocarbon Survey, Inc. | Pierce | 1 | DA | 700 | Ground level | 2,080 | Silurian | 3/2/1981 |
| 456 | 121152144700 | 12743 | -88.94027600 | 39.91526800 | 23-17N-2E | Barger Engineering, Inc. | Rohrkasse | 2 | OIL | 673 | Ground level | 2,163 | Silurian | 3/25/1981 |
| 457 | 121152144800 | 12747 | -88.93801700 | 39.91898300 | 23-17N-2E | Barger Engineering, Inc. | Rohrkasse | 3 | OILP | 678 | Ground level | 2,160 | Silurian | 4/7/1981 |
| 458 | 121152144900 | 12748 | -88.94031100 | 39.91891700 | 23-17N-2E | Barger Engineering, Inc. | Rohrkasse | 4 | OILP | 677 | Ground level | 2,160 | Silurian | 1/20/1981 |
| 459 | 121152145200 | 12746 | -88.93999800 | 39.89614000 | 26-17N-2E | Barger Engineering, Inc. | Casey | 4 | OIL | 659 | Kelly Bushing | 2,160 | Silurian | 3/1/1981 |
| 460 | 121152145400 | 12898 | -89.03236100 | 39.86522500 | 1-16N-1E | Watters, Charles | Hays, Martha L. #1 | 1 | OIL | 679 | Ground level | 2,046 | Silurian | 2/27/1981 |
| 461 | 121152145402 | 201066 | -89.03236100 | 39.86522500 | 1-16N-1E | Watters Oil & Gas Co. | Hays, Martha L. | 1 | SWD | 679 | Ground level | | | 4/29/1994 |
| 462 | 121152145600 | 12873 | -89.04192600 | 39.86498900 | 1-16N-1E | Comanche Oil (now Atlantic Energy) | Robey-Miller | 1-B | OILP | 683 | Kelly Bushing | 2,059 | Silurian | 7/6/1981 |
| 463 | 121152145700 | 12872 | -89.11165200 | 39.80789500 | 29-16N-1E | Pawnee Oil & Gas, Inc. | Macon County Materials | 1 | DAP | 601 | Ground level | 1,941 | Silurian | 1/26/1981 |
| 464 | 121152145800 | 12899 | -89.01845800 | 39.87297400 | 6-16N-2E | Watters, Charles | Garver, E. Jr., & N. G. | 1 | DAOP | 490 | Ground level | 2,050 | Silurian | 2/13/1981 |
| 465 | 121152145900 | 12968 | -89.03705700 | 39.87060100 | 1-16N-1E | Carroll, Dell Oil Prop. | Gulick, O. R. Estate #2 | 2 | OILP | 687 | Kelly Bushing | 2,030 | Silurian | 8/25/1981 |
| 466 | 121152146000 | 12954 | -89.04900100 | 39.87600200 | 35-17N-1E | Barger Engineering, Inc. | Doss-Gepford | 1 | OIL | 681 | Ground level | 2,020 | Silurian | 5/19/1981 |
| 467 | 121152146100 | 13110 | -89.04666000 | 39.87230300 | 1-16N-1E | Decatur Petroleum Co. | Bear Hybrid #2-A | 2-A | OIL | 681 | Ground level | 2,030 | Silurian | 6/13/1981 |
| 468 | 121152146201 | 13082 | -89.09063900 | 39.83179500 | 16-16N-1E | Watters, Charles | Hostetler, W. B. & J. C. | 1 | DAP | 649 | Ground level | 2,015 | Silurian | 3/26/1981 |
| 469 | 121152146300 | 13114 | -89.04421000 | 39.87233200 | 1-16N-1E | Triple G Oil Company Ltd. | Bear Hybrid #2 | 2 | OIL | 685 | Kelly Bushing | 2,018 | Silurian | 6/9/1981 |
| 470 | 121152146400 | 13284 | -89.03717300 | 39.86330100 | 1-16N-1E | Carroll, Dell Oil Prop. | Sawyer-Gulick Community | 3 | OIL | 692 | Kelly Bushing | 2,058 | Silurian | 10/29/1981 |
| 471 | 121152146401 | 200210 | -89.03717300 | 39.86330100 | 1-16N-1E | Carroll, Dell Oil Prop. | Sawyer-Gulick Community | 3 | UNKP | 688 | Ground level | 2,060 | | |
| 472 | 121152146500 | 13347 | -89.03458100 | 39.87245400 | 1-16N-1E | Decatur Petroleum Co. | Bear, Robt. #2 | 2 | OIL | 681 | Kelly Bushing | 2,030 | Silurian | 6/13/1981 |
| 473 | 121152146600 | 13348 | -89.01949100 | 39.90898000 | 19-17N-2E | Decatur Petroleum Co. | Beery | 1 | DAP | 698 | Ground level | 1,976 | Silurian | 3/8/1981 |
| 474 | 121152146700 | 13349 | -88.94858300 | 39.89712400 | 26-17N-2E | North Shore Oil Co. | Walston, Leroy Community | 1 | DAOP | 678 | Kelly Bushing | 2,153 | Silurian | 3/21/1981 |
| 475 | 121152146800 | 13434 | -88.94246800 | 39.89241200 | 26-17N-2E | Lynch, W.H. Oil Prod. | Hughes-Norfleet | 1 | OILP | 659 | Ground level | 2,150 | Silurian | 3/16/1981 |
| 476 | 121152146900 | 13393 | -88.99925600 | 39.88384600 | 32-17N-2E | Decatur Petroleum Co. | Kath Comm. | 1 | DAP | 631 | Ground level | 1,981 | Silurian | 3/17/1981 |
| 477 | 121152147000 | 13559 | -88.93110500 | 39.93282700 | 13-17N-2E | Triple G Oil Company Ltd. | Albert, Keith | 1 | DAOP | 685 | Kelly Bushing | 2,133 | Silurian | 5/12/1981 |
| 478 | 121152147100 | 12451 | -88.87822100 | 39.91651900 | 21-17N-3E | Bianucci, Ray Management | Hirsch, E & P | 1 | DAP | 669 | Ground level | 2,230 | Silurian | 3/31/1981 |
| 479 | 121152147200 | 13539 | -88.97979300 | 39.88511100 | 33-17N-2E | Lane, Virgil | Barnett, Vernie J. | 1 | DAOP | 628 | Kelly Bushing | 2,145 | Devonian | 3/26/1981 |
| 480 | 121152147300 | 13624 | -88.95946500 | 39.75809500 | 11-15N-2E | Harness Oil Properties | Jacobs Well #1 | 1 | DAP | 711 | Ground level | 2,459 | Silurian | 4/10/1981 |
| 481 | 121152147400 | 13693 | -89.06303000 | 39.86472200 | 2-16N-1E | Pawnee Oil & Gas, Inc. | Parish, Howard | 1 | DAP | 700 | Kelly Bushing | 2,060 | Devonian | 4/8/1981 |
| 482 | 121152147500 | 13694 | -89.04904800 | 39.86855500 | 2-16N-1E | Pawnee Oil & Gas, Inc. | Parish, James | 4 | OIL | 696 | Kelly Bushing | 2,055 | Silurian | 5/9/1981 |
| 483 | 121152147600 | 13695 | -89.07008000 | 39.87211800 | 3-16N-1E | Pawnee Oil & Gas, Inc. | Randle | 1 | DAP | 681 | Ground level | 2,014 | Silurian | 6/3/1981 |
| 484 | 121152147700 | 13697 | -89.14193800 | 39.86778600 | 6-16N-1E | Comanche Oil (now Atlantic Energy) | Pritchett #1 | 1 | DAOP | 607 | Ground level | 1,790 | Silurian | 6/12/1981 |
| 485 | 121152147800 | 13699 | -89.04180500 | 39.87970000 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Dingman | 4 | OILP | 683 | Kelly Bushing | 2,013 | Silurian | 6/30/1981 |
| 486 | 121152147900 | 13696 | -89.03698400 | 39.87792300 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Lehn | 3 | OILP | 691 | Kelly Bushing | 2,026 | Silurian | 5/22/1981 |
| 487 | 121152148000 | 13698 | -89.03698600 | 39.87974500 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Lehn | 4 | OILP | 690 | Kelly Bushing | 2,011 | Silurian | 6/1/1981 |
| 488 | 121152148100 | 13576 | -89.05837700 | 39.86484300 | 2-16N-1E | Carroll, Dell Oil Prop. | Gulick, Herb #2 | 2 | OILP | 689 | Kelly Bushing | 2,050 | Silurian | 7/27/1981 |
| 489 | 121152148200 | 14030 | -88.91673800 | 39.92089800 | 19-17N-3E | Triple G Oil Company Ltd. | Jurg-Padrutt | 1 | OILP | 684 | Kelly Bushing | 2,180 | Silurian | 9/21/1981 |
| 490 | 121152148300 | 14052 | -89.03953800 | 39.86320000 | 1-16N-1E | Comanche Oil (now Atlantic Energy) | Robey-Miller #5-C | 5-C | OIL | 687 | Kelly Bushing | 2,073 | Silurian | 7/7/1981 |
| 491 | 121152148400 | 14053 | -89.05371000 | 39.87224400 | 2-16N-1E | Comanche Oil (now Atlantic Energy) | Parish, Gerald | 6 | OILP | 690 | Kelly Bushing | 2,021 | Silurian | 7/24/1981 |
| 492 | 121152148500 | 14080 | -89.05863400 | 39.90317000 | 26-17N-1E | C & H Oil & Gas | Games, Lee | 1 | DAP | 680 | Ground level | 1,969 | Silurian | 6/29/1981 |
| 493 | 121152148600 | 14415 | -89.07440000 | 39.83547400 | 15-16N-1E | Watters, Charles | Hoffman, Howard #2 | 2 | OIL | 668 | Ground level | 2,050 | Silurian | 7/13/1981 |
| 494 | 121152148700 | 14414 | -89.00313700 | 39.88016900 | 32-17N-2E | Watters, Charles | Dalton, John S. | 1 | DAOP | 685 | Kelly Bushing | 2,024 | Silurian | 2/11/1982 |
| 495 | 121152148800 | 14486 | -88.98922500 | 39.89126600 | 28-17N-2E | Decatur Petroleum Co. | Staley-Butts | 1 | DAOP | 680 | Ground level | 2,052 | Silurian | 6/20/1981 |
| 496 | 121152148900 | 14609 | -88.94961700 | 39.90782700 | 23-17N-2E | Triple G Oil Company Ltd. | Phillips, Loeb | 4 | OILP | 673 | Ground level | 2,150 | Silurian | 6/28/1982 |
| 497 | 121152149000 | 14610 | -88.92148800 | 39.92040200 | 24-17N-2E | Triple G Oil Company Ltd. | Pense | 4 | OIL | 678 | Ground level | 2,170 | Silurian | 10/9/1981 |
| 498 | 121152149100 | 14611 | -88.91677600 | 39.92453300 | 18-17N-3E | Triple G Oil Company Ltd. | Fombelle | 2 | DAP | 682 | Ground level | 2,141 | Silurian | 11/18/1981 |
| 499 | 121152149200 | 14806 | -89.02748900 | 39.86914400 | 6-16N-2E | Bianucci, Ray Management | Stein | 1 | OILP | 681 | Ground level | 2,035 | Silurian | 7/26/1981 |
| 500 | 121152149300 | 15167 | -89.03453700 | 39.88343600 | 36-17N-1E | Carey, John Oil Co., Inc | Powers | 1 | DAP | 695 | Kelly Bushing | 2,200 | Silurian | 7/27/1981 |
| 501 | 121152149400 | 15262 | -88.91650900 | 39.90058300 | 30-17N-3E | Triple G Oil Company Ltd. | Schwarze, R. D. | 1 | DAP | 684 | Kelly Bushing | 2,187 | Silurian | 9/8/1981 |
| 502 | 121152149500 | 15300 | -89.06762400 | 39.85913100 | 10-16N-1E | Carey, John Oil Co., Inc | Hurst #1 | 1 | DA | 699 | Kelly Bushing | 2,160 | Silurian | 8/17/1981 |
| 503 | 121152149600 | 15332 | -89.06764100 | 39.84647600 | 10-16N-1E | John Carey Oil Co., Inc. | Richardson | 1 | OILP | 700 | Kelly Bushing | 2,087 | Silurian | 10/30/1981 |
| 504 | 121152149700 | 15441 | -89.07437500 | 39.83182300 | 15-16N-1E | Marquand, Charles L. | Breyfogle, Paul | 1 | OILP | 656 | Kelly Bushing | 2,075 | Silurian | 10/4/1981 |
| 505 | 121152149800 | 15444 | -89.11451100 | 39.79160600 | 32-16N-1E | Blackland Oil Co. | Kraft | 1 | DAOP | 587 | Ground level | 1,986 | Silurian | 8/11/1981 |
| 506 | 121152150000 | 15594 | -89.05140800 | 39.86299200 | 2-16N-1E | Watters, Charles | Dingman, Lyle Communitized #2 | 2 | DAOP | 684 | Ground level | 2,047 | Silurian | 8/22/1981 |
| 507 | 121152150101 | 41296 | -89.07442000 | 39.83913400 | 15-16N-1E | Watters Oil & Gas Co. | Hoffman, Howard | 3 | OIL | 682 | Kelly Bushing | 2,066 | Silurian | 1/27/1988 |
| 508 | 121152150400 | 15614 | -89.03444000 | 39.88067800 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Lehn, Melvin | 5 | OILP | 694 | Kelly Bushing | 2,000 | Silurian | 11/16/1981 |
| 509 | 121152150500 | 15615 | -89.03207500 | 39.87978900 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Lehn, Melvin | 6 | OILP | 695 | Kelly Bushing | 2,002 | Silurian | 11/16/1981 |
| 510 | 121152151000 | 15773 | -88.92611800 | 39.90959400 | 24-17N-2E | Barger Engineering, Inc. | Baby Fold | 1 | OIL | 663 | Ground level | 2,196 | Silurian | 10/29/1981 |
| 511 | 121152151100 | 15938 | -89.08588400 | 39.83182200 | 16-16N-1E | Watters, Charles | Brown, Rex L. Communitized #2 | 2 | DAOP | 671 | Ground level | 2,033 | Silurian | 10/10/1981 |
| 512 | 121152151200 | 16104 | -88.92623100 | 39.92207600 | 13-17N-2E | Triple G Oil Company Ltd. | Oldweiler, Eugenia | 3 | OILP | 689 | Kelly Bushing | 2,160 | Silurian | 12/14/1981 |

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 513 | 121152151400 | 16115 | -89.02744600 | 39.87083000 | 6-16N-2E | Bianucci, Ray Management | Stein | 2 | DAOP | 681 | Ground level | 2,020 | Silurian | 9/23/1981 |
| 514 | 121152151800 | 16226 | -89.02971600 | 39.88167000 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Lehn, Melvin | 7 | OILP | 702 | Kelly Bushing | 2,002 | Silurian | 11/21/1981 |
| 515 | 121152152001 | 28989 | -89.03708700 | 39.86876500 | 1-16N-1E | Carroll, Dell Oil Prop. | Gulick, O. R. Estate #3-A | 3-A | OIL | 692 | Kelly Bushing | 2,028 | Silurian | 5/19/1984 |
| 516 | 121152152100 | 16353 | -89.05837100 | 39.86302100 | 2-16N-1E | Carroll, Dell Oil Prop. | Gulick, Herb #3 | 3 | DAP | 684 | Ground level | 2,038 | Silurian | 5/22/1982 |
| 517 | 121152152200 | 16403 | -89.05579200 | 39.81935800 | 23-16N-1E | Carter Oil Prop., Inc. | Bourne | 2 | TAP | 592 | Ground level | 2,092 | Maquoketa | 4/5/1982 |
| 518 | 121152152300 | 16406 | -89.03956800 | 39.86137800 | 1-16N-1E | Comanche Oil (now Atlantic Energy) | Robey-Miller #6-C | 6-C | OILP | 689 | Kelly Bushing | 2,080 | Silurian | 11/16/1981 |
| 519 | 121152152400 | 16442 | -88.87801100 | 39.90137400 | 28-17N-3E | Davis, C. G. | Cundiff | 1 | DAP | 689 | Kelly Bushing | 2,285 | Silurian | 11/6/1981 |
| 520 | 121152152500 | 16499 | -89.03720300 | 39.86145200 | 1-16N-1E | Dell Carroll Oil Pro | Sawyer-Gulick Comm. #4 | 4 | OIL | 691 | Kelly Bushing | 2,060 | Silurian | 11/8/1981 |
| 521 | 121152152700 | 16725 | -89.03239900 | 39.86340300 | 1-16N-1E | Watters, Charles | Hays, Martha #2 | 2 | OIL | 682 | Ground level | 2,055 | Silurian | 12/4/1981 |
| 522 | 121152152800 | 16825 | -89.06983800 | 39.83913900 | 15-16N-1E | John Carey Oil Co., Inc. | Brown | 1 | OILP | 674 | Kelly Bushing | 2,079 | Silurian | 5/21/1982 |
| 523 | 121152152900 | 16951 | -89.03721500 | 39.85963000 | 12-16N-1E | Watters, Charles | McGrath & McNeill | 1 | OILP | 694 | Kelly Bushing | 2,065 | Silurian | 5/23/1982 |
| 524 | 121152153000 | 17235 | -88.92849600 | 39.91104700 | 24-17N-2E | Triple G Oil Company Ltd. | Schwartz Childrens Trust | 6 | OIL | 674 | Kelly Bushing | 2,180 | Silurian | 3/4/1982 |
| 525 | 121152154400 | 17333 | -88.92613500 | 39.91144400 | 24-17N-2E | Barger Engineering, Inc. | Baby Fold | 2 | OIL | 669 | Kelly Bushing | 2,188 | Silurian | 12/17/1982 |
| 526 | 121152154500 | 17434 | -89.03243600 | 39.86159800 | 1-16N-1E | Watters, Charles | Hays, Martha #3 | 3 | OIL | 681 | Ground level | 2,051 | Silurian | 2/18/1982 |
| 527 | 121152154600 | 17419 | -89.06062100 | 39.83924300 | 14-16N-1E | North Shore Oil Co. | Milne #1 | 1 | DAOP | 684 | Kelly Bushing | 2,075 | Silurian | 2/5/1982 |
| 528 | 121152154700 | 17383 | -89.07676200 | 39.83547200 | 15-16N-1E | Carey, John Oil Co., Inc | Fortney Community #1 | 1 | OIL | 670 | Kelly Bushing | 2,042 | Silurian | 5/4/1982 |
| 529 | 121152154800 | 17384 | -89.07912500 | 39.83546900 | 15-16N-1E | Carey, John Oil Co., Inc | Fortney Community #2 | 2 | OIL | 680 | Kelly Bushing | 2,054 | Silurian | 9/22/1982 |
| 530 | 121152154900 | 17405 | -88.97073800 | 39.91724700 | 22-17N-2E | Champaign Valley Res. | Hickory Point | 1 | DAP | 672 | Kelly Bushing | 2,064 | Silurian | 2/19/1982 |
| 531 | 121152155000 | 17501 | -89.03957600 | 39.85955700 | 12-16N-1E | Pawnee Oil & Gas, Inc. | Davis | 1 | OILP | 685 | Kelly Bushing | 2,080 | Silurian | 5/12/1982 |
| 532 | 121152155200 | 17839 | -88.93529600 | 39.89627500 | 25-17N-2E | Barger Engineering, Inc. | Security Savings & Loan | 1 | OIL | 669 | Ground level | 2,185 | Silurian | 9/29/1982 |
| 533 | 121152155300 | 17897 | -89.02995600 | 39.84893100 | 12-16N-1E | Pawnee Oil Corp. | Elwood | 1 | OILP | 671 | Kelly Bushing | 2,135 | Silurian | 3/2/1983 |
| 534 | 121152155400 | 17898 | -89.03956400 | 39.85594100 | 12-16N-1E | Pawnee Oil & Gas, Inc. | Macon Seed | 1 | OILP | 684 | Kelly Bushing | 2,100 | Silurian | 5/12/1982 |
| 535 | 121152155600 | 17954 | -89.09547800 | 39.82446700 | 21-16N-1E | Pawnee Oil & Gas, Inc. | Roby-Miller | 1-P | OILP | 623 | Kelly Bushing | 2,010 | Silurian | 6/19/1982 |
| 536 | 121152155700 | 17953 | -89.09314000 | 39.82267600 | 21-16N-1E | Pawnee Oil & Gas, Inc. | Rothwell | 1 | OILP | 631 | Kelly Bushing | 2,040 | Silurian | 6/20/1982 |
| 537 | 121152155800 | 18021 | -88.93308500 | 39.89451400 | 25-17N-2E | Triple G Oil Company Ltd. | Henderson Community | 2 | OILP | 660 | Ground level | 2,185 | Silurian | 5/2/1982 |
| 538 | 121152156000 | 18131 | -89.00872600 | 39.82943500 | 20-16N-2E | Triple G Oil Company Ltd. | Massey | 1 | DAP | 648 | Ground level | 2,130 | Silurian | 10/26/1982 |
| 539 | 121152156100 | 18130 | -88.94490800 | 39.91057600 | 23-17N-2E | Triple G Oil Company Ltd. | Phillips | 14 | OIL | 681 | Kelly Bushing | 2,165 | Silurian | 4/28/1982 |
| 540 | 121152156300 | 18474 | -89.02762800 | 39.86395000 | 6-16N-2E | Watters, Charles | Hayes, Wayne | 2 | DAOP | 686 | Ground level | 2,056 | Silurian | 4/25/1982 |
| 541 | 121152156400 | 18441 | -88.91717300 | 39.99670200 | 19-18N-3E | R & M Oil Prod. Corp. | Gardner-West | 1 | DAP | 701 | Ground level | 2,082 | Silurian | 4/29/1982 |
| 542 | 121152156500 | 18575 | -89.03458700 | 39.86881100 | 1-16N-1E | Carroll, Dell Oil Prop. | Gulick, O. R. Estate | 4 | OIL | 684 | Ground level | 2,030 | Silurian | 6/18/1982 |
| 543 | 121152156501 | 200208 | -89.03458700 | 39.86881100 | 1-16N-1E | Carroll, Dell Oil Prop. | Gulick, O. R. Estate | 4 | INJW | 684 | Ground level | 2,020 | | 6/19/1989 |
| 544 | 121152156600 | 18619 | -89.03472600 | 39.86516500 | 1-16N-1E | Dell Carroll Oil Pro | Sawyer-Gulick Comm. #5 | 5 | OIL | 686 | Ground level | 2,043 | Silurian | 6/4/1982 |
| 545 | 121152156700 | 18574 | -89.03481200 | 39.85970300 | 12-16N-1E | Carroll, Dell Oil Prop. | Gulick, Helen | 1 | OIL | 682 | Ground level | 2,071 | Silurian | 6/11/1982 |
| 546 | 121152156701 | 200209 | -89.03481200 | 39.85970300 | 12-16N-1E | Carroll, Dell Oil Prop. | Gulick, Helen | 1 | UNKP | 682 | Ground level | 2,071 | | |
| 547 | 121152156800 | 18694 | -89.03245100 | 39.85977700 | 12-16N-1E | Watters, Charles | Johnson Communitized | 1 | OILP | 686 | Kelly Bushing | 2,090 | Silurian | 5/21/1982 |
| 548 | 121152156900 | 18693 | -88.92386800 | 39.92215000 | 13-17N-2E | Triple G Oil Company Ltd. | Oldweiler, Eugenia | 4 | OILP | 681 | Kelly Bushing | 2,160 | Silurian | 6/17/1982 |
| 549 | 121152157000 | 18692 | -88.92150500 | 39.92222100 | 13-17N-2E | Triple G Oil Company Ltd. | Oldweiler, Eugenia | 5 | OILP | 680 | Kelly Bushing | 2,177 | Silurian | 1/7/1983 |
| 550 | 121152157300 | 18861 | -89.07325400 | 39.81012100 | 27-16N-1E | Pawnee Oil & Gas, Inc. | Clifton | 1 | DAP | 608 | Kelly Bushing | 2,037 | Silurian | 5/18/1982 |
| 551 | 121152157600 | 19162 | -89.02312100 | 39.86937200 | 6-16N-2E | Triple G Oil Company Ltd. | Stein | 1-A | DAOP | 683 | Kelly Bushing | 2,035 | Silurian | 7/12/1982 |
| 552 | 121152157700 | 19204 | -89.03243800 | 39.85796300 | 12-16N-1E | Watters, Charles | Dipper Comm. #1 | 1 | DAP | 683 | Ground level | 2,071 | Silurian | 6/14/1982 |
| 553 | 121152158000 | 19533 | -89.03471100 | 39.82515500 | 24-16N-1E | Carey, John Oil Co., Inc | Barding | 1 | DAP | 642 | Ground level | 2,115 | Silurian | 7/23/1982 |
| 554 | 121152158300 | 19752 | -89.07674800 | 39.83365000 | 15-16N-1E | Watters, Charles | Hoffman, Howard A. | 1-A | OILP | 667 | Ground level | 2,054 | Silurian | 8/24/1982 |
| 555 | 121152158500 | 19908 | -89.07000400 | 39.84646000 | 10-16N-1E | John Carey Oil Co., Inc. | Richardson | 2 | OILP | 700 | Kelly Bushing | 2,083 | Silurian | 11/15/1982 |
| 556 | 121152158600 | 19912 | -88.96614600 | 39.79563900 | 34-16N-2E | Watters, Charles | Tallman | 1 | DAOP | 690 | Ground level | 2,293 | Devonian | 8/1/1982 |
| 557 | 121152158700 | 20137 | -89.07911100 | 39.83364700 | 15-16N-1E | Watters, Charles | Hoffman, Howard A. #2-A | 2-A | OILP | 669 | Ground level | 2,049 | Silurian | 8/10/1982 |
| 558 | 121152158900 | 20252 | -89.08595300 | 39.83909000 | 16-16N-1E | Watters, Charles | Hollar, Susannah D. #1 | 1 | DAOP | 664 | Ground level | 2,029 | Silurian | 8/19/1982 |
| 559 | 121152159000 | 20381 | -88.93880200 | 39.89434300 | 26-17N-2E | Barger Engineering, Inc. | Casey-Hatch-Snow Community | 1 | OILP | 666 | Kelly Bushing | 2,167 | Silurian | 10/7/1982 |
| 560 | 121152159200 | 20588 | -89.06300600 | 39.85014900 | 11-16N-1E | Triple G Oil Company Ltd. | Lutz #1 | 1 | OIL | 704 | Kelly Bushing | 2,120 | Silurian | 1/13/1983 |
| 561 | 121152159300 | 20749 | -89.10426700 | 39.92998800 | 16-17N-1E | R. L. R. Development Corp. | Richardson | 1 | DAP | 644 | Kelly Bushing | 1,990 | Silurian | 9/20/1982 |
| 562 | 121152159400 | 20827 | -89.08134100 | 39.83546600 | 15-16N-1E | Carey, John Oil Co., Inc | Fortney Community #3 | 3 | OIL | 675 | Kelly Bushing | 2,050 | Silurian | 11/21/1982 |
| 563 | 121152159500 | 20822 | -89.07302200 | 39.93753800 | 10-17N-1E | R. L. R. Development Corp. | Richardson Communitzed | 1 | DAP | 654 | Kelly Bushing | 1,947 | Silurian | 9/24/1982 |
| 564 | 121152160100 | 21032 | -89.04673200 | 39.86115500 | 1-16N-1E | Comanche Oil (now Atlantic Energy) | Roby-Miller #7-C | 7-C | OIL | 689 | Kelly Bushing | 2,073 | Silurian | 5/10/1983 |
| 565 | 121152160400 | 21111 | -89.04416900 | 39.87967900 | 36-17N-1E | Comanche Oil (now Atlantic Energy) | Dingman | 5 | OIL | 682 | Kelly Bushing | 2,035 | Silurian | 6/7/1983 |
| 566 | 121152160600 | 21491 | -89.09544900 | 39.82628900 | 21-16N-1E | Pawnee Oil Corp. | Roby-Miller | 2-P | DAP | 623 | Kelly Bushing | 2,017 | Silurian | 11/13/1982 |
| 567 | 121152160700 | 21492 | -89.09311500 | 39.82449800 | 21-16N-1E | Pawnee Oil & Gas, Inc. | Roby-Miller | 3-P | OILP | 639 | Kelly Bushing | 2,053 | Silurian | 11/21/1982 |
| 568 | 121152160801 | 23510 | -89.10019600 | 39.82440300 | 21-16N-1E | Triple G Oil Company Ltd. | Scherer | 1 | OIL | 639 | Kelly Bushing | 2,010 | Silurian | 8/17/1983 |
| 569 | 121152161000 | 21535 | -89.05604100 | 39.87413300 | 2-16N-1E | Comanche Oil (now Atlantic Energy) | Parish, G. #8 | 8 | OIL | 679 | Kelly Bushing | 2,020 | Silurian | 6/7/1983 |
| 570 | 121152161800 | 21766 | -89.07690000 | 39.85362200 | 10-16N-1E | Carey, John Oil Co., Inc | Stookey #1 | 1 | DAP | 701 | Kelly Bushing | 2,180 | Silurian | 11/20/1982 |
| 571 | 121152162100 | 21851 | -88.92590900 | 39.89836000 | 25-17N-2E | Triple G Oil Company Ltd. | Klepzig Community | 1 | OILP | 661 | Kelly Bushing | 2,200 | Silurian | 5/14/1983 |
| 572 | 121152162200 | 22080 | -89.03957800 | 39.85050600 | 12-16N-1E | Pawnee Oil Corp. | Kick | 1 | DAP | 685 | Kelly Bushing | 2,102 | Silurian | 1/31/1983 |
| 573 | 121152162400 | 22317 | -89.03096500 | 39.86887900 | 1-16N-1E | Decatur Petroleum Co. | Bear, Robert #3 | 3 | OILP | 682 | Kelly Bushing | 2,016 | Silurian | 1/30/1984 |
| 574 | 121152162500 | 22322 | -89.06763600 | 39.85009400 | 10-16N-1E | Triple G Oil Company Ltd. | Lutz | 2 | OILP | 700 | Ground level | 2,100 | Silurian | 7/4/1983 |
| 575 | 121152162600 | 22316 | -89.03149200 | 39.87429400 | 1-16N-1E | Decatur Petroleum Co. | Bear, Robert #4 | 4 | DAP | 678 | Ground level | 1,990 | Silurian | 11/15/1983 |
| 576 | 121152163000 | 22578 | -89.06867800 | 39.84371700 | 15-16N-1E | Carey, John Oil Co., Inc | Hoyt Community #2 | 2 | DAP | 689 | Kelly Bushing | 2,102 | Silurian | 1/19/1983 |

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 577 | 121152163400 | | -89.02268700 | 39.73299000 | 19-15N-2E | owner | Taylorville Aquifer Study | TA-3 | STRAT | 688 | Topographic map | 165 | | 7/10/1980 |
| 578 | 121152163600 | | -88.96729600 | 39.78560800 | 3-15N-2E | owner | Taylorville Aquifer Study | TA-6 | STRAT | 712 | Topographic map | 145 | | 7/16/1980 |
| 579 | 121152164300 | 23770 | -89.00573800 | 39.87657000 | 32-17N-2E | Watters Oil & Gas Co. | Dalton, John | 2 | DAOP | 669 | Kelly Bushing | 2,028 | Silurian | 5/12/1983 |
| 580 | 121152164400 | 24301 | -89.03239000 | 39.87066000 | 1-16N-1E | Carroll, Dell Oil Prop. | Gulick, O. R. Estate #5 | 5 | DAP | 678 | Ground level | 2,019 | | 6/29/1983 |
| 581 | 121152164401 | 4129 | -89.03239000 | 39.87066000 | 1-16N-1E | Carroll, Dell Oil Prop. | Gulick, O. R. Estate | 5 | WATRSP | 678 | Ground level | 1,101 | | 7/13/1989 |
| 582 | 121152164600 | 24620 | -89.11435900 | 39.81340800 | 29-16N-1E | Guyon, Armand J. | Pistorius, Neil E. et al | 1 | TAOP | 601 | Ground level | 1,950 | Silurian | 6/24/1983 |
| 583 | 121152164601 | 38765 | -89.11435900 | 39.81340800 | 29-16N-1E | Watters Oil & Gas Co. | Pistorius etal | 1 | OILP | 601 | Ground level | 1,950 | Silurian | 9/1/1986 |
| 584 | 121152164800 | 24882 | -89.08235800 | 39.83000800 | 22-16N-1E | Watters Oil & Gas Co. | Cooper, Carl E. et al | 1-A | DAOP | 661 | Ground level | 2,064 | Silurian | 10/3/1983 |
| 585 | 121152165000 | 24944 | -88.92107600 | 39.89304000 | 25-17N-2E | Triple G Oil Company Ltd. | Harrison-Oliver Community | 1 | DAP | 656 | Ground level | 2,500 | Silurian | 9/12/1983 |
| 586 | 121152165100 | 24884 | -89.01247800 | 39.87627800 | 31-17N-2E | Watters Oil & Gas Co. | Noland, Christina | 1 | OIL | 693 | Kelly Bushing | 2,169 | Silurian | 7/26/1983 |
| 587 | 121152165200 | 24883 | -89.00548500 | 39.87839300 | 32-17N-2E | Watters Oil & Gas Co. | Dalton, John | 3 | DAOP | 671 | Kelly Bushing | 2,027 | Silurian | 7/14/1983 |
| 588 | 121152165400 | 25364 | -89.10255100 | 39.82437000 | 21-16N-1E | Triple G Oil Company Ltd. | Scherer | 2 | OIL | 611 | Kelly Bushing | 2,100 | Silurian | 12/1/1983 |
| 589 | 121152165500 | 25725 | -89.04414200 | 39.82314400 | 24-16N-1E | Carey, John Oil Co., Inc | Alsup-Goodrich Comm. | 1 | DAOP | 628 | Kelly Bushing | 2,136 | Silurian | 8/16/1983 |
| 590 | 121152165700 | 25158 | -89.11199700 | 39.81340800 | 29-16N-1E | Watters Oil & Gas Co. | Alsup, Raymond | 1 | OILP | 604 | Ground level | 1,971 | Silurian | 4/5/1987 |
| 591 | 121152165900 | 25726 | -89.01597900 | 39.87459500 | 6-16N-2E | Watters Oil & Gas Co. | Graves | 1 | OIL | 687 | Kelly Bushing | 2,070 | Silurian | 9/14/1983 |
| 592 | 121152166000 | 25431 | -89.01248000 | 39.87809400 | 31-17N-2E | Watters Oil & Gas Co. | Nolan, Christina | 2 | DAOP | 681 | Ground level | 2,075 | Silurian | 8/14/1983 |
| 593 | 121152166100 | 25429 | -89.01011600 | 39.87653000 | 32-17N-2E | Watters Oil & Gas Co. | Dalton, John | 4 | OIL | 681 | Kelly Bushing | 2,085 | Silurian | 8/15/1983 |
| 594 | 121152166201 | 26227 | -89.01011800 | 39.87831900 | 32-17N-2E | Watters Oil & Gas Co. | Dalton, John | 5 | OIL | 676 | Ground level | 2,084 | Silurian | 9/26/1983 |
| 595 | 121152166202 | 202610 | -89.01011800 | 39.87831900 | 32-17N-2E | IBEX Geological Consultants, Inc. | Dalton | 5-WI | INJW | 679 | Kelly Bushing | 2,085 | Silurian | 1/13/2005 |
| 596 | 121152166300 | 26101 | -89.05601200 | 39.85202400 | 11-16N-1E | Triple G Oil Company Ltd. | Bear, Robert #1 | 1 | OILP | 700 | Kelly Bushing | 2,180 | Silurian | 3/5/1984 |
| 597 | 121152166502 | 37494 | -89.05138600 | 39.85208200 | 11-16N-1E | Great Northern Oil Co., Ltd. | Bear, Robert | 2 | DAP | 694 | Kelly Bushing | 2,073 | | 4/6/1986 |
| 598 | 121152166600 | 25807 | -89.01361500 | 39.87464600 | 6-16N-2E | Watters Oil & Gas Co. | Garver | 2-A | DAOP | 676 | Ground level | 2,074 | Silurian | 9/4/1983 |
| 599 | 121152166700 | 25840 | -89.01720700 | 39.87623700 | 31-17N-2E | Niemeyer, Stephen M. | Friend, Ezra | 1 | OIL | 692 | Kelly Bushing | 2,102 | Silurian | 8/30/1983 |
| 600 | 121152166900 | 25809 | -89.00777300 | 39.87655100 | 32-17N-2E | Watters Oil & Gas Co. | Dalton, John | 6 | DAP | 674 | Kelly Bushing | 2,070 | Silurian | 8/21/1983 |
| 601 | 121152166901 | 44996 | -89.00779100 | 39.87655100 | 32-17N-2E | Watters Oil & Gas Co. | Dalton, John | WS-1 | WATRSP | 674 | Kelly Bushing | 2,045 | | 7/16/1991 |
| 602 | 121152167200 | 26368 | -89.00903600 | 39.87472900 | 5-16N-2E | Kaufman, E.H. | Reising | 1 | DAOP | 673 | Kelly Bushing | 2,090 | Silurian | 9/17/1983 |
| 603 | 121152167400 | 26565 | -89.00894200 | 39.86927200 | 5-16N-2E | John Carey Oil Co., Inc. | Shimer | 2 | OILP | 695 | Kelly Bushing | 2,084 | Silurian | 12/27/1983 |
| 604 | 121152167500 | 26736 | -89.01609400 | 39.87295300 | 6-16N-2E | Watters Oil & Gas Co. | Garver | 3-A | DAOP | 682 | Ground level | 2,089 | Silurian | 10/8/1983 |
| 605 | 121152167800 | 26631 | -89.01956800 | 39.87621600 | 31-17N-2E | Niemeyer, Stephen M. | Friend | 2 | OIL | 694 | Kelly Bushing | 2,127 | Silurian | 11/1/1983 |
| 606 | 121152167900 | 26226 | -89.01484100 | 39.87653300 | 31-17N-2E | Watters Oil & Gas Co. | Nolan, Christina | 3 | OIL | 682 | Ground level | 2,074 | Silurian | 10/3/1983 |
| 607 | 121152167901 | 200645 | -89.01484100 | 39.87653300 | 31-17N-2E | Watters Oil & Gas Co. | Nolan, Christine | 3 | INJW | 682 | Ground level | 2,075 | | 7/15/1991 |
| 608 | 121152168000 | 26737 | -89.01012300 | 39.88011000 | 32-17N-2E | Watters Oil & Gas Co. | Dalton, John | 7 | DAOP | 675 | Kelly Bushing | 2,031 | Silurian | 10/19/1983 |
| 609 | 121152168100 | 26738 | -89.00778400 | 39.88013600 | 32-17N-2E | Watters Oil & Gas Co. | Dalton, John | 8 | DAOP | 675 | Ground level | 2,070 | Silurian | 10/14/1983 |
| 610 | 121152168200 | 27348 | -89.10491400 | 39.82435900 | 20-16N-1E | Triple G Oil Company Ltd. | Hill Estate #1 | 1 | OIL | 608 | Ground level | 1,966 | Silurian | 4/3/1984 |
| 611 | 121152168201 | 45913 | -89.10491400 | 39.82435900 | 20-16N-1E | Pawnee Oil Corp. | Hill Estate | 1 | OILP | 608 | Ground level | 1,945 | Silurian | 8/20/1991 |
| 612 | 121152168700 | 27457 | -89.10255800 | 39.82254800 | 21-16N-1E | Pawnee Oil Corp. | Beatty | 2 | OIL | 611 | Kelly Bushing | 2,003 | Silurian | 12/13/1984 |
| 613 | 121152168800 | 27459 | -89.10022800 | 39.82073800 | 21-16N-1E | Pawnee Oil & Gas, Inc. | Beatty | 3 | OIL | 612 | Kelly Bushing | 2,050 | Silurian | 1/26/1984 |
| 614 | 121152168900 | 27458 | -89.09785100 | 39.82261200 | 21-16N-1E | Pawnee Oil & Gas, Inc. | Beatty | 4 | OIL | 620 | Kelly Bushing | 2,057 | Silurian | 7/4/1984 |
| 615 | 121152169000 | 27460 | -89.09783300 | 39.82443400 | 21-16N-1E | Pawnee Oil & Gas, Inc. | Robey-Miller | 4-P | OILP | 620 | Kelly Bushing | 2,008 | Silurian | 4/25/1984 |
| 616 | 121152169100 | 27733 | -89.10254100 | 39.82804400 | 21-16N-1E | Triple G Oil Company Ltd. | Scherer | 3-A | DA | 608 | Ground level | 2,011 | Silurian | 2/5/1984 |
| 617 | 121152169400 | 27516 | -89.02055800 | 39.87449200 | 6-16N-2E | Decatur Petroleum Co. | Stein | 1 | DAOGP | 682 | Kelly Bushing | 2,043 | Silurian | 12/20/1983 |
| 618 | 121152170300 | 28309 | -89.04906000 | 39.86673400 | 2-16N-1E | Pawnee Oil & Gas, Inc. | Garver | 1 | OIL | 685 | Ground level | 2,175 | Silurian | 5/28/1984 |
| 619 | 121152170400 | 27957 | -89.05483200 | 39.86478800 | 2-16N-1E | Comanche Oil (now Atlantic Energy) | Parish, Gerald #9 | 9 | OILP | 691 | Kelly Bushing | 2,110 | Silurian | 3/12/1984 |
| 620 | 121152170600 | 28310 | -89.09788200 | 39.81895500 | 21-16N-1E | Pawnee Oil & Gas, Inc. | Beatty | 5 | OIL | 616 | Kelly Bushing | 2,021 | Silurian | 6/30/1984 |
| 621 | 121152170700 | 28311 | -89.10256800 | 39.81887500 | 21-16N-1E | Pawnee Oil & Gas, Inc. | Beatty | 6 | OIL | 610 | Ground level | 2,010 | Silurian | 1/31/1984 |
| 622 | 121152170800 | 28140 | -88.88286400 | 39.97050200 | 32-18N-3E | Western Reserves Oil Co. | Parr Trust | 1 | DAO | 690 | Kelly Bushing | 2,165 | Silurian | 1/4/1984 |
| 623 | 121152171100 | 29100 | -89.05837600 | 39.85020900 | 11-16N-1E | Triple G Oil Company Ltd. | Wattley #1 | 1 | OIL | 703 | Kelly Bushing | 2,150 | Silurian | 5/20/1984 |
| 624 | 121152171200 | 29101 | -89.06073900 | 39.85017900 | 11-16N-1E | Triple G Oil Company Ltd. | Wattley #2 | 2 | OIL | 703 | Kelly Bushing | 2,100 | Silurian | 11/29/1984 |
| 625 | 121152171300 | 29321 | -89.09076200 | 39.84637700 | 9-16N-1E | Watters Oil & Gas Co. | Ennis, Arthur | 1 | DAP | 674 | Ground level | 2,050 | Silurian | 5/13/1984 |
| 626 | 121152171400 | 29341 | -89.06300700 | 39.84832700 | 11-16N-1E | Triple G Oil Company Ltd. | Davis #1 | 1 | OIL | 701 | Kelly Bushing | 2,050 | Silurian | 8/31/1984 |
| 627 | 121152171500 | 29340 | -89.06527400 | 39.84829700 | 11-16N-1E | Triple G Oil Company Ltd. | Davis #2 | 2 | OIL | 702 | Kelly Bushing | 2,090 | Silurian | 5/1/1985 |
| 628 | 121152171600 | 29322 | -88.97535500 | 39.90428400 | 28-17N-2E | Watters Oil & Gas Co. | Hazen, Velma | 1 | DAOP | 667 | Kelly Bushing | 2,100 | Silurian | 5/7/1984 |
| 629 | 121152171700 | 29477 | -89.01836300 | 39.86750600 | 6-16N-2E | Watters Oil & Gas Co. | Garver Communitized | 1-A | DAP | 675 | Ground level | 2,062 | Silurian | 6/20/1984 |
| 630 | 121152171900 | 29885 | -89.11436200 | 39.81156900 | 29-16N-1E | Watters Oil & Gas Co. | Pistorius | 2-A | DAP | 602 | Ground level | 1,977 | | 6/10/1984 |
| 631 | 121152172000 | 29871 | -89.02187200 | 39.91085600 | 19-17N-2E | Jordan Oil & Gas Co. | Stahl | 1 | DAOP | 702 | Kelly Bushing | 2,200 | Silurian | 6/2/1984 |
| 632 | 121152172100 | 29999 | -88.98004300 | 39.90420000 | 28-17N-2E | Watters Oil & Gas Co. | Butt, Howard | 1 | OILP | 663 | Kelly Bushing | 2,071 | Silurian | 7/2/1984 |
| 633 | 121152172200 | 30277 | -89.05341800 | 39.78284600 | 2-15N-1E | Carey, John Oil Co., Inc | Hopkins | 1 | DAOP | 681 | Kelly Bushing | 2,225 | Silurian | 6/21/1984 |
| 634 | 121152172500 | 30667 | -89.03549400 | 39.79433900 | 36-16N-1E | Watters Oil & Gas Co. | Hill, Allie | 1-A | DAOP | 689 | Kelly Bushing | 2,219 | Silurian | 7/13/1984 |
| 635 | 121152172600 | 30366 | -89.03899200 | 39.79244300 | 36-16N-1E | Watters Oil & Gas Co. | Hill, Allie R. | 4 | DAOP | 688 | Ground level | 2,200 | Silurian | 6/27/1984 |
| 636 | 121152172800 | | -88.93589000 | 39.81075600 | 26-16N-2E | IL State Water Survey | Lake Decatur Sediments | | STRAT | | | | | 6/30/1956 |
| 637 | 121152173500 | 30772 | -89.03932200 | 39.78083700 | 1-15N-1E | Carey, John Oil Co., Inc | Jockisch | 1 | DAOP | 675 | Kelly Bushing | 2,200 | Silurian | 7/21/1984 |
| 638 | 121152173600 | 30868 | -88.82807100 | 39.87072800 | 2-16N-3E | Baldwin, Don H. | Barnett, Richey | 1 | OIL | 691 | Kelly Bushing | 2,375 | Silurian | 11/2/1984 |
| 639 | 121152173700 | 31134 | -88.98236100 | 39.90233400 | 28-17N-2E | Watters Oil & Gas Co. | Butt, Howard | 2 | DAOGP | 664 | Kelly Bushing | 2,082 | Silurian | 8/14/1984 |
| 640 | 121152173800 | 31040 | -89.17245800 | 39.89101800 | 26-17N-1W | Carey, John Oil Co., Inc | Moore, J & B | 1 | DAOP | 601 | Kelly Bushing | 2,374 | Trenton | 8/14/1984 |

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 641 | 121152173801 | 31250 | -89.17245800 | 39.89101800 | 26-17N-1W | Carey, John Oil Co., Inc | Moore, J. & B. | 1 | DAP | 596 | Ground level | 2,378 | | 8/14/1984 |
| 642 | 121152174000 | 31408 | -89.08850700 | 39.80265700 | 28-16N-1E | Watters Oil & Gas Co. | Koonce, Carroll L. et al | 1-A | DAOP | 584 | Ground level | 2,000 | Silurian | 8/31/1984 |
| 643 | 121152174100 | 31397 | -88.78456000 | 39.87878500 | 6-16N-4E | Modern Explorations | Berry, Francis | 1 | DAOP | 678 | Kelly Bushing | 2,360 | Silurian | 9/16/1984 |
| 644 | 121152174200 | 31586 | -89.09323700 | 39.80339100 | 28-16N-1E | Watters Oil & Gas Co. | Koonce, Carroll et al | 2-A | DAP | 587 | Ground level | 1,979 | Silurian | 9/7/1984 |
| 645 | 121152174300 | 31585 | -89.04132600 | 39.79058900 | 36-16N-1E | Watters Oil & Gas Co. | Hill, Allie R. | 5 | OIL | 690 | Kelly Bushing | 2,193 | Silurian | 10/3/1984 |
| 646 | 121152174400 | 31888 | -88.99841900 | 39.87671800 | 32-17N-2E | Barger Engineering, Inc. | Wright, A. | 2 | OILP | 634 | Kelly Bushing | 2,123 | Silurian | 10/17/1984 |
| 647 | 121152174500 | 32064 | -89.04370200 | 39.79055900 | 36-16N-1E | Watters Oil & Gas Co. | Hill, Allie R. | 6 | DAOP | 686 | Ground level | 2,179 | Silurian | 11/1/1984 |
| 648 | 121152174600 | 32063 | -89.01366900 | 39.88172800 | 31-17N-2E | Watters Oil & Gas Co. | Nolan, Christina | 4 | DAOP | 684 | Kelly Bushing | 2,025 | Silurian | 10/11/1984 |
| 649 | 121152174700 | 32248 | -89.06064700 | 39.84836000 | 11-16N-1E | Triple G Oil Company Ltd. | Wattley #3 | 3 | OIL | 700 | Ground level | 2,160 | Silurian | 7/22/1985 |
| 650 | 121152174800 | 32172 | -89.00310500 | 39.87659500 | 32-17N-2E | Watters Oil & Gas Co. | Dalton, John | 9 | OIL | 671 | Kelly Bushing | 2,060 | Silurian | 11/7/1984 |
| 651 | 121152174900 | 32173 | -89.00312100 | 39.87839200 | 32-17N-2E | Watters Oil & Gas Co. | Dalton, John | 10 | OIL | 667 | Kelly Bushing | 2,051 | Silurian | 10/30/1984 |
| 652 | 121152183700 | 32326 | -89.04910400 | 39.85928700 | 11-16N-1E | Energy One 1984-1 | Mimms #2 | 2 | OILP | 692 | Kelly Bushing | 2,090 | Silurian | 10/9/1984 |
| 653 | 121152183800 | 32327 | -89.05147200 | 39.85744700 | 11-16N-1E | Energy One 1984-1 | Mimms #3 | 3 | OILP | 690 | Ground level | 2,130 | Silurian | 11/10/1984 |
| 654 | 121152183900 | 32328 | -89.04911000 | 39.85564400 | 11-16N-1E | Energy One 1984-1 | Mimms #4 | 4 | OILP | 694 | Kelly Bushing | 2,125 | Silurian | 11/13/1984 |
| 655 | 121152184000 | 32545 | -89.09316500 | 39.82085700 | 21-16N-1E | Basin Exploration, Inc. | Rothwell | 1-B | PLUG | 647 | Kelly Bushing | 2,050 | Silurian | 7/24/1985 |
| 656 | 121152184300 | 33245 | -88.79386900 | 39.93194800 | 18-17N-4E | Power Explorations | Anderson | 1 | DAP | 660 | Kelly Bushing | 2,310 | Silurian | 1/8/1985 |
| 657 | 121152184500 | 33377 | -88.97770300 | 39.90605900 | 21-17N-2E | Watters Oil & Gas Co. | Plankenhorn Comm. | 1 | DAP | 666 | Kelly Bushing | 2,064 | Devonian | 1/23/1985 |
| 658 | 121152184700 | 33428 | -89.01720900 | 39.87806100 | 31-17N-2E | Niemeyer, Stephen M. | Friend | 3 | DAO | 687 | Kelly Bushing | 2,068 | Silurian | 3/23/1985 |
| 659 | 121152184800 | 33512 | -88.79424200 | 39.88607800 | 31-17N-4E | Carey, John Oil Co., Inc | Eads, R. | 1 | DAOP | 687 | Kelly Bushing | 2,391 | Silurian | 2/10/1985 |
| 660 | 121152185000 | 33595 | -89.00128100 | 39.78938700 | 32-16N-2E | John Carey Oil Co., Inc. | Hubble | 1 | DAP | 723 | Kelly Bushing | 2,350 | Silurian | 2/19/1985 |
| 661 | 121152185200 | 33859 | -88.92119900 | 39.89849700 | 25-17N-2E | Triple G Oil Company Ltd. | Batthauer Community | 1 | OILP | 676 | Kelly Bushing | 2,223 | Silurian | 2/16/1986 |
| 662 | 121152185600 | 34307 | -89.10493100 | 39.81886100 | 20-16N-1E | Pawnee Oil & Gas, Inc. | Beatty | 9 | OIL | 611 | Kelly Bushing | 2,005 | Silurian | 5/8/1985 |
| 663 | 121152185900 | 34804 | -88.99858900 | 39.89107700 | 29-17N-2E | Petra Oil. Ltd. | Hughes-Robinson Tr.C | 1 | DAP | 674 | Kelly Bushing | 2,045 | Silurian | 9/4/1985 |
| 664 | 121152186000 | 34826 | -89.11198800 | 39.81705100 | 20-16N-1E | Pawnee Oil & Gas, Inc. | Beatty | 12 | OIL | 600 | Kelly Bushing | 2,000 | Silurian | 7/22/1985 |
| 665 | 121152187300 | 36172 | -89.11435000 | 39.81706500 | 20-16N-1E | Watters Oil & Gas Co. | Pistorius #4-A | 4-A | DAP | 604 | Ground level | 1,949 | Silurian | 8/22/1985 |
| 666 | 121152187400 | 36173 | -89.11199400 | 39.81523000 | 29-16N-1E | Watters Oil & Gas Co. | Alsup, Raymond | 2 | OILP | 609 | Kelly Bushing | 1,940 | Silurian | 8/26/1985 |
| 667 | 121152187500 | 36171 | -89.11435700 | 39.81524300 | 29-16N-1E | Watters Oil & Gas Co. | Pistorius | 5-A | OILP | 609 | Kelly Bushing | 1,948 | Silurian | 10/14/1985 |
| 668 | 121152188000 | 36268 | -89.00291000 | 39.87477200 | 5-16N-2E | Watters Oil & Gas Co. | Reising, Richard et al Comm | 1 | DAP | 631 | Ground level | 2,028 | Silurian | 9/6/1985 |
| 669 | 121152188300 | 36760 | -89.10965400 | 39.81521400 | 29-16N-1E | Watters Oil & Gas Co. | Alsup, Raymond | 3 | OILP | 609 | Kelly Bushing | 1,941 | Silurian | 10/16/1985 |
| 670 | 121152188400 | 36752 | -89.10729200 | 39.81519800 | 29-16N-1E | Watters Oil & Gas Co. | Alsup, Raymond | 4 | DAP | 612 | Ground level | 1,976 | Silurian | 10/6/1985 |
| 671 | 121152188800 | 36960 | -89.14834800 | 39.82566700 | 24-16N-1W | Watters Oil & Gas Co. | Durflinger | 1 | DAP | 605 | Ground level | 1,874 | Silurian | 10/29/1985 |
| 672 | 121152188900 | 37233 | -89.10728200 | 39.81701900 | 20-16N-1E | Pawnee Oil & Gas, Inc. | Beatty | 10 | OIL | 611 | Kelly Bushing | 2,005 | Silurian | 1/14/1986 |
| 673 | 121152189000 | 37234 | -89.10964400 | 39.81703500 | 20-16N-1E | Pawnee Oil Corp. | Beatty | 11 | OIL | 606 | Kelly Bushing | 1,980 | Silurian | 1/8/1987 |
| 674 | 121152193000 | 40365 | -88.86924200 | 39.96002700 | 4-17N-3E | Watters Oil & Gas Co. | Jackson, Nelson et al | 1 | DAP | 686 | Kelly Bushing | 2,161 | Silurian | 7/31/1987 |
| 675 | 121152193500 | 40488 | -88.80182600 | 39.87501100 | 6-16N-4E | Jasper Oil Company | Garber | 1 | OILP | 692 | Kelly Bushing | 2,339 | Silurian | 10/26/1987 |
| 676 | 121152197200 | 41301 | -89.10548400 | 39.80060700 | 32-16N-1E | Jason Recovery System, Ltd. | Kornewald, R | 1 | OILP | 594 | Kelly Bushing | 1,995 | Silurian | 2/23/1988 |
| 677 | 121152197300 | 41302 | -89.10730900 | 39.80059400 | 32-16N-1E | Jason Recovery System, Ltd. | Kornewald, R. | 2 | TAP | 586 | Ground level | 1,992 | Silurian | 9/27/1988 |
| 678 | 121152203500 | 41942 | -89.03662700 | 39.79233900 | 36-16N-1E | Watters Oil & Gas Co. | Hill, Allie Community | 1-B | TAP | 687 | Ground level | 2,160 | Silurian | 6/15/1988 |
| 679 | 121152204200 | 42172 | -89.10028000 | 39.81342700 | 28-16N-1E | Great Northern Oil Co., Ltd. | Dunn | 1 | OIL | 621 | Kelly Bushing | 2,010 | Silurian | 11/2/1988 |
| 680 | 121152205500 | 42403 | -88.97308800 | 39.76596300 | 10-15N-2E | White, Carl | Snow, James #1 | 1 | DAP | 722 | Kelly Bushing | 2,435 | Silurian | 9/24/1988 |
| 681 | 121152208200 | 42654 | -89.10258500 | 39.81520100 | 28-16N-1E | Great Northern Oil Co., Ltd. | Dunn | 2 | OIL | 622 | Kelly Bushing | 2,015 | Silurian | 1/31/1989 |
| 682 | 121152211500 | 42823 | -89.09792400 | 39.81164900 | 28-16N-1E | Great Northern Oil Co., Ltd. | Dunn | 3 | OIL | 619 | Ground level | 2,026 | Silurian Middle | 7/11/1989 |
| 683 | 121152225300 | | -89.07304300 | 39.93571900 | 10-17N-1E | Schwarthout | Engham, George | | UNK | 664 | Digital Elevation Model | 118 | | |
| 684 | 121152225700 | | -89.00770400 | 39.85572600 | 8-16N-2E | Woollen Brothers | Forster, George | | UNK | 606 | Digital Elevation Model | 170 | | |
| 685 | 121152226300 | | -88.99382500 | 39.88391600 | 32-17N-2E | | Janvrin, Lynn | | GAS | 670 | Digital Elevation Model | | | |
| 686 | 121152226400 | | -88.84512000 | 39.92034800 | 22-17N-3E | | Rowe | | GAS | 685 | Ground level | 93 | | |
| 687 | 121152232600 | 49460 | -89.15423000 | 39.84374100 | 13-16N-1W | Equitable Resources Exploration | IL-3026 | | DAP | 607 | Kelly Bushing | 2,200 | Maquoketa | 5/12/1993 |
| 688 | 121152259800 | 52765 | -89.10254700 | 39.81125900 | 28-16N-1E | Dart Oil & Gas Corp. | Dunn etal | | DAOP | 615 | Ground level | 2,080 | Silurian | 6/20/1997 |
| 689 | 121152259900 | | -88.88245700 | 39.85353700 | 8-16N-3E | IL State Water Survey | Lake Decatur Sediments | | STRAT | | | | | |
| 690 | 121152260000 | | -88.89181800 | 39.84975000 | 8-16N-3E | IL State Water Survey | Lake Decatur Sediments | | STRAT | | | | | |
| 691 | 121152260100 | | -88.86798900 | 39.83919900 | 16-16N-3E | Lentz Tony | Decatur Airport | 1 | UNK | 678 | Digital Elevation Model | | | |
| 692 | 121152260800 | | -88.85340200 | 39.91001800 | 22-17N-3E | IL State Water Survey | Lake Decatur Sediments | | STRAT | | | | | |
| 693 | 121152260900 | | -88.86290000 | 39.88434900 | 33-17N-3E | IL State Water Survey | Lake Decatur Sediments | | STRAT | | | 45 | | |
| 694 | 121152261000 | | -88.86290000 | 39.88434900 | 33-17N-3E | IL State Water Survey | Lake Decatur Sediments | | STRAT | | | 2 | | |
| 695 | 121152261600 | | -88.93828000 | 39.81619400 | 26-16N-2E | IL State Water Survey | Lake Decatur Sediments | | STRAT | | | 1 | | |
| 696 | 121152263000 | | -88.82876500 | 39.95353900 | 2-17N-3E | Pure Oil Company | Illinois Prospect | A-1 | STRU | 686 | Digital Elevation Model | 1,194 | | |
| 697 | 121152281700 | 54313 | -89.10257700 | 39.80775400 | 28-16N-1E | Lockwood, Ronald G. | Dunn Heirs - RGL | 1 | DAP | 615 | Ground level | 2,028 | | 1/9/2000 |
| 698 | 121152292100 | 55044 | -88.99423900 | 39.95074000 | 5-17N-2E | Lincoln Oil & Gas, L.L.C. | Bunselmeyer | 05-1S | DAP | 674 | Kelly Bushing | 2,100 | Silurian | 4/19/2001 |
| 699 | 121152292300 | 55041 | -89.01016400 | 39.95749000 | 5-17N-2E | Lincoln Oil & Gas, L.L.C. | Bunselmeyer | 05-1N | DAP | 701 | Kelly Bushing | 2,106 | Silurian | 4/23/2001 |
| 700 | 121152292700 | 55086 | -89.01829200 | 39.90710900 | 19-17N-2E | Lincoln Oil & Gas, L.L.C. | Lehn | 19-01 | DAP | 700 | Kelly Bushing | 2,150 | Silurian | 5/11/2001 |
| 701 | 121152292800 | 55087 | -89.01874800 | 39.91644800 | 19-17N-2E | Lincoln Oil & Gas, L.L.C. | McClure | 19-01 | DAP | 710 | Kelly Bushing | 2,125 | Silurian | 5/6/2001 |
| 702 | 121152293100 | 55066 | -88.99710500 | 39.96866500 | 32-18N-2E | Lincoln Oil & Gas, L.L.C. | Westerman | 32-2 | DAP | 710 | Kelly Bushing | 2,100 | Silurian | 4/30/2001 |
| 703 | 121152296800 | | -88.82147200 | 39.72458800 | 25-15N-3E | IL State Geological Survey | Soy Capital Agricultural Serv | | STRAT | | | 10 | | 10/15/2000 |
| 704 | 121152296900 | | -88.82159800 | 40.00952800 | 14-18N-3E | IL State Geological Survey | Penhallegon, Helen | | STRAT | | | 15 | | 10/25/2000 |

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 705 | 121152316200 | 56500 | -89.01695500 | 39.90985300 | 19-17N-2E | MDM Energy, Inc. | Beery, A. | 1 | DAP | 701 | Ground level | 2,096 | Hunton | 8/15/2004 |
| 706 | 121152337800 | | -88.89219700 | 39.87726600 | 5-16N-3E | Illinois State Geological Survey | Archer Daniels Midland | MMV-01B | CONF | | | | | |
| 707 | 121152339000 | | -88.90643800 | 39.88261000 | 31-17N-3E | Illinois State Geological Survey | ADM | MMV-02S | CONF | | | | | |
| 708 | 121152339200 | | -88.89710100 | 39.88387200 | 32-17N-3E | Illinois State Geological Survey | ADM | MMV-03S | CONF | | | | | |
| 709 | 121152339300 | | -88.89713600 | 39.88113500 | 32-17N-3E | Illinois State Geological Survey | ADM | MMV-04S | CONF | | | | | |
| 710 | 121152339400 | | -88.89712000 | 39.88111800 | 32-17N-3E | Illinois State Geological Survey | ADM | MMV-04UG | CONF | | | | | |
| 711 | 121152339500 | | -88.89709900 | 39.88109000 | 32-17N-3E | Illinois State Geological Survey | ADM | MMV-04P | CONF | | | | | |
| 712 | 121152339600 | | -88.89710600 | 39.88068100 | 32-17N-3E | Illinois State Geological Survey | ADM | MMV-04B | CONF | | | | | |
| 713 | 121152339700 | | -88.89772400 | 39.87617000 | 5-16N-3E | Illinois State Geological Survey | ADM | MMV-07UG | CONF | | | | | |
| 714 | 121152339800 | | -88.88917200 | 39.87963800 | 5-16N-3E | Illinois State Geological Survey | ADM | MMV-05S | CONF | | | | | |
| 715 | 121152339900 | | -88.88944200 | 39.87570100 | 5-16N-3E | Illinois State Geological Survey | ADM | MMV-08UG | CONF | | | | | |
| 716 | 121152340000 | | -88.88938400 | 39.87569000 | 5-16N-3E | Illinois State Geological Survey | ADM | MMV-08S | CONF | | | | | |
| 717 | 121152340100 | | -88.87725400 | 39.87150500 | 4-16N-3E | Illinois State Geological Survey | ADM | MMV-09S | CONF | | | | | |
| 718 | 121152341500 | | -88.89344800 | 39.87692800 | 5-16N-3E | Archer Daniels Midland | CCS Well | 1 | CONF | | | | | |
| 719 | 121152343800 | | -88.89395500 | 39.87704100 | 5-16N-3E | Archer Daniels Midland | Geophysical Monitoring Well | 1 | CONF | | | | | |
| 720 | 121152345500 | 60678 | -88.95488700 | 39.72923200 | 23-15N-2E | Stewart Producers, Inc. | Cooper Trust | 1 | DAP | 714 | Kelly Bushing | 2,600 | Silurian | 7/28/2010 |
| 721 | 121152346000 | | -88.89335900 | 39.87979500 | 32-17N-3E | Archer Daniels Midland | Verification Well | 1 | CONF | | | | | |
| 722 | 121152346600 | 60858 | -89.05795700 | 39.80297800 | 26-16N-1E | Minard Run Oil Company | Hill, W. | 1 | DAP | 669 | Kelly Bushing | 2,199 | | 10/24/2010 |
| 723 | 121152347000 | 60998 | -89.01280600 | 39.78315100 | 5-15N-2E | Production Energy, LLC | Bowman | 1 | OIL | 697 | Kelly Bushing | 2,340 | Silurian | 4/24/2011 |
| 724 | 121152347400 | 61118 | -89.01168000 | 39.78492000 | 5-15N-2E | Production Energy, LLC | Bowman | 2 | OIL | 697 | Kelly Bushing | 2,273 | Silurian | 5/5/2011 |
| 725 | 121152347500 | 61159 | -89.01066100 | 39.78126400 | 5-15N-2E | Production Energy, LLC | Butterfield | 1 | OIL | 703 | Kelly Bushing | 2,320 | Silurian | 5/14/2011 |
| 726 | 121152347600 | 61153 | -89.01036500 | 39.77944300 | 5-15N-2E | Production Energy, LLC | Butterfield | 2 | OIL | 706 | Kelly Bushing | 2,320 | | 5/14/2011 |
| 727 | 121152348700 | 61310 | -89.01266400 | 39.77771600 | 5-15N-2E | Swits, Gary D. | CMC Farms | 1 | DAP | 707 | Kelly Bushing | 2,313 | | 7/18/2011 |
| 728 | 121152348800 | 61315 | -89.00811600 | 39.78303700 | 5-15N-2E | Swits, Gary D. | Miller | 1 | OIL | 692 | Kelly Bushing | 2,305 | | 11/20/2011 |
| 729 | 121152349000 | | -88.88595000 | 39.88961200 | 32-17N-3E | Illinois State Geological Survey | ADM MVA-11LG | | CONF | | | | | |
| 730 | 121152349100 | | -88.88366800 | 39.88934400 | 32-17N-3E | Illinois State Geological Survey | MVA-11UG | | CONF | | | | | |
| 731 | 121152349300 | | -88.87988000 | 39.88345300 | 32-17N-3E | Illinois State Geological Survey | ADM MVA-13LG | | CONF | | | | | |
| 732 | 121152349400 | | -88.88347100 | 39.88205700 | 32-17N-3E | Illinois State Geological Survey | MVA-13-UG | | CONF | | | | | |
| 733 | 121152349500 | | -88.88347100 | 39.88205700 | 32-17N-3E | Illinois State Geological Survey | MVA-13B | | CONF | | | | | |
| 734 | 121152349600 | | -88.89650900 | 39.89265400 | 32-17N-3E | Illinois State Geological Survey | ADM MVA-10UG | | CONF | | | | | |
| 735 | 121152349700 | 61532 | -89.01526500 | 39.77975600 | 5-15N-2E | Reef Production, LLC | Hibbard, J. | 1 | DAP | 705 | Kelly Bushing | 2,310 | | 10/2/2011 |
| 736 | 121152350100 | | -88.89312100 | 39.88911300 | 32-17N-3E | Illinois State Geological Survey | Richland Community College | MNA-10B | CONF | | | | | |
| 737 | 121152350200 | | -88.89312100 | 39.88911300 | 32-17N-3E | Illinois State Geological Survey | Richland Community College | MVA-10LG | CONF | | | | | |
| 738 | 121152350300 | | -88.88347100 | 39.88205700 | 32-17N-3E | Illinois State Geological Survey | ADM | MVA 12B | CONF | | | | | |
| 739 | 121152350400 | | -88.88347100 | 39.88205700 | 32-17N-3E | Illinois State Geological Survey | ADM | MVA12UG | CONF | | | | | |
| 740 | 121152350500 | | -88.88347100 | 39.88205700 | 32-17N-3E | Illinois State Geological Survey | ADM | MVA12LG | CONF | | | | | |
| 741 | 121152350600 | 203664 | -89.01163400 | 39.78289500 | 5-15N-2E | Production Energy, LLC | Bowman | 3 | SWD | 690 | Kelly Bushing | 2,100 | | 12/1/2011 |
| 742 | 121152350700 | 61579 | -89.01515200 | 39.78323500 | 5-15N-2E | Production Energy, LLC | Church | 2 | OILP | 700 | Kelly Bushing | 2,320 | | 7/22/2012 |
| 743 | 121152350800 | 61559 | -89.01062800 | 39.78667600 | 5-15N-2E | Swits, Gary D. | Jones-Mowery-Miller | 1 | OIL | 697 | Kelly Bushing | 2,366 | | 11/28/2011 |
| 744 | 121152350900 | 61571 | -88.85476600 | 39.76016800 | 10-15N-3E | Sundog Oil, LLC | Stocks | 2 | OIL | 697 | Kelly Bushing | 3,835 | Trenton | 11/14/2011 |
| 745 | 121152351100 | 61603 | -88.79552700 | 39.78727600 | 5-15N-4E | Sundog Oil, LLC | Casner | 2 | OIL | 708 | Kelly Bushing | 1,870 | St Louis | 12/2/2011 |
| 746 | 121152351200 | 61604 | -88.79787500 | 39.78725700 | 6-15N-4E | Sundog Oil, LLC | Casner | 1 | TA | 705 | Kelly Bushing | 2,650 | Silurian | 11/26/2011 |
| 747 | 121152351600 | 61706 | -88.98896400 | 39.77362900 | 4-15N-2E | Production Energy, LLC | Winters | 1 | DAP | 723 | Kelly Bushing | 2,431 | Silurian | 1/5/2012 |
| 748 | 121152351800 | 61720 | -88.98775500 | 39.77000700 | 9-15N-2E | Production Energy, LLC | Winters | 3 | DAP | 727 | Kelly Bushing | 2,463 | Silurian | 3/14/2012 |
| 749 | 121152351900 | 61680 | -88.79566000 | 39.78914400 | 5-15N-4E | Sundog Oil, LLC | Casner | 4 | TA | 705 | Kelly Bushing | 3,527 | | 1/31/2012 |
| 750 | 121152351901 | 203761 | -88.79566000 | 39.78914400 | 5-15N-4E | Sundog Oil, LLC | Casner | 4 | SWD | 701 | Ground level | 3,474 | Benoist | 3/19/2012 |
| 751 | 121152353400 | 61740 | -89.00074500 | 39.77004800 | 8-15N-2E | Pioneer Oil Co., Inc. | Hudson | 1 | DAP | 705 | Ground level | 2,400 | Devonian - Siluria | 1/26/2012 |
| 752 | 121152353500 | 61769 | -88.79546700 | 39.78546500 | 5-15N-4E | Sundog Oil, LLC | Casner | 10 | UNK | 709 | Kelly Bushing | 1,777 | | 2/24/2012 |
| 753 | 121152353600 | 61760 | -88.79781500 | 39.78544600 | 6-15N-4E | Sundog Oil, LLC | Casner | 9 | TA | 707 | Kelly Bushing | 1,870 | | 2/6/2012 |
| 754 | 121152353700 | 61870 | -89.01044800 | 39.77781800 | 5-15N-2E | Production Energy, LLC | Kater | 1 | OIL | 718 | Kelly Bushing | 2,350 | | 7/11/2012 |
| 755 | 121152353800 | 61889 | -88.90342700 | 39.71655400 | 29-15N-3E | Bi-Petro, Inc. | Bromley | 1 | DAP | 693 | Kelly Bushing | 2,580 | | 4/8/2012 |
| 756 | 121152354801 | 62954 | -89.04066100 | 39.80520900 | 25-16N-1E | Sundog Oil, LLC | Hannah | 2 | UNK | 663 | Kelly Bushing | 2,820 | Trenton | 1/29/2014 |
| 757 | 121152355200 | 11171 | -88.89201000 | 39.89187500 | 32-17N-3E | Archer Daniels Midland | Verification Well | 2 | CONF | | | | | |
| 758 | 121152355300 | 62222 | -88.99165000 | 39.78452000 | 4-15N-2E | Production Energy, LLC | Aschauer | 1 | DAP | 704 | Kelly Bushing | 2,380 | | 8/27/2012 |
| 759 | 121152355500 | 62293 | -89.01768100 | 39.78344000 | 5-15N-2E | Production Energy, LLC | Church | 3 | DAP | 707 | Kelly Bushing | 2,320 | | 9/3/2012 |
| 760 | 121152359400 | | -88.88709200 | 39.88470200 | 32-17N-3E | Pioneer Oil Co., Inc. | Geophysical Monitoring | 2 | CONF | | | | | |
| 761 | 121152360100 | 62734 | -88.99620000 | 39.77558300 | 4-15N-2E | R K Petroleum Corp. | Snow Comm. | 1 | DAP | 715 | Kelly Bushing | 2,400 | | 6/15/2013 |
| 762 | 121152360200 | 62741 | -88.90896800 | 39.90822700 | 19-17N-3E | Crows Point Exploration, LTD. | Long | 1 | OIL | 683 | Kelly Bushing | 2,260 | | 7/14/2013 |
| 763 | 121152360300 | 62740 | -88.90424700 | 39.90643900 | 30-17N-3E | Crows Point Exploration, LTD. | Long | 2 | DAP | 683 | Kelly Bushing | 2,260 | | 4/4/2013 |
| 764 | 121152360301 | 63179 | -88.90424700 | 39.90643900 | 30-17N-3E | Crows Point Exploration, LTD. | Long | 2-A | OIL | 685 | Kelly Bushing | 2,289 | | 9/1/2014 |
| 765 | 121152360400 | 62762 | -88.79051400 | 39.79279500 | 31-16N-4E | Benchmark Properties, Ltd. | South Shores, Inc. Community | 1 | DAP | 714 | Kelly Bushing | 2,775 | Silurian | 6/21/2013 |
| 766 | 121152366600 | 62861 | -88.98410000 | 39.78093600 | 4-15N-2E | Sundog Oil, LLC | Tosh | 2 | UNK | 711 | Kelly Bushing | 3,000 | Trenton | 10/29/2013 |
| 767 | 121152366700 | 62862 | -88.98415300 | 39.78273500 | 4-15N-2E | Sundog Oil, LLC | Tosh | 3 | UNK | 707 | Kelly Bushing | 3,000 | | 11/7/2013 |
| 768 | 121152366800 | 62863 | -88.98420600 | 39.78453300 | 4-15N-2E | Sundog Oil, LLC | Tosh | 4 | UNK | 705 | Kelly Bushing | 3,000 | | 11/19/2013 |

**Table B.1: Oil and Gas Wells Within the AoR**

| Map ID | API Number | Permit Number | Longitude | Latitude | Location | Company Name | Well Name | Well Number | Status Code | Elevation (ft) | Elev Ref | Known TD (ft) | TD Formation | Completion Date |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 769 | 121152366900 | 62856 | -89.12268300 | 39.90431700 | 20-17N-1E | R K Petroleum Corp. | Bender | 1 | DAP | 645 | Kelly Bushing | 2,050 | | 6/25/2013 |
| 770 | 121152367100 | 62951 | -89.04494500 | 39.80877400 | 25-16N-1E | Sundog Oil, LLC | Hannah | 4 | UNK | 625 | Kelly Bushing | 3,202 | St Peter | 1/29/2014 |
| 771 | 121152367500 | 63003 | -89.04166800 | 39.80700700 | 25-16N-1E | Sundog Oil, LLC | Hannah | 3 | UNK | 650 | Kelly Bushing | 2,790 | Trenton | 1/29/2014 |
| 772 | 121152369400 | 63106 | -88.85636900 | 39.88176300 | 34-17N-3E | Blackwater Energy, LLC | Bradshaw | 1 | DA | 639 | Ground level | 2,970 | | 10/5/2013 |
| 773 | 121152369600 | 63201 | -88.84451300 | 39.88092400 | 34-17N-3E | MDM Energy, Inc. | Marietta | 1 | DAP | 695 | Kelly Bushing | 2,370 | Silurian | 12/20/2013 |
| 774 | 121152371200 | 64209 | -89.05155000 | 39.85574800 | 11-16N-1E | Penneco Oil Company | Bangert, Sharon R. | 1 | OIL | 698 | Kelly Bushing | 2,240 | Moccasin Springs | 4/19/2015 |
| 775 | 121152371300 | | -88.88799600 | 39.88490200 | 32-17N-3E | Pioneer Oil Co., Inc. | CCS | 2 | STRAT | 707 | Kelly Bushing | 7,192 | | |
| 776 | 121152372800 | 64568 | -88.82554300 | 39.88207700 | 35-17N-3E | Performance Plus Consulting | Arends | 1 | DAP | 688 | Kelly Bushing | 2,525 | | 4/30/2016 |
| 777 | 121152375400 | 64818 | -88.82749000 | 39.82649300 | 23-16N-3E | Long Creek Energy LLC | Rutherford | 1 | OILP | 690 | Kelly Bushing | 2,869 | | 12/16/2015 |
| 778 | 121152375500 | 64960 | -88.82508100 | 39.82333700 | 23-16N-3E | Long Creek Energy LLC | Rutherford | 3 | OILP | 682 | Kelly Bushing | 3,238 | | 6/27/2016 |
| 779 | 121152378100 | 65068 | -88.79888300 | 39.80929600 | 30-16N-4E | Gaitros Oil, LLC | Gaitros | 1 | DAP | 714 | Kelly Bushing | 3,327 | | 9/20/2016 |
| 780 | 121152378200 | | -88.89646000 | 39.88082400 | 32-17N-3E | IL State Geological Survey | ISGS Powerprobe | 1 | STRAT | | | 34 | | |
| 781 | 121152378300 | | -88.89690400 | 39.87715100 | 5-16N-3E | IL State Geological Survey | ISGS Powerprobe | 2 | STRAT | | | 48 | | |
| 782 | 121152378400 | | -88.89690400 | 39.87715100 | 5-16N-3E | IL State Geological Survey | ISGS Powerprobe | 3 | STRAT | | | 40 | | |
| 783 | 121152378500 | 65113 | -89.11687700 | 39.81352500 | 29-16N-1E | Pioneer Oil Co., Inc. | Pistorius | | DAP | 601 | Kelly Bushing | 2,042 | | 11/18/2016 |
| 784 | 121152381600 | | -88.91658000 | 39.87365000 | 6-16N-3E | IL State Geological Survey | ISGS | S09 | STRATP | | | | | |
| 785 | 121152381700 | | -88.91660900 | 39.87360300 | 35-17N-2E | IL State Geological Survey | ISGS | S06 | STRATP | | | | | |
| 786 | 121152381800 | | -88.87714500 | 39.87151000 | 4-16N-3E | IL State Geological Survey | ISGS | S04-05 | STRATP | | | | | |
| 787 | 121152381900 | | -88.91681600 | 39.89129800 | 31-17N-3E | IL State Geological Survey | ISGS | | STRATP | | | | | |
| 788 | 121152387201 | 65992 | -89.03555000 | 39.87052900 | 1-16N-1E | Countrymark Energy Resources, LLC | Gulick Estate | 6 | OIL | 679 | Kelly Bushing | 2,299 | | 11/5/2019 |
| 789 | 121152387400 | 65649 | -88.93556600 | 39.91086900 | 24-17N-2E | Podolsky Oil Co. | Schwarze Community | 7 | OIL | 687 | Kelly Bushing | 2,215 | | 6/25/2019 |
| 790 | 121390014700 | 294 | -88.77553400 | 39.73934300 | 21-15N-4E | Proctor, Richard S. | Reeter Heirs | 1 | DAP | 712 | Derrick Floor | 2,669 | Devonian | 3/13/1959 |
| 791 | 121470000600 | | -88.68910100 | 39.91543900 | 24-17N-4E | Myers, Theo | Wagoner Estate #1 | 1 | DA | 752 | Derrick Floor | 2,420 | Galena | 6/30/1955 |
| 792 | 121470000601 | | -88.68910100 | 39.91543900 | 24-17N-4E | Myers, Theo | WAGONER EST | 1 | DAP | 752 | Derrick Floor | 3,160 | | 9/19/1955 |
| 793 | 121470001200 | | -88.72461700 | 40.01325600 | 14-18N-4E | Alco Oil & Gas Corp. | Cisco | | UNK | 689 | Digital Elevation Model | 113 | | |
| 794 | 121470001600 | 765 | -88.68977900 | 39.82980200 | 24-16N-4E | Myers, Theo | Grady W. J. | 1 | DAOP | 691 | Derrick Floor | 2,550 | Tully | 4/30/1958 |
| 795 | 121470001800 | | -88.69928400 | 39.82797600 | 24-16N-4E | Unger, John | Shively, S. C. | 1 | DAP | 694 | Derrick Floor | 2,575 | Devonian | 5/31/1956 |
| 796 | 121470002000 | 1238 | -88.69706000 | 39.81519500 | 25-16N-4E | Haines, D. C. | Davis, Paul | 1 | DA | 697 | Ground level | 1,621 | Mississippian | 6/30/1958 |
| 797 | 121470002100 | 1632 | -88.68728600 | 39.83888200 | 18-16N-5E | Dotson Charles W | Peterson, Elbert | 1 | DAP | 699 | Ground level | 2,479 | Devonian | 8/31/1958 |
| 798 | 121470002200 | 1487 | -88.70877200 | 39.83512000 | 23-16N-4E | Dotson Charles W | Shively, S. L. | 2 | DAGP | 699 | Ground level | 2,503 | Devonian | 7/31/1958 |
| 799 | 121470002300 | 1284 | -88.68510100 | 39.82978400 | 19-16N-5E | Myers, Theo | Evans, Kenneth E. | 1 | DAOP | 696 | Derrick Floor | 2,493 | Lingle | 8/14/1958 |
| 800 | 121470002400 | 2268 | -88.66867600 | 39.83339800 | 20-16N-5E | Myers, Theodore F. | Hamman | 1 | DAP | 690 | Ground level | 2,567 | Silurian | 9/30/1958 |
| 801 | 121470002600 | 2466 | -88.72547600 | 39.82978600 | 23-16N-4E | Larson Arthur | Randall | 1 | DAP | 714 | Ground level | 2,587 | Devonian | 10/31/1958 |
| 802 | 121470002800 | 617 | -88.66052400 | 39.92604200 | 17-17N-5E | Jay-Vee Development Corp. | Woodward #1 | 1 | DAP | 729 | Ground level | 2,400 | Silurian | 4/30/1959 |
| 803 | 121470002900 | | -88.74436800 | 39.81512800 | 27-16N-4E | | Groff | 1 | DAP | 736 | Ground level | 2,669 | Silurian | 10/31/1959 |
| 804 | 121470003000 | 2263 | -88.69682200 | 39.83158100 | 24-16N-4E | Hill Production Co. | Grady, W. J. | 1 | DAP | 691 | Digital Elevation Model | 2,460 | Hardin | 10/31/1959 |
| 805 | 121470003600 | 1843 | -88.69685500 | 39.84246200 | 13-16N-4E | Wausau Petroleum Corporation | Cripe-Still Community | 1 | DAP | 699 | Kelly Bushing | 2,495 | Devonian | 8/31/1960 |
| 806 | 121470005100 | 342 | -88.69920500 | 39.83516900 | 24-16N-4E | Hill Production Co. | Grady | B-1 | DAOP | 696 | Kelly Bushing | 2,471 | Devonian | 4/2/1962 |
| 807 | 121470009700 | | -88.67290100 | 39.87887900 | 6-16N-5E | Unknown | Reed, Howard | 1 | DAP | 711 | Derrick Floor | 2,490 | Silurian | 9/30/1949 |
| 808 | 121470010700 | | -88.74034200 | 39.89108300 | 34-17N-4E | Woollen Brothers | Cerro Gordo #T 1-49 | T149 | UNK | 732 | Digital Elevation Model | 35 | | 12/31/1948 |
| 809 | 121470010800 | | -88.74034200 | 39.89108300 | 34-17N-4E | Woollen Brothers | Cerro Gordo #T 2-49 | T249 | UNK | 732 | Digital Elevation Model | 28 | | 12/31/1948 |
| 810 | 121470010900 | | -88.74034200 | 39.89108300 | 34-17N-4E | Woollen Brothers | Cerro Gordo #T 3-49 | T349 | UNK | 732 | Digital Elevation Model | 26 | | 12/31/1948 |
| 811 | 121470011200 | | -88.66852500 | 39.94515700 | 8-17N-5E | Woollen Brothers | Long, Floyd | | UNK | 680 | Digital Elevation Model | 56 | | 11/30/1947 |
| 812 | 121470011300 | | -88.68677100 | 39.93177600 | 18-17N-5E | Swartz & Biggs | Weir, E. W. (Dr.) | | GAS | 728 | Digital Elevation Model | 99 | | 6/30/1954 |
| 813 | 121470020800 | 171 | -88.67785200 | 39.86416900 | 7-16N-5E | Durr, D. & Lyons, G. L. | Tallman | 1 | DAP | 710 | Kelly Bushing | 2,430 | Devonian | 3/13/1966 |
| 814 | 121470026700 | | -88.71849300 | 39.79266200 | 35-16N-4E | Schwartz Dale E | Wheel Inn Motel | | GAS | 704 | Topographic map | 64 | | 12/31/1964 |
| 815 | 121470028900 | | -88.74584100 | 39.85090600 | 15-16N-4E | Carter Oil Co., The | Core Hole | 193 | STRU | 736 | Ground level | 1,490 | | 12/31/1939 |
| 816 | 121472033400 | | -88.71190600 | 39.81397600 | 26-16N-4E | Luttrell, Gerald D. | Wallace, Robert Jr. | | GAS | 702 | Topographic map | 64 | | 12/31/1971 |
| 817 | 121472070800 | | -88.74169200 | 40.01786800 | 15-18N-4E | Woollen Bros. | Hill, Lee | | UNK | 685 | Topographic map | 132 | | 3/31/1936 |
| 818 | 121472098600 | | -88.70702700 | 39.90178000 | 25-17N-4E | Woollen Bros. | Dobson, Locke | | GAS | 737 | Digital Elevation Model | | | 1/1/1944 |
| 819 | 121472156000 | | -88.70235600 | 39.98201700 | 24-18N-4E | IL State Geological Survey | West Mahomet | W-2 | OBS | 641 | GPS | 137 | | |
| 820 | 121472156200 | | -88.68579900 | 39.98345900 | 30-18N-4E | IL State Geological Survey | ISWS, North Mahomet | | OBS | 632 | GPS | 197 | | |
| 821 | 121472156300 | | -88.67814600 | 39.96347700 | 6-17N-4E | IL State Geological Survey | ISWS, S. Observation Well | | OBS | 668 | GPS | 199 | | |

Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR

Sensitive, Confidential, or Privileged Information

Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR

Sensitive, Confidential, or Privileged Information

Table B.2: Water Wells Within the AoR

Sensitive, Confidential, or Privileged Information

Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR

Sensitive, Confidential, or Privileged Information

Table B.2: Water Wells Within the AoR

Sensitive, Confidential, or Privileged Information

Table B.2: Water Wells Within the AoR




Table B.2: Water Wells Within the AoR

Sensitive, Confidential, or Privileged Information

Table B.2: Water Wells Within the AoR

Sensitive, Confidential, or Privileged Information

# APPENDIX C: Quality Assurance and Surveillance Plan

A quality assurance and surveillance plan (QASP) for all testing and monitoring activities pursuant to 40 CFR 146.90(k).

# Carbon Capture and Sequestration (CCS) Project
# Class VI Injection Wells: Quality Assurance and Surveillance Plan (QASP)

Carbon Sequestration Wells (CCS) #1, #2, #3, #4, #5, #6, and #7

U.S. EPA ID Number:
IL-115-6A-0001 (CCS#2)
IL-115-6A-0002 (CCS#1)

April 2023

Prepared by:
Archer Daniels Midland Company (ADM)

# Class VI Injection Wells: Quality Assurance and Surveillance Plan (QASP)

## Carbon Sequestration Wells (CCS) #1, #2, #3, 4, #5, #6, and #7

## Approvals:

| | |
|---|---|
| _____ | _____ |
| Douglas Kirk, Plant Manager, Decatur Corn | Date |
| _____ | _____ |
| Scott McDonald, Director, ADM UIC | Date |
| _____ | _____ |
| Jeff Neisslie, Environmental Manager, Decatur Corn | Date |
| _____ | _____ |
| Adam O'Connell, Decatur Area Environmental Manager | Date |

# Table of Contents


Table of Contents ..... 3

A. Project Management ..... 5

A.1. Project/Task Organization ..... 5

A.2. Problem Definition/Background ..... 6

A.3. Project/Task Description ..... 7

A.4. Quality Objectives and Criteria ..... 9

A.5. Special Training ..... 16

A.6. Documentation and Records ..... 17

B. Data Generation and Acquisition ..... 17

B.1. Sampling Process Design (Experimental Design) ..... 17

B.2. Sampling Methods ..... 20

B.3. Sample Handling and Custody ..... 23

B.4. Analytical Methods ..... 29

B.5. Quality Control ..... 29

B.6. Instrument/Equipment Testing, Inspection, and Maintenance ..... 31

B.7. Instrument/Equipment Calibration and Frequency ..... 31

B.8. Inspection/Acceptance for Supplies and Consumables ..... 32

B.9. Nondirect Measurements ..... 32

B.10. Data Management ..... 33

C. Assessment and Oversight ..... 34

C.1. Assessments and Response Actions ..... 34

C.2. Reports to Management ..... 34

D. Data Validation and Usability ..... 35

D.1. Data Review, Verification, and Validation ..... 35

D.2 Verification and Validation Methods ..... 35

D.3 Reconciliation with User Requirements ..... 36

References ..... 36

# A. Project Management

## A.1. Project/Task Organization

A.1. a/b. Key Individuals and Responsibilities

The project, led by Archer Daniels Midland Company (ADM), includes participation from several subcontractors. The Testing and Monitoring Activities responsibilities will be shared between ADM and their designated subcontractor and the program will be broken in six subcategories:

1. Shallow Groundwater Sampling
2. Deep Groundwater Sampling
3. Well Logging
4. Mechanical Integrity Testing (MIT)
5. Pressure/Temperature Monitoring
6. $CO_2$ Stream Analysis
7. Geophysical Monitoring

A.1.c. Independence of Project QA Manager from Data Gathering

The majority of the physical samples collected and data gathered as part of the monitoring, verification, and accounting (MVA) program is analyzed, processed, or witnessed by third parties independent and outside of the project management structure.

A.1.d. QA Project Plan Responsibility

ADM will be responsible for maintaining the QASP. ADM will periodically review this QASP and consult with USEPA if/when changes to the plan are warranted.

A.1.e. Project Organization

The individuals and organizations participating in this project which hold roles and responsibilities for the QASP are as follows:

- UIC Program Director – technical expertise for CCS operations
- Environmental Manager, Decatur Corn Plant – environmental and regulatory expertise for CCS operations

- Plant Manager, Decatur Corn Plant – overall responsibility for running and maintaining CCS operations
- Decatur Area Environmental Manager – environmental and regulatory expertise for CCS operations
- Consultants and Contractors – will be utilized by ADM to fulfil testing, monitoring, reporting, and quality control activities as directed by ADM

## A.2. Problem Definition/Background

A.2.a Reasoning

The CCS Project's monitoring, verification, and accounting (MVA) program has operational monitoring, verification, and environmental monitoring components. Operational monitoring is used to ensure safety with all procedures associated with fluid injection, monitor the response of storage unit, and the movement of the $CO_2$ plume. Key monitoring parameters include the pressure of injection well tubing & annulus, storage unit, above seal strata, and the lowermost USDW reservoir. Other monitoring parameters include injection rate, total mass & volume injected, injection well temperature profile, and geophysical monitoring. The verification component will provide information to evaluate if leakage of $CO_2$ through the caprock is occurring. This includes geophysical logging , pressure, and temperature monitoring. The environmental monitoring components will determine if the injectate is being released into the shallow subsurface or biosphere. This monitoring includes geophysical logging and ground water monitoring.

A robust MVA program has been developed for the CCS project based on the experience gained through the CCS#1 and CCS#2 projects. The knowledge and experience gained provides a high level of confidence that the storage unit (Mt Simon) is capable to accept and permanently retain the injectate. The primary goal of the MVA program is to demonstrate that project activities are protective of human health and the environment. To help achieve this goal, this Quality Assurance Surveillance Plan (QASP) was developed to insure the quality standards of the testing and monitoring program meet the requirements of the U.S. Environmental Protection Agency's (USEPA) Underground Injection Control (UIC) Program for Class VI wells.

A.2.b. Reasons for Initiating the Project

The goal of the injection project is permanent geologic sequestration of industrial-scale volumes of $CO_2$ in the Mt. Simon Sandstone to reduce atmospheric concentrations of $CO_2$.

A.2.c. Regulatory Information, Applicable Criteria, Action Limits

The Class VI regulations under 40 CFR 146 Subpart H requires owners or operators of Class VI wells to perform several types of activities during the lifetime of the project in order to ensure that the injection well maintains its mechanical integrity, that fluid migration and the extent of pressure elevation are within the limits described in the permit application, and that underground sources of

drinking water (USDWs) are not endangered. These monitoring activities include mechanical integrity tests (MITs), injection well testing during operation, monitoring of ground water quality in several zones, tracking of the CO2 plume and associated pressure front. This document details both the measurements that will be taken as well as the steps to ensure that the quality of all the data is such that the data can be used with confidence in making decisions during the life of the project.

## A.3. Project/Task Description

A.3. a/b. Summary of Work to be Performed and Work Schedule

The facility Testing and Monitoring program summarizes the testing and monitoring tasks, reasoning, responsible parties, locations and testing frequency.

| Well | Permit # |
|---|---|
| **CCS#1** | IL-115-6A-0002 Attachment C |
| **CCS#2** | IL-115-6A-0001 Attachment C |
| **CCS#3** | * |
| **CCS#4** | * |
| **CCS#5** | ** |
| **CCS#6** | ** |
| **CCS#7** | ** |

*Proposed wells under application documents under Project Number IL-0007 in GSDT.
** Proposed wells under application documents under Project Number IL-0010 in GSDT.

Figure 1 shows the geographic locations of CCS wells and associated monitoring wells.





**Figure 1**. CCS#1, CCS#2, CCS#3 CCS#4, CCS#5, CCS#6, and CCS#7 Injection, shallow groundwater, geophysical, and deep monitoring well locations.

## A.4. Quality Objectives and Criteria

A.4.a. Performance/Measurement Criteria

The overall QA objective for monitoring is to develop and implement procedures for subsurface monitoring, field sampling, laboratory analysis, and reporting which will provide results that will meet the characterization and non-endangerment goals of this project. Groundwater monitoring will be conducted during the pre-injection, injection, and post-injection phases of the project. Shallow and deep groundwater monitoring wells will be used to gather water-quality samples and pressure data. All the groundwater analytical and field monitoring parameters for each interval are listed in the facility Testing and Monitoring Plan. Table 1 presents the analytical parameters to be collected for groundwater samples. Table 2 presents analytical parameters associated with the $CO_2$ gas stream, also presented in the Testing and Monitoring plan. Table 3 presents a summary of analytical parameters for corrosion coupons and Table 4 presents a summary of measurement parameters for field gauges. Table 5 shows the actionable testing and monitoring outputs. The lists of analytes and other data may be reassessed periodically and adjusted to include or exclude analytes based on their effectiveness to the overall monitoring program goals.

Key testing and monitoring areas may include but are not limited to:

1. Shallow Groundwater Sampling
    - Aqueous chemical concentrations
2. Deep Formation Fluid Sampling
    - Aqueous chemical concentrations
3. Well Logging
    - pulse neutron, pressure, temperature, spinner
4. Mechanical Integrity Testing (MIT)
    - Pulsed neutron, temperature, cement evaluation logging
5. Pressure/Temperature Monitoring
    - Pressure/temperature from in-situ gauges
    - Pressure/temperature from surface gauges
6. $CO_2$ Stream Analysis
    - $CO_2$ Purity (% v/v, [GC])
    - Oxygen ($O_2$, ppm v/v)
    - Nitrogen ($N_2$, ppm v/v)
    - Carbon Monoxide (CO, ppm v/v)
    - Oxides of Nitrogen (NOx, ppm v/v)

- Total Hydrocarbons (THC, ppm v/v as $CH_4$)
- Methane ($CH_4$, ppm v/v)
- Acetaldehyde (AA, ppm v/v)
- Sulfur Dioxide ($SO_2$, ppm v/v)
- Hydrogen Sulfide ($H_2S$ ppm v/v)
- Ethanol (ppm v/v)

7. Geophysical Monitoring
    - Seismic data files (e.g., seg files for triggered events)
    - Processed time-lapse report

**Table 1.** Summary of analytical and field parameters for groundwater samples.

| Parameters | Analytical Methods [(1)] | Detection limit | Typical Precisions | QC Requirements |
|---|---|---|---|---|
| **Cations:** Ca, Fe, K, Mg, Na, and Si | ICP-OES, EPA Method 6010B | 0.001 to 0.1 mg/L (analyte, dilution and matrix dependent) | ±15% | Daily calibration; blanks, duplicates and matrix spikes at 10% or greater frequency |
| **Anions:** Br, Cl, F, NO3, and SO4 | Ion Chromatography, EPA Method 300.0 | 0.005 to 0.5 mg/L (analyte, dilution and matrix dependent) | ±15% | Daily calibration; blanks, duplicates and matrix spikes at 10% or greater frequency |
| **Dissolved $CO_2$** | Coulometric titration, ASTM D513-11 | 0.02 to 0.13 mg/L (analyte, dilution and matrix dependent) | ±15% | Duplicate measurement; standards at 10% or greater frequency |
| **Isotopes:** $\delta^{13}C$ of DIC | Isotope ratio mass spectrometry | 12.2 mg/L HCO3- for δ13C | ±0.15‰ for δ13C | 10% duplicates; 4 standards/batch |
| **Total Dissolved Solids** | Gravimetry; APHA 2540C | 12 mg/L | ±10% | Balance calibration, duplicate analysis |
| **Water Density (field)** | Oscillating body method | 0.0000 to 2.0000 | ±0.0002 g/mL | Duplicate measurements |
| **Alkalinity** | APHA 2320B | 4 mg/L | ±0.2°C | Factory calibration |
| **pH (field)** | EPA 150.1 | 2 to 12 pH units | ±0.2 pH unit | User calibration per manufacturer recommendation |
| **Specific conductance (field)** | APHA 2510 | 0 to 200 mS/cm | ±1% of reading | User calibration per manufacturer recommendation |
| **Temperature (field)** | Thermocouple | -5 to 50°C | ±0.2°C | Factory calibration |

Note 1: ICP = inductively coupled plasma; MS = mass spectrometry; OES = optical emission spectrometry; GC-P = gas chromatography - pyrolysis. An equivalent method may be employed with the approval of the UIC Program Director.

**Table 2.** Summary of analytical parameters for $CO_2$ gas stream. All analysis will be performed by ADM or a designated third-party laboratory.

| Parameters | Analytical Methods[1] | Detection Limit/Range | Typical Precisions | QC Requirements |
|---|---|---|---|---|
| **Oxygen** | ISBT 4.0 (GC/DID) | 1 uL/L to 5,000 uL/L (ppm by volume) | ± 10 % of reading | daily standard within 10 % of calibration, secondary standard after calibration |
| | GC/TCD | 0.1 % to 100 % | 5 - 10 % relative across the range, RT ± 0.1 min | daily standard, duplicate analysis within 10 % of each other |
| **Nitrogen** | ISBT 4.0 GC/DID | 1 uL/L to 5,000 uL/L (ppm by volume) | ± 10 % of reading | daily standard within 10 % of calibration, secondary standard after calibration |
| | GC/TCD | 0.1 % to 100 % | 5 - 10 % relative across the range, RT ± 0.1 min | daily standard, duplicate analysis within 10 % of each other |
| **Carbon Monoxide** | ISBT 5.0 Colorimetric | 5 uL/L to 100 uL/L (ppm by volume) | ± 20 % of reading | duplicate analysis |
| | ISBT 4.0 (GC/DID) | 1 uL/L to 5,000 uL/L (ppm by volume) | ± 10 % of reading | daily standard within 10 % of calibration, secondary standard after calibration |
| **Oxides of Nitrogen** | ISBT 7.0 Colorimetric | 0.2 uL/L to 5 uL/L (ppm by volume) | ± 20 % of reading | duplicate analysis |
| **Total Hydrocarbons** | ISBT 10.0 THA (FID) | 1 uL/L to 10,000 uL/L (ppm by volume) | 5 - 10 % of reading relative across the range | daily blank, daily standard within 10 % of calibration, secondary standard after calibration |
| **Methane** | ISBT 10.1 GC/FID) | 0.1 uL/L to 1,000 uL/L (ppm by volume)- dilution dependent | 5 - 10 % of reading relative across the range | daily blank, daily standard within 10 % of calibration, secondary standard after calibration |
| **Acetaldehyde** | ISBT 11.0 (GC/FID) | 0.1 uL/L to 100 uL/L (ppm by volume)- dilution dependent | 5 - 10 % of reading relative across the range | daily blank, daily standard within 10 % of calibration, secondary standard after calibration |
| **Sulfur Dioxide** | ISBT 14.0 (GC/SCD) | 0.01 uL/L to 50 uL/L (ppm by volume)- dilution dependent | 5 - 10 % of reading relative across the range | daily blank, daily standard within 10 % of calibration, secondary standard after calibration |
| **Hydrogen Sulfide** | ISBT 14.0 (GC/SCD) | 0.01 uL/L to 50 uL/L (ppm by volume)- dilution dependent | 5 - 10 % of reading relative across the range | daily blank, daily standard within 10 % of calibration, secondary standard after calibration |

| Parameters | Analytical Methods[1] | Detection Limit/Range | Typical Precisions | QC Requirements |
|---|---|---|---|---|
| **Ethanol** | ISBT 11.0 (GC/FID) | 0.1 uL/L to 100 uL/L (ppm by volume)- dilution dependent | 5 - 10 % of reading relative across the range | daily blank, daily standard within 10 % of calibration, secondary standard after calibration |
| **$CO_2$ Purity** | ISBT 2.0 Caustic absorption Zahm- Nagel | 99.00% to 99.99% | ± 10 % of reading | User calibration per manufacturer recommendation |
| | ALI method SAM 4.1 subtraction method (GC/DID) | 1 ppm for each target analyte (analyte dependent) - refer to Oxygen and Nitrogen analysis. | 5-10 % relative across the range | duplicate analysis within 10 % of each other |
| | GC/TCD | 0.1 % to 100 % | 5-10 % relative across the range, RT ± 0.1 min | standard with every sample, duplicate analysis within 10 % of each other |

Note 1: ICP = inductively coupled plasma; MS = mass spectrometry; OES = optical emission spectrometry; GC-P = gas chromatography - pyrolysis. An equivalent method may be employed with the approval of the UIC Program Director.

**Table 3.** Summary of analytical parameters for corrosion coupons. Instrument calibration conducted by 3rd party lab providing services.

| Parameters | Analytical Methods | Detection Limit/Range | Typical Precisions | QC Requirements |
|---|---|---|---|---|
| Mass | ASTM G1-03 | .005mg | +/-2% | Annually - OEM Standard Practice for Calibration of Instrument |
| Thickness | ASTM G1-03 | .001mm | +/-.0005mm | Annually - OEM Standard Practice for Calibration of Instrument |

**Table 4.** Summary of measurement parameters for field gauges.

| Parameters | Methods | Detection Limit/Range | Typical Precisions | QC Requirements |
|---|---|---|---|---|
| **Pressure** | Factory Calibrated in NIST certified lab. | +/- 0.001 psi / 0-3000 psi | +/- 0.01 psi | Annual Calibration of Instrument (3rd party) |
| **Temperature** | Factory Calibrated in NIST certified lab. | +/- 0.001 F / 0-500 F | +/- 0.01 F | Annual Calibration of Instrument (3rd party) |
| **Flowrate** | Factory Calibrated in NIST certified lab. | +/- 0.1000% of maximum scale | +/- 0.01 lbs/hr | Annual Calibration of Instrument (3rd party) |

**Table 5.** Actionable testing and monitoring outputs.

| | Project Action Limit | Detection Limit | Anticipated Reading |
|---|---|---|---|
| **MIT—Pulse neutron logging** | Action taken when log indicates $CO_2$ outside of expected range | +/- 0.5 SIGM or per OEM specification | Brine saturated ~ 60<br>$CO_2$ saturated ~ 8 |
| **Annual Wellbore MIT testing pressure** | <3% pressure loss over 1 hour | +/- 0.001 psi or per OEM specification | >3% pressure loss over 1 hour |
| **Fixed Surface and downhole gauges and logging gauges** | Action will be taken when pressures are well outside of modeled/expected range | Refer to Table 4 for surface gauges Refer to OEM specifications for other gauges | Within injection formation: >80% fracture gradient 0.71 psi/ft |
| **Wellbore integrity—DTS fiber optic temperature** | Action will be taken when there is an anomaly in temperature profile | Refer to OEM specifications | DTS provides continuous** temperature profile |
| **Seismic data files** | Detected $CO_2$ outside the AOR | Dependent on fluid saturation, and formation velocities | $CO_2$ plume migration similar to modeled outcome |

** Continuous DTS temperature monitoring will be satisfied with a minimum 10-minute sampling and hourly recording. If the DTS continuous monitoring is unavailable, the well can continue to operate by monitoring the surface tubing pressure and annulus pressure every 4 hours.

### A.4.b. Precision

Precision is the measure of agreement among a set of replicate measurements (e.g., field duplicates); accuracy is the closeness of a measure result to an accepted reference value. For groundwater sampling, data accuracy will be assessed by the collection and analysis of field blanks to test sampling procedures and matrix spikes to test lab procedures. Field blanks will be taken no less than one per sampling event to spot check for sample bottle contamination. Laboratory assessment of analytical precision will be the responsibility of the individual laboratories per their standard operating procedures.

Table 6 presents the calibrated pressure and temperature of representative downhole quartz gauge specifications. For direct pressure and logging measurements, precision data is presented in Table 7.

**Table 6.** Pressure and temperature—representative downhole quartz gauge specifications. Actual gauge utilized may have different specifications.

| | |
|---|---|
| Calibrated working pressure range | Atmospheric to 10,000 psi |
| Initial pressure accuracy | <+/-2 psi over full scale |
| Pressure resolution | 0.005 psi at 1-s sample rate |
| Pressure drift stability | <+/-1 psi per year over full scale |
| Calibrated working temperature range | 77–266°F |
| Initial temperature accuracy | <+/-0.9°F per +/-0.27°F |
| Temperature resolution | 0.009°F at 1-s sample rate |
| Temperature drift stability | <+/-0.1°F per year at 302 |
| Max temperature | 302°F |

**Table 7**. Representative Logging tool specifications. Actual logging tool may have different specifications.

| | RST | CBL | USI | Isolation Scanner |
|---|---|---|---|---|
| **Logging speed** | 1,800 ft/hr | 3,600 ft/hr | Standard resolution: 2,700 ft/hr High resolution: 563 ft/hr | Standard resolution: 2,700 ft/hr High resolution: 563 ft/hr |
| **Vertical resolution** | 15 inches | 3 ft | Standard resolution: 0.6 in High speed: 6 in | High resolution: 0.6 in High speed: 6 in |
| **Investigation** | Formation | Casing, annulus, and formation | Casing and annulus | Casing and annulus |
| **Temperature rating** | 302°F | 350°F | 350°F | 350°F |
| **Pressure rating** | 15,000 psi | 20,000 psi | 20,000 psi | 20,000 psi |

### A.4.c. Bias

Bias is the systemic distortion of a measurement process that causes error in one direction, and can be introduced during sampling and analysis. Sampling bias is address by using correct sampling methods and tools, analytical bias is assessed by comparing a measured value to a known value (i.e., matrix spike). Pressure or logging bias is address through use of consistent tools, equipment and methodology. Laboratory assessment of analytical bias will be the responsibility of the individual laboratories per their standard operating procedures and analytical methodologies. For direct pressure or logging measurements, there should be no bias.

### A.4.d. Representativeness

For groundwater sampling, data representativeness expresses the degree to which data accurately and precisely represents a characteristic of a population, parameter variations at a sampling point, a process condition, or an environmental condition. The sampling network has been designed to provide data representative of site conditions. For analytical results of individual groundwater samples, representativeness will be estimated by ion and mass balances. Ion balances with ±10% error or less will

be considered valid. Mass balance assessment will be used in cases where the ion balance is greater than ±10% to help determine the source of error. For a sample and its duplicate, if the relative percent difference is greater than 10%, the sample may be considered non-representative.

### A.4.e. Completeness

For groundwater sampling, data completeness is a measure of the amount of valid data obtained from a measurement system compared to the amount that was expected to be obtained under normal conditions. It is anticipated that data completeness of 90% for groundwater sampling will be acceptable to meet monitoring goals. For direct pressure and temperature measurements, it is expected that data will be recorded no less than 90% of the time.

### A.4.f. Comparability

Data comparability expresses the confidence with which one data set can be compared to another. The data sets to be generated by this project will be very comparable to future data sets because of the use of standard methods and the level of QA/QC effort. If historical groundwater quality data become available from other sources, their applicability to the project and level of quality will be assessed prior to use with data gathered on this project. Direct pressure, temperature, and logging measurements will be directly comparable to previously obtained data due to consistent measurement techniques.

### A.4.g. Method Sensitivity

Table 6 and Table 7 provide details regarding select gauge and logging tool specifications.

## A.5. Special Training

### A.5.a. Specialized Training

The geophysical survey equipment and wireline logging tools will be operated by trained personnel according to the standards of the service company conducting the work. The subsequent data will be processed and analyzed according to standard industry practice.

Trained personnel will be utilized for all groundwater field sampling activities. Upon request, ADM will provide the agency with all laboratory SOPs developed for the specific parameter using the appropriate standard method. Each laboratory technician conducting the analysis on the samples will be trained on the SOP developed for each standard method.

### A.5. b/c. Training Provider and Responsibility

Training for personnel will be provided by ADM or by the subcontractor responsible for the data collection activity.

## A.6. Documentation and Records

### A.6.a. Report Format and Package Information

A semi-annual report from ADM to USEPA will contain all required project data, including testing and monitoring information as specified by the UIC Class VI permit. Data will be provided in electronic or other formats as required by the UIC Program Director.

### A.6.b. Other Project Documents, Records, and Electronic Files

Other documents, records, and electronic files such as well logs, test results, or other data will be provided as required by the UIC Program Director.

### A.6.c/d. Data Storage and Duration

ADM or a designated contractor will maintain the required project data as provided elsewhere in the permit.

### A.6.e. QASP Distribution Responsibility

The QASP copy will be available and distributed through Policy Tech that will be owned by the Environmental Manager, Decatur Corn Plant. Colleagues who have responsibilities for implementing the plan will be marked as a read requirement and will therefore have distribution of the plan.

# B. Data Generation and Acquisition

## B.1. Sampling Process Design (Experimental Design)

Discussion in this section is focused on groundwater and fluid sampling and does not address monitoring methods that do not gather physical samples (e.g., logging, seismic monitoring, and pressure/temperature monitoring). During the pre-injection and injection phases, groundwater sampling is planned to include an extensive set of chemical parameters to establish aqueous geochemical reference data. Parameters will include selected constituents that: (1) have primary and secondary USEPA drinking water maximum contaminant levels, (2) are the most responsive to interaction with $CO_2$ or brine, (3) are needed for quality control, and (4) may be needed for geochemical modeling. The full set of parameters for each sampling interval is given in the Testing and Monitoring Plan.

After a sufficient baseline is established, monitoring scope may shift to a subset of indicator parameters that are (1) the most responsive to interaction with $CO_2$ or brine and (2) are needed for quality control. Implementation of a reduced set of parameters would be done in consultation with the USEPA. Revised QASP submittals are a form of consultation with USEPA. Isotopic analyses will be performed on baseline samples to the degree that the information helps verify a condition or establish an understanding of non-project related variations. For non-baseline samples, isotopic analyses may be reduced in all monitoring wells if a review of the historical project results or other data determines that further sampling for isotopes is not needed. During any period where a reduced set of analytes is used, if statistically significant trends are observed that are the result of unintended $CO_2$ or brine migration, the

analytical list would be expanded to the full set of monitoring parameters. The Ironton-Galesville groundwater samples will be analyzed by ADM or a third-party laboratory. Dissolved $CO_2$ will be analyzed by methods consistent with Test Method B of ASTM D 513-06, "Standard Test Methods for Total and Dissolved Carbon Dioxide in Water" or equivalent. Isotopic analysis will be conducted using established methods.

B.1.a. Design Strategy

*$CO_2$ Stream Monitoring Strategy*
The primary purpose of analyzing the carbon dioxide stream is to evaluate the potential interactions of carbon dioxide and/or other constituents of the injectate with formation solids and fluids. This analysis can also identify (or rule out) potential interactions with well materials. Establishing the chemical composition of the injectate also supports the determination of whether the injectate meets the qualifications of hazardous waste under the Resource Conservation and Recovery Act (RCRA), 42 U.S.C. 6901 et seq. (1976), and/or the Comprehensive Environmental Response, Compensation, and Liability Act, (CERCLA) 42 U.S.C. 9601 et seq. (1980). Additionally, monitoring the chemical and physical characteristics of the carbon dioxide (e.g., isotopic signature, other constituents) may help distinguish the injectate from the native fluids and gases if unintended leakage from the storage reservoir occurred. Injectate monitoring is required at a sufficient frequency to detect changes to any physical and chemical properties that may result in a deviation from the permitted specifications.

Calibration of transmitters used to monitor pressures, temperatures, and flow rates of $CO_2$ into the subsurface at the injection well and subsequent movement to the verification well shall be conducted annually. Reports shall contain test equipment used to calibrate the transmitters, including test equipment manufacturers, model numbers, serial numbers, calibration dates and expiration dates.

*Corrosion Monitoring Strategy*
Corrosion coupon analyses will be conducted quarterly to aid in ensuring the mechanical integrity of the equipment in contact with the carbon dioxide. Coupons shall be sent quarterly to a company for analysis and an analysis conducted in accordance with ASTM G01-03 or similar to determine and document corrosion wear rates based on mass loss.

*Shallow Groundwater Monitoring Strategy*
Eight dedicated monitoring wells have been selected for shallow groundwater monitoring. These wells have already been installed and screened in the Quaternary-age deposits to depths less than 150 ft below ground surface (bgs). The local Quaternary-age deposits are used predominantly as private water well sources in the area. The wells are designated as 10LG, 11LG, 12LG, 13LG, G101, G102,G103, and G104 (Figure 1). The wells were selected to give a spatial distribution around the planned $CO_2$ injection well locations.

*Deep Groundwater Monitoring Strategy*
Monitoring of the deeper St. Peter and Ironton-Galesville Sandstones will be used for early leakage detection in formations that are much closer to the Mt. Simon Sandstone injection reservoir. Fluid sampling at wells VW#1, VW#2, VW#3, VW#4, VW#5, GM#2, GM#3, GM#4, GM#5, GM#6 and GM#7 in combination with pressure monitoring, temperature monitoring, and pulse neutron logging will be used to determine if leakage is occurring at or near the injection well. The Ironton-Galesville Sandstone, has sufficient permeability (over 100 mD) such that pressure monitoring at the verification wells would detect a failure of the confining zone should it occur. MIT testing and DTS monitoring at the injection

well will also provide data to insure the mechanical integrity of the well is maintained. With the planned sampling and monitoring frequencies, it is expected that baseline conditions can be documented, natural variability in conditions can be characterized, unintended brine or $CO_2$ leakage could be detected if it occurred, and sufficient data will be collected to demonstrate that the effects of $CO_2$ injection are limited to the intended storage reservoir. No groundwater fluid sampling is planned for the Mt Simon intervals where free phase $CO_2$ has broken through.

B.1.b. Type and Number of Samples/Test Runs

Sampling frequencies are detailed in the permit Testing and Monitoring Plan (Permit Attachment C).

B.1.c. Site/Sampling Locations

Shallow groundwater monitoring will use existing wells 10LG, 11LG, 12LG, 13LG, G101, G102,G103, and G104 as noted in Section B.1.a. Deep groundwater monitoring will use existing wells VW#1, VW#2, VW#3, VW#4, VW#5, GM#2, GM#3, GM#4, GM#5, GM#6, and GM#7 (Figure 1) as noted in Section B.1.a.

$CO_2$ gas stream and corrosion coupon sampling will occur in the selected $CO_2$ collection or compression areas for each $CO_2$ source (i.e, ADM ethanol and cogeneration facilities, and ADM or 3rd party carbon capture systems).

B.1.d. Sampling Site Contingency

The shallow and deep groundwater monitoring wells are located on property of ADM and Richland Community College; access permissions have already been granted. No problems of site inaccessibility are anticipated. If inclement weather makes site access difficult, sampling schedules will be reviewed and alternative dates may be selected that would still meet permit-related conditions.

No problems of site inaccessibility are anticipated for $CO_2$ gas stream or corrosion coupon sampling. If inclement weather makes site access difficult, sampling schedules will be reviewed and alternative dates may be selected that would still meet permit related conditions.

B.1.e. Activity Schedule

The groundwater sampling activities and frequencies are summarized in the Testing and Monitoring Plan. The $CO_2$ gas stream and corrosion coupon sampling activities and frequencies are also summarized in the Testing and Monitoring Plan.

B.1.f. Critical/Informational Data

During both groundwater sampling and analytical efforts, detailed field and laboratory documentation will be recorded in field and laboratory forms and notebooks. Critical information will include time and date of activity, person/s performing activity, location of activity (well- field sampling) or instrument (lab analysis), field or laboratory instrument calibration data, field parameter values. For laboratory analyses, much of the critical data are generated during the analysis and provided to end users in digital and printed formats. Noncritical data may include appearance and odor of the sample, problems with well or sampling equipment, and weather conditions.

B.1.g. Sources of Variability

Potential sources of variability related to monitoring activities include:

1. Natural variation in fluid quality, formation pressure and temperature and seismic activity;
2. Variation in fluid quality, formation pressure and temperature, and seismic activity due to project operations;
3. Changes in recharge due to rainfall, drought, and snowfall;
4. Changes in instrument calibration during sampling or analytical activity;
5. Different staff collecting or analyzing samples;
6. Differences in environmental conditions during field sampling or monitoring activities;
7. Changes in analytical data quality during life of project; and
8. Data entry errors related to maintaining project database.

Activities to eliminate, reduce, or reconcile variability related to monitoring activities include:

1. Collecting long-term baseline data to observe and document natural variation in monitoring parameters,
2. Evaluating data in timely manner after collection to observe anomalies in data that can be addressed be resampled or reanalyzed,
3. Conducting statistical analysis of monitoring data to determine whether variability in a data set is the result of project activities or natural variation,
4. Maintaining weather- related data using on-site weather monitoring data or data collected near project site (such as from local airports),
5. Checking instrument calibration before, during and after sampling or sample analysis,
6. Trained staff,
7. Conducting laboratory quality assurance checks using third party reference materials, and/or blind and/or replicate sample checks, and
8. Developing a systematic review process of data that can include sample-specific data quality checks (i.e., cation/anion balance for aqueous samples).

## B.2. Sampling Methods

Logging, geophysical monitoring, and pressure/temperature monitoring does not apply to this section, and is omitted.

B.2. a/b. Sampling SOPs

Groundwater samples will be collected primarily using a low-flow sampling method consistent with ASTM D6452-99 (2005) or Puls and Barcelona (1996). If a flow-through cell is not used, field parameters will be measured in grab samples. Groundwater wells will be purged to ensure samples are representative of formation water quality. Static water levels in each well will be determined using an

electronic water level indicator before any purging or sampling activities begin. Dedicated pumps (e.g., bladder pumps) will be installed in each monitoring well to minimize potential cross contamination between wells. Groundwater pH, temperature, specific conductance, and dissolved oxygen will be monitored in the field using portable probes and a flow-through cell consistent with standard methods (e.g., APHA, 2005) given sufficient flow rates and volumes. Field chemistry probes will be calibrated at the beginning of each sampling day according to equipment manufacturer procedures using standard reference solutions. When a flow-through cell is used, field parameters will be continuously monitored and will be considered stable when three successive measurements made three minutes apart meet the criteria listed in Table 8.

**Table 8.** Stabilization criteria of water quality parameters during shallow well purging.

| FIELD PARAMETER | STABILIZATION CRITERIA |
|---|---|
| pH | +/- 0.2 units |
| Temperature | +/- 1°C |
| Specific Conductance | +/- 3% of reading in µS/cm |
| Dissolved Oxygen | +/- 10% of reading or 0.3 mg/L whichever is greater |

After field parameters have stabilized, samples will be collected. Samples requiring filtration will be filtered through a new 0.45 µm flow-through filter cartridges as appropriate and consistent with ASTM D6564-00. Prior to sample collection, filters will be purged with a minimum of 100 mL of well water (or more if required by the filter manufacturer). For alkalinity and total $CO_2$ samples, efforts will be made to minimize exposure to the atmosphere during filtration, collection in sample containers, and analysis.

Wells GM#2, GM#3, GM#4, VW#1, VW#2 and VW#3 will use a wireline sampling system with a sampling device (e.g., Kuster sampler or downhole pump) capable of collecting a sample from a discrete interval. The downhole samples will be processed in a manner consistent with ISGS-SOP-WB-V1.14 (dated August 10, 2012).

The existing deep groundwater monitoring wells were developed and purged extensively at the time of completion and similar plans will be used to develop GM#4. Prior to sampling, each zone will be purged to ensure representative samples are collected. Due to the extensive well development, the amount of fluid to be purged at the time of sampling will be relatively small. If a three-foot zone is perforated (similar to VW#1), then the annular space between the 2-7/8-in. tubing and the 5-1/2-in. casing is only 1.92 gal. Thus, relatively small purge volumes will adequately refresh each isolated sampling interval. Similar purging techniques will be used for collecting deep groundwater samples. Additional information about sampling procedures are given in Locke et al. (2013).

For the deep groundwater monitoring wells, gas lifts using a downhole gas lift mandrel will be used to produce fresh reservoir fluid from the formation. Alternatively, a downhole pump or other methods maybe utilized to produce reservoir fluids. During fluid sampling, the sampling device will be positioned at a point at which a representative sample of the reservoir's fluid is collected.

B.2.c. In-situ Monitoring.

In-situ monitoring of groundwater chemistry parameters is not planned.

B.2.d. Continuous Monitoring.

Pressure data will be collected from shallow groundwater wells on a periodic basis (e.g., hourly to daily) using dedicated pressure transducers with data loggers to generally characterize shallow water level trends. These data are not to satisfy any regulatory requirement and are strictly informational.

B.2.e. Sample Homogenization, Composition, Filtration.

Described in section B.2.b.

B.2.f. Sample Containers and Volumes

For $CO_2$ stream monitoring, samples will be collected in a clean sample container rated for the appropriate collection pressure (i.e., mini cylinders, polybags or equivalent).

For shallow and deep groundwater samples, all sample bottles will be new. Sample bottles and bags for analytes will be used as received (ready for use) from the vendor or contract analytical laboratory for the analyte of interest. A summary of sample containers is presented in Table 9.

B.2.g. Sample Preservation

No preservation is required or used for $CO_2$ gas stream, and additional details of sampling requirements are shown in Table 9. For groundwater and other aqueous samples, the preservation methods in Table 10 will be used. Corrosion coupon sampling only requires that the coupons be physically separated (e.g., sleeves, baggies) during transportation to prevent physical abrasion.

**Table 9.** Summary of sample containers, preservation treatments, and holding times for $CO_2$ gas stream analysis.

| Target Parameters | Volume/Container Material | Preservation Technique | Sample Holding time (max) |
|---|---|---|---|
| CO2 gas stream | (2) 2L MLB Polybags<br>(1) 75 cc Mini Cylinder | Sample Storage Cabinets | 5 Business Days |

B.2.h. Cleaning/Decontamination of Sampling Equipment

Dedicated pumps (e.g., bladder pumps) will be installed in each groundwater monitoring well to minimize potential cross contamination between wells. These pumps will remain in each well throughout the project period except for maintenance. Prior to installation, the pumps will be cleaned on the outside with a non-phosphate detergent. Pumps will be rinsed a minimum of three times with deionized water and a minimum of 1 L of deionized water will be pumped through pump and sample tubing. Individual cleaned pumps and tubing will be placed in plastic garbage bags for transport to the field for installation. All field glassware (pipets, beakers, filter holders, etc.) are cleaned with tap water to remove any loose dirt, washed in a dilute nitric acid solution, and rinsed three times with deionized water before use.

$CO_2$ gas stream sampling containers will be either disposed or decontaminated by the analytical lab. No sampling equipment will be utilized with the corrosion coupons or annual field gauge calibrations.

B.2.i Support Facilities

For sampling of groundwater, the following are required: air compressor, vacuum pump, generator, multi-electrode water quality sonde, analytical meters (pH, specific conductance, etc.). Field activities are usually completed in field vehicles and portable laboratory trailers located on site.

Sampling tubing, connectors and valves required to sample the $CO_2$ gas stream will be supplied by the analytical lab providing the sampling containers. Sampling will occur within the existing $CO_2$ compression building.

Similarly, corrosion coupons will be removed from the $CO_2$ injection line at each $CO_2$ source.

Field gauges will be removed from the injection well and verification well utilizing existing standard industry tools and equipment. Deployment and retrieval of verification well gauges will be done using procedures and equipment recommended by the vendor, subcontractor, or is standard per industry practice.

B.2.i. Corrective Action, Personnel, and Documentation

Field staff will be responsible for properly testing equipment and performing corrective actions on broken or malfunctioning field equipment. If corrective action cannot be taken in the field, then equipment will be returned to the manufacturer for repair or replaced. Significant corrective actions affecting analytical results will be documented in field notes.

## B.3. Sample Handling and Custody

Logging, geophysical monitoring, and pressure/temperature monitoring does not apply to this section, and is omitted.

Sample holding times (Table 10) will be consistent with those described in US EPA (1974), American Public Health Association (APHA, 2005), Wood (1976), and ASTM Method D6517-00 (2005). After collection, samples will be placed in ice chests in the field and maintained thereafter at approximately 4°C until analysis. The samples will be maintained at their preservation temperature and sent to the designated laboratory under Chain-of-Custody within 24 hours. Analysis of the samples will be completed within the holding time listed in Table 10. As appropriate, alternative sample containers and preservation techniques approved by the UIC Program Director will be used to meet analytical requirements.

B.3.a Maximum Hold Time/Time Before Retrieval

See Table 10.

B.3.b. Sample Transportation

See description at the beginning of Section B.3.

B.3.c. Sampling Documentation

Field notes will be collected for all groundwater samples collected. These forms will be retained and archived as reference. The sample documentation is the responsibility of groundwater sampling personnel.

An analysis authorization form shall be provided with each $CO_2$ gas stream sample provided for analysis.

B.3.d. Sample Identification

All sample bottles will have waterproof labels with information denoting project, sampling date, sampling location, sample identification number, sample type (freshwater or brine), analyte, volume, filtration used (if any), and preservative used (if any). See Figure 2 for an example of a label. Figure 3 is an example of a $CO_2$ gas stream analysis authorization form.






**Figure 2.** Example label for groundwater sample bottles.



# Airborne Labs International, Inc.

22C World's Fair Drive, Somerset, NJ 08873 Fax: 732-302-3035 Phone: 732-302-1950
E-mail: airbornelabs@aol.com Website: www.airbornelabs.com

## Analysis Authorization

*This form MUST be completed & returned with a sample shipment*

**1.) Report Results to*:**

Company: _____
Address: _____
Address: _____
Address: _____
Address: _____
Attention: _____
Telephone: (_____)_____
Fax: (_____)_____
E-Mail: _____

Sampled On (mm/dd/yy): _____
P.O. #: _____
Credit Card: Visa Amex MasterCard Discover
Card #: _____
Cardholder: _____
Exp. Date: _____
Check #: _____
Other: _____
Pricing Discussed/Quoted? Y N

*Please attach complete billing address if different from reporting address.

**2.) Number of Samples Submitted:** _____ Container Type(s): _____

**3.) Sample Description** (circle): Liquid $CO_2$ CO2 (Final) Vapor CO2 Feedgas* $CO_2$ In-Process Food Grade $CO_2$ LIN LOX LAR RELOX (Reboiler) ABO

*IF $CO_2$ Feedgas –Identify source (e.g. Ethanol/Ammonia/Nat. Well/Ethylene/Combustion, Self-Gen, etc.) _____

Aviator Breathing Oxygen (ABO) Natural Gas Refinery Gas Syn Gas Propane Butane Air Oxygen Nitrogen Argon Hydrogen Helium Neon Xenon Krypton Freon® Refrigerant Gas Mixture Fuel Oil Lubricant

Other (Describe): _____

**4.) Sample Type** (Check) : Industrial____Medical_____ MilSpec_____ Other_____
(attach a log for multiple samples)

**5.) Sample ID:** _____

**6.) Potential Hazards/Safety Issues:** _____

**7.) Analytical Test(s) Requested** (check program or select individual tests required where applicable):

Std ISBT/Vendor $CO_2$ Test Program_____ Std $CO_2$ Feedgas Program_____ Std CGA Test Program_____ Std Medical Gas_____
Std Contract Program_____ Std ASTM Test Program____ MIL Spec Test Program____

%Purity THC $CH_4$ TNMHC Vol Hydrocarbons (C1-C6) BTEX Water Vapor NVR/NVOR Oil/Grease Total Sulfur $H_2S$ $SO_2$ COS MeSH t-Butyl Mercaptan Vol Sulfur Compnds Odorants Total Nitrogen $N_2$ $NO_x$ $NH_3$ NO $NO_2$ HCN Nitrous Oxide ($N_2O$) $PH_3$ Oxygen Argon Hydrogen Helium CO $CO_2$ Xenon Neon Krypton Vinyl Chloride Acetaldehyde Vol Oxygenates GC/MS Scan IR Scan IR Microscope Halogenated Hydrocarbons $SF_6$ Gas Mixture% Btu (Heat) Content % CHNO Sediment Wt Patch Test Viscosity Flash/Fire Point Density Specific Gravity Trace Metals TAN TBN XRF SEM-XRF Scan Light Microscope

Other Testing: _____

**8.) Sample Disposition**

Retain for _____ Period Perform Clean-up/Maintenance Actions & Return* ____ Report for Instructions ____

Other: _____

*Supply all return address & shipping instructions

**9.) Report Disposition** (circle one): E-Mail Fax Mail Telephone Other:_____
(Reports will be sent to the address & contact(s) specified at the top of this form)

**10.) Priority Conditions** (circle), Note: Additional fees will apply for non-std test scheduling:

Standard 2-Work Day 1-Work Day Same Day Emergency Other:_____

*Analytical testing cannot be performed unless this form is completed & returned*

Page 1 of 1 F-18v3 (05/2011)

**Figure 3.** Example of $CO_2$ gas stream analysis authorization form.

**Table 10**. Summary of anticipated sample containers, preservation treatments, and holding times.

| Target Parameters | Volume/Container Material | Preservation Technique | Sample Holding time | Relative Sampling Depth |
|---|---|---|---|---|
| **Cations:** Ca, Fe, K, Mg, Na, Si | 250 ml/HDPE | Filtered, nitric acid, cool 4°C | 60 days | Shallow |
| **Dissolved CO2** | 2 × 60 ml/HDPE | Filtered, cool 4°C | 14 days | Shallow |
| **Dissolved CO2** | 60 ml/HDPE | Filtered, cool 4°C | 14 days | Deep |
| **Isotopes:** $^{3}H$, $\delta D$, $\delta^{18}O$, $\delta^{34}S$, and $\delta^{13}C$ | 2 × 60 ml/HDPE | Filtered, cool 4°C | 4 weeks | Shallow |
| **Isotopes:** $\delta^{34}S$ | 250 ml/HDPE | Filtered, cool 4°C | 4 weeks | Deep |
| **Isotopes:** $\delta D$, $\delta^{18}O$, $\delta^{13}C$ | 60 ml/HDPE | Filtered, cool 4°C | 4 weeks | Deep |
| **Alkalinity, anions (**Br, Cl, F, NO3, SO4**)** | 500 ml/HDPE | Filtered, cool 4°C | 45 days | Shallow |
| **Field Confirmation:** Temperature, dissolved oxygen, specific conductance, pH | 200 ml/glass jar | None | < 1 hour | Deep |
| **Field Confirmation:** Density | 60 ml/HDPE | Filtered | < 1 hour | Deep |

B.3.e. Sample Chain-of-Custody

For $CO_2$ stream analysis, an analysis authorization form (Figure 3) will accompany the sample to the lab at which point a chain-of-custody accompanies the sample through their processes.

For groundwater samples, chain-of-custody will be documented using a standardized form. A typical form is shown in Figure 4, and it or a similar form will be used for all groundwater sampling. Copies of the form will be provided to the person/lab receiving the samples as well as the person/lab transferring the samples. These forms will be retained and archived to allow simplified tracking of sample status. The chain-of -custody form and record keeping is the responsibility of groundwater sampling personnel.

PRAIRIE RESEARCH INSTITUTE

## CHAIN OF CUSTODY RECORD (Page __ of __)

Illinois State Water Survey – Analytical Services Group
Illinois State Geological Survey – Geochemistry Section

For Midwest Geological Sequestration Consortium (MGSC) Projects

| | MGSC ID | ISGS MVA ID | Matrix | Date Collected | Time Collected | Sampling Team | Circle analyses to be performed |
|---|---|---|---|---|---|---|---|
| 1 | | | | | | | anions, cations, TDS, alk, $NH_3$, NVOC |
| 2 | | | | | | | anions, cations, TDS, alk, $NH_3$, NVOC |
| 3 | | | | | | | anions, cations, TDS, alk, $NH_3$, NVOC |
| 4 | | | | | | | anions, cations, TDS, alk, $NH_3$, NVOC |
| 5 | | | | | | | anions, cations, TDS, alk, $NH_3$, NVOC |
| 6 | | | | | | | anions, cations, TDS, alk, $NH_3$, NVOC |
| 7 | | | | | | | anions, cations, TDS, alk, $NH_3$, NVOC |
| 8 | | | | | | | anions, cations, TDS, alk, $NH_3$, NVOC |
| 9 | | | | | | | anions, cations, TDS, alk, $NH_3$, NVOC |
| 10 | | | | | | | anions, cations, TDS, alk, $NH_3$, NVOC |
| 11 | | | | | | | anions, cations, TDS, alk, $NH_3$, NVOC |
| 12 | | | | | | | anions, cations, TDS, alk, $NH_3$, NVOC |
| 12 | | | | | | | |

| CHAIN OF CUSTODY | | |
|---|---|---|
| Relinquished by: | Print Name: | Date and Time: |
| Received by: | Print Name: | Date and Time: |
| General Remarks: - Field parameters are to be recorded on separate sheets by sampling teams.<br>- Any special laboratory instructions or remarks should be made below. | | |
| **Data Contacts:** | Fund: | |
| **Billing Contact:** | Billing Address: | |
| Send Data To: | | |

**Remarks:**

Rev. Oct. 2011 (RL)

**Figure 4.** Example chain-of-custody form.

## B.4. Analytical Methods

Logging, geophysical monitoring, and pressure/temperature monitoring does not apply to this section, and is omitted.

B.4.a. Analytical SOPs

Analytical SOPs are referenced in the Testing and Monitoring Plan and Table 1. Other laboratory specific SOPs utilized by the laboratory utilized by ADM. Each laboratory technician conducting the analysis on the samples will be trained on the SOP developed for each standard method.

B.4.b. Equipment/Instrumentation Needed

Equipment and instrumentation is specified in the individual analytical methods referenced in Table 1.

B.4.c. Method Performance Criteria

Nonstandard method performance criteria are not anticipated for this project.

B.4.d. Analytical Failure

Each laboratory conducting the analyses in Table 1 will be responsible for appropriately addressing analytical failure according to their individual SOPs.

B.4.e. Sample Disposal

Each laboratory conducting the analyses in in Table 1 will be responsible for appropriate sample disposal according to their individual SOPs.

B.4.f Laboratory Turnaround

Laboratory turnaround will vary by laboratory, but generally turnaround of verified analytical results within one month will be suitable for project needs.

B.4.g Method Validation for Nonstandard Methods

Nonstandard methods are not anticipated for this project.

## B.5. Quality Control

Geophysical monitoring and pressure/temperature monitoring does not apply to this section, and is omitted.

B.5.a. QC activities

*Blanks*
For shallow groundwater sampling, a field blank will be collected and analyzed for the inorganic analytes in Table 1 at a frequency of 10% or greater. Field blanks will be exposed to the same field and transport

conditions as the groundwater samples. Blanks will also be utilized for deep groundwater sampling and analyzed for the inorganic analytes in Table1 at a frequency of 10% or greater. Field blanks will be used to detect contamination resulting from the collection and transportation process.

*Duplicates*
For each shallow groundwater sampling round, a duplicate groundwater sample is collected from a well from a rotating schedule. Duplicate samples are collected from the same source immediately after the original sample in different sample containers and processed as all other samples. Duplicate samples are used to assess sample heterogeneity and analytical precision.

B.5.b. Exceeding Control Limits

If the sample analytical results exceed control limits (i.e., ion balances > ±10%), further examination of the analytical results will be done by evaluating the ratio of the measured total dissolved solids (TDS) to the calculated TDS (i.e., mass balance) per APHA method. The method indicates which ion analyses should be considered suspect based on the mass balance ratio. Suspect ion analyses are then reviewed in the context of historical data and interlaboratory results, if available. Suspect ion analyses are then brought to the attention of the analytical laboratory for confirmation and/or reanalysis. The ion balance is recalculated, and if the error is still not resolved, suspect data are identified and may be given less importance in data interpretations.

B.5.c. Calculating Applicable QC Statistics

*Charge Balance*
The analytical results are evaluated to determine correctness of analyses based on anion-cation charge balance calculation. Because all potable waters are electrically neutral, the chemical analyses should yield equally negative and positive ionic activity. The anion-cation charge balance will be calculated using the formula:

$$\%\ difference = 100\frac{\sum cations - \sum anions}{\sum cations + \sum anions}\ , \qquad \text{(Equation 1)}$$

where the sums of the ions are represented in milliequivalents (meq) per liter and the criteria for acceptable charge balance is ±10%.

*Mass Balance*
The ratio of the measured TDS to the calculated TDS will be calculated in instances where the charge balance acceptance criteria are exceeded using the formula:

$$1.0 < \frac{measured\ TDS}{calculated\ TDS} < 1.2\ , \qquad \text{(Equation 2)}$$

where the anticipated values are between 1.0 and 1.2.

*Outliers*
A determination of one or more statistical outliers is essential prior to the statistical evaluation of groundwater. This project will use the USEPA's Unified Guidance (March 2009) as a basis for selection of recommended statistical methods to identify outliers in groundwater chemistry data sets as appropriate. These techniques include Probability Plots, Box Plots, Dixon's test, and Rosner's test. The

EPA-1989 outlier test may also be used as another screening tool to identify potential outliers.

## B.6. Instrument/Equipment Testing, Inspection, and Maintenance

Logging tool equipment will be maintained as per OEM standard industry practice.

For groundwater sampling, field equipment will be maintained, factory serviced, and factory calibrated per manufacturer's recommendations. Spare parts that may be needed during sampling will be included in supplies on-hand during field sampling.

For all laboratory equipment, testing, inspection and maintenance will be the responsibility of the analytical laboratory per standard practice, method-specific protocol, or NELAP requirement.

## B.7. Instrument/Equipment Calibration and Frequency

Geophysical monitoring does not apply to this section, and is omitted.

B.7.a. Calibration and Frequency of Calibration

Pressure/temperature gauge calibration information is located in Table 6 . Logging tool calibration will be at the discretion of the service company providing the equipment, following standard industry practice. Calibration frequency will be determined by standard industry practices.

For groundwater sampling, portable field meters or multiprobe sondes used to determine field parameters (e.g., pH, temperature, specific conductance, dissolved oxygen) are calibrated according to manufacturer recommendations and equipment manuals (Hach, 2006) each day before sample collection begins. Recalibration is performed if any components yield atypical values or fail to stabilize during sampling.

B.7.b. Calibration Methodology

Logging tool calibration methodology will follow standard industry practice.

For groundwater sampling, standards used for calibration are typically 4, 7 and 10 for pH, a potassium chloride solution yielding a value of 1413 microsiemens per centimeter (µS/cm) at 25°C for specific conductance, and a 100% dissolved $O_2$ solution for dissolved oxygen. Calibration is performed for the pH meters per manufacturer's specifications using a 2 or 3-point calibration bounding the range of the sample. For coulometry, sodium carbonate standards (typically yielding a concentration of 4,000 mg $CO_2$/L) are routinely analyzed to evaluate instrument.

*B.7.c. Calibration Resolution and Documentation*
Logging tool calibration resolution and documentation will follow standard industry.

For groundwater sampling, calibration values are recorded in daily sampling records and any errors in calibration are noted. For parameters where calibration is not acceptable, redundant equipment may be used so loss of data is minimized.

## B.8. Inspection/Acceptance for Supplies and Consumables

B.8. a/b. Supplies, Consumables, and Responsibilities

Supplies and consumables for field and laboratory operations will be procured, inspected, and accepted as required from vendors approved by ADM or the respective subcontractor responsible for the data collection activity. Acquisition of supplies and consumables related to groundwater analyses will be the responsibility of the laboratory per established standard methodology or operating procedures.

## B.9. Nondirect Measurements

Seismic Monitoring Methods for $CO_2$ Plume Tracking

B.9.a Data Sources

For time lapse seismic surveys, repeatability is paramount for accurate differential comparison. Therefore, to ensure survey quality, the locations for the shots and acquisition methodology of sequential surveys will be consistent. Once these surveys are conducted, they will be compared to a baseline survey to track and monitor plume development.

For in-zone pressure monitoring, the in-zone pressure gauges in VW#1, VW#2, VW#3, VW#4 and VW#5 will be used to gather pressure data.

B.9.b. Relevance to Project

Time lapse seismic surveys will be used to track changes in the $CO_2$ plume in the subsurface. Processing and comparing subsequent surveys to a baseline will allow project managers to monitor plume growth, as well as to ensure that the plume does not move outside of the intended storage reservoir. Numerical modeling will be used to predict the $CO_2$ plume growth and migration over time by combining the processed seismic data with the existing geologic model.

In-zone pressure monitoring data will be used in numerical modeling to predict plume and pressure front behavior and confirm the plume stage within the AOR.

B.9.c. Acceptance Criteria

Following standard industry practices will ensure that the gathered seismic data will be used for accurate modeling and monitoring. Similar ground conditions, shot points located within tolerable limits, functional geophones, and similar seismic input signal will be used from survey to survey to ensure repeatability.

When processing seismic data, several QA checks will be done in accordance with industry standards including reformatting to Omega structured files, geometry application, amplitude compensation, predictive deconvolution, elevation statics correction, RMS amplitude gain, velocity analysis every 2 km, NMO application using picked velocities, CMP stacking, random noise attenuation, and instantaneous gain.

B.9.d. Resources/Facilities Needed

ADM will subcontract all necessary resources and facilities for the seismic monitoring, in-zone pressure monitoring, and groundwater sampling.

B.9.e. Validity Limits and Operating Conditions

For seismic surveys and numerical modeling, intraorganizational checks between trained and experienced personnel will ensure that all surveys and numerical modeling are conducted conforming to standard industry practices.

## B.10. Data Management

B.10.a. Data Management Scheme

ADM or a designated contractor will maintain the required project data as provided elsewhere in the permit. Data will be backed up on tape or held on secure servers with adequate redundancy.

B.10.b. Record-keeping and Tracking Practices

All records of gathered data will be securely held and properly labeled for auditing purposes.

B.10.c. Data Handling Equipment/Procedures

All equipment used to store data will be properly maintained and operated according to proper industry techniques. ADM SCADA system and vendor data acquisition systems will interface with one another and all subsequent data will be held on a secure server.

B.10.d. Responsibility

The primary project managers will be responsible for ensuring proper data management is maintained.

B.10.e. Data Archival and Retrieval

All data will be held by ADM. These data will be maintained and stored for auditing purposes as described in section B.10.a.

B.10.f. Hardware and Software Configurations

All ADM and vendor hardware and software configurations will be appropriately interfaced.

B.10.g. Checklists and Forms

Checklists and forms will be procured and generated as necessary.

# C. Assessment and Oversight

## C.1. Assessments and Response Actions

### C.1.a. Activities to be Conducted

Please refer to the Testing and Monitoring plan for groundwater quality data collection frequency. Sample analysis is presented in Table 1. After completion of sample analysis, results will be reviewed for QC criteria as noted in section B.5. If the data quality fails to meet criteria set in section B.5., samples will be reanalyzed, if still within holding time criteria. If outside of holding time criteria, additional samples may be collected or sample results may be excluded from data evaluations and interpretations. Evaluation for data consistency will be performed according to procedures described in the USEPA 2009 Unified Guidance (USEPA, 2009).

### C.1.b. Responsibility for Conducting Assessments

Organizations gathering data will be responsible for conducting their internal assessments. All stop work orders will be handled internally within individual organizations.

### C.1.c. Assessment Reporting

All assessment information should be reported to the individual organizations project manager outlined in A.1.a/b.

### C.1.d. Corrective Action

All corrective action affecting only an individual organization's data collection responsibility should be addressed, verified, and documented by the individual project managers and communicated to the other project managers as necessary. Corrective actions affecting multiple organizations should be addressed by all members of the project leadership and communicated to other members on the distribution list for the QASP. Assessments may require integration of information from multiple monitoring sources across organizations (operational, in-zone monitoring, above-zone monitoring) to determine whether correction actions are required and/or the most cost-efficient and effective action to implement. ADM will coordinate multiorganization assessments and corrective actions as warranted.

## C.2. Reports to Management

### C.2.a/b. QA status Reports

QA status reports should not be needed. If any testing or monitoring techniques are changed, the QASP will be reviewed and updated as appropriate in consultation with USEPA. Revised QASPs will be distributed by ADM to the full distribution list at the beginning of this document.

# D. Data Validation and Usability

## D.1. Data Review, Verification, and Validation

D.1.a. Criteria for Accepting, Rejecting, or Qualifying Data

Groundwater quality data validation will include the review of the concentration units, sample holding times, and the review of duplicate, blank and other appropriate QA/QC results. All groundwater quality results will be entered into a database or spreadsheet with periodic data review and analysis. ADM will retain copies of the laboratory analytical test results and/or reports. Analytical results will be reported on a frequency based on the approved UIC permit conditions. In the periodic reports, data will be presented in graphical and tabular formats as appropriate to characterize general groundwater quality and identify intrawell variability with time. After sufficient data have been collected, additional methods, such as those described in the USEPA 2009 Unified Guidance (USEPA, 2009), will be used to evaluate intrawell variations for groundwater constituents, to evaluate if significant changes have occurred that could be the result of $CO_2$ or brine seepage beyond the intended storage reservoir.

## D.2 Verification and Validation Methods

D.2.a. Data Verification and Validation Processes

See Sections D.1.a. and B.5.

Appropriate statistical software will be used to determine data consistency.

D.2.b. Data Verification and Validation Responsibility

ADM or its designated subcontractor will verify and validate groundwater sampling data.

D.2.c. Issue Resolution Process and Responsibility

ADM or its designated Coordinator will overview the groundwater data handling, management, and assessment process. Staff involved in these processes will consult with the Coordinator to determine actions required to resolve issues.

D.2.d. Checklist, Forms, and Calculations

Checklists and forms will be developed specifically to meet permit requirements. Table 11 provides an example of the type of information used for data verification of groundwater quality data.

**Table 11.** A representative example table of criteria used to evaluate data quality.

| MVA ID | Anion charge | Cation charge | Charge balance | CB rating | Calculated TDS | Measured TDS | TDS ratio | TDS rating |
|---|---|---|---|---|---|---|---|---|
| ICCS_10B_01A | 14.4 | 13.60 | -2.84 | Pass | 760.50 | 785 | 1.0 | pass |
| ICCS_10B_02A | 14.26 | 15.06 | 2.73 | Pass | 783.03 | 777 | 1.0 | pass |
| ICCS_10B_03A | 14.39 | 14.96 | 1.94 | Pass | 786.86 | 806 | 1.0 | pass |
| ICCS_10B_04A | 14.39 | 14.79 | 1.38 | Pass | 780.15 | 777 | 1.0 | pass |
| ICCS_10B_04B | 14.33 | 14.90 | 1.96 | Pass | 780.95 | 785 | 1.0 | pass |

## D.3 Reconciliation with User Requirements

D.3.a Evaluation of Data Uncertainty

Statistical software will be used to determine groundwater data consistency using methods consistent with USEPA 2009 Unified Guidance (USEPA, 2009).

D.3.b. Data Limitations Reporting

The organization-level project managers will be responsible for ensuring that data developed by their respective organizations is presented with the appropriate data-use limitations.

ADM will use the current operating procedure on the use, sharing, and presentation of results and/or data for the IL-ICCS project. This procedure has been developed to ensure quality, internal consistency and facilitate tracking and record keeping of data end users and associated publications.

# References


APHA, 2005, *Standard methods for the examination of water and wastewater (21st edition),* American Public Health Association, Washington, DC.

ASTM, 2010, Method D7069-04 (reapproved 2010), *Standard guide for field quality assurance in a ground-water sampling event*, ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA.

ASTM, 2010, Method D6911-03 (reapproved 2010), *Standard guide for packaging and shipping environmental samples for laboratory analysis*, ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA.

ASTM, 2005, Method D6517-00 (reapproved 2005), *Standard guide for field preservation of ground-water samples*, ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA.

ASTM, 2005, Method D6564-00 (reapproved 2005), *Standard guide for field filtration of ground-water samples*, ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA.

ASTM, 2005, Method D6452-99 (reapproved 2005), *Standard Guide for Purging Methods for Wells Used for Ground-Water Quality Investigations*, ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA.

ASTM, 2002, Method D513-11, *Standard test methods for total and dissolved carbon dioxide in water*, ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA.

ASTM, 2002, Method D6771-02, *Standard guide for low-flow purging and sampling for wells and devices used for ground-water quality investigations*, ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA.

Gibb, J.P., R.M. Schuller, and R.A. Griffin, 1981, *Procedures for the collection of representative water quality data from monitoring wells,* Illinois State Geological Survey Cooperative Groundwater Report 7, Champaign, IL, 61 p.

Hach Company, February 2006, *Hydrolab DS5X, DS5, and MS5 Water Quality Multiprobes User Manual*, Hach Company, 73 p.

Larson, D.R., B.L. Herzog, and T.H. Larson, 2003, *Groundwater geology of DeWitt, Piatt, and Northern Macon Counties, Illinois.* Illinois State Geological Survey Environmental Geology 155, 35 p.

Locke II, R.**,** D. Larssen, W. Salden, C. Patterson, J. Kirksey, A. Iranmanesh, B. Wimmer, I. Krapac. *Preinjection reservoir fluid characterization at a CCS demonstration site: Illinois Basin – Decatur Project, USA*. Proceedings of the 11th International Conference on Greenhouse Gas Technologies, November 18– 22, 2012, Kyoto, Japan. *Energy Procedia v. 37, 2013, p. 6,424–6,433.* http://dx.doi.org/10.1016/j.egypro.2013.06.572

Dell, J.W., J.D. Pfaff, M.E. Gales, and G.D. McKee, 1984, *Test Method—The Determination of Inorganic Anions in Water by Ion Chromatography-Method 300*, U.S. Environmental Protection Agency, EPA-600/4-84-017.

Orion Research Inc., 1990, *$CO_2$ Electrode Instruction Manual*, Orion Research Inc., 36 p.

Puls, R.W., and M.J. Barcelona, 1996, *Low-Flow (Minimal Drawdown) Ground-Water Sampling Procedures*. U.S. Environmental Protection Agency, EPA-540/S-95/504.

U.S. Environmental Protection Agency (US EPA), 2009, *Statistical analysis of groundwater monitoring data at RCRA facilities—Unified Guidance*, US EPA, Office of Solid Waste, Washington, DC.

U.S. Environmental Protection Agency (US EPA), 1974, *Methods for chemical analysis of water and wastes,* US EPA Cincinnati, OH, EPA-625-/6-74-003a.

Wood, W.W., 1976, *Guidelines for collection and field analysis of groundwater samples for selected unstable constituents*, In U.S. Geological Survey, Techniques for Water Resources Investigations, Chapter D-2, 24 p.

# APPENDIX D: Existing Site Wells Coring Summary

# TABLE 1
# LOG SUMMARY: EXISTING SITE WELLS

| Well Name | Log Vendor | Log Title | Date Run | Depth Interval (MD ft. KB ) |
|---|---|---|---|---|
| CCS-1 | Schlumberger | GR, CAL, SP, Resistivity, RHOB, NPHI | 3/9/2009 | 352 - 3,541 |
| CCS-1 | | Variable Density CBL | | |
| CCS-1 | Schlumberger | GR, CAL, SP, Resistivity, RHOB, NPHI | 4/5/2009 | 352 - 5,317 |
| CCS-1 | Schlumberger | Sonic Scanner and FMI | 4/5/2009 | 352 - 5,317 |
| CCS-1 | Schlumberger | CMR, ECS, HNGS | 4/5/2009 | 352 - 5,317 |
| CCS-1 | Schlumberger | MSCT | 4/5/2009 | 352 - 5,317 |
| CCS-1 | | Ultrasonic Cement Imaging | | |
| CCS-1 | Schlumberger | GR, CAL, SP, Resistivity, RHOB, NPHI | 4/26/2009 | 5,339 - 7,221 |
| CCS-1 | Schlumberger | Sonic Scanner and FMI | 4/26/2009 | 5,339 - 7,221 |
| CCS-1 | Schlumberger | CMR, ECS, HNGS | 4/26/2009 | 5,339 - 7,221 |
| CCS-1 | Schlumberger | MSCT | 4/26/2009 | 5,339 - 7,221 |
| CCS-1 | Schlumberger | MDT | 4/26/2009 | 5,339 - 7,221 |
| CCS-1 | Schlumberger | VSIT | 4/26/2009 | 5,339 - 7,221 |
| CCS-1 | | Ultrasonic Cement Imaging | | |
| CCS-1 | | Variable Density CBL | | |
| CCS-1 | | Pressure/Temperature Log | | |
| CCS-1 | | Thermal Neutron Decay (Formation Sigma) Log | | |
| CCS-1 | | Multi-Finger Caliper Log | | |
| CCS-1 | | CCL and Perforation Record | | |
| CCS-1 | | Injection Fullbore Spinner Logs | | |
| | | | | |
| CCS-2 | Schlumberger | GR, Resistivity, NPHI, SlimPulse | 1/12/2015 | 50 - 349 |
| CCS-2 | Schlumberger | CAL, DSLT, GPIT | 1/12/2015 | 50 - 349 |
| CCS-2 | Wayne County Well Surveys | CBL | 1/16/2015 | 0 - 351 |
| CCS-2 | Schlumberger | GR, CAL, SP, Resistivity, RHOB, NPHI | 5/3/2015 | 344 - 5,252 |
| CCS-2 | Schlumberger | Sonic Scanner, FMI, CAL, GPIT | 5/3/2015 | 344 - 5,252 |
| CCS-2 | Schlumberger | ECS, HNGS | 5/3/2015 | 344 - 5,252 |
| CCS-2 | Schlumberger | Variable Density CBL | 5/31/2015 | 200 - 5,231 |
| CCS-2 | Schlumberger | Isolation Scanner Cement Evaluation | 5/31/2015 | 200 - 5,231 |
| CCS-2 | Schlumberger | Isolation Scanner Casing Integrity | 5/31/2015 | 200 - 5,231 |
| CCS-2 | Schlumberger | GR, CAL, SP, Resistivity, RHOB, NPHI | 5/29/2015 | 5,234 - 7,193 |
| CCS-2 | Schlumberger | Sonic Scanner, FMI, CAL, GPIT | 5/29/2015 | 5,234 - 7,193 |

## TABLE 1
## LOG SUMMARY: EXISTING SITE WELLS

| Well Name | Log Vendor | Log Title | Date Run | Depth Interval (MD ft. KB ) |
|---|---|---|---|---|
| CCS-2 | Schlumberger | CMR, Litho Scanner, HNGS | 5/29/2015 | 5,234 - 7,193 |
| CCS-2 | Schlumberger | MSCT | 5/29/2015 | 5,234 - 7,193 |
| CCS-2 | Schlumberger | Multi-finger Imaging Tool | 6/10/2015 | 30 - 7,048 |
| CCS-2 | Schlumberger | Variable Density CBL | 6/10/2015 | 40 - 7,048 |
| CCS-2 | Schlumberger | Isolation Scanner Cement Evaluation | 6/10/2015 | 40 - 7,048 |
| CCS-2 | Schlumberger | Isolation Scanner Third Interface Echo | 6/10/2015 | 40 - 7,048 |
| | | | | |
| VW-1 | | GR, SP, Resistivity, RHOB, NPHI, Sonic | | |
| VW-1 | | CBL and/or Cement Imaging | | |
| VW-1 | Schlumberger | GR, CAL, Resistivity, RHOB, NPHI | | 350 - 5,250 |
| VW-1 | Schlumberger | Sonic Scanner | | 350 - 5,250 |
| VW-1 | Schlumberger | GR, CAL, Resistivity, RHOB, NPHI | | 5,250 - 7,228 |
| VW-1 | Schlumberger | Sonic Scanner | | 5,250 - 7,228 |
| VW-1 | Schlumberger | MDT | 10/25/2010 | 3,642 - 5,007 |
| VW-1 | Schlumberger | XPT (Pressure Express Tool) | 11/17/2010 | |
| | | | | |
| VW-2 | Schlumberger | GR, CAL, Resistivity, RHOB, NPHI | 10/8/2012 | 300 - 5,220 |
| VW-2 | Schlumberger | Sonic Scanner | 10/8/2012 | 300 - 5,220 |
| VW-2 | Schlumberger | GR, CAL, Resistivity, RHOB, NPHI | 10/31/2012 | 5,320 - 7,150 |
| VW-2 | Schlumberger | Sonic Scanner | 10/31/2012 | 5,320 - 7,150 |
| VW-2 | Schlumberger | XPT (Pressure Express Tool) | 10/31/2012 | 5,578 - 7,102 |
| VW-2 | Schlumberger | RST | | 203 - 7,110 |

**TABLE 2**

Sensitive, Confidential, or Privileged Information

**TABLE 2**
**CORING SUMMARY: EXISTING SITE WELLS**

Sensitive, Confidential, or Privileged Information

**TABLE 2**

Sensitive, Confidential, or Privileged Information

**TABLE 2**
**CORING SUMMARY: EXISTING SITE WELLS**

Sensitive, Confidential, or Privileged Information

**TABLE 2**

Sensitive, Confidential, or Privileged Information

**TABLE 2**
**CORING SUMMARY: EXISTING SITE WELLS**

Sensitive, Confidential, or Privileged Information

**TABLE 2**
**CORING SUMMARY: EXISTING SITE WELLS**

Sensitive, Confidential, or Privileged Information

**TABLE 2**
**CORING SUMMARY: EXISTING SITE WELLS**

Sensitive, Confidential, or Privileged Information

**TABLE 2**
**CORING SUMMARY: EXISTING SITE WELLS**

Sensitive, Confidential, or Privileged Information

# APPENDIX E: Stimulation Attachments and Procedures

180.05.CO2.206 CCS#2 Backflow Maintenance Procedure

Enhanced Energetics Publication: "GasGun – Vertical Containment – Sandia Study (undated)

Letter of Determination, Natural Resources Agency of California Department of Conservation, Division of Oil, Gas, & Geothermal Resources, Dated 4/12/2019

Kraken-enhance Perforating Flow Performance Tests, API RP19B Section 4 Test Results, Enhanced Energetics, 2020

Schmidt, Richard A., Warpinski, Norman R., and Paul W. Cooper. "In Situ Evaluation Of Several Tailored-Pulse Well-Shooting Concepts." Paper presented at the SPE Unconventional Gas Recovery Symposium, Pittsburgh, Pennsylvania, May 1980. doi: https://doi.org/10.2118/8934-MS

# CCS #2 Solvent/Acid Stimulation Procedure



## List of Controlled Copies, Location, and Responsibility:

| Copy # | Location | Responsibility |
|---|---|---|
| Original | DCS/DMS | Alcohol Superintendent |

## Approvers:

- Plant Manager
- Alcohol Superintendent

## Revisions:

| Date | Version | Author | Reason(s) for revision |
|---|---|---|---|
| 12/07/2022 | 2.0 | S. McDonald | • Added revisions table.<br>• Modified to incorporate the change in the treatment fluids, Petrotech recommendations and vendor recommendations.<br>o Solvent Treatment Volumes Modified<br>o Jetting Treatment Volumes Modified<br>o Treatment Fluids Modified<br>o Modified tables to add Tubular ID's<br>o Coil volumes and other specifications have been updated.<br>o Permit restriction language on page 2 was updated to make it clearer.<br>o Section 12 Health, safety and environmental discussion was modified for the changed fluids.<br>o The operational procedure has been modified to re-order the sequence of operations and to incorporate other vendor recommendations:<br>o Step 8 - Modified language to ensure permit requirements are understood and monitored during operations.<br>o Modifications to wellhead rig up sequence, flushing line and pressure testing sequence.<br>o Modifications to jetting treatment procedure as per vendor recommendations.<br>o Added N2 pad before solvent treatment (previously optional) and N2 blanket on stack. Modified treatment soak time to less than 6 hours ( Petrotech Recommendation)<br>• Added Appendix II: SDS Sheets |
| 10/11/2022 | 1.0 | S. McDonald | Initial release. |

## 1. Scope

Solid buildup across perforations contributes to an increase in the downhole injection pressure, restricting the $CO_2$ injection rate. For significant and long-term injectivity improvement at CCS #2, this treatment procedure will displace particulates and buildup at the well perforations to improve $CO_2$ injectivity.

## 2. Source of Injectivity Reduction

To determine the source of the injectivity reduction observed at CCS #2, samples of the scale buildup in the wellbore were acquired on August 11, 2022. Detailed laboratory results of the samples tested are presented in Appendix I. The analysis indicated the following:

- Inductively Coupled Plasma (ICP) optical emission spectrometry by ADM Research Analytical lab indicated high concentrations of Calcium (1.08%), Sodium (2.5%), Sulfur (1.06%), and Iron (0.81%). Trace amounts of triethylene glycol, long chain methacrylates (~C12), fatty acids (C16, C18, C19), hydrocarbons (C16-C20), triethylene glycol C12 ether were also observed.
- Flexchem gravimetric solids analysis indicated 65% hydrocarbon material (soluble in xylene), 5% carbonates (soluble in acetic acid), and 3% iron oxides (soluble in HCl). The remaining 27% was largely quartz. The quartz is an artifact from obtaining the sample from the bottom of the well and is not considered a fouling element.
- Fourier Transform Infrared (FTIR) spectroscopy by Flexchem indicated large amounts of hydrocarbons and polar OH groups with the presence of amines. The hydrocarbon portion matches more closely to heavy paraffin than asphaltenes.

## 3. Well Information

**Table 1** – CCS #2 well information.

| | |
|---|---|
| **Well Name** | CCS #2 |
| **Operator** | Archer Daniels Midland Company |
| **County, State** | Macon, IL |
| **US-EPA Permit Number** | IL-115-6A-0001 |
| **Proposed Stimulation Date** | ~Q4-2022 |
| **API #** | 12-115-23713-00 |
| **Drilled Dates** | 1/12/2015 – 5/29/2015 |
| **Location** | 39°53'09.32835", -88°53'16.68306" |
| **Ground Level (KB)** | 675.7' (+15.5') |

**Table 2** – CCS #2 Well construction and tubulars information.

| Section | Hole Size, (inches) | Tubular OD, (inches) | Tubular ID, (inches) | Section Depth, (feet) | Tubular Specification (Weight/Grade) | Rating (psi) Burst/Collapse | Capacity (bbl/ft) |
|---|---|---|---|---|---|---|---|
| **Coil Tubing** | N/A | 2” | 1.688” | N/A | 3.075#/HS80 | 10000 (Int. Yield) | 0.0027 |
| **Final** | 12-1/4” | 9-5/8” | 8.681” | 7,190’ | 40#/N-80 | 8960/7820 | 0.0732 |
| **Intermediate** | 17-1/2” | 13-3/8” | 12.515” | 5,234’ | 61#/J-55 | 3090/1540 | 0.1525 |
| **Surface** | 26” | 20” | 19.124” | 347’ | 94#/J55 | 2110/520 | 0.3553 |
| **Tubing** | N/A | 5-1/2” | 4.839” | 6,350’ | 17#/13CR80 | 8960/7820 | 0.0227 |

Note: Smallest restriction on the 5 ½” tubing is a XN profile (ID = 4.455”) at 6,330’ (KB).

**Table 3** – CCS #2 well and tubular volumes.

| Description | Volume (bbl) |
|---|---|
| Bottoms Up at TD | 178 |
| Coiled Tubing Volume (15,000’) | 41 |
| End of Tubing (EOT) | 144 |
| EOT to Top Perf | 20 |
| Top Perf to Bottom Perf | 14 |

## 4. Well Head Diagram





**Figure 1** - CCS #2 wellhead schematic.

## 5. Primary Approach – Hydro Jet & Solvent Wash Through Coiled Tubing

The operations will involve a hydro jetting treatment followed by a solvent treatment slurry. The heated water passes with the hydro jet will be made across the perforations while circulating the well to clean the scale buildup in the well. After which, a solvent treatment slurry will be spotted and injected into the near wellbore matrix to target the near wellbore damage in the reservoir. After adequate soak time, the well will be flowed back to recover the treatment slurry and fines. An additional, heated water hydro jetting run with coiled tubing will be performed to further clean the well head, tubing and casing post flowback. A preliminary site layout for the equipment is presented in Figure 2.

Hydro Jet Treatment Composition: Fresh Water with 2% KCL, 5% Heavy Aromatic Naphtha (PT – 330), and Biocide mixed at 2 gallons per thousand (gpt). Approximately 2020 bbl of total hydro jetting treatment is planned before and after the solvent treatment.

Solvent Treatment Composition: The solvent treatment will be a mixture of 50% acid and 50% Heavy Aromatic Naphtha. The 50 % acid will consist of 1% HCl (fresh water source). The 50% Heavy Aromatic Naphtha (HAN) will be a proprietary blend named PT – 330. As a major portion of the sample acquired (65%) consisted of organic material soluble in HAN, a HAN based solvent treatment slurry is proposed to treat the skin buildup. The mixture creates an emulsion, where the HAN is intended to dissolve organic buildup and allow acid to clean the acid soluble particulates (iron oxides). Iron control, acid corrosion control, scale inhibitor, non-emulsifier, surfactants, citric acid, and biocide will also be present in the solvent treatment.

Solvent Treatment Volume: 250 bbl

**Table 4** – Expected Treatment/Return Volumes (Approximate)

| Operation (Coil Movement Footage) | Step In Procedure | Fluid | Estimated Volume (bbl) |
|---|---|---|---|
| Load the Hole & RIH to above Top Perf. (6,600') | 42-43 | Hydro Jet Treatment | 200 |
| Pass 1: Clean Out from top perf to TD (1,180') | 44 | Hydro Jet Treatment | 300 |
| Additional Passes: Hydro Jet Perforations (1,530') | 45 | Hydro Jet Treatment | 600 |
| Short Trip to 6,300' & RIH to TD (1,190') | 46 | Hydro Jet Treatment | 100 |
| Circulate, while reciprocating coil | 47 | Hydro Jet Treatment | 260 |
| Inject $N_2$ pad | 48 | $N_2$ | 500MSCF |
| Inject Solvent Treatment | 51 | Solvent Treatment | 125 |
| Flow Back/Surge | 52 | Solvent Treatment | 7 (~100 feet) |
| Inject Solvent Treatment | 53 | Solvent Treatment | 125 |
| Flow Back (after soak time) | 59 | Solvent Treatment, $N_2$, $CO_2$ | ~250 |
| Wash Up (Post Flowback) | 61-63 | Hydro Jet Treatment | 560 |

**Note:** *These volumes are estimations and may change based on the equipment availability and other operational aspects. (i.e. if string starts to take weight may increase pump rate, increase speed during subsequent passes, etc.)*





**Figure 2** - Representative plan for site layout during coiled tubing cleanout on CCS#2 well. Actual plan may differ in equipment and configuration.

## 6. Responsibilities

Project Manager –

- Oversees all aspects of the coiled tubing cleanout operations are carried as per the procedure to achieve the desired objective (Well Cleanout).
- Ensures personnel on site are certified on use of proper PPE including supplied breathing air and mask. PPE will be utilized for the duration of the cleanout operation.
- Communicates the cleanout operation date and time to Richland Community College (RCC).
- Coordinates with ADM Security to ensure security personnel are available during times of the backflow operation to limit access to the well site.
- Responsible for communicating with ADM management and environmental.

Safety/Environmental Manager –

- Communicates with US-EPA regulators.
- Confirms containment berms are installed under storage tanks for spill protection
- Confirm a wash station is available and functional for all personnel at the wellsite during operations.
- Confirm SDS for all chemicals on site is present and accessible.
- Ensure windsocks are installed and visually accessible.
- Ensure steps to mitigate leaks and spills are taken and procedures to deal with spills are in place.
- Confirms personal gas monitors are available for all personnel at the wellsite during operations.
- Confirms all on site gas atmospheric monitors are operating properly and in good working order.
- Confirms all personnel at the well site have adequate PPE including, but not limited to, hard hat, goggles, long sleeve shirts, gloves with a cut rating of 2 or higher, and double hearing protection (ear plugs and soundproof earmuffs).
- Conducts a Job Safety Analysis (JSA) form on the day of the event prior to the coiled tubing cleanout operation.
- Maintains full authority to stop operations at any time during the backflow operation.

Engineer in Charge –

- Strictly focuses on incoming and outgoing communications as needed.
- Responsible for communicating and updating project manager.
- Ensures all necessary tools and equipment are on site.
- Responsible for AFE, daily report, and budget tracking and communicating significant deviations.

Wellsite Supervisor –

- Maintains responsibility for work conducted on the CCS #2 equipment and the coiled tubing operations.
- Communicate and ensure all personnel understands the procedure and their respective functions.
- Communicate and ensure all personnel understands Permit IL-115-6A-0001 Attachment F: Emergency and Remedial Response Plan for ADM CCS#2.
- Ensures operability of radio communication and maintains communication with all affected colleagues: at the well, production personnel monitoring the parameters of the well, ADM Security and others as applicable.
- Coordinate operations and equipment required for operations with vendors.
- Responsible for communicating and updating engineer.
- Monitors atmospheric conditions to ensure adequacy prior to commencement of the backflow operation.

Vendor Supervisors –

- Maintains responsibility for work conducted on their respective equipment.
- Ensure all personnel reporting to them understand their responsibilities and follow the procedure.

ADM Management –

- Maintains communication with the CCS PM and S/E Manager for the duration of the coiled tubing cleanout operation.

ADM $CO_2$ Operators –

- Confirms nitrogen supply at well site. Nitrogen is required to actuate the automatic upper master valve.
- Coordinate injection shutdown and startup.
- Monitor and maintain required annulus and wellhead pressure. Communicate with wellsite supervisor if parameters are outside allowable.

ADM Security –

- Limits access to the road entrance to the well site.

## 7. Health, Safety, and Environmental Considerations and Discussion

**Potential hazards include**:

- **Additive Chemicals** – Multiple additives will be preblended into the HCL solution transported to site. For additional information review the SDS attached for each additive, in Appendix II.
    - Corrosion Inhibitor – Envirohib 600
    - Iron Control – Ferriplex 40
    - Non-Emulsifier – PlexBreak 145
    - Surfactant – Waxaid 19
    - Surfactant – Waxaid 19
- **Biocide – Bioclear 1430:** Glutaraldehyde (C5H8O2) is a primary component of Biocide. It is a colorless, oily liquid with a sharp, pungent odor. It is used as a biocide to destroy bacterial activity in the fluid. Contact with liquid causes severe irritation of eyes and irritation of skin. Chemical readily penetrates skin in harmful amounts. Ingestion causes irritation of mouth and stomach (National Center for Biotechnology Information, 2005). For additional information review SDS attached in the Appendix II.
- **Carbon dioxide ($CO_2$):** Carbon Dioxide gas is colorless. At low concentrations, the gas is odorless. At higher concentrations it has a sharp, acidic odor. It will act as an asphyxiant and an irritant. Carbon Dioxide is a powerful cerebral dilator. At concentrations between 2 and 10%, Carbon Dioxide can cause nausea, dizziness, headache, mental confusion, increased blood pressure and respiratory rate. Above 8%, nausea and vomiting appear. Above 10%, suffocation and death can occur within minutes. Contact with the cold gas can cause freezing of exposed tissue. Moisture in the air can lead to formation of carbonic acid that can irritate the eyes. All forms of Carbon Dioxide are noncombustible. Carbon Dioxide is heavier than air and should not be allowed to accumulate in low lying areas.
- **Fire:** A fire hazard is present due to flaring operations. Site operators should have fire extinguishers available and windsocks to monitor wind conditions. A 100' no-go zone should be clearly marked around the vent/flare stack.
- **Heavy Aromatic Naphtha (PT-330)**: Heavy Aromatic Naphtha is a complex combination of hydrocarbons obtained from distillation of aromatic streams. Naphtha can cause nose and throat irritation on inhalation or irritate and burn the skin and eyes on contact. Additionally, it can also cause headache, dizziness, nausea and vomiting. Naphtha is a

flammable or combustible liquid depending on its hydrocarbon composition. An SDS for PT-330 is attached in the Appendix II.

Additional information regarding Naphtha can be found at https://www.cdc.gov/niosh/npg/npgd0664.html

A Volatile Organic Compound (VOC) gas monitors, will be present on site to monitor vaporized fume content.

- **Hydrochloric Acid (Hydrogen Chloride - HCl):** Hydrochloric acid, solution is a colorless watery liquid with a sharp, irritating odor. Consists of hydrogen chloride, a gas, dissolved in water. Sinks and mixes with water. Produces irritating vapor. At room temperature, hydrogen chloride is a colorless to slightly yellow, corrosive, nonflammable gas that is heavier than air and has a strong irritating odor. Hydrochloric acid is corrosive to the eyes, skin, and mucous membranes. Acute (short-term) inhalation exposure may cause eye, nose, and respiratory tract irritation and inflammation and pulmonary edema in humans. Acute oral exposure may cause corrosion of the mucous membranes, esophagus, and stomach and dermal contact may produce severe burns, ulceration, and scarring in humans. Chronic (long-term) occupational exposure to hydrochloric acid has been reported to cause gastritis, chronic bronchitis, dermatitis, and photosensitization in workers. Prolonged exposure to low concentrations may also cause dental discoloration and erosion (National Center for Biotechnology Information, 2004). Additional information regarding HCL exposure hazards can be found at https://www.osha.gov/chemicaldata/620

  Personnel on site, with potential of HCL exposure will require Volatile Organic Compound (VOC) gas monitors. Photoionization Detector (PID) gas monitors. Additionally, HCL recovered after flowback will need to be neutralized.
- **Noise:** The injection pumps used during the coiled tubing cleanout operation will produce noise levels in excess of 85 decibels. Noise levels above 85 decibels can cause permanent damage to the hair cells in the inner ear, leading to hearing loss. It is required by OSHA to wear double hearing protection consisting of ear plugs and earmuffs when noise levels reach 140 decibels or more.
- **Particulate:** The flaring operation as part of the coiled tubing cleanout operation may produce minor levels of particulate to be suspended in the air. The operation should be stopped or slowed at the discretion of the site team if particulate levels are higher than expected as monitored on personal safety monitoring devices.
- **Pressure:**
  - **Operational Rating**: All wellhead valves except the bottom casing flange are rated up to 5,000 PSIG. The bottom casing flange is rated up to 3,000 PSIG.

**IMPORTANT:** ***All activity <u>shall cease</u> if wellhead pressure exceeds 3,000 PSIG.***

**$CO_2$ Mixing in Atmosphere:** Wellsite supervisor confirms all site conditions are met before proceeding with the operation and that temperature and wind conditions are conducive to $CO_2$ mixing in atmosphere.

- **Temperature**: During the backflow process as part of the coiled tubing cleanout operation. A pressure drop in the lower assembly of the well head will cause cooling. If temperatures extend outside the backflow range, particularly below -10°F, operations will begin to choke back flow to decrease the temperature drop.
  - **Operating Range**: Wellhead valves have an operating range of -20° to 1,300°F.
  - **During Backflow**: Typically, 0° to -10°F.

**IMPORTANT:** ***All activity <u>shall cease</u> if temperature falls below -15°F.***

**Emergency and Remedial Response:** In the event that the Emergency and Remedial Response Plan (ERRP) is activated and/or followed, ADM shall implement the verbal and written reporting requirements set forth in Section N(3) of Permit #IL-115-6A-0001

**Required Training**

- **Well Control Training:** Wellsite supervisor in charge of operations will be trained and certified in well control.

**Records**

- **Carbon Dioxide Venting Calculation:** The amount of $CO_2$ emitted to the atmosphere must be calculated to be included on the greenhouse gas report for submittal the following year.
- **Daily Operational Reports:** Daily operational reports will be developed for each day of the operation.
- **Job Safety Analysis:** A completed JSA form must be reviewed by all affected colleagues priorto the start of the backflow operation.

**Disposal:**

- Proper disposal of the backflow materials will be performed based on generator knowledge and SDS's of materials present, in accordance with all local, state, and federal regulations.
- The waste mixture will be stored in the Waste Frac Tanks, and labeled as "Hazardous Waste - Waste Pending Analysis"
- The Safety/Environmental Manager will ensure that all applicable regulatory requirements under RCRA are met while storing the waste onsite.
- Once analytical results are received, the materials will be disposed of at the appropriate treatment, storage, or disposal facility.

## 8. Procedure

***Notes***:

- Review safety protocol with the crew at the start of the job and ensure site personnel are aware of the site-specific hazards and Emergency Response Protocols. Ensure proper handovers during shift change is conducted.
- This procedure is only a guideline and will be subject to change based on vendor selection and equipment availability. Other procedural changes may be necessary during treatment execution due to changing operational conditions and ongoing evaluation of treatment efficacy.

1. Conduct notifications necessary prior to cleanout operation:
    - Notify ADM site supervisor 2 weeks prior to planned move in date.
    - Notify agency 30 days prior to treatment operations.
    - Notify JULIE or preferred underground locating service at least 72 hours in advance of moving in equipment to mark buried lines (unit grounding).
    - Notify vendors and disposal companies
2. Order long lead equipment prior to commencing operations:
    - Full set of ring gaskets, studs, nuts, and wrenches for entire Christmas tree stack.
    - VOC, HCl, and $CO_2$ safety meters.
    - Disposal company.
3. Install barriers and cones around above ground pipes and valves. Remove fencing around wellhead. Mobilize forklift and manlift.
4. Spot Coil Tubing Unit prior to support equipment ensure to utilize spotters while trailer is backing into position.

5. Spot and rig-up surface equipment:
    - Pump truck
    - Injection and flowback lines, meters, and hoses.
    - Crane
    - Separator
    - Choke manifold
    - Vent stack
    - Hot oiler, line heater and or heat baths.
    - Transfer pumps
    - Wash station (shower)
    - Porta Pots
    - Light plants X 3
    - Dumpster

    Confirm coiled tubing and ancillary equipment was pressure tested and ready for operations. Utilize spotters while backing equipment. Manifold pump trucks to be able to inject into the coil or surface return lines (to inject $N_2$ to blanket stack and/or cut flowback).

6. Designate a rally point for personnel to meet at, in the event a well control emergency takes place.
7. Conduct a Job Safety Analysis (JSA) and review operations with the entire crew required repeat as needed as new crew arrive for night shift.
8. Confirm anulus pressure is 100 psi and tubing pressure differential directly above and across the packer is 100 psi. If pressure is not 100 psi above tubing pressure **DO NOT PROCEED,** notify engineering, and await instruction**.** Monitor annulus pressure across the packer at all times during operations to ensure a positive 100-psig differential.
9. Install lay flat from Progress City hydrant to CCS #2 wellsite. Fill 5 frac tanks with fresh water (install berms under frac tanks).
10. Ensure all fresh water pumped has biocide added at 2 gpt.
11. Move in hot oiler(s) and begin heating water. Heat up 1500 BBL of fresh water to approx. 180° F. Designate three frac tank as hot water tank. Heating process may take 8-12 hours.
12. Halt $CO_2$ injection.
13. Close Injection wing valve. Record the number of turns required to close the valve.
14. Close Lower Master valve. Record the number of turns required to close the valve.
15. Close pneumatic Upper Master gate valve.
16. Close 2-1/16" kill valve on well head. Record the number of turns required to close the valve.
17. Close crown valve and bleed off pressure through needle valve in tree cap. Record the number of turns required to close the valve.
18. Unbolt and remove 4-½" tree cap.
19. Install 7-1/16" work valve, flow tee, and quad BOP (Blind Ram, Shear Ram, Slip Rams, and Pipe Seal Ram) above crown valve in open position. All elastomers dressed for $CO_2$ duty service.
20. Close 7-1/16" work valve.
21. Open Upper Master and crown gate valve. Verify 7-1/16" work valve holding pressure.
22. LOTO valve to ensure it cannot close during well work operation. Follow site procedure for LOTO and valve operation.
23. Ensure bottom master gate is in the open position.
24. Make up jetting tool assembly include jetting tool, IBOP (Internal BOP) and knuckle joints in assembly.
25. Load coil tubing, and well head stack with hot water. Fill separator to required level with hot water.

26. Flush 2-time coil tubing volume, through coil tubing, and surface lines.
27. Close choke and pressure test pump iron, coiled tubing, entire stack, and flowline to choke with 3,000psi.
28. Investigate for leaks. Hold pressure for 30 minutes. Tighten connections as needed.
29. Bleed off pressure into frac tank through return valve.
30. Test BOP stack through the choke.
31. Bleed off pressure into frac tank through return valve. Pressure up the wellhead stack with a $N_2$ blanket, match well pressure.
32. Setup to monitor downhole wellbore pressure and temperature parameters prior to treatment operation and during treatment operation to not exceed downhole tubing pressure greater than 4,125 psia.
33. Ensure Return valve is closed. Then open 7-16" Working valve.
34. Start loading the hole with hydro jetting treatment fluid. Do not exceed 4,125 psia downhole tubing pressure.
35. Trip in Hole (TIH) with jetting tool (at ~ 60 ft/min) to 6,600' pump the heated treatment fluid, ensure CO2 is displaced into the formation and coil is always in treatment fluid (use about 200 bbl). Stop every 1,000 ft and pull back to ensure no restrictions. If jetting nozzle stacks off TOOH and switch to a mechanical cleanout with mud motor and bit. Monitor annulus pressure during TIH.
36. Open return valve and increase pumping rate to at least 2 bpm and perform hydro jetting pass 1 (6,600 – TD): TIH (~10-5 ft/min) while hydro jetting down to TD and TOOH back to 6,600' above top perf. Adjust choke and match return rate with pump rate to limit CO2 influx. If injection rate changes adjust flowback rate accordingly. *Rate and speed are dependent on operational conditions (i.e., if string starts to take weight may increase pump rate, increase speed during subsequent passes, etc.).
37. Perform additional jetting tool passes through the perforations from 6,600' to 6,855' with heated hydro jetting treatment at ~5-10 ft/min and 2 bpm injection rate. If injection rate changes adjust flowback rate accordingly. *Rate and speed are dependent on operational conditions (i.e., if string starts to take weight may increase pump rate, increase speed during subsequent passes, etc.).
38. Perform a short trip above XN nipple to 6,300' and RIH to TD, while circulating at 2 bpm. Once at TD, increase rate to 3-3.5 bpm (circulate 2 x bottom-up total). Adjust flowback rate accordingly.
39. POOH to bottom perf. Close return line and inject a 500,000 SCF $N_2$ pad into formation, while tripping out of hole slowly.

    Note: Crew will stop after a 12-hour shift and resume operations the next day. Hot oiler will continue to heat fluid overnight. Based on operational progress through steps 1- 39 operational changes might be made for a safe overnight shut-in.
40. Make first solvent treatment pass at ~5-10 ft/min pumping at ~2 bpm from 6,600' to 6,855' treating perforations with 125 bbl of solvent treatment. *Rate and speed are dependent on operational conditions (i.e., if string starts to take weight may increase pump rate, increase speed during subsequent passes, etc.)
41. Pull coil up to ~6,400', continue to reciprocate coil. Surge well back by opening return valve for about 100' of surge (~7 bbl). Close return valve. Move down to 6,500'.
42. Make second solvent treatment pass at ~5-10 ft/min pumping at ~2 bpm from 6,855' to 6,500' treating perforations with 125 bbl of solvent treatment.
43. When all treatment fluid is pumped, TOOH to ~6,475' switch to fresh water and flush lines displacing solvent treatment into perforations.
44. TOOH pull above 7-1/16" working valve.
45. Close 7-1/16" working valve.
46. Allow treatment fluid to soak for less than 6 hours.
47. While well is soaking check freshwater volumes and top off as needed. Using hot oiler heat up 500 BBL of water to approximately 180° F.

48. Monitor well head and downhole tubing pressure. Do not exceed 4,125 psia downhole tubing pressure. Bleed off gas into as needed to maintain pressure not to exceed 4,125 psia downhole tubing pressure
49. Initiate backflow to recover treatment fluid. Open return valve, and choke return line valves allowing well to unload using nitrogen pad and reservoir pressure until treatment fluid returns cease or significant $CO_2$ returns are observed. Monitor for hydrate formation and inject nitrogen as needed to support backflow venting. Flow back into frac tanks through separator and choke manifold to unload the well fluids. Monitor returns and shut-in well/stop flowback once significant $CO_2$ is observed at surface.
50. Open 7-1/16" working valve. Load the hole with hydro jetting treatment fluid pad (60 bbl) and displace $CO_2$ into the well.
51. TIH with the jetting tool to ~TD' (at ~ 60 ft/min) pumping heated fresh at 2 bpm (use about 250 bbl), Choke return to ensure coil tubing is always in treatment fluid.
52. TOOH jetting hot water at 2 Bpm (use about 250 bbl) at ~60 ft/min. Choke return to ensure coil tubing is always in treatment fluid.
53. Close 7-1/16" working valve.
54. Regrease and retorque all wellhead flanges.
55. Resume $CO_2$ injection and monitor downhole pressures and injectivity performance.
56. Rig down move out.
    - Flush hoses with fresh water.
    - Send samples for disposal analysis.
    - Remove/dispose of flowback fluids.
    - Remove/dispose and solids in flowback tanks.
    - Conduct tank cleaning.

## Appendix I: Sample Analytical Results

Analysis of Metals in Unknown Hydrocarbon by ICP

08/19/2022 Dawn Buschek - ADM Research Analytical

Submitted by - Scott McDonald

Charge Code - Corn Syrup B02

Project Code - 13-1201 R&D General Support - Corn Syrup

AST Form - 106171

AST Request - 2022-03706

Analytical ELN Record - 2022-0819-006

| Sample Name | 2022-03706 CCS2 Sample 8-11-22 | Units | LOD |
|---|---|---|---|
| Al | 1110 | mg/kg | 0.2 |
| B | 12.4 | mg/kg | 0.2 |
| Ca | 10800 | mg/kg | 0.2 |
| Co | ND | mg/kg | 1 |
| Cr | 403 | mg/kg | 1 |
| Cu | 797 | mg/kg | 1 |
| Fe | 8100 | mg/kg | 0.2 |
| K | 841 | mg/kg | 10 |
| Mg | 1690 | mg/kg | 0.2 |
| Mn | 107 | mg/kg | 1 |
| Mo | 11 | mg/kg | 1 |
| Na | 25000 | mg/kg | 0.2 |
| Ni | 62.4 | mg/kg | 1 |
| P | 149 | mg/kg | 1 |
| S | 10600 | mg/kg | 1 |
| Zn | 1220 | mg/kg | 0.2 |

## Appendix II: SDS Sheets

### SDS CO2

# SAFETY DATA SHEET

Carbon Dioxide

Airgas
an Air Liquide company

## Section 1. Identification

**GHS product identifier** : Carbon Dioxide

**Chemical name** : Carbon dioxide, gas

**Other means of identification** : Carbonic, Carbon Dioxide, Carbonic Anhydride, R744, Carbon Dioxide USP

**Product type** : Gas.

**Product use** : Synthetic/Analytical chemistry and Medical use.

**Synonym** : Carbonic, Carbon Dioxide, Carbonic Anhydride, R744, Carbon Dioxide USP

**SDS #** : 001013

**Supplier's details** : Airgas USA, LLC and its affiliates
259 North Radnor-Chester Road
Suite 100
Radnor, PA 19087-5283
1-610-687-5253

**24-hour telephone** : 1-866-734-3438

## Section 2. Hazards identification

**OSHA/HCS status** : This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).

**Classification of the substance or mixture** : GASES UNDER PRESSURE - Liquefied gas
Simple asphyxiant.

**GHS label elements**

**Hazard pictograms** :



**Signal word** : Warning

**Hazard statements** : Contains gas under pressure; may explode if heated.
May displace oxygen and cause rapid suffocation.
May increase respiration and heart rate.

**Precautionary statements**

**General** : Read and follow all Safety Data Sheets (SDS'S) before use. Read label before use. Keep out of reach of children. If medical advice is needed, have product container or label at hand. Close valve after each use and when empty. Use equipment rated for cylinder pressure. Do not open valve until connected to equipment prepared for use. Use a back flow preventative device in the piping. Use only equipment of compatible materials of construction. Always keep container in upright position.

**Prevention** : Use and store only outdoors or in a well ventilated place.

**Response** : Not applicable.

**Storage** : Protect from sunlight. Store in a well-ventilated place.

**Disposal** : Not applicable.

**Hazards not otherwise classified** : In addition to any other important health or physical hazards, this product may displace oxygen and cause rapid suffocation.
May cause frostbite.

*Carbon Dioxide*

## Section 3. Composition/information on ingredients

**Substance/mixture** : Substance

**Chemical name** : Carbon dioxide, gas

**Other means of identification** : Carbonic, Carbon Dioxide, Carbonic Anhydride, R744, Carbon Dioxide USP

**Product code** : 001013

**CAS number/other identifiers**

**CAS number** : 124-38-9

| Ingredient name | % | CAS number |
|---|---|---|
| Carbon Dioxide | 100 | 124-38-9 |

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

**There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment and hence require reporting in this section.**

**Occupational exposure limits, if available, are listed in Section 8.**

## Section 4. First aid measures

**Description of necessary first aid measures**

**Eye contact** : Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention if irritation occurs.

**Inhalation** : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention if adverse health effects persist or are severe. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

**Skin contact** : Flush contaminated skin with plenty of water. Remove contaminated clothing and shoes. Get medical attention if symptoms occur. Wash clothing before reuse. Clean shoes thoroughly before reuse.

**Ingestion** : As this product is a gas, refer to the inhalation section.

**Most important symptoms/effects, acute and delayed**

**Potential acute health effects**

**Eye contact** : No known significant effects or critical hazards.

**Inhalation** : No known significant effects or critical hazards.

**Skin contact** : No known significant effects or critical hazards.

**Frostbite** : Try to warm up the frozen tissues and seek medical attention.

**Ingestion** : As this product is a gas, refer to the inhalation section.

**Over-exposure signs/symptoms**

**Eye contact** : No specific data.

**Inhalation** : No specific data.

**Skin contact** : No specific data.

**Ingestion** : No specific data.

**Indication of immediate medical attention and special treatment needed, if necessary**

**Notes to physician** : Treat symptomatically. Contact poison treatment specialist immediately if large quantities have been ingested or inhaled.

**Specific treatments** : No specific treatment.

## Section 4. First aid measures

**Protection of first-aiders** : No action shall be taken involving any personal risk or without suitable training. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation.

**See toxicological information (Section 11)**

## Section 5. Fire-fighting measures

**Extinguishing media**

**Suitable extinguishing media** : Use an extinguishing agent suitable for the surrounding fire.

**Unsuitable extinguishing media** : None known.

**Specific hazards arising from the chemical** : Contains gas under pressure. In a fire or if heated, a pressure increase will occur and the container may burst or explode.

**Hazardous thermal decomposition products** : Decomposition products may include the following materials:
carbon dioxide
carbon monoxide

**Special protective actions for fire-fighters** : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Contact supplier immediately for specialist advice. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.

**Special protective equipment for fire-fighters** : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

## Section 6. Accidental release measures

**Personal precautions, protective equipment and emergency procedures**

**For non-emergency personnel** : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Avoid breathing gas. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.

**For emergency responders** : If specialized clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".

**Environmental precautions** : Ensure emergency procedures to deal with accidental gas releases are in place to avoid contamination of the environment. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

**Methods and materials for containment and cleaning up**

**Small spill** : Immediately contact emergency personnel. Stop leak if without risk.

**Large spill** : Immediately contact emergency personnel. Stop leak if without risk. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

## Section 7. Handling and storage

**Precautions for safe handling**

**Protective measures** : Put on appropriate personal protective equipment (see Section 8). Contains gas under pressure. Avoid breathing gas. Do not puncture or incinerate container. Use equipment rated for cylinder pressure. Close valve after each use and when empty. Protect cylinders from physical damage; do not drag, roll, slide, or drop. Use a suitable hand truck for cylinder movement.
Avoid contact with eyes, skin and clothing. Empty containers retain product residue and can be hazardous.

*Carbon Dioxide*

## Section 7. Handling and storage

**Advice on general occupational hygiene** : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

**Conditions for safe storage, including any incompatibilities** : Store in accordance with local regulations. Store in a segregated and approved area. Store away from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10). Cylinders should be stored upright, with valve protection cap in place, and firmly secured to prevent falling or being knocked over. Cylinder temperatures should not exceed 52 °C (125 °F). Keep container tightly closed and sealed until ready for use. See Section 10 for incompatible materials before handling or use.

## Section 8. Exposure controls/personal protection

**Control parameters**

**Occupational exposure limits**

| Ingredient name | Exposure limits |
|---|---|
| Carbon Dioxide | **ACGIH TLV (United States, 3/2017). Oxygen Depletion [Asphyxiant].**<br>STEL: 54000 mg/m³ 15 minutes.<br>STEL: 30000 ppm 15 minutes.<br>TWA: 9000 mg/m³ 8 hours.<br>TWA: 5000 ppm 8 hours.<br>**NIOSH REL (United States, 10/2016).**<br>STEL: 54000 mg/m³ 15 minutes.<br>STEL: 30000 ppm 15 minutes.<br>TWA: 9000 mg/m³ 10 hours.<br>TWA: 5000 ppm 10 hours.<br>**OSHA PEL (United States, 6/2016).**<br>TWA: 9000 mg/m³ 8 hours.<br>TWA: 5000 ppm 8 hours.<br>**OSHA PEL 1989 (United States, 3/1989).**<br>STEL: 54000 mg/m³ 15 minutes.<br>STEL: 30000 ppm 15 minutes.<br>TWA: 18000 mg/m³ 8 hours.<br>TWA: 10000 ppm 8 hours. |

**Appropriate engineering controls** : Good general ventilation should be sufficient to control worker exposure to airborne contaminants.

**Environmental exposure controls** : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

**Individual protection measures**

**Hygiene measures** : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

**Eye/face protection** : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: safety glasses with side-shields.

**Skin protection**

*Carbon Dioxide*

## Section 8. Exposure controls/personal protection

**Hand protection** : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.

**Body protection** : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

**Other skin protection** : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

**Respiratory protection** : Based on the hazard and potential for exposure, select a respirator that meets the appropriate standard or certification. Respirators must be used according to a respiratory protection program to ensure proper fitting, training, and other important aspects of use. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator.

## Section 9. Physical and chemical properties

**Appearance**

**Physical state** : Gas. [Compressed gas.]

**Color** : Colorless.

**Odor** : Odorless.

**Odor threshold** : Not available.

**pH** : Not available.

**Melting point** : Sublimation temperature: -79°C (-110.2 to °F)

**Boiling point** : Not available.

**Critical temperature** : 30.85°C (87.5°F)

**Flash point** : [Product does not sustain combustion.]

**Evaporation rate** : Not available.

**Flammability (solid, gas)** : Not available.

**Lower and upper explosive (flammable) limits** : Not available.

**Vapor pressure** : 830 (psig)

**Vapor density** : 1.53 (Air = 1) Liquid Density@BP: Solid density = 97.5 lb/ft3 (1562 kg/m3)

**Specific Volume ($ft^3$/lb)** : 8.7719

**Gas Density (lb/$ft^3$)** : 0.114

**Relative density** : Not applicable.

**Solubility** : Not available.

**Solubility in water** : Not available.

**Partition coefficient: n-octanol/water** : 0.83

**Auto-ignition temperature** : Not available.

**Decomposition temperature** : Not available.

**Viscosity** : Not applicable.

**Flow time (ISO 2431)** : Not available.

**Molecular weight** : 44.01 g/mole

*Carbon Dioxide*

## Section 10. Stability and reactivity

**Reactivity** : No specific test data related to reactivity available for this product or its ingredients.

**Chemical stability** : The product is stable.

**Possibility of hazardous reactions** : Under normal conditions of storage and use, hazardous reactions will not occur.

**Conditions to avoid** : No specific data.

**Incompatible materials** : No specific data.

**Hazardous decomposition products** : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

**Hazardous polymerization** : Under normal conditions of storage and use, hazardous polymerization will not occur.

## Section 11. Toxicological information

**Information on toxicological effects**

**Acute toxicity**
Not available.

**Irritation/Corrosion**
Not available.

**Sensitization**
Not available.

**Mutagenicity**
Not available.

**Carcinogenicity**
Not available.

**Reproductive toxicity**
Not available.

**Teratogenicity**
Not available.

**Specific target organ toxicity (single exposure)**
Not available.

**Specific target organ toxicity (repeated exposure)**
Not available.

**Aspiration hazard**
Not available.

**Information on the likely routes of exposure** : Not available.

**Potential acute health effects**

**Eye contact** : No known significant effects or critical hazards.

**Inhalation** : No known significant effects or critical hazards.

**Skin contact** : No known significant effects or critical hazards.

*Carbon Dioxide*

## Section 11. Toxicological information

**Ingestion** : As this product is a gas, refer to the inhalation section.

**Symptoms related to the physical, chemical and toxicological characteristics**

**Eye contact** : No specific data.

**Inhalation** : No specific data.

**Skin contact** : No specific data.

**Ingestion** : No specific data.

**Delayed and immediate effects and also chronic effects from short and long term exposure**

**Short term exposure**

**Potential immediate effects** : Not available.

**Potential delayed effects** : Not available.

**Long term exposure**

**Potential immediate effects** : Not available.

**Potential delayed effects** : Not available.

**Potential chronic health effects**

Not available.

**General** : No known significant effects or critical hazards.

**Carcinogenicity** : No known significant effects or critical hazards.

**Mutagenicity** : No known significant effects or critical hazards.

**Teratogenicity** : No known significant effects or critical hazards.

**Developmental effects** : No known significant effects or critical hazards.

**Fertility effects** : No known significant effects or critical hazards.

**Numerical measures of toxicity**

**Acute toxicity estimates**

Not available.

## Section 12. Ecological information

**Toxicity**

Not available.

**Persistence and degradability**

Not available.

**Bioaccumulative potential**

| Product/ingredient name | $LogP_{ow}$ | BCF | Potential |
|---|---|---|---|
| Carbon Dioxide | 0.83 | - | low |

**Mobility in soil**

**Soil/water partition coefficient ($K_{OC}$)** : Not available.

**Other adverse effects** : No known significant effects or critical hazards.

*Carbon Dioxide*

## Section 13. Disposal considerations

**Disposal methods** : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Empty Airgas-owned pressure vessels should be returned to Airgas. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Empty containers or liners may retain some product residues. Do not puncture or incinerate container.

## Section 14. Transport information

| | DOT | TDG | Mexico | IMDG | IATA |
|---|---|---|---|---|---|
| **UN number** | UN1013 | UN1013 | UN1013 | UN1013 | UN1013 |
| **UN proper shipping name** | CARBON DIOXIDE | CARBON DIOXIDE | CARBON DIOXIDE | CARBON DIOXIDE | CARBON DIOXIDE |
| **Transport hazard class(es)** | 2.2  | 2.2  | 2.2  | 2.2  | 2.2  |
| **Packing group** | - | - | - | - | - |
| **Environmental hazards** | No. | No. | No. | No. | No. |

**"Refer to CFR 49 (or authority having jurisdiction) to determine the information required for shipment of the product."**

**Additional information**

**DOT Classification** : **Limited quantity** Yes.
**Quantity limitation** Passenger aircraft/rail: 75 kg. Cargo aircraft: 150 kg.

**TDG Classification** : Product classified as per the following sections of the Transportation of Dangerous Goods Regulations: 2.13-2.17 (Class 2).
**Explosive Limit and Limited Quantity Index** 0.125
**Passenger Carrying Road or Rail Index** 75

**IATA** : **Quantity limitation** Passenger and Cargo Aircraft: 75 kg. Cargo Aircraft Only: 150 kg.

**Special precautions for user** : **Transport within user's premises:** always transport in closed containers that are upright and secure. Ensure that persons transporting the product know what to do in the event of an accident or spillage.

**Transport in bulk according to Annex II of MARPOL and the IBC Code** : Not available.

## Section 15. Regulatory information

**U.S. Federal regulations** : **TSCA 8(a) CDR Exempt/Partial exemption**: This material is listed or exempted.

**Clean Air Act Section 112 (b) Hazardous Air Pollutants (HAPs)** : Not listed

*Carbon Dioxide*

## Section 15. Regulatory information

**Clean Air Act Section 602 Class I Substances** : Not listed

**Clean Air Act Section 602 Class II Substances** : Not listed

**DEA List I Chemicals (Precursor Chemicals)** : Not listed

**DEA List II Chemicals (Essential Chemicals)** : Not listed

**SARA 302/304**

**Composition/information on ingredients**

No products were found.

**SARA 304 RQ** : Not applicable.

**SARA 311/312**

**Classification** : Refer to Section 2: Hazards Identification of this SDS for classification of substance.

**State regulations**

**Massachusetts** : This material is listed.

**New York** : This material is not listed.

**New Jersey** : This material is listed.

**Pennsylvania** : This material is listed.

**International regulations**

**Chemical Weapon Convention List Schedules I, II & III Chemicals**

Not listed.

**Montreal Protocol (Annexes A, B, C, E)**

Not listed.

**Stockholm Convention on Persistent Organic Pollutants**

Not listed.

**Rotterdam Convention on Prior Informed Consent (PIC)**

Not listed.

**UNECE Aarhus Protocol on POPs and Heavy Metals**

Not listed.

**Inventory list**

**Australia** : This material is listed or exempted.

**Canada** : This material is listed or exempted.

**China** : This material is listed or exempted.

**Europe** : This material is listed or exempted.

**Japan** : **Japan inventory (ENCS)**: This material is listed or exempted.
**Japan inventory (ISHL)**: This material is listed or exempted.

**Malaysia** : Not determined.

**New Zealand** : This material is listed or exempted.

**Philippines** : This material is listed or exempted.

**Republic of Korea** : This material is listed or exempted.

**Taiwan** : This material is listed or exempted.

**Thailand** : Not determined.

**Turkey** : This material is listed or exempted.

**United States** : This material is listed or exempted.

**Viet Nam** : Not determined.

*Carbon Dioxide*

## Section 16. Other information

**Hazardous Material Information System (U.S.A.)**




**Caution: HMIS® ratings are based on a 0-4 rating scale, with 0 representing minimal hazards or risks, and 4 representing significant hazards or risks. Although HMIS® ratings and the associated label are not required on SDSs or products leaving a facility under 29 CFR 1910.1200, the preparer may choose to provide them. HMIS® ratings are to be used with a fully implemented HMIS® program. HMIS® is a registered trademark and service mark of the American Coatings Association, Inc.**

**The customer is responsible for determining the PPE code for this material. For more information on HMIS® Personal Protective Equipment (PPE) codes, consult the HMIS® Implementation Manual.**

**National Fire Protection Association (U.S.A.)**




**Reprinted with permission from NFPA 704-2001, Identification of the Hazards of Materials for Emergency Response Copyright ©1997, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.**

**Copyright ©2001, National Fire Protection Association, Quincy, MA 02269. This warning system is intended to be interpreted and applied only by properly trained individuals to identify fire, health and reactivity hazards of chemicals. The user is referred to certain limited number of chemicals with recommended classifications in NFPA 49 and NFPA 325, which would be used as a guideline only. Whether the chemicals are classified by NFPA or not, anyone using the 704 systems to classify chemicals does so at their own risk.**

**Procedure used to derive the classification**

| Classification | Justification |
|---|---|
| GASES UNDER PRESSURE - Liquefied gas | Expert judgment |

**History**

**Date of printing** : 2/12/2018

**Date of issue/Date of revision** : 2/12/2018

**Date of previous issue** : 4/25/2017

**Version** : 0.03

**Key to abbreviations** : ATE = Acute Toxicity Estimate
BCF = Bioconcentration Factor
GHS = Globally Harmonized System of Classification and Labelling of Chemicals
IATA = International Air Transport Association
IBC = Intermediate Bulk Container
IMDG = International Maritime Dangerous Goods
LogPow = logarithm of the octanol/water partition coefficient
MARPOL = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution)
UN = United Nations

**References** : Not available.

**Notice to reader**

*Carbon Dioxide*

## Section 16. Other information

**To the best of our knowledge, the information contained herein is accurate. However, neither the above-named supplier, nor any of its subsidiaries, assumes any liability whatsoever for the accuracy or completeness of the information contained herein.**
**Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.**

**SDS HCl**

Sigma-Aldrich. www.sigmaaldrich.com

## SAFETY DATA SHEET

Version 6.7
Revision Date 06/07/2021
Print Date 09/11/2022

### SECTION 1: Identification of the substance/mixture and of the company/undertaking

**1.1 Product identifiers**

Product name : Hydrochloric acid

Product Number : H1758
Brand : Sigma
Index-No. : 017-002-01-X
CAS-No. : 7647-01-0

**1.2 Relevant identified uses of the substance or mixture and uses advised against**

Identified uses : Laboratory chemicals, Synthesis of substances

**1.3 Details of the supplier of the safety data sheet**

Company : Sigma-Aldrich Inc.
3050 SPRUCE ST
ST. LOUIS MO 63103
UNITED STATES

Telephone : +1 314 771-5765
Fax : +1 800 325-5052

**1.4 Emergency telephone**

Emergency Phone # : 800-424-9300 CHEMTREC (USA) +1-703-527-3887 CHEMTREC (International) 24 Hours/day; 7 Days/week

### SECTION 2: Hazards identification

**2.1 Classification of the substance or mixture**

**GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)**

Corrosive to Metals (Category 1), H290
Skin corrosion (Category 1B), H314
Serious eye damage (Category 1), H318
Specific target organ toxicity - single exposure (Category 3), Respiratory system, H335

For the full text of the H-Statements mentioned in this Section, see Section 16.

**2.2 GHS Label elements, including precautionary statements**

Pictogram



Signal word Danger




The life science business of Merck KGaA, Darmstadt, Germany
operates as MilliporeSigma in the US and Canada

| | |
|---|---|
| Hazard statement(s) | |
| H290 | May be corrosive to metals. |
| H314 | Causes severe skin burns and eye damage. |
| H335 | May cause respiratory irritation. |
| Precautionary statement(s) | |
| P234 | Keep only in original container. |
| P261 | Avoid breathing dust/ fume/ gas/ mist/ vapors/ spray. |
| P264 | Wash skin thoroughly after handling. |
| P271 | Use only outdoors or in a well-ventilated area. |
| P280 | Wear protective gloves/ protective clothing/ eye protection/ face protection. |
| P301 + P330 + P331 | IF SWALLOWED: Rinse mouth. Do NOT induce vomiting. |
| P303 + P361 + P353 | IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water/ shower. |
| P304 + P340 + P310 | IF INHALED: Remove person to fresh air and keep comfortable for breathing. Immediately call a POISON CENTER/ doctor. |
| P305 + P351 + P338 + P310 | IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. Immediately call a POISON CENTER/ doctor. |
| P363 | Wash contaminated clothing before reuse. |
| P390 | Absorb spillage to prevent material damage. |
| P403 + P233 | Store in a well-ventilated place. Keep container tightly closed. |
| P405 | Store locked up. |
| P406 | Store in corrosive resistant container with a resistant inner liner. |
| P501 | Dispose of contents/ container to an approved waste disposal plant. |

**2.3 Hazards not otherwise classified (HNOC) or not covered by GHS** - none

## SECTION 3: Composition/information on ingredients

**3.2 Mixtures**

| Component | | Classification | Concentration |
|---|---|---|---|
| **Hydrochloric Acid** | | | |
| CAS-No.<br>EC-No.<br>Index-No.<br>Registration number | 7647-01-0<br>231-595-7<br>017-002-01-X<br>01-2119484862-27-XXXX | Met. Corr. 1; Skin Corr. 1B; Eye Dam. 1; STOT SE 3; H290, H314, H318, H335<br>Concentration limits: >= 0.1 %: Met. Corr. 1, H290; >= 25 %: Skin Corr. 1B, H314; 10 - < 25 %: Skin Irrit. 2, H315; 10 - < 25 %: Eye Irrit. 2, H319; >= 10 %: STOT SE 3, H335; | >= 30 - < 50 % |

For the full text of the H-Statements mentioned in this Section, see Section 16.




The life science business of Merck KGaA, Darmstadt, Germany
operates as MilliporeSigma in the US and Canada

## SECTION 4: First aid measures

### 4.1 Description of first-aid measures

**General advice**
First aiders need to protect themselves. Show this material safety data sheet to the doctor in attendance.

**If inhaled**
After inhalation: fresh air. Call in physician.

**In case of skin contact**
In case of skin contact: Take off immediately all contaminated clothing. Rinse skin with water/ shower. Call a physician immediately.

**In case of eye contact**
After eye contact: rinse out with plenty of water. Immediately call in ophthalmologist. Remove contact lenses.

**If swallowed**
After swallowing: make victim drink water (two glasses at most), avoid vomiting (risk of perforation). Call a physician immediately. Do not attempt to neutralise.

### 4.2 Most important symptoms and effects, both acute and delayed
The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

### 4.3 Indication of any immediate medical attention and special treatment needed
No data available

## SECTION 5: Firefighting measures

### 5.1 Extinguishing media

**Suitable extinguishing media**
Use extinguishing measures that are appropriate to local circumstances and the surrounding environment.

**Unsuitable extinguishing media**
For this substance/mixture no limitations of extinguishing agents are given.

### 5.2 Special hazards arising from the substance or mixture
Hydrogen chloride gas
Hydrogen chloride gas
Not combustible.
Ambient fire may liberate hazardous vapours.

### 5.3 Advice for firefighters
Stay in danger area only with self-contained breathing apparatus. Prevent skin contact by keeping a safe distance or by wearing suitable protective clothing.

### 5.4 Further information
Suppress (knock down) gases/vapors/mists with a water spray jet. Prevent fire extinguishing water from contaminating surface water or the ground water system.




The life science business of Merck KGaA, Darmstadt, Germany
operates as MilliporeSigma in the US and Canada

## SECTION 6: Accidental release measures

**6.1 Personal precautions, protective equipment and emergency procedures**
Advice for non-emergency personnel: Do not breathe vapors, aerosols. Avoid substance contact. Ensure adequate ventilation. Evacuate the danger area, observe emergency procedures, consult an expert.
For personal protection see section 8.

**6.2 Environmental precautions**
Do not let product enter drains.

**6.3 Methods and materials for containment and cleaning up**
Cover drains. Collect, bind, and pump off spills. Observe possible material restrictions (see sections 7 and 10). Take up with liquid-absorbent and neutralising material (e.g. Chemizorb® $H^+$, Merck Art. No. 101595). Dispose of properly. Clean up affected area.

**6.4 Reference to other sections**
For disposal see section 13.

## SECTION 7: Handling and storage

**7.1 Precautions for safe handling**
For precautions see section 2.2.

**7.2 Conditions for safe storage, including any incompatibilities**

**Storage conditions**
No metal containers.
Tightly closed.
Storage class (TRGS 510): 8B: Non-combustible, corrosive hazardous materials

**7.3 Specific end use(s)**
Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

## SECTION 8: Exposure controls/personal protection

**8.1 Control parameters**

**Ingredients with workplace control parameters**

| Component | CAS-No. | Value | Control parameters | Basis |
|---|---|---|---|---|
| Hydrochloric Acid | 7647-01-0 | C | 2 ppm | USA. ACGIH Threshold Limit Values (TLV) |
| | Remarks | Not classifiable as a human carcinogen | | |




The life science business of Merck KGaA, Darmstadt, Germany
operates as MilliporeSigma in the US and Canada

| | | | | |
|---|---|---|---|---|
| | | C | 5 ppm<br>7 mg/m3 | USA. NIOSH Recommended Exposure Limits |
| | | C | 5 ppm<br>7 mg/m3 | USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants |
| | | C | 5 ppm<br>7 mg/m3 | USA. OSHA - TABLE Z-1 Limits for Air Contaminants - 1910.1000 |
| | | PEL | 0.3 ppm<br>0.45 mg/m3 | California permissible exposure limits for chemical contaminants (Title 8, Article 107) |
| | | C | 2 ppm | California permissible exposure limits for chemical contaminants (Title 8, Article 107) |

**8.2 Exposure controls**

**Appropriate engineering controls**
Immediately change contaminated clothing. Apply preventive skin protection. Wash hands and face after working with substance.

**Personal protective equipment**

**Eye/face protection**
Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU). Tightly fitting safety goggles

**Skin protection**
This recommendation applies only to the product stated in the safety data sheet, supplied by us and for the designated use. When dissolving in or mixing with other substances and under conditions deviating from those stated in EN374 please contact the supplier of CE-approved gloves (e.g. KCL GmbH, D-36124 Eichenzell, Internet: www.kcl.de).
Full contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:KCL 741 Dermatril® L

This recommendation applies only to the product stated in the safety data sheet, supplied by us and for the designated use. When dissolving in or mixing with other substances and under conditions deviating from those stated in EN374 please contact the supplier of CE-approved gloves (e.g. KCL GmbH, D-36124 Eichenzell, Internet: www.kcl.de).
Splash contact
Material: Latex gloves
Minimum layer thickness: 0.6 mm
Break through time: 120 min
Material tested:Lapren® (KCL 706 / Aldrich Z677558, Size M)

**Body Protection**
Acid-resistant protective clothing

**Respiratory protection**
required when vapours/aerosols are generated.




The life science business of Merck KGaA, Darmstadt, Germany
operates as MilliporeSigma in the US and Canada

Our recommendations on filtering respiratory protection are based on the following standards: DIN EN 143, DIN 14387 and other accompanying standards relating to the used respiratory protection system.

**Control of environmental exposure**
Do not let product enter drains.

## SECTION 9: Physical and chemical properties

### 9.1 Information on basic physical and chemical properties

| | | |
|---|---|---|
| a) | Appearance | Form: liquid<br>Color: light yellow |
| b) | Odor | pungent |
| c) | Odor Threshold | No data available |
| d) | pH | < 1 at 20 °C (68 °F) |
| e) | Melting point/freezing point | -30 °C (-22 °F) |
| f) | Initial boiling point and boiling range | > 100 °C > 212 °F - lit. |
| g) | Flash point | ()Not applicable |
| h) | Evaporation rate | No data available |
| i) | Flammability (solid, gas) | No data available |
| j) | Upper/lower flammability or explosive limits | No data available |
| k) | Vapor pressure | 227 hPa at 21.1 °C (70.0 °F)<br>547 hPa at 37.7 °C(99.9 °F) |
| l) | Vapor density | No data available |
| m) | Relative density | No data available |
| n) | Water solubility | soluble |
| o) | Partition coefficient: n-octanol/water | No data available |
| p) | Autoignition temperature | Not applicable |
| q) | Decomposition temperature | No data available |
| r) | Viscosity | No data available |
| s) | Explosive properties | No data available |
| t) | Oxidizing properties | No data available |

### 9.2 Other safety information
No data available




The life science business of Merck KGaA, Darmstadt, Germany
operates as MilliporeSigma in the US and Canada

## SECTION 10: Stability and reactivity

**10.1 Reactivity**
No data available

**10.2 Chemical stability**
The product is chemically stable under standard ambient conditions (room temperature) .

**10.3 Possibility of hazardous reactions**
No data available

**10.4 Conditions to avoid**
no information available

**10.5 Incompatible materials**
Bases, Amines, Alkali metals, Metals, permanganates, for example potassium permanganate, Fluorine, metal acetylides, hexalithium disilicideMetals

**10.6 Hazardous decomposition products**
In the event of fire: see section 5

## SECTION 11: Toxicological information

**11.1 Information on toxicological effects**

**Mixture**

**Acute toxicity**
Symptoms: If ingested, severe burns of the mouth and throat, as well as a danger of perforation of the esophagus and the stomach.
Symptoms: mucosal irritations, Cough, Shortness of breath, Possible damages:, damage of respiratory tract
Dermal: No data available

**Skin corrosion/irritation**
Mixture causes burns.

**Serious eye damage/eye irritation**
Mixture causes serious eye damage. Risk of blindness!

**Respiratory or skin sensitization**
No data available

**Germ cell mutagenicity**
No data available

**Carcinogenicity**

IARC: No ingredient of this product present at levels greater than or equal to 0.1% is identified as probable, possible or confirmed human carcinogen by IARC.

NTP: No ingredient of this product present at levels greater than or equal to 0.1% is identified as a known or anticipated carcinogen by NTP.

OSHA: No component of this product present at levels greater than or equal to 0.1% is on OSHA's list of regulated carcinogens.

**Reproductive toxicity**
No data available

**Specific target organ toxicity - single exposure**




The life science business of Merck KGaA, Darmstadt, Germany
operates as MilliporeSigma in the US and Canada

Mixture may cause respiratory irritation.

**Specific target organ toxicity - repeated exposure**
No data available

**Aspiration hazard**
No data available

**11.2 Additional Information**

RTECS: MW4025000
Other dangerous properties can not be excluded.

Handle in accordance with good industrial hygiene and safety practice.

**Components**

**Hydrochloric Acid**

**Acute toxicity**
Oral: No data available
Inhalation: Cough Difficulty in breathing
Inhalation: absorption
Inhalation: Corrosive to respiratory system.
Symptoms: mucosal irritations, Cough, Shortness of breath, Inhalation may lead to the formation of oedemas in the respiratory tract., Possible damages:, damage of respiratory tract, tissue damage
Dermal: No data available

**Skin corrosion/irritation**
Skin - reconstructed human epidermis (RhE)
Result: Corrosive
(OECD Test Guideline 431)

**Serious eye damage/eye irritation**
Eyes - Bovine cornea
Result: Corrosive
(OECD Test Guideline 437)

**Respiratory or skin sensitization**
Maximization Test - Guinea pig
Result: negative
(OECD Test Guideline 406)

**Germ cell mutagenicity**
Test Type: Chromosome aberration test in vitro
Test system: Chinese hamster ovary cells
Result: Conflicting results have been seen in different studies.

**Carcinogenicity**
Carcinogenicity - Did not show carcinogenic effects in animal experiments. (IUCLID)

**Reproductive toxicity**
No data available

**Specific target organ toxicity - single exposure**
May cause respiratory irritation.
The substance or mixture is classified as specific target organ toxicant, single exposure, category 3 with respiratory tract irritation.




The life science business of Merck KGaA, Darmstadt, Germany
operates as MilliporeSigma in the US and Canada

Acute inhalation toxicity - mucosal irritations, Cough, Shortness of breath, Inhalation may lead to the formation of oedemas in the respiratory tract., Possible damages:, damage of respiratory tract, tissue damage

**Specific target organ toxicity - repeated exposure**
The substance or mixture is not classified as specific target organ toxicant, repeated exposure.**Aspiration hazard**
No aspiration toxicity classification

## SECTION 12: Ecological information

**12.1 Toxicity**

**Mixture**
No data available

**12.2 Persistence and degradability**
No data available

**12.3 Bioaccumulative potential**
No data available

**12.4 Mobility in soil**
No data available

**12.5 Results of PBT and vPvB assessment**
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

**12.6 Other adverse effects**
No data available

**Components**

**Hydrochloric Acid**
No data available

| | |
|---|---|
| Toxicity to fish | LC50 - Gambusia affinis (Mosquito fish) - 282 mg/l - 96 h<br>Remarks: (IUCLID) |

## SECTION 13: Disposal considerations

**13.1 Waste treatment methods**

**Product**
Waste material must be disposed of in accordance with the national and local regulations. Leave chemicals in original containers. No mixing with other waste. Handle uncleaned containers like the product itself. See www.retrologistik.com for processes regarding the return of chemicals and containers, or contact us there if you have further questions.

## SECTION 14: Transport information

**DOT (US)**
UN number: 1789 Class: 8 Packing group: II
Proper shipping name: Hydrochloric acid




The life science business of Merck KGaA, Darmstadt, Germany
operates as MilliporeSigma in the US and Canada

Reportable Quantity (RQ):
Poison Inhalation Hazard: No

**IMDG**
UN number: 1789 Class: 8 Packing group: II EMS-No: F-A, S-B
Proper shipping name: HYDROCHLORIC ACID

**IATA**
UN number: 1789 Class: 8 Packing group: II
Proper shipping name: Hydrochloric acid

## SECTION 15: Regulatory information

**SARA 302 Components**
This material does not contain any components with a section 302 EHS TPQ.

**SARA 313 Components**
The following components are subject to reporting levels established by SARA Title III, Section 313:

| | CAS-No. | Revision Date |
|---|---|---|
| Hydrochloric Acid | 7647-01-0 | 2013-02-08 |

**SARA 311/312 Hazards**
Acute Health Hazard

**Massachusetts Right To Know Components**

| | CAS-No. | Revision Date |
|---|---|---|
| Hydrochloric Acid | 7647-01-0 | 2013-02-08 |

No components are subject to the Massachusetts Right to Know Act.

**Pennsylvania Right To Know Components**

| | CAS-No. | Revision Date |
|---|---|---|
| water | 7732-18-5 | |
| Hydrochloric Acid | 7647-01-0 | 2013-02-08 |

**New Jersey Right To Know Components**

| | CAS-No. | Revision Date |
|---|---|---|
| water | 7732-18-5 | |
| Hydrochloric Acid | 7647-01-0 | 2013-02-08 |

## SECTION 16: Other information

**Further information**
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to




The life science business of Merck KGaA, Darmstadt, Germany
operates as MilliporeSigma in the US and Canada

appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Copyright 2020 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The branding on the header and/or footer of this document may temporarily not visually match the product purchased as we transition our branding. However, all of the information in the document regarding the product remains unchanged and matches the product ordered. For further information please contact mlsbranding@sial.com.



Version: 6.7 Revision Date: 06/07/2021 Print Date: 09/11/2022





The life science business of Merck KGaA, Darmstadt, Germany
operates as MilliporeSigma in the US and Canada

**SDS PT-330**

ProTreat TECHNOLOGY CORP

## Safety Data Sheet

### 1.Identification

| | | |
|---|---|---|
| **Product Identifier** | PT-330 | |
| **Other Means of Identification** | | |
| **Generic Name** | Parafin Inhibitor | |
| **Recommended Use** | Parafin Inhibitor | |
| **Recommended Restrictions** | For industrial use only | |
| **Supplier Information** | | |
| **Supplier** | | |
| **Company Name** | ProTreat Technology Corporation | |
| **Address** | P.O. Box 16640 | |
| | Golden, Colorado 80402 | |
| | USA | |
| **Telephone** | General | (303) 463-1984 |
| **Emergency Phone Number** | Medical | (303) 463-1984 |

### 2. Hazard(s) Identification

| | | |
|---|---|---|
| **Physical Hazards** | Flammable Liquids | Category 4 |
| **Health Hazards** | Carcinogen | Category 2 |
| | Acute Toxicity - Oral | Category 5 |
| | Aspiration Toxicant | Category 1 |
| | Specific Target Organ Toxicant(CNS) | Category 3 |
| | Skin Corrosion/Irritation | Category 2 |
| | Serious Eye Damage/Eye Irritant | Category 2A |
| **Environmental Hazards** | Hazardous To Aquatic Environment - Acute | Category 3 |
| **OSHA Defined Hazards** | Not Clasified | |
| **Label Elements** |  | |
| **Signal Word** | Danger | |
| **Hazard Statement** | Combustable Liquid. Suspected of causing cancer. Harmful if swallowed. May be fatal if swallowed and enters airways. May cause drowsiness or dizziness. Causes skin irritation. Causes serious eye irritation. Harmful to aquatic life. | |
| **Prevention** | Keep away from flames and hot surfaces - no smoking. Wear protective gloves/eye protection/face protection. Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Use personal protective equipment as required. Wash hands thoroughly after handling. Do not eat, drink, or smoke when using this product. Avoid breathing dust/fumes/gas,mist/vapors/spray Use only outdoors or in a well-ventilated area. Avoid release into the environment. | |

| | |
|---|---|
| **Response** | In case of fire: Use water, fog, foam, dry chemical, or carbon dioxide($CO_2$) to extinguish. IF exposed or concerned: Get medical advice/attention. IF SWALLOWED: Immediately call a poison center or doctor/physician. Rinse mouth. Do NOT Induce vomiting. IF ON SKIN: Remove/Take off immediately all contaminated clothing. Rinse skin with water/shower. Wash contaminated clothing before reuse. IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing. Immediately call a poison center or doctor/physician. Specific treatment(see section 4, *First Aid Measures).* IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if prevent and easy to do. Continue rinsing. If eye irritation persists, Get medical advice/attention |
| **Storage** | Store in a well-ventilated place. Keep container tightly closed. Keep cool. Store locked up. |
| **Disposal** | Dispose of contents/container in accordance with local/regional/national/international/ regulations. |
| **Hazard(s) not otherwise classified (HNOC)** | N/A |
| **Supplemental Information** | N/A |

## 3. Composition/Information on Ingredients

| Substances | CAS Number | Percent (w/w) | GHS Classification |
|---|---|---|---|
| Solvent Naptha (Petroleum), Heavy Aromatic | 64742-94-5 | 60-80% | Flam. Liq. 4, H227<br>Aspiration 1, H304<br>STOT SE 3, H336<br>Carcinogen 3, H351<br>Haz. to Aqua. 2 (Acute), H401<br>Haz. to Aqua. 2 (Chronic), H411 |
| Component A | N/A | 15-25% | Eye Dam. 2A, H319<br>Skin Corr. 2, H315 |

*The substance name and/or exact percentage (concentration) of the composition has been withheld as proprietary

## 4. First Aid Measures

| | |
|---|---|
| **Inhalation** | Move to fresh air. If respiratory irritation, dizziness, nausea, or unconsciousness |
| **Skin Contact** | Wash with plenty of soap and water. If skin irritation occurs: get medical attention. Take off contaminated clothing, and wash before reuse. |
| **Eye Contact** | Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. If eye irritation persists, Get medical advice/attention. |
| **Ingestion** | Rinse mouth. Immediately Call a poison center or doctor/physician. Do NOT induce vomiting. |

| | |
|---|---|
| **Most important symptoms/ effects acute and delayed.** | Symptoms may include stinging, burning, redness, swelling, and blurred vision. Permanent eye damage and blindness can result. Skin irritation may occur. Ingestion may cause headache, weakness, nausea, vomiting, decreased blood pressure, increased heart rate, pulmonary edema, kidney failure, unconsciousness, convulsions, and coma. |
| **Indication of immediate medical attention and special treatment needed** | Provide general supportive measures and treat symptomatically. Keep victim under observation. Symptoms may be delayed. |
| **General Information** | Ensure that medical personnel are aware of the material(s) involved, and take precautions to protect themselves. Show this safety data sheet(sds) to the doctor in attendance |

## 5. Fire-fighting methods

| | |
|---|---|
| **Suitable extinguishing** | Use water fog, foam, dry chemical powder, or Carbon dioxide (CO2). |
| **Unsuitable extinguishing media** | Do not use water jet as an extinguisher, as this wil spread the fire. |
| **Specific hazards arising from the chemical** | This liquid is volatile and gives off invisible vapors. Vapor may settle in low areas or travel some distance along the ground or surface to ignition sources. |
| **Special protective equipment** | Self-contained breathing apparatus and full protective clothing must be worn in case of fire. |
| **Fire Fighting equipment instructions** | Use water to cool fire exposed surfaces, and move containers from fire area if you can do so without risk |
| **Specific methods** | Use standard firefighting procedures and consider the hazards of other involved materials. |

## 6. Accidental release measures

| | |
|---|---|
| **Personal precautions, protective equipment and emergency procedures** | Keep unnecessary personnel away. Keep people away from and upwind of spill/leak. Wear appropriate protective equipment and clothing during clean-up. Do not breathe mist or vapor. Do not touch damaged containers or spilled material unless wearing appropriate protective clothing. Ensure ventilation. Local authorities should be advised if significant spillage cannot be contained. For personal protection, see section 8 of the SDS. |
| **Methods and materials for containment and cleaning up** | Large spills: Stop the flow of material, if this is without risk. Dike the spilled material, where this is possible. Cover with plastic sheet to prevent spreading. Use a non-combustible material like vermiculite, sand, or earth to soak up the product and place into a container for later disposal. Following product recovery, flush area with water.<br><br>Small Spills: Wipe up with absorbent material, or absorb with vermiculite or other inert material. Clean surface thoroughly to remove residual contamination. Never return spills to original container for re-use. For waste disposal, see section 13 of the SDS. |
| **Environmental precautions** | Prevent further leakage or spillage if safe to do so. Do not contaminate water. Avoid discharge into drains, water courses, or onto the ground. |

## 7. Handling and storage

| | |
|---|---|
| **Precautions for safe handling** | Do not breathe mist or vapor. Do not get in eyes, on skin or on clothing. Do not taste or swallow. When using, do not eat, drink or smoke. Provide adequate ventilation. Wear appropriate personal protective equipment. Wash hands thoroughly after handling. Observe good industrial hygiene practices. |
| **Conditions for safe storage, including any incompatibilities** | Store Locked up. Store in a cool dry place. Keep tightly sealed. Store away from incompatible materials (see section 10 of SDS). |

## 8. Exposure controls/personal protection

**Occupational Exposure Limits**

| U.S. - OSHA Components | Type | Value | Form |
|---|---|---|---|
| Napthalene | TWA | 52 mg/m3, 10ppm | N/A |
| Napthalene | STEL | 75 mg/m3, 15ppm | N/A |
| Trimethyl Benzene | TWA | 125 mg/m3, 25ppm | N/A |
| **ACGIH Components** | **Type** | **Value** | **Form** |
| Napthalene | TWA | 50mg/m3, 10ppm | N/A |
| Napthalene | STEL | 79mg/m3, 15ppm | N/A |
| Trimethyl Benzene | TWA | 123 mg/m3, 25ppm | |

| | |
|---|---|
| **Appropriate engineering controls** | Good general ventilation should be used. Ventilation rates should be matched to conditions. If applicable use process enclosures, local exhaust ventilation, or other engineering controls to maintain airborne levels below recommended exposure limits. If exposure limits have not been established, maintain airborne levels to an acceptable level. |

**Individual protection measures, such as personal protective equipment.**

| | |
|---|---|
| **Eye/face protection** | Wear safety glasses with side shield, or goggles. |
| **Skin protection** | |
| **Hand protection** | Wear appropriate chemical resistant gloves. |
| **Other** | Wear suitable protective clothing. |
| **Respiratory protection** | In case of inadequate ventilation, wear suitable respirtoy equipment. |
| **Thermal protection** | N/A |
| **General hygiene considerations** | Keep away from food and drink. Always observe good personal personal hygiene measures, such as washing after handling material and before eating, drinking, an/or smoking. Routinely wash work clothing and protective equipment to remove contaminants. Eye wash fountain and emergency showers are recommended. |

## 9. Physical and chemical properties

| | |
|---|---|
| **Appearance** | |
| **Physical State** | Liquid |
| **Form** | Liquid |
| **Color** | Light Amber |
| **Odor** | Aromatic odor |
| **Odor threshold** | N/A |
| **pH** | N/A |
| **Melting point/freezing point** | -40 °F (-40 °C) |
| **Initial boiling point and boiling range** | Greater than 212° |
| **Flash point** | 165 °F (62.7 °C) |
| **Evaporation rate** | N/A |
| **Upper/lower flammability or explsive limits** | |
| **Flammability limit - lower(%)** | N/A |
| **Flammability limit - upper(%)** | N/A |
| **Explosive limit - lower(%)** | 1.8% |
| **Explosive limit - upper(%)** | 11.7% |
| **Vapor pressure** | N/A |
| **Vapor density** | N/A |
| **Relative density** | N/A |
| **Solubility(ies)** | N/A |
| **Solubility (water)** | negligible |
| **Partition coefficient** | N/A |
| **(n-octanol/water)** | N/A |
| **Auto-ignition temerature** | ~830 °F (443.3 °C) |
| **Decomposition temperature** | N/A |
| **Viscosity** | N/A |
| **Other information** | N/A |
| **Flammability** | Flammable liquid |
| **Flammability class** | category 4 |
| **Pounds per gallon** | N/A |
| **Specific Gravity** | 0.94 |

## 10. Stability and reactivity

| | |
|---|---|
| **Reactivity** | The product is stable and non-reactive under normal conditions of use, storage, and transport |
| **Stability** | Material is stable under normal conditions |

| | |
|---|---|
| **Possibility of hazardous reactions** | Hazardous polymerization will not occur |
| **Conditions to avoid** | Strong oxidizing agents. Avoid storing/using near heat, sparks, or open flames |
| **Incompatible materials** | Avoid contact with strong oxidizers (eg. chlorine, peroxides, chromates, nitric acid, per-chlorates, concentrated oxygen, permanganates) which can generate heat, flames, explosions, and the release of toxic fumes. |
| **Hazardous decomposition products** | In the event of thermal decomposition, CO, NOx, and $CO_2$ may be formed. Heating in air may produce irritating aldehydes, acids, and ketones. |

## 11. Toxicological information

**Information on likely routes of exposure**

| | |
|---|---|
| **Inhalation** | Prolonged inhalation may be harmful |
| **Skin contact** | Causes skin irritation |
| **Eye contact** | Causes serious eye irritation |
| **Ingestion** | May be harmful if swallowed |
| **Symptoms related to the physical, chemical, and toxicological characteristics** | Burning pain and irritating corrosive skin damage. Causes serious eye irritation. Symptoms may include stinging, burning, redness, swelling, and blurred vision. |

**Information on toxicological effects**

| | |
|---|---|
| **Acute toxicity** | May be harmful if swallowed |
| **Skin corrosion/irritation** | Causes skin irritation |
| **Respiratory or skin sensitization** | |
| **Respiratory** | This product is not expected to cause respiratory sensitization |
| **Skin** | This product is not expected to cause skin sensitization |
| **Germ cell mutagenicity** | No data available to indicate product or any components present at greater than .1% are mutagenic or genotoxic |
| **Carcinogenicity** | Substances in this product caused cancer in laboratory animals, but the relevance to humans is uncertain. |

**OSHA Specifically Regulated Substances (29 CFR 1910.1001-1050)**

not listed

| | |
|---|---|
| **Reproductive toxicity** | This product is not expected to cause reproductive or development effects |
| **STOT - single exposure** | May cause drowsiness or dizziness |
| **STOT - repeated exposure** | Not classified |
| **Aspiration hazard** | May be fatal if swallowed and enters airways. Based on physico-chemical properties of the material |

## 12. Ecological information

| | |
|---|---|
| **Ecotoxicity** | This material is expected to be toxic to aquatic organisms. May cause long term adverse effects in the aquatic environment. |

| | |
|---|---|
| **Persistence and degradability** | No data is available on the degradability of this product |
| **Bioaccumulative potential** | No data available |
| **Mobility in soil** | No data available |
| **Other adverse effects** | No other adverse environmental effects (e.g. ozone depletion, photochemical ozone creation potential, endocrine disruption, global warming potential) are expected from this component. |

## 13. Disposal Considerations

| | |
|---|---|
| **Disposal instructions** | Collect and reclaim or dispose in sealed containers at licensed waste disposal site. Do not allow this material to drain into sewers/water supplies. Dispose of contents in accordance with local/regional/national/international regulations. |
| **Local disposal regulations** | Dispose in accordance with aa applicable regulations |
| **Hazardous waste code** | D001: ignitable waste |
| **Waste from residues/ unused products** | Dispose in accordance with local regulations. Empty containers or liners may contain some product residue. |
| **Contaminated packaging** | Empty containers should be taken to an approved waste handling site for recycling and disposal. Since empty containers may contain product residue, follow label warnings even after container is empty. |

## 14. Transport Information

**DOT**

Not regulated as dangerous goods

**IATA**

Not regulated as dangerous goods

**IMDG**

Not regulated as dangerous goods

## 15. Regulatory information

**US federal regulations** This product is a "hazardous chemical" as defined by the OSHA Hazard Communication Standard, 29 CFR 1910.1200.

**TSCA Section 12(b) Export Notification List (40 CFR 707, Subpt. d)**

Not regulated

**CERCLA hazardous substance list**

This products contains the following substance(s):

| Substance | CAS # | CERCLA RQ(lbs) |
|---|---|---|
| Napthalene | 91-20-3 | 1,400 |

**SARA 304 emergency release notification**

Not regulated

**OSHA Specifiaclly Regulated Substances (29 CFR 1910.1001-1050**

Not listed

**Superfund Amendments and Reauthorization Act of 1986 (SARA)**

**Hazard Categories** Immediate Hazard - No
Delayed Hazard - Yes
Fire Hazard - Yes
Pressure Hazard - No
Reactivity Hazard - No

**SARA 302 Extremely hazardous substance**

Not listed

**SARA 311/312 hazardous chemical**

Yes

**SARA 313 (TRI reporting)**

This product contains the following substance(s):

| Substance | CAS # | Maximum % |
|---|---|---|
| Napthalene | 91-20-3 | 7% |
| 1,2,4, Trimethylbenzene | 95-63-6 | 1% |

**Other federal regulations**

N/A

**US State regulations**

**US. California Proposition 65**

California Safe Drinking Water and Toxic Enforcement Act of 1986 (Proposition 65): This material is not know to contain any chemicals listed as carcinogens or reproductive toxins.

## 16. Other information, including date of preparation or last revision

| | |
|---|---|
| **Issue Date** | 06-01-2015 |
| **Revision Date** | 06-01-2015 |
| **Version #** | 1.0 |
| **User's Responsibility** | This product safety data sheet provides health and safety information. The product is to be used in applications consistent with our product literature. Individuals handling this product should be informed of the recommended safety precautions and should have access to this information. For any other uses, exposures should be evaluated so that appropriate handling practices and training programs can be established to ensure safe workplace operations. Please consult your local sales representative for any further information. |
| **Disclaimers** | Some of the information presented an conclusions drawn herein are from sources other than direct test data on the product itself. The information in this SDS was obtained from sources which we believe are reliable. However, the information is |

provided without any warranty, express or implied, regarding its correctness. The conditions or methods handling, storage, use and disposal of the product are beyond our control and may be beyond our knowledge. For this and other reasons, we do not assume responsibility and expressly disclaim liability for loss, damage, or expense arising out of or in any way connected with the handling, storage, use, or disposal of the product. This SDS was prepared and is to be used only for this product. If the product is used as a component in another product, this SDS may not be applicable

**SDS Iron Control (Ferriplex 40)**

SAFETY DATA SHEET

**FERRIPLEX 40**

Revision Date 06 /23/2017

## SECTION 1: Identification of the substance/mixture and of the company/undertaking

**1.1 Product identifier**

- Trade name FERRIPLEX 40

**1.2 Relevant identified uses of the substance or mixture and uses advised against**

**Uses of the Substance / Mixture**

- Chelating agent
- Oil & gas industry

**1.3 Details of the supplier of the safety data sheet**

**Company**

Chemplex
Solvay USA Inc.
NOVECARE
506 CR 137
P.O. Box 1071
Snyder, TX 79550
Phone (325) 573-7298

**1.4 Emergency telephone**

FOR EMERGENCIES INVOLVING A SPILL, LEAK, FIRE, EXPOSURE OR ACCIDENT CONTACT: CHEMTREC 800-424-9300 within the United States and Canada, or 703-527-3887 for international collect calls.

## SECTION 2: Hazards identification

Although OSHA has not adopted the environmental portion of the GHS regulations, this document may include information on environmental effects.

**2.1 Classification of the substance or mixture**

**HCS 2012 (29 CFR 1910.1200)**

| | |
|---|---|
| Eye irritation, Category 2A | H319: Causes serious eye irritation. |
| Carcinogenicity, Category 2 | H351: Suspected of causig canc er. |

**2.2 Label elements**

**HCS 2012 (29 CFR 1910.1200)**

**Pictogram**



**Signal Word**

- Warning

**Hazard Statements**

| | |
|---|---|
| - H319 | Causes serious eye irritation. |
| - H351 | Suspected of causing cancer. |

**Precautionary Statemats**

Prevention

SAFETY DATA SHEET

**FERRIPLEX 40**

Revision Date 06 /23/2017

- P201 Obtain special instructions before use.
- P202 Do not handle until all safety precautions have been read and understood.
- P264 Wash skin thoroughly after handling.
- P280 Wear protective gloves/ protective clothing/ eye protection/ face protection.

Response

- P305 + P351 + P338 IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing.
- P308 + P313 IF exposed or concerned: Get medical advice/ attention.
- P337 + P313 If eye irritation persists: Get medical advice/ attention.

Storage

- P405 Store locked up.

Disposal

- P501 Dispose of contents/ container to an approved waste disposal pl ant.

**2.3 Other hazards which do not result in classification**

None identified

## SECTION 3: Composition/information on ingredients

**3.1 Substance**

- Not applicable, this product is a mixture.

**3.2 Mixture**

**Hazardous Ingredients and Impurities**

| Chemical name | Identification number CAS-No. | Concentr ation [%] |
|---|---|---|
| Trisodium nitrilotriacetate | 5064-31-3 | >= 35 - < 45 |

The specific chemical identity and/or exact percentage (concentration) of composition has been withheld as a trade secret.

## SECTION 4: First aid measures

**4.1 Description of first-aid measures**

**General advice**

- Show this material safety data sheet to the doctor in attendance.
- First responder needs to protect himself.
- Place affected apparel in a sealed bag for subsequent decontamination.
- Plan first aid action before beginning work with this product.

**In case of inhalation**

- If breathed in, move person into fresh air.
- If breathing is difficult, give oxygen.
- If victim has stopped breathing:
- administer CPR (cardio-pulmonary resuscitation)
- Get immediate medical advice/ attention.

**In case of skin contact**

- In case of contact, immediately flush skin with plenty of water for at least 15 minutes while removing contaminated clothing and shoes.
- Seek medical advice.

- Wash contaminated clothing before re-use.

**In case of eye contact**

- Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes.
- Seek medical advice.

**In case of ingestion**

- Do not induce vomiting without medical advice.
- If victim is conscious:
- Rinse with water.
- Keep at rest.
- Do not give anything to drink.
- Do not leave the victim unattended.
- Vomiting may occur spontaneously
- Risk of product entering the lungs on vomiting after ingestion.
- Lay victim on side.
- Seek medical advice.

### 4.2 Most important symptoms and effects, both acute and delayed

**Effects**

- Skin contact may aggravate existing skin disease
- Inhalation of product may aggravate existing chronic respiratory problems such as asthma, emphysema or bronchitis

### 4.3 Indication of any immediate medical attention and special treatment needed

**Notes to physician**

- All treatments should be based on observed signs and symptoms of distress in the patient. Consideration should be given to the possibility that overexposure to materials other than this product may have occurred.

- Treat symptomatically.
- There is no specific antidote available.

## SECTION 5: Firefighting measures

| | |
|---|---|
| **Flash point** | Not applicable (aqueous liquid). |
| **Autoignition temperature** | no data available |
| **Flammability / Explosive limit** | no data available |

### 5.1 Extinguishing media

**Suitable extinguishing media**

- Extinguishing media - small fires
- Dry chemical
- Carbon dioxide (CO2)

- Extinguishing media - large fires
- Foam
- Water spray

**Unsuitable extinguishing media**

- High volume water jet

**5.2 Special hazards arising from the substance or mixture**

**Specific hazards during fire fighting**

- Under fire conditions:
- Will burn
- Container may rupture on heating.

**Hazardous combustion products:**

- On combustion or on thermal decomposition (pyrolysis), releases:
- Carbon oxides
- Nitrogen oxides (NOx)

**5.3 Advice for firefighters**

**Special protective equipment for fire-fighters**

- Firefighters should wear NIOSH/MSHA approved self-contained breathing apparatus and full protective clothing.

**Further information**

- Standard procedure for chemical fires.
- Collect contaminated fire extinguishing water separately. This must not be discharged into drains.
- Fire residues and contaminated fire extinguishing water must be disposed of in accordance with local regulations.

## SECTION 6: Accidental release measures

**6.1 Personal precautions, protective equipment and emergency procedures**

- Wear suitable protective equipment.
- Avoid contact with the skin and the eyes.
- Evacuate personnel to safe areas.
- For further information refer to section 8 "Exposure controls / personal protection."

**6.2 Environmental precautions**

- Do not flush into surface water or sanitary sewer system.
- Take all necessary measures to avoid accidental discharge of products into drains and waterways due to the rupture of containers or transfer systems.
- Spills may be reportable to the National Response Center (800-424-8802) and to state and/or local agencies

**6.3 Methods and materials for containment and cleaning up**

***Methods for containment***

- Stop the leak. Turn leaking containers leak-side up to prevent the escape of liquid.
- Dam up with sand or inert earth (do not use combustible materials).

***Recovery***

- Soak up with inert absorbent material.
- Shovel or sweep up.
- Keep in suitable, closed containers for disposal.
- Never return spills in original containers for re-use.

***Decontamination / cleaning***

- Wash nonrecoverable remainder with large amounts of water.
- Clean contaminated surface thoroughly.
- Recover the cleaning water for subsequent disposal.
- Decontaminate tools, equipment and personal protective equipment in a segregated area.

***Disposal***

- Dispose of in accordance with local regulations.

SAFETY DATA SHEET

**FERRIPLEX 40**

Revision Date 06 /23/2017

**Additional advice**

- Material can create slippery conditions.

**6.4 Reference to other sections**

- 7. HANDLING AND STORAGE
- 8. EXPOSURE CONTROLS/PERSONAL PROTECTION
- 13. DISPOSAL CONSIDERATIONS

## SECTION 7: Handling and storage

**7.1 Precautions for safe handling**

- Avoid splashes.
- Handle in accordance with good industrial hygiene and safety practice.
- Avoid inhalation of vapor or mist.
- Avoid contact with skin and eyes.
- Vapors are heavier than air and may spread along floors.

**Hygiene measures**

- Personal hygiene is an important work practice exposure control measure and the following general measures should be taken when working with or handling this materials:
- 1) Do not store, use, and/or consume foods, beverages, tobacco products, or cosmetics in areas where this material is stored.
- 2) Wash hands and face carefully before eating, drinking, using tobacco, applying cosmetics, or using the toilet.
- 3) Wash exposed skin promptly to remove accidental splashes or contact with material.

**7.2 Conditions for safe storage, including any incomptibilitie s**

**Technical measures/Storage conditions**

- Store at room temperature in the original container.
- Stable under normal conditions.
- Keep container tightly closed in a dry and well-ventilated place.
- Keep away from incompatible materials to be indicated by the manufacturer
- Keep away from open flames, hot surfaces and sources of ignition.
- Keep away from: Do not mix with incompatible materials (See list, section 10).

**Requirements for storage rooms and vessels**

**Recommended storage temperature:** < 120 °F (< 49 °C)

**7.3 Specific end use(s)**

- no data available

## SECTION 8: Exposure controls/personal protection

Introductory Remarks: These recommendations provide general guidance for handling this product. Because specific work environments and material handling practices vary, safety procedures should be developed for each intended application. Assistance with selection, use and maintenance of worker protection equipment is generally available from equipment manufacturers.

**8.1 Control parameters**

- Cotains n o substances with occupational exposure limit values.

SAFETY DATA SHEET

**FERRIPLEX 40**

Revision Date 06 /23/2017

***Hazardous components without workplace control parameters***

| Chemical name | Identification number CAS-No. | Exposure Limit Values |
|---|---|---|
| Trisodium nitrilotriacetate | 5064-31-3 | None |

**8.2 Exposure controls**

**Control measures**

**Engineering measures**

- Where engineering controls are indicated by use conditions or a potential for excessive exposure exists, the following traditional exposure control techniques may be used to effectively minimize employee exposures :
- Effective exhaust ventilation system

**Individual protection measures**

**Respiratory protection**

- When respirators are required, select NIOSH/MSHA approved equipment based on actual or potential airborne concentrations and in accordance with the appropriate regulatory standards and/or industrial recommendations.
- Use a respirator with an approved filter if a risk assessment indicates this is necessary.

**Hand protection**

- Recommended preventive skin protection
- Protective gloves
- Please observe the instructions regarding permeability and breakthrough time whib are pr ovded by the supplier of the gloves. Also take into consideration the specific local conditions under which the product is used, such as the danger of cuts, abrasion, and the contact time.
- Gloves must be inspected prior to use.

**Eye protection**

- Eye and face protection requirements will vary dependent upon work environment conditions and material handling practices. Appropriate ANSI Z87 approved equipment should be selected for the particular use intended for this material.
- Eye contact should be prevented through the use of:
- Safety glasses with side-shields

**Skin and body protection**

- Recommended preventive skin protection
- Footwear protecting against chemicals
- Impervious clothing
- Choose body protection according to the amount and concentration of the dangerous substance at the work place.

**Hygiene measures**

- Personal hygiene is an important work practice exposure control measure and the following general measures should be taken when working with or handling this materials:
- 1) Do not store, use, and/or consume foods, beverages, tobacco products, or cosmetics in areas where this material is stored.
- 2) Wash hands and face carefully before eating, drinking, using tobacco, applying cosmetics, or using the toilet.
- 3) Wash exposed skin promptly to remove accidental splashes or contact with material.

**Protective measures**

SAFETY DATA SHEET

**FERRIPLEX 40**

Revision Date 06 /23/2017

- Ensure that eyewash stations and safety showers are close to the workstation location.
- Emergency equipment immediately accessible, with instructions for use.
- The protective equipment must be selected in accordance with current local standards and in cooperation with the supplier of the protective equipment.

- Selection of appropriate personal protective equipment should be based on an evaluation of the performance characteristics of the protective equipment relative to the task(s) to be performed, conditions present, duration of use, and the potential hazards, and/or risks that may occur during use.

## SECTION 9: Physical and chemical properties

Physical and Chemical properties here represent typical properties of this product. Contact the business area using the Product information phone number in Section 1 for its exact specifications.

### 9.1 Information on basic physical and chemical properties

| | | |
|---|---|---|
| **Appearance** | Physical state:<br>Color: | liquid<br>colorless to pale yellow. |
| **Odor** | slight ammonia | |
| **Odor Threshold** | no data available | |
| **pH** | 10.0 ( 10 g/l) | |
| **Melting point/freezing point** | no data available | |
| **Initial boiling point and boiling range** | > Boiling point/boiling range: 212F (100 ° C) | |
| **Flash point** | Not applicable (aqueous liquid). | |
| **Evaporation rate (Butylacetate = 1)** | no data available | |
| **Flammability (solid, gas)** | no data available | |
| **Flammability (liquids)** | no data available | |
| **Flammability / Explosive limit** | no data available | |
| **Autoignition temperature** | no data available | |
| **Vapor pressure** | no data available | |
| **Vapor density** | no data available | |
| **Density** | 1.3 g/cm3 | |
| **Relative density** | 1.3 | |
| **Solubility** | Water solubility:<br>completely soluble | |
| **Partition coefficient: n-octanol/water** | no data available | |
| **Decomposition temperature** | no data available | |

SAFETY DATA SHEET

**FERRIPLEX 40**

Revision Date 06 /23/2017

| | |
|---|---|
| **Viscosity** | no data available |
| **Explosive properties** | no data available |
| **Oxidizing properties** | no data available |

**9.2 Other information**

no data available

## SECTION 10: Stability and reactivity

**10.1 Reactivity**

- no data available

**10.2 Chemical stability**

- Stable under normal conditions.

**10.3 Possibility of hazardous reactions**

**polymerization**
- Hazardous polymerization does not occur.

**10.4 Conditions to avoid**

- Keep away from heat and sources of ignition.
- Avoid excessive heat for prolonged periods of time.

**10.5 Incompatible ma terials**

- Strong oxidizing agents
- Strong acids

**10.6 Hazardous decomposition products**

- On combustion or on thermal decomposition (following the evaporation of water) releases:
- (Carbon oxides (CO + CO2)).
- Nitrogen oxides (NOx)

## SECTION 11: Toxicological information

**11.1 Information on toxicological effects**

**Acute toxicity**

| | |
|---|---|
| **Acute oral toxicity** | Not classified as hazardous for acute oral toxicity according to GHS.<br>According to the available data on the components<br>According to the classification criteria for mixtures. |
| **Acute inhalation toxicity** | Not classified as hazardous for acute inhalation toxicity according to GHS.<br>According to the available data on the components<br>According to the classification criteria for mixtures. |
| **Acute dermal toxicity** | Not classified as hazardous for acute dermal toxicity according to GHS.<br>According to the available data on the components<br>According to the classification criteria for mixtures. |
| **Acute toxicity (other routes of administration)** | no data available |

SAFETY DATA SHEET

**FERRIPLEX 40**

Revision Date 06 /23/2017

**Skin corrosion/irritation**

Not classified as irritating to skin
According to the available data on the components
According to the classification criteria for mixtures.

**Serious eye damage/eye irritation**

Irritating to eyes.
According to the available data on the components
According to the classification criteria for mixtures.

**Respiratory or skin sensitization**

Does not cause skin sensitization.
According to the available data on the components
According to the classification criteria for mixtures.

**Mutagenicity**

**Genotoxicity in vitro**

According to the available data on the components
Product is not considered to be genotoxic
According to the classification criteria for mixtures.

**Genotoxicity in vivo**

According to the available data on the components
Product is not considered to be genotoxic
According to the classification criteria for mixtures.

**Carcinogenicity**

Trisodium nitrilotriacetate

Rat , male and female
Oral
Exposure duration: 2 y
Method: OECD Test Guideline 451
Animal studies have shown tumor promotion effects
Published data

Mouse , male
Oral
Exposure duration: 2 y
Method: OECD Test Guideline 451
Animal studies have shown tumor promotion effects
Published data

| Ingredients | CAS-No. | Rating | Basis |
|---|---|---|---|
| Trisodium nitrilotriacetate | 5064-31-3 | Group 2B: Possibly carcinogenic to humans | IARC |

This product does not contain any ingredient designated as probable or suspected human carcinogens by:
NTP
OSHA
ACGIH

SAFETY DATA SHEET

**FERRIPLEX 40**

Revision Date 06 /23/2017

**Toxicity for reproduction and development**

| | |
|---|---|
| **Toxicity to reproduction / fertility** | According to the available data on the components, The product is not considered to affect fertility., According to the classification criteria for mixtures. |
| **Developmental Toxicity/Teratogenicity** | According to the available data on the components, The product is not considered to be toxic for development., The product is not considered to be teratogenic., According to the classification criteria for mixtures. |

**STOT**

| | |
|---|---|
| **STOT-single exposure** | The substance or mixture is not classified as specific target organ toxicant, single exposure according to GHS criteria. According to the classification criteria for mixtures. |
| **STOT-repeated exposure** | The substance or mixture is not classified as specific target organ toxicant, repeated exposure according to GHS criteria. According to the classification criteria for mixtures. |

**CMR effects**

| | |
|---|---|
| **Carcinogenicity** | |
| Trisodium nitrilotriacetate | Limited evidence of carcinogenicity in animal studies |
| **Aspiration toxicity** | no data available |

## SECTION 12: Ecological information

**12.1 Toxicity**

**Aquatic Compartment**

| | |
|---|---|
| **Acute toxicity to fish** | The product itself has not been tested. |
| **Acute toxicity to daphnia and other aquatic invertebrates.** | The product itself has not been tested. |
| **Toxicity to aquatic plants** | The product itself has not been tested. |
| **Toxicity to microorganisms** | The product itself has not been tested. |
| **Chronic toxicity to fish** | The product itself has not been tested. |
| **Chronic toxicity to daphnia and other aquatic invertebrates.** | The product itself has not been tested. |
| **Chronic Toxicity to aquatic plants** | The product itself has not been tested. |

SAFETY DATA SHEET

**FERRIPLEX 40**

Revision Date 06 /23/2017

**12.2 Persistence and degradability**

| | |
|---|---|
| **Abiotic degradation** | no data available |
| **Physical- and photo-chemical elimination** | no data available |

**Biodegradation**

**Biodegradability**
Trisodium nitrilotriacetate

Ready biodegradability study:
Method: OECD Test Guideline 301
100 % - 14 Days
The substance fulfills the criteria for ultimate aerobic biodegradability and ready biodegradability
Dissolved organic carbon (DOC)
Conc. in standard unit mg / l: 70 mg/l
Unpublished reports

**Degradability assessment**
Trisodium nitrilotriacetate

The product is considered to be rapidly degradable in the environment

**12.3 Bioaccumulative potential**

| | |
|---|---|
| **Partition coefficient: n-octanol/water** | no data available |

**Bioconcentration factor (BCF)**
Trisodium nitrilotriacetate

Species: Danio rerio (zebra fish)
Bioconcentration factor (BCF): 1 - 3
Exposure time: 96 h
Published data
Not potentially bioaccumulable

**12.4 Mobility in soil**

| | |
|---|---|
| **Adsorption potential (Koc)** | no data available |
| **Known distribution to environmental compartments** | no data available |

**12.5 Results of PBT and vPvB assessment** no data available

**12.6 Other adverse effects**

**Ecotoxicity assessment**

| | |
|---|---|
| **Acute aquatic toxicity** | According to the available data on the components<br>The product does not have any known adverse effects on the aquatic organisms tested<br>According to the classification criteria for mixtures. |
| **Chronic aquatic toxicity** | According to the available data on the components<br>Does not have any known long term adverse effects on the aquatic organisms tested<br>According to the classification criteria for mixtures. |

## SECTION 13: Disposal considerations

**13.1 Waste treatment methods**

**Product Disposal**

- Chemical additions, processing or otherwise altering this material may make the waste management information presented in this SDS incomplete, inaccurate or otherwise inappropriate. Please be advised that state and local requirements for waste disposal may be more restrictive or otherwise different from federal laws and regulations. Consult state and local regulations regarding the proper disposal of this material.

**Waste Code**

- Environmental Protection Agency
- Hazardous Waste – NO

## SECTION 14: Transport information

**DOT**
not regulated

**TDG**
not regulated

**NOM**
not regulated

**IMDG**
not regulated

**IATA**
not regulated

Note: The above regulatory prescriptions are those valid on the date of publication of this sheet. Given the possible evolution of transportation regulations for hazardous materials, it would be advisable to check their validity with your sales office.

SAFETY DATA SHEET

**FERRIPLEX 40**

Revision Date 06 /23/2017

## SECTION 15: Regulatory information

**15.1 Notification status**

| Inventory Information | Status |
|---|---|
| United States TSCA Inventory | - Listed on Inventory |
| Canadian Domestic Substances List (DSL) | - Listed on Inventory |
| Australia Inventory of Chemical Substances (AICS) | - Listed on Inventory |
| Japan. CSCL - Inventory of Existing and New Chemical Substances | - Listed on Inventory |
| Korea. Korean Existing Chemicals Inventory (KECI) | - Listed on Inventory |
| China. Inventory of Existing Chemical Substances in China (IECSC) | - Listed on Inventory |
| Philippines Inventory of Chemicals and Chemical Substances (PICCS) | - Listed on Inventory |

**15.2 Federal Regulations**

**US. EPA EPCRA SARA Title III**

**SARA HAZARD DESIGNATION SECTIONS 311/312 (40 CFR 370)**

| | |
|---|---|
| Fire Hazard | no |
| Reactivity Hazard | no |
| Sudden Release of Pressure Hazard | no |
| Acute Health Hazard | yes |
| Chronic Health Hazard | yes |

**Section 313 Toxic Chemicals (40 CFR 372.65)**
This material does not contain any chemical components with known CAS numbers that exceed the threshold (De Minimis) reporting levels established by SARA Title III, Section 313.

**Section 302 Emergency Planning Extremely Hazardous Substance Threshold Planning Quantity (40 CFR 355)**
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

**Section 302 Emergency Planning Extremely Hazardous Substance Reportable Quantity (40 CFR 355)**
This material does not contain any components with a SARA 302 RQ.

**Section 304 Emergency Release Notification Reportable Quantity (40 CFR 355)**
This material does not contain any components with a section 304 EHS RQ.

**US. EPA CERCLA Hazardous Substances and Reportable Quantities (40 CFR 302.4)**

This material does not contain any components with a CERCLA RQ.

**15.3 State Regulations**

**US. California Safe Drinking Water & Toxic Enforcement Act (Proposition 65)**

This product does not contain any chemicals known to the State of California to cause cancer, birth, or any other reproductive defects.

## SECTION 16: Other information

**NFPA (National Fire Protection Association) - Classification**

| | |
|---|---|
| Health | 2 moderate |
| Flammability | 0 minimal |
| Instability or Reactivity | 0 minimal |

SAFETY DATA SHEET

**FERRIPLEX 40**

Revision Date 06 /23/2017

**HMIS (Hazardous Materials Identification System (Paint & Coating)) - Classification**

| | |
|---|---|
| Health | 2 moderate |
| Flammability | 0 minimal |
| Reactivity | 0 minimal |
| PPE | Determined by User; dependent on local conditions |

**Date Prepared:** 06/23/2017

- ACGIH — American Conference of Governmental Industrial Hygienists
- OSHA — Occupational Safety and Health Administration
- NTP — National Toxicology Program
- IARC — International Agency for Research on Cancer
- NIOSH — National Institute for Occupational Safety and Health

The information provided in this Safety Data Sheet is correct to the best of our knowledge, information, and belief at the date of its publication. Such information is only given as a guidance to help the user handle, use, process, store, transport, dispose, and release the product in satisfactory safety conditions and is not to be considered as a warranty or quality specification. It should be used in conjunction with technical sheets but do not replace them. Thus, the information only relates to the designated specific product and may not be applicable if such product is used in combination with other materials or in any other manufacturing process, unless otherwise specifically indicated. It does not release the user from ensuring he is in conformity with all regulations linked to its activity.

**Non-Emulsifier (PlexBreak 145)**

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

According to the available data on the components.
According to the classification criteria for mixtures.
Unpublished reports and/or published data.

**Genotoxicity in vivo**

Product is not considered to be genotoxic

According to the available data on the components.
According to the classification criteria for mixtures.
Unpublished reports and/or published data.

**Carcinogenicity**

The product is not considered to be carcinogenic.

According to the available data on the components.
According to the classification criteria for mixtures.
Unpublished reports and/or published data.

| Components | CAS-No. | Rating | Basis |
|---|---|---|---|
| Coconut Fatty Acid Diethanolamide | 68603-42-9 | Group 2B: Possibly carcinogenic to humans | IARC |
| Diethanolamine | 111-42-2 | Group 2B: Possibly carcinogenic to humans | IARC |

This product does not contain any ingredient designated as probable or suspected human carcinogens by:
NTP
OSHA

**Toxicity for reproduction and development**

**Toxicity to reproduction / fertility**

2-butoxyethanol

Two-generation study - Mouse, male and female, Oral
General Toxicity Parent NOAEL: 720 mg/kg
Fertility NOAEL Parent: 720 mg/kg
according to a standardized method

Methanol

Fertility study 2 generations - Rat, male and female, Inhalation
General Toxicity Parent NOAEL: 1.3 mg/l
General Toxicity F1 NOAEL: 0.13 mg/l
General Toxicity F2 NOAEL: 0.13 mg/l
OECD Test Guideline 416
Published data

Fertility study 1 generation - Monkey, female, Inhalation
General Toxicity Parent NOAEL: 2.39 mg/l
Published data

Coconut Fatty Acid Diethanolamide

No effect observed in male or female reproductive system in repeated dose tox studies ., Information given is based on data obtained from similar substances., Unpublished reports

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

| | |
|---|---|
| Fatty acids, tall-oil, compds. with diethanolamine | By analogy<br><br>Reproduction / developmental toxicity screening test - Rat, male and female, Oral<br>OECD Test Guideline 422<br>no impairment of fertility has been observed, Gavage, Unpublished reports |
| Diethanolamine | Extended One-Generation Reproductive Toxicity Study - Rat, male and female, Oral<br>General Toxicity Parent NOAEL: 100 ppm<br>Fertility NOAEL Parent: 300 ppm<br>OECD Test Guideline 443<br><br>Fertility NOAEL F1: 300 ppm<br>drinking water, Effects on fertility, Unpublished reports |
| **Developmental Toxicity/Teratogenicity** | |
| 2-butoxyethanol | Rat, female, Oral<br>General Toxicity Maternal NOAEL: 30 mg/kg<br>Teratogenicity NOAEL:100mg/kg<br>Method: OECD Test Guideline 414<br>Gavage |
| Methanol | Rat, Oral<br>General Toxicity Maternal NOAEL: 2,054 mg/kg bw/day<br>Method: OECD Test Guideline 414<br>Developmental toxicity was observed in the presence of maternal toxicity.,<br>Published data |

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

| | |
|---|---|
| | Rat, Oral<br>General Toxicity Maternal LOAEL: 1,027 mg/kg bw/day<br>Teratogenicity LOAEL:1,027mg/kg bw/day<br>Developmental toxicity was observed in the presence of maternal toxicity.,<br>Published data<br><br>Mouse, male and female, Inhalation<br>General Toxicity Maternal NOAEL: 19.94 mg/l<br>Teratogenicity NOAEL:1.33mg/l<br>Method: OECD Test Guideline 414<br>Vapor, Published data<br><br>Rat, Inhalation<br>General Toxicity Maternal NOAEL: > 1.33 mg/l<br>Teratogenicity NOAEL:> 1.33mg/l<br>Method: OECD Test Guideline 414<br>Vapor, Developmental toxicity was observed in the presence of maternal toxicity.,<br>Published data<br><br>Rat, Inhalation<br>General Toxicity Maternal LOAEL: 6.65 mg/l<br>Teratogenicity LOAEL:6.65mg/l<br>Method: OECD Test Guideline 414<br>Developmental toxicity was observed in the presence of maternal toxicity.,<br>Published data |
| Coconut Fatty Acid Diethanolamide | Rat, male and female<br>General Toxicity Maternal NOAEL: >= 1,000 mg / kg / day<br>Teratogenicity NOAEL:>= 1,000mg / kg / day<br>Method: OECD Test Guideline 414<br>Gavage, Information given is based on data obtained from similar substances., no embryotoxic or teratogenic effects have been observed |
| Fatty acids, tall-oil, compds. with diethanolamine | By analogy<br><br>Reproduction / developmental toxicity screening test - Rat, male and female, Oral<br>Method: OECD Test Guideline 422<br>No effect observed on development, Gavage, Unpublished reports |
| Diethanolamine | Rabbit, male and female, Dermal<br>General Toxicity Maternal NOAEL: 35 mg/kg bw/day<br>Teratogenicity NOAEL:> 350mg/kg bw/day<br>Method: OECD Test Guideline 414<br>no embryotoxic or teratogenic effects have been observed, Published data, Unpublished reports |

Rat, male and female, Inhalation
General Toxicity Maternal NOAEL: 0.05 mg/l
Teratogenicity NOAEL:>= 0.2mg/l
Method: OECD Test Guideline 414
no embryotoxic or teratogenic effects have been observed. Unpublished reports

Rat, male and female, Oral
General Toxicity Maternal NOAEL: 50 mg/kg bw/day
Teratogenicity NOAEL:50mg/kg bw/day
Gavage, Effects on the progeny are not considered significant as they were observed only in doses leading to maternal toxicity, Published data, Unpublished reports

Rat, male and female, Oral
General Toxicity Maternal NOAEL: 100 ppm
Developmental Toxicity NOAEL F1: 100 ppm
Method: OECD Test Guideline 443
drinking water, Effects on development were observed, Unpublished reports

**STOT**

**STOT-single exposure**

Target Organs: Central nervous system, optic nerve

The substance or mixture is classified as specific target organ toxicant, single exposure, category 1 according to GHS criteria.

According to the available data on the components.
According to the classification criteria for mixtures.
Unpublished reports and/or published data.

**STOT-repeated exposure**

The substance or mixture is classified as specific target organ toxicant, repeated exposure, category 2 according to GHS criteria.

According to the available data on the components.
According to the classification criteria for mixtures.
Unpublished reports and/or published data.

2-butoxyethanol

Inhalation Chronic - Rat , male and female
NOAEC: < 31 ppm
Target Organs: Liver
Method: OECD Test Guideline 453

Methanol

Inhalation (vapor) 28-day - Rat , male and female
NOAEC: 6.66 mg/l
Method: OECD Test Guideline 412
No adverse effect has been observed in toxicity tests by repeated administration
Published data

Coconut Fatty Acid Diethanolamide

Oral 28 Days - Rat , male and female
NOAEL: > 750 mg/kg bw/day
Method: OECD Test Guideline 407
No adverse effect has been observed in chronic toxicity tests.
Information given is based on data obtained from similar substances.
Unpublished reports

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

| | |
|---|---|
| | Dermal 90 Days - Rat , male and female<br>NOAEL: 50 mg/kg<br>Method: OECD Test Guideline 407<br>Not considered to cause serious damage to health on repeated exposure<br>Unpublished reports<br><br>Dermal two-year - Rat , male and female<br>NOAEL: 50 mg/kg bw/day<br>Not considered to cause serious damage to health on repeated exposure<br>Unpublished reports |
| Fatty acids, tall-oil, compds. with diethanolamine | category approach<br><br>Oral Subchronic exposure - Rat<br>Target Organs: Kidney, Blood<br>According to the available data on the constituents<br>Expert judgment<br>Unpublished reports |
| Diethanolamine | Oral 13 weeks - Rat |

, female
LOAEL: 14 mg/kg bw/day

LOAEL: 25 mg/kg bw/day

Target Organs: Blood, Kidney
drinking water
Published data
Unpublished reports
Repeated or prolonged exposure to high levels may affect the liver and kidneys.

Oral 13 weeks - Mouse

, male
LOAEL: 104 mg/kg bw/day

LOAEL: 142 mg/kg bw/day

Target Organs: Liver
Method: OECD Test Guideline 408
drinking water
Liver toxicity
Published data
Unpublished reports

Inhalation (aerosol) 90-day - Rat , male and female
NOAEC: 15 mg/m³
Method: OECD Test Guideline 413
Published data
Unpublished reports
Respiratory irritation

Dermal 13 weeks - Rat , male and female
LOAEL: 32 mg/kg bw/day
Method: OECD Test Guideline 411
Published data
Unpublished reports
Hemotoxic effects
Renal toxicity effects.

Dermal 13 weeks - Mouse , male and female
LOAEL: 80 mg/kg bw/day
Method: OECD Test Guideline 411
Published data
Unpublished reports
Repeated or prolonged exposure to high levels may affect the liver and kidneys.

**Experience with human exposure**

**Experience with human exposure : Inhalation**

| | |
|---|---|
| Methanol | Target Organs: Central nervous system |

Target Organs: optic nerve
Symptoms: Inhalation may provoke the following symptoms:
Dizziness
Nausea
acidosis
Blurred vision
Impairment of vision
Published data

**Experience with human exposure : Ingestion**

| | |
|---|---|
| Methanol | Target Organs: Central nervous system |
| | Target Organs: optic nerve<br>Symptoms: Ingestion may provoke the following symptoms:<br>Dizziness<br>Nausea<br>acidosis<br>Abdominal pain<br>Vomiting<br>Central nervous system depression<br>Headache<br>Breathing difficulties<br>Impairment of vision<br>Blurred vision<br>Coma<br>Death<br>May cause respiratory arrest.<br>Poison, may be fatal or cause blindness if swallowed. |

**CMR effects**

**Carcinogenicity**

| | |
|---|---|
| Diethanolamine | Not classified as a carcinogen according to GHS criteria: the mechanism or mode of action of tumour formation is considered not relevant for humans. |

**Mutagenicity**

| | |
|---|---|
| Fatty acids, tall-oil, compds. with diethanolamine | Not classified as mutagen according to GHS criteria. |
| Diethanolamine | The product is considered to be non-mutagenic based on an overall assessment of the data from animal and/or in vitro testing. |

**Teratogenicity**

| | |
|---|---|
| Fatty acids, tall-oil, compds. with diethanolamine | Not classified as toxic for the reproduction (development) according to GHS criteria |
| Diethanolamine | Classified as toxic for the reproduction in Category 2 (development) according to GHS criteria |

**Reproductive toxicity**

| | |
|---|---|
| Fatty acids, tall-oil, compds. with diethanolamine | Not classified as toxic for the reproduction (fertility and/or development) according to GHS criteria |
| Diethanolamine | Classified as toxic for the reproduction in Category 2 (fertility) according to GHS criteria |

| | |
|---|---|
| **Aspiration toxicity** | Not classified for aspiration toxicity according to GHS criteria |

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

According to the available data on the components, According to the classification criteria for mixtures., internal evaluation

## SECTION 12: Ecological information

### 12.1 Toxicity

**Aquatic Compartment**

| | |
|---|---|
| **Acute toxicity to fish** | The product itself has not been tested. Global ecotoxicity assessment available below. |
| **Acute toxicity to daphnia and other aquatic invertebrates** | The product itself has not been tested. Global ecotoxicity assessment available below. |
| **Toxicity to aquatic plants** | The product itself has not been tested. Global ecotoxicity assessment available below. |
| **Toxicity to microorganisms** | The product itself has not been tested. |
| **Chronic toxicity to fish** | The product itself has not been tested. Global ecotoxicity assessment available below. |
| **Chronic toxicity to daphnia and other aquatic invertebrates** | The product itself has not been tested. Global ecotoxicity assessment available below. |

**Sediment compartment**

| | |
|---|---|
| **Toxicity to benthic organisms** | The product itself has not been tested. |

**Terrestrial Compartment**

| | |
|---|---|
| **Toxicity to soil dwelling organisms** | The product itself has not been tested. |
| **Toxicity to terrestrial plants** | The product itself has not been tested. |
| **Toxicity to above ground organisms** | The product itself has not been tested. |

### 12.2 Persistence and degradability

**Abiotic degradation**

| | |
|---|---|
| **Stability in water** | Conclusion is not possible for a mixture as a whole. |
| **Photodegradation** | Conclusion is not possible for a mixture as a whole. |

**Physical- and photo-chemical elimination**

| | |
|---|---|
| **Physico-chemical removability** | Conclusion is not possible for a mixture as a whole. |

**Biodegradation**

| | |
|---|---|
| **Biodegradability** | As (bio)degradability is not relevant for mixtures, all the components of the mixture were assessed individually (rapid degradability assessment available below). |
| **Degradability assessment** | All or most of the components are considered to be rapidly degradable in the environment |

**12.3 Bioaccumulative potential**

**Partition coefficient: n-octanol/water**

| | |
|---|---|
| 2-butoxyethanol | Due to the distribution coefficient n-octanol/water, accumulation in organisms is not expected. |
| Methanol | Due to the distribution coefficient n-octanol/water, accumulation in organisms is not expected. |
| Diethanolamine | Due to the distribution coefficient n-octanol/water, accumulation in organisms is not expected. |
| **Bioconcentration factor (BCF)** | None of the components are considered to be potentially bioaccumulable |

**12.4 Mobility in soil**

| | |
|---|---|
| **Adsorption potential (Koc)** | Conclusion is not possible for a mixture as a whole. |

**Known distribution to environmental compartments**

| | |
|---|---|
| Methanol | Ultimate destination of the product: Air |
| | Water |
| Coconut Fatty Acid Diethanolamide | Ultimate destination of the product: Soil |
| | Water |
| | Predicted distribution to environmental compartments<br>Unpublished reports |

| | |
|---|---|
| **12.5 Results of PBT and vPvB assessment** | This mixture contains no substance considered to be persistent, bioaccumulating and toxic (PBT).<br>This mixture contains no substance considered to be very persistent and very bioaccumulating (vPvB). |

**12.6 Other adverse effects**

**Ecotoxicity assessment**

| | |
|---|---|
| **Short-term (acute) aquatic hazard** | Harmful to aquatic life.<br>According to the available data on the components.<br>According to the classification criteria for mixtures.<br>Unpublished reports and/or published data. |
| **Long-term (chronic) aquatic hazard** | Harmful to aquatic life with long lasting effects.<br>According to the available data on the components.<br>According to the classification criteria for mixtures.<br>Unpublished reports and/or published data. |

## SECTION 13: Disposal considerations

**13.1 Waste treatment methods**

**Product Disposal**

***Prohibition***

- Do not discharge directly into the environment.
- Do not dispose of with domestic refuse.

- Dispose of as hazardous waste in compliance with local and national regulations.

- Chemical additions, processing or otherwise altering this material may make the waste management information presented in this SDS incomplete, inaccurate or otherwise inappropriate. Please be advised that state and local requirements for waste disposal may be more restrictive or otherwise different from federal laws and regulations. Consult state and local regulations regarding the proper disposal of this material.

**Waste Code**

- Environmental Protection Agency
- Hazardous Waste – YES

- RCRA Hazardous Waste (40 CFR 302)
- D001 - Ignitable waste – (I)

**Advice on cleaning and disposal of packaging**

***Prohibition***
- Do NOT dispose of untreated packaging with industrial waste.
- Do not dispose of with domestic refuse.

- Empty remaining contents.

- Clean using steam.
- Monitor the residual vapors.
- Dispose of rinse water in accordance with local and national regulations.

- Containers that cannot be cleaned must be treated as waste.

- Dispose of contents/ container to an approved waste disposal plant.
- Dispose of in accordance with local regulations.

- In accordance with IMDG regulations containers or tankers that have not been cleaned or deodorized and that previously contained a hazardous product, must either be labeled or have hazard signs.

- Where possible recycling is preferred to disposal or incineration.
- The recycled material must be completely dry and free of pollutants.

## SECTION 14: Transport information

Transportation status: IMPORTANT! Statements below provide additional data on listed transport classification.
The listed Transportation Classification does not address regulatory variations due to changes in package size, mode of shipment or other regulatory descriptors.

**DOT**

| | |
|---|---|
| **14.1 UN number** | UN 1992 |
| **14.2 Proper shipping name** | FLAMMABLE LIQUIDS, TOXIC, N.O.S. (Methanol, 2-Butoxyethanol) |
| **14.3 Transport hazard class** | 3 |
| Subsidiary hazard class | 6.1 |
| Label(s) | 3 (6.1) |
| **14.4 Packing group** | |
| Packing group | III |
| ERG No | 131 |

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

| | |
|---|---|
| **14.5 Environmental hazards**<br>**Marine pollutant** | NO |

**TDG**

| | |
|---|---|
| **14.1 UN number** | UN 1992 |
| **14.2 Proper shipping name** | FLAMMABLE LIQUID, TOXIC, N.O.S. (Methanol, 2-Butoxyethanol) |
| **14.3 Transport hazard class**<br>Subsidiary hazard class<br>Label(s) | 3<br>6.1<br>3 (6.1) |
| **14.4 Packing group**<br>Packing group<br>ERG No | III<br>131 |
| **14.5 Environmental hazards**<br>**Marine pollutant** | NO |

**NOM**

| | |
|---|---|
| **14.1 UN number** | UN 1992 |
| **14.2 Proper shipping name** | FLAMMABLE LIQUID, TOXIC, N.O.S. (Methanol, 2-Butoxyethanol) |
| **14.3 Transport hazard class**<br>Subsidiary hazard class<br>Label(s) | 3<br>6.1<br>3 (6.1) |
| **14.4 Packing group**<br>Packing group<br>ERG No | III<br>131 |
| **14.5 Environmental hazards**<br>**Marine pollutant** | NO |

**IMDG**

| | |
|---|---|
| **14.1 UN number** | UN 1992 |
| **14.2 Proper shipping name**<br>IMDG Code segregation group | FLAMMABLE LIQUID, TOXIC, N.O.S. (Methanol, 2-Butoxyethanol)<br>Not Relevant |
| **14.3 Transport hazard class**<br>Subsidiary hazard class<br>Label(s) | 3<br>6.1<br>3 (6.1) |
| **14.4 Packing group**<br>Packing group | III |

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

**14.5 Environmental hazards** NO
**Marine pollutant**

**14.6 Special precautions for user**
EmS F-E , S-D

For personal protection see section 8.

**14.7 Transport in bulk vessels according to IMO instruments**
No data available

**IATA**

**14.1 UN number** UN 1992

**14.2 Proper shipping name** FLAMMABLE LIQUID, TOXIC, N.O.S. (Methanol, 2-Butoxyethanol)

**14.3 Transport hazard class** 3
Subsidiary hazard class: 6.1
Label(s): 3 (6.1)

**14.4 Packing group**
Packing group III

Packing instruction (cargo aircraft) 366
Max net qty / pkg 220.00 L
Packing instruction (passenger aircraft) 355
Max net qty / pkg 60.00 L

**14.5 Environmental hazards** NO

**14.6 Special precautions for user**
For personal protection see section 8.

Note: The above regulatory prescriptions are those valid on the date of publication of this sheet. Given the possible evolution of transportation regulations for hazardous materials, it would be advisable to check their validity with your sales office.

## SECTION 15: Regulatory information

**15.1 Notification status**

| Inventory Information | Status |
|---|---|
| United States TSCA Inventory | - All substances listed as active on the TSCA inventory |
| Canadian Domestic Substances List (DSL) | - Listed on Inventory |
| Australia Inventory of Chemical Substances (AICS) | - Listed on Inventory |
| Japan. CSCL - Inventory of Existing and New Chemical Substances | - Listed on Inventory |
| Korea. Korean Existing Chemicals Inventory (KECI) | - Listed on Inventory |
| China. Inventory of Existing Chemical Substances in China (IECSC) | - Listed on Inventory |

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

| | |
|---|---|
| Philippines Inventory of Chemicals and Chemical Substances (PICCS) | - Listed on Inventory |
| Taiwan Chemical Substance Inventory (TCSI) | - Listed on Inventory |
| New Zealand. Inventory of Chemical Substances | - All components are listed on the NZIOC inventory. The HSNO status of the product has not been assessed. |
| EU. European Registration, Evaluation, Authorisation and Restriction of Chemical (REACH) | - When purchased from a Solvay legal entity based in the EEA ("European Economic Area"), this product is compliant with the registration provisions of the REACH Regulation (EC) No. 1907/2006 as all its components are either excluded, exempt, and/or registered. When purchased from a legal entity outside of the EEA, please contact your local representative for additional information. |

**15.2 Federal Regulations**

**US. EPA EPCRA SARA Title III**

**SARA HAZARD DESIGNATION SECTIONS 311/312 (40 CFR 370)**

| | |
|---|---|
| Flammable (gases, aerosols, liquids, or solids) | Yes |
| Acute toxicity (any route of exposure) | Yes |
| Skin corrosion or irritation | Yes |
| Serious eye damage or eye irritation | Yes |
| Reproductive toxicity | Yes |
| Specific target organ toxicity (single or repeated exposure) | Yes |

**The categories not mentioned are not relevant for the product.**

**Section 313 Toxic Chemicals (40 CFR 372.65)**
The following components are subject to reporting levels established by SARA Title III, Section 313:

| Components | CAS-No. | Concentration |
|---|---|---|
| 2-butoxyethanol | 111-76-2 | 10- 15% |
| Methanol | 67-56-1 | 10- 15% |
| Diethanolamine | 111-42-2 | 1- 5% |

**Section 302 Emergency Planning Extremely Hazardous Substance Threshold Planning Quantity (40 CFR 355)**
This material does not contain any components with a section 302 EHS TPQ.

**Section 302 Emergency Planning Extremely Hazardous Substance Reportable Quantity (40 CFR 355)**
This material does not contain any components with a SARA 302 RQ.

**Section 304 Emergency Release Notification Reportable Quantity (40 CFR 355)**
This material does not contain any components with a section 304 EHS RQ.

**US. EPA CERCLA Hazardous Substances and Reportable Quantities (40 CFR 302.4)**

| Components | CAS-No. | Reportable quantity |
|---|---|---|
| Diethanolamine | 111-42-2 | 100 lb |

Calculated RQ exceeds reasonably attainable upper limit.

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

**15.3 State Regulations**

**US. California Safe Drinking Water & Toxic Enforcement Act (Proposition 65)**

This product can expose you to chemicals including Coconut Fatty Acid Diethanolamide (CAS # 68603-42-9), Diethanolamine (CAS # 111-42-2) , which is/are known to the State of California to cause cancer, and
This product can expose you to chemicals including Methanol (CAS # 67-56-1) , which is/are known to the State of California to cause birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov.

## SECTION 16: Other information

**NFPA (National Fire Protection Association) - Classification**

| | |
|---|---|
| Health | 3 serious |
| Flammability | 3 serious |
| Instability or Reactivity | 0 minimal |

**HMIS (Hazardous Materials Identification System (Paint & Coating)) - Classification**

| | |
|---|---|
| Health | 3 serious |
| Flammability | 3 serious |
| Reactivity | 0 minimal |
| PPE | Determined by User; dependent on local conditions |

**Date Prepared:** 05/14/2020

**Key or legend to abbreviations and acronyms used in the safety data sheet**

- ST: STEL - 15-minute TWA exposure that should not be exceeded at any time during a workday
- STEL: Short-term exposure limit
- TWA: 8-hour, time-weighted average
- ACGIH: American Conference of Governmental Industrial Hygienists
- OSHA: Occupational Safety and Health Administration
- NTP: National Toxicology Program
- IARC: International Agency for Research on Cancer
- NIOSH: National Institute for Occupational Safety and Health
- ADR: European Agreement on International Carriage of Dangerous Goods by Road.
- ADN: European Agreement on the International Carriage of Dangerous Goods by Inland Waterways.
- RID: European Agreement concerning the International Carriage of Dangerous Goods by Rail.
- IATA: International Air Transport Association.
- ICAO-TI: Technical Specification for Safe Transport of Dangerous Goods by Air.
- IMDG: International Maritime Dangerous Goods.
- TWA: Time weighted average
- ATE: Estimated value of acute toxicity
- EC: European Community number
- CAS: Chemical Abstracts Service.
- LD50: Substance that causes 50% (half) death in the test animals group (Median Fatal Dose).
- LC50: Substance concentration causing 50% (half) death in the test animals group.
- EC50: Effective Concentration of the substance causing the maximum of 50%.
- PBT: Persistent, Bioaccumulative and Toxic substance.
- vPvB: Very Persistent and Very Bioaccumulative.
- SEA: Classification, labeling, packaging regulation
- DNEL: Derived No Effect Level
- PNEC: Predicted No Effect Concentration
- BHOT: Specific Target Organ Toxicity

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

**Not all acronyms listed above are referenced in this SDS.**

The information provided in this Safety Data Sheet is correct to the best of our knowledge, information, and belief at the date of its publication. Such information is only given as a guidance to help the user handle, use, process, store, transport, dispose, and release the product in satisfactory safety conditions and is not to be considered as a warranty or quality specification. It should be used in conjunction with technical sheets but do not replace them. Thus, the information only relates to the designated specific product and may not be applicable if such product is used in combination with other materials or in any other manufacturing process, unless otherwise specifically indicated. It does not release the user from ensuring he is in conformity with all regulations linked to its activity.

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

## SECTION 1: Identification of the substance/mixture and of the company/undertaking

### 1.1 Product identifier

- Trade name PLEXBREAK 145

### 1.2 Relevant identified uses of the substance or mixture and uses advised against

**Uses of the Substance / Mixture**

- Oil & gas industry

**Remarks**

- For professional and industrial installation and use only.

### 1.3 Details of the supplier of the safety data sheet

**Company**

Chemplex
Solvay USA Inc.
NOVECARE
506 CR 137
P.O. Box 1071
Snyder, TX 79550
Phone (325) 573-7298

### 1.4 Emergency telephone

FOR EMERGENCIES INVOLVING A SPILL, LEAK, FIRE, EXPOSURE OR ACCIDENT, CONTACT CHEMTREC (24-Hour Number): 800-424-9300 within the United States and Canada, or 703-527-3887 for international collect calls.

## SECTION 2: Hazards identification

Although OSHA has not adopted the environmental portion of the GHS regulations, this document may include information on environmental effects.

### 2.1 Classification of the substance or mixture

**HCS 2012 (29 CFR 1910.1200)**

| | |
|---|---|
| Flammable liquids, Category 3 | H226: Flammable liquid and vapor. |
| Acute toxicity, Category 3 | H331: Toxic if inhaled. |
| Acute toxicity, Category 4 | H312: Harmful in contact with skin. |
| Skin irritation, Category 2 | H315: Causes skin irritation. |
| Serious eye damage, Category 1 | H318: Causes serious eye damage. |
| Reproductive toxicity, Category 2 | H361: Suspected of damaging fertility or the unborn child. |
| Specific target organ toxicity - single exposure, Category 1 | H370: Causes damage to organs. (Central nervous system, optic nerve) |
| Specific target organ toxicity - repeated exposure, Category 2 | H373: May cause damage to organs through prolonged or repeated exposure. |

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

**2.2 Label elements**

**HCS 2012 (29 CFR 1910.1200)**

**Pictogram**



**Signal Word**
- Danger

**Hazard Statements**

| | |
|---|---|
| - H226 | Flammable liquid and vapor. |
| - H312 | Harmful in contact with skin. |
| - H315 | Causes skin irritation. |
| - H318 | Causes serious eye damage. |
| - H331 | Toxic if inhaled. |
| - H361 | Suspected of damaging fertility or the unborn child. |
| - H370 | Causes damage to organs (Central nervous system, optic nerve). |
| - H373 | May cause damage to organs through prolonged or repeated exposure. |

**Precautionary Statements**

Prevention

| | |
|---|---|
| - P201 | Obtain special instructions before use. |
| - P202 | Do not handle until all safety precautions have been read and understood. |
| - P210 | Keep away from heat/ sparks/ open flames/ hot surfaces. No smoking. |
| - P233 | Keep container tightly closed. |
| - P240 | Ground/bond container and receiving equipment. |
| - P241 | Use explosion-proof electrical/ ventilating/ lighting/ equipment. |
| - P242 | Use only non-sparking tools. |
| - P243 | Take precautionary measures against static discharge. |
| - P260 | Do not breathe dust/ fume/ gas/ mist/ vapors/ spray. |
| - P264 | Wash skin thoroughly after handling. |
| - P270 | Do not eat, drink or smoke when using this product. |
| - P271 | Use only outdoors or in a well-ventilated area. |
| - P280 | Wear protective gloves/ protective clothing/ eye protection/ face protection. |

Response

| | |
|---|---|
| - P303 + P361 + P353 | IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water/ shower. |
| - P304 + P340 + P311 | IF INHALED: Remove person to fresh air and keep comfortable for breathing. Call a POISON CENTER/ doctor. |
| - P305 + P351 + P338 + P310 | IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. Immediately call a POISON CENTER/ doctor. |
| - P307 + P311 | IF exposed: Call a POISON CENTER or doctor/ physician. |
| - P332 + P313 | If skin irritation occurs: Get medical advice/ attention. |
| - P362 | Take off contaminated clothing and wash before reuse. |
| - P370 + P378 | In case of fire: Use dry sand, dry chemical or alcohol-resistant foam to extinguish. |

Storage

| | |
|---|---|
| - P403 + P233 | Store in a well-ventilated place. Keep container tightly closed. |
| - P403 + P235 | Store in a well-ventilated place. Keep cool. |
| - P405 | Store locked up. |

Disposal

| | |
|---|---|
| - P501 | Dispose of contents/ container to an approved waste disposal plant. |

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

**2.3 Other hazards which do not result in classification**

- H402: Harmful to aquatic life.
- H412: Harmful to aquatic life with long lasting effects.

## SECTION 3: Composition/information on ingredients

**3.1 Substance**

- Not applicable, this product is a mixture.

**3.2 Mixture**

**Hazardous Ingredients and Impurities**

| Chemical name | Identification number CAS-No. | Concentration [%] |
|---|---|---|
| 2-butoxyethanol | 111-76-2 | >= 10 - < 15 |
| Methanol | 67-56-1 | >= 10 - < 15 |
| Coconut Fatty Acid Diethanolamide | 68603-42-9 | >= 5 - < 10 |
| Fatty acids, tall-oil, compds. with diethanolamine | 61790-66-7 | >= 1 - < 5 |
| Diethanolamine | 111-42-2 | >= 1 - < 5 |

The specific chemical identity and/or exact percentage (concentration) of composition has been withheld as a trade secret.

## SECTION 4: First aid measures

**4.1 Description of first-aid measures**

**General advice**

- Plan first aid action before beginning work with this product.
- For effective first-aid, special training / education is needed.
- The first aid procedure should be established in consultation with the doctor responsible for industrial medicine.

- First responder needs to protect himself.
- Do not leave the victim unattended.
- Show this material safety data sheet to the doctor in attendance.
- Place affected apparel in a sealed bag for subsequent decontamination.

- When symptoms persist or in all cases of doubt seek medical advice.
- Medical examination necessary even only on suspicion of intoxication.

**In case of inhalation**

- Remove to fresh air immediately. Get medical attention immediately.

- Rescuers should put on appropriate protective gear for rescue

- Remove victim from exposure and then have him lie down in the recovery position.
- Keep patient warm and at rest.
- Get immediate medical advice/ attention.

**In case of skin contact**

- Take off contaminated clothing and shoes immediately.
- Wash off immediately with soap and plenty of water.
- Use a mild soap if available.

- Immediate medical attention is required.

- Discard contaminated shoes and clothing.
- Dispose of promptly.

**In case of eye contact**

- Rinse immediately with plenty of water, also under the eyelids.
- Take victim immediately to hospital.
- Continue rinsing eyes during transport to hospital.

**In case of ingestion**

- Do not induce vomiting without medical advice.
- Rinse mouth with water.
- Do not give anything to drink.
- Never give anything by mouth to an unconscious person.
- Keep at rest.
- Get immediate medical advice/ attention.

**4.2 Most important symptoms and effects, both acute and delayed**

**Symptoms**

- Symptoms of poisoning may not appear for several hours. Keep under medical supervision for at least 48 hours.
- Symptoms will depend on the target organs.

**4.3 Indication of any immediate medical attention and special treatment needed**

**Notes to physician**

- All treatments should be based on observed signs and symptoms of distress in the patient. Consideration should be given to the possibility that overexposure to materials other than this product may have occurred.

## SECTION 5: Firefighting measures

| | |
|---|---|
| **Flash point** | 86 °F (30 °C) |
| | Flammability class: Flammable |
| **Autoignition temperature** | No data available |
| **Flammability / Explosive limit** | No data available |

**5.1 Extinguishing media**

**Suitable extinguishing media**

- Extinguishing media - small fires
- Multipurpose powders
- Carbon dioxide ($CO_2$)
- Alcohol Resistant Aqueous Film Forming Foam (AR-AFFF)

- Extinguishing media - large fires
- Alcohol Resistant Aqueous Film Forming Foam (AR-AFFF)

**Unsuitable extinguishing media**

- Water may be ineffective.

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

**5.2 Special hazards arising from the substance or mixture**

**Specific hazards during fire fighting**

- Flammable liquid and vapor.
- May burn with a colourless flame
- The pressure in sealed containers can increase under the influence of heat.
- In case of heating:
- Highly flammable gas is released, which increases fire / explosion hazards.
- Flash back possible over considerable distance.
- In case of heating:
- Harmful or toxic vapors are released.
- Hazardous decomposition products formed under fire conditions.
- (following evaporation of water)
- High concentrations of toxic or harmful products may remain in the residual liquid once the fire has been extinguished.

**Hazardous combustion products:**

- Carbon monoxide, carbon dioxide and unburned hydrocarbons (smoke).
- Nitrogen oxides (NOx)

**5.3 Advice for firefighters**

**Special protective equipment for fire-fighters**

- Firefighters should wear NIOSH/MSHA approved self-contained breathing apparatus and full protective clothing.
- Personal protective equipment comprising: suitable protective gloves, safety goggles and protective clothing

**Specific fire fighting methods**

- Stay upwind.
- Pay attention to flashback.
- Fight fire remotely due to the risk of explosion.
- Suppress (knock down) gases/vapors/mists with a water spray jet.
- Do not use a solid water stream as it may scatter and spread fire.
- Cool down the containers / equipment exposed to heat with a water spray. Ensure that there is NO direct contact between the water and the product.
- Use extinguishing measures that are appropriate to local circumstances and the surrounding environment.
- Persons who may have been exposed to contaminated smoke should be immediately examined by a physician and checked for symptoms of poisoning. The symptoms should not be mistaken for heat exhaustion or smoke inhalation.

**Further information**

- Evacuate personnel to safe areas.
- Intervention only by capable personnel who are trained and aware of the hazards of the product.
- Never approach containers which have been exposed to fire, without cooling them sufficiently.

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

- Collect contaminated fire extinguishing water separately. This must not be discharged into drains.
- Fire residues and contaminated fire extinguishing water must be disposed of in accordance with local regulations.

## SECTION 6: Accidental release measures

### 6.1 Personal precautions, protective equipment and emergency procedures

- Immediately evacuate personnel to safe areas.
- Stay upwind.
- Only qualified personnel equipped with suitable protective equipment may intervene.

- Avoid inhalation, ingestion and contact with skin and eyes.
- Wear chemical resistant personal protective equipment
- Wear suitable gloves.
- Wear suitable protective clothing.

- Respiratory protection

- Wear as appropriate:
- Face-shield
- Tightly fitting safety goggles

- In the case of dust or aerosol formation use respirator with an approved filter.
- In the case of vapor formation use a respirator with an approved filter.

- Eliminate all ignition sources if safe to do so.

- Ventilate the area.

- Stop leak if safe to do so.

- If spillage occurs on the public highway, indicate the danger and notify the authorities (police, fire service).

- For further information refer to section 8 "Exposure controls / personal protection."

### 6.2 Environmental precautions

- Take all necessary measures to avoid accidental discharge of products into drains and waterways due to the rupture of containers or transfer systems.

- Prevent further leakage or spillage if safe to do so.
- Contain the spilled material by diking.
- The product should not be allowed to enter drains, water courses or the soil.

- Local authorities should be advised if significant spillages cannot be contained.
- If the product contaminates rivers and lakes or drains inform respective authorities.
- If the spill area is porous, the contaminated material must be collected for subsequent treatment or disposal.

- Spills may be reportable to the National Response Center (800-424-8802) and to state and/or local agencies

### 6.3 Methods and materials for containment and cleaning up

- No sparking tools should be used.

- Stop leak if safe to do so.
- Dam up with sand or inert earth (do not use combustible materials).

- Control the vapors with:
- Alcohol Resistant Aqueous Film Forming Foam (AR-AFFF)

- Soak up with inert absorbent material (e.g. sand, silica gel, acid binder, universal binder).
- Shovel or sweep up.
- Keep in suitable, closed containers for disposal.
- Never return spills in original containers for re-use.

- Wash nonrecoverable remainder with large amounts of water.
- Clean contaminated surface thoroughly.
- Recover the cleaning water for subsequent disposal.
- Decontaminate tools, equipment and personal protective equipment in a segregated area.

- Dispose of as hazardous waste in compliance with local and national regulations.

**Additional advice**

- Possible need to alert the neighborhood.

- Mark the contaminated area with signs and prevent access to unauthorized personnel.
- Only qualified personnel equipped with suitable protective equipment may intervene.

- Ventilate the area.

- Following decontamination, wait several hours before allowing anyone to enter the area.

- Material can create slippery conditions.

**6.4 Reference to other sections**

- 7. HANDLING AND STORAGE
- 8. EXPOSURE CONTROLS/PERSONAL PROTECTION
- 13. DISPOSAL CONSIDERATIONS

## SECTION 7: Handling and storage

**7.1 Precautions for safe handling**

- Handle in accordance with good industrial hygiene and safety practice.

- The product must only be handled by specifically trained employees.

- Provide sufficient air exchange and/or exhaust in work rooms.
- Vapor extraction at source
- Do not use in areas without adequate ventilation.
- Do NOT handle in a confined space.
- Extracted air must not be allowed to return to the workplace.

- The product should only be used in areas from which all naked lights and other sources of ignition have been excluded.

- Use explosion-proof electrical/ ventilating/ lighting/ equipment.

- Take precautionary measures against static discharges.
- Ground/bond container and receiving equipment.
- To avoid ignition of vapors by static electricity discharge, all metal parts of the equipment must be grounded.
- Ensure all equipment is electrically grounded before beginning transfer operations.
- Use only non-sparking tools.

- Avoid high temperatures.

- Wear personal protective equipment.
- Wear suitable protective clothing.

- Avoid inhalation, ingestion and contact with skin and eyes.
- Do NOT handle without gloves.
- Do NOT handle if hands have any cuts or wounds.

- Avoid splashes.
- Avoid formation of aerosol.

- Pregnant or breastfeeding workers should not be occupied in the blending and high temperature processing operations.

- For personal protection see section 8.

**Hygiene measures**

- Personal hygiene is an important work practice exposure control measure and the following general measures should be taken when working with or handling this materials:
- 1) Do not store, use, and/or consume foods, beverages, tobacco products, or cosmetics in areas where this material is stored.
- 2) Wash hands and face carefully before eating, drinking, using tobacco, applying cosmetics, or using the toilet.
- 3) Wash exposed skin promptly to remove accidental splashes or contact with material.

- The user is responsible for monitoring the working environment in accordance with local laws and regulations.

- Exposed employees should have regular medical check-ups

**7.2 Conditions for safe storage, including any incompatibilities**

**Technical measures/Storage conditions**

- Take appropriate measures to prevent static discharges, which may include thorough electrical interconnecting, grounding of equipment, and/or conveyance under inert gas.

- Vapour space above stored liquid may be flammable/explosive unless blanketed with inert gas.

- Take all necessary measures to avoid accidental discharge of products into drains and waterways due to the rupture of containers or transfer systems.

- Keep in a contained area
- The floor of the storage area should be impermeable and designed to form a water-tight basin.

- Keep locked up or in an area accessible only to qualified or authorized persons.

- Keep containers tightly closed in a dry, cool and well-ventilated place.
- Keep away from open flames, hot surfaces and sources of ignition.
- Keep away from incompatible materials to be indicated by the manufacturer

- Do not freeze.

- Keep away from: Hazardous reactions may occur on contact with certain chemicals. (Refer to the list of incompatible materials section 10: "Stability-Reactivity").

**Packaging material**

**Suitable material**
- Electrical conducting materials

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

**Unsuitable material**
- Electrical insulating materials

**Requirements for storage rooms and vessels**

- Do not freeze.

**7.3 Specific end use(s)**

- no data available

## SECTION 8: Exposure controls/personal protection

Introductory Remarks: These recommendations provide general guidance for handling this product. Because specific work environments and material handling practices vary, safety procedures should be developed for each intended application. Assistance with selection, use and maintenance of worker protection equipment is generally available from equipment manufacturers.

**8.1 Control parameters**

**Components with workplace occupational exposure limits**

| Components | Value type | Value | Basis |
|---|---|---|---|
| 2-butoxyethanol | TWA | 5 ppm<br>24 mg/m3 | National Institute for Occupational Safety and Health |
| | Potential for dermal absorption | | |
| 2-butoxyethanol | TWA | 20 ppm | American Conference of Governmental Industrial Hygienists |
| 2-butoxyethanol | TWA | 50 ppm 240 mg/m3 | Occupational Safety and Health Administration - Table Z-1 Limits for Air Contaminants |
| | Skin designation | | |
| Methanol | TWA | 200 ppm<br>260 mg/m3 | National Institute for Occupational Safety and Health |
| | Potential for dermal absorption | | |
| Methanol | ST | 250 ppm<br>325 mg/m3 | National Institute for Occupational Safety and Health |
| | Potential for dermal absorption | | |
| Methanol | TWA | 200 ppm | American Conference of Governmental Industrial Hygienists |
| | Danger of cutaneous absorption | | |
| Methanol | STEL | 250 ppm | American Conference of Governmental Industrial Hygienists |
| | Danger of cutaneous absorption | | |

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

| | | | |
|---|---|---|---|
| Methanol | TWA | 200 ppm<br>260 mg/m3 | Occupational Safety and Health Administration - Table Z-1 Limits for Air Contaminants |
| | The value in mg/m3 is approximate. | | |
| Diethanolamine | TWA | 3 ppm<br>15 mg/m3 | National Institute for Occupational Safety and Health |
| Diethanolamine | TWA | 1 mg/m3 | American Conference of Governmental Industrial Hygienists |
| | Form of exposure : Inhalable fraction and vapor<br>Danger of cutaneous absorption | | |

**NIOSH IDLH (Immediately Dangerous to Life or Health Concentrations)**

| Components | CAS-No. | Concentration |
|---|---|---|
| 2-butoxyethanol | 111-76-2 | 700 parts per million |
| Methanol | 67-56-1 | 6000 parts per million |

**Biological Exposure Indices**

| Components | Value type | Value | Basis |
|---|---|---|---|
| 2-butoxyethanol | BEI | 200 mg/g Creatinine<br>Butoxyacetic acid (BAA)<br>Urine<br>End of shift (As soon as possible after exposure ceases) | American Conference of Governmental Industrial Hygienists |
| | With hydrolyses | | |
| Methanol | BEI | 15 mg/l<br>Methanol<br>Urine<br>End of shift (As soon as possible after exposure ceases) | American Conference of Governmental Industrial Hygienists |

**8.2 Exposure controls**

**Control measures**

**Engineering measures**

- Where engineering controls are indicated by use conditions or a potential for excessive exposure exists, the following traditional exposure control techniques may be used to effectively minimize employee exposures :

- Effective exhaust ventilation system
- Ensure adequate ventilation.

- Extract at emission point.
- Ensure that extracted air cannot be returned to the workplace through the ventilation system.

- Use mechanical handling to reduce human contact with materials.
- Use closed processing systems or containment technologies.

- Avoid splashes.
- Avoid formation of aerosol.

**Individual protection measures**

**Respiratory protection**

- This should be achieved by a good general extraction and -if practically feasible- by the use of a local exhaust ventilation.
- When respirators are required, select NIOSH/MSHA approved equipment based on actual or potential airborne concentrations and in accordance with the appropriate regulatory standards and/or industrial recommendations.
- If mist is formed:
- If vapor is released:
- Wear a positive-pressure supplied-air respirator with full facepiece.

**Hand protection**

- Where there is a risk of contact with hands, use appropriate gloves
- Gloves must be inspected prior to use.
- Please observe the instructions regarding permeability and breakthrough time which are provided by the supplier of the gloves. Also take into consideration the specific local conditions under which the product is used, such as the danger of cuts, abrasion, and the contact time.
- Gloves should be discarded and replaced if there is any indication of degradation or chemical breakthrough.

***Suitable material***

- butyl-rubber

**Eye protection**

- Eye and face protection requirements will vary dependent upon work environment conditions and material handling practices. Appropriate ANSI Z87 approved equipment should be selected for the particular use intended for this material.
- Eye contact should be prevented through the use of:

- Tightly fitting safety goggles
- Face-shield

**Skin and body protection**

- Wear fire resistant and antistatic coveralls
- Workers should wear antistatic footwear.

- Full protective suit
- Footwear protecting against chemicals

- Choose body protection according to the amount and concentration of the dangerous substance at the work place.

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

**Hygiene measures**

- Personal hygiene is an important work practice exposure control measure and the following general measures should be taken when working with or handling this materials:
- 1) Do not store, use, and/or consume foods, beverages, tobacco products, or cosmetics in areas where this material is stored.
- 2) Wash hands and face carefully before eating, drinking, using tobacco, applying cosmetics, or using the toilet.
- 3) Wash exposed skin promptly to remove accidental splashes or contact with material.
- The user is responsible for monitoring the working environment in accordance with local laws and regulations.
- Exposed employees should have regular medical check-ups

**Protective measures**

- Emergency equipment immediately accessible, with instructions for use.
- Ensure that eyewash stations and safety showers are close to the workstation location.
- Selection of appropriate personal protective equipment should be based on an evaluation of the performance characteristics of the protective equipment relative to the task(s) to be performed, conditions present, duration of use, and the potential hazards, and/or risks that may occur during use.
- The protective equipment must be selected in accordance with current local regulations and in cooperation with the supplier of the protective equipment.

## SECTION 9: Physical and chemical properties

Physical and Chemical properties here represent typical properties of this product. Contact the business area using the Product information phone number in Section 1 for its exact specifications.

### 9.1 Information on basic physical and chemical properties

| | |
|---|---|
| **Appearance** | Physical state: liquid (68 °F (20 °C)) |
| | Color: yellow |
| **Odor** | alcohol-like |
| | Do not attempt to smell the product as it is hazardous. |
| **Odor Threshold** | No data available |
| **pH** | No data available |
| **Melting point/freezing point** | No data available |
| **Initial boiling point and boiling range** | No data available |
| **Flash point** | 86 °F (30 °C) |
| | Flammability class: Flammable |
| **Evaporation rate (Butylacetate = 1)** | No data available |
| **Flammability (solid, gas)** | No data available |
| **Flammability (liquids)** | No data available |
| **Flammability / Explosive limit** | No data available |

| | |
|---|---|
| **Autoignition temperature** | No data available |
| **Vapor pressure** | No data available |
| **Vapor density** | 1.11<br>(Air = 1.0) |
| **Density** | 0.974 g/cm3 ( 68 °F (20 °C)) |
| **Relative density** | No data available |
| **Solubility** | Water solubility:<br>soluble |
| **Partition coefficient: n-octanol/water** | No data available |
| **Decomposition temperature** | No data available |
| **Viscosity** | No data available |
| **Explosive properties** | No data available |
| **Oxidizing properties** | Not considered as oxidizing., Structure-activity relationship (SAR) |

**9.2 Other information**

No data available

## SECTION 10: Stability and reactivity

**10.1 Reactivity**

- Stable at normal ambient temperature and pressure.

**10.2 Chemical stability**

- Stable under recommended storage conditions.

**10.3 Possibility of hazardous reactions**

- Explosion possible with gas/vapor and air mixtures above flash point., Vapors may form explosive mixture with air.

**10.4 Conditions to avoid**

- Prevent the build-up of electrostatic charge.
- Avoid high temperatures.
- Keep away from open flames, hot surfaces and sources of ignition.

**10.5 Incompatible materials**

- Strong oxidizing agents

**10.6 Hazardous decomposition products**

**Hazardous decomposition products**

- On combustion or on thermal decomposition (pyrolysis), releases:
- Carbon monoxide, carbon dioxide and unburned hydrocarbons (smoke).
- Nitrogen oxides (NOx)

SAFETY DATA SHEET

**PLEXBREAK 145**

Revision Date 05/14/2020

## SECTION 11: Toxicological information

### 11.1 Information on toxicological effects

**Acute toxicity**

**Acute oral toxicity**

The product has a low acute toxicity

According to the available data on the components.
According to the classification criteria for mixtures.
Unpublished reports and/or published data.

**Acute inhalation toxicity**

2-butoxyethanol

LC50 - 4 h ( vapor ) : 2.2 mg/l - Rat , male and female
This product is classified as acute toxicity category 3

Methanol

LC50 - 4 h : > 115.9 mg/l - Rat , female
Unpublished reports

LC50 - 4 h ( vapor ) : 130.7 mg/l - Rat , male
Unpublished reports

Humans
Target Organs: Central nervous system, optic nerve
Symptoms: Inhalation may provoke the following symptoms:, Dizziness, Nausea, acidosis, Blurred vision, Impairment of vision, Symptoms may be delayed.
This product is classified as acute toxicity category 3
Published data

**Acute dermal toxicity**

This product is classified as acute toxicity category 4

According to the available data on the components.
According to the classification criteria for mixtures.
Unpublished reports and/or published data.

**Acute toxicity (other routes of administration)**

Not applicable

**Skin corrosion/irritation**

Irritating to skin.

According to the available data on the components.
According to the classification criteria for mixtures.
Unpublished reports and/or published data.

**Serious eye damage/eye irritation**

Risk of serious damage to eyes.

According to the available data on the components.
According to the classification criteria for mixtures.
Unpublished reports and/or published data.

**Respiratory or skin sensitization**

Does not cause skin sensitization.

According to the available data on the components.
According to the classification criteria for mixtures.
Unpublished reports and/or published data.

**Mutagenicity**

**Genotoxicity in vitro**

Product is not considered to be genotoxic

**SDS Biocide (Bioclear 1430)**

Lubrizol

Version: 1.0
Revision Date: 02/26/2016



**Signal Word:** Danger

**Hazard Statement:** Causes severe skin burns and eye damage.
May cause allergy or asthma symptoms or breathing difficulties if inhaled.
May cause an allergic skin reaction.
May cause respiratory irritation.

**Precautionary Statement:**

**Prevention:** Use only outdoors or in a well-ventilated area. Wash thoroughly after handling. Do not eat, drink or smoke when using this product. Do not breathe dust or mists. Wear protective gloves/protective clothing/eye protection/face protection. [In case of inadequate ventilation] wear respiratory protection. Contaminated work clothing must not be allowed out of the workplace. Avoid release to the environment.

**Response:** IF INHALED: Remove person to fresh air and keep comfortable for breathing. If experiencing respiratory symptoms: Call a POISON CENTER/doctor. If in eyes: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water/shower. If skin irritation or rash occurs: Get medical advice/attention. IF SWALLOWED: Call a POISON CENTER/doctor/ if you feel unwell. Rinse mouth. Do NOT induce vomiting. Immediately call a POISON CENTER/doctor. Specific treatment (see this label). Wash contaminated clothing before reuse. Collect spillage.

**Storage:** Store locked up. Store in well-ventilated place. Keep container tightly closed.

**Disposal:** Dispose of contents/container to an appropriate treatment and disposal facility in accordance with applicable laws and regulations, and product characteristics at time of disposal.

**Other hazards which do not result in GHS classification:** None identified.

## 3. Composition/information on ingredients

| Chemical name | CAS number | Percent by Weight |
|---|---|---|
| Glutaraldehyde | 111-30-8 | 10 - 20% |
| Alkyl dimethyl benzyl ammonium chloride | 68424-85-1 | 1 - 5% |
| Dimethylamine | 68439-70-3 | 0.1 - 0.5% |

## 4. First-aid measures

**Ingestion:** Do NOT induce vomiting. Rinse mouth. Call a physician or poison control center immediately.

**Inhalation:** Remove to fresh air and keep at rest in a position comfortable for breathing. Call a physician or poison control center immediately. If experiencing respiratory symptoms call a poison center or doctor.

**Skin Contact:** Take off immediately all contaminated clothing. Wash skin thoroughly with soap and water. Immediately call a POISON CENTER/doctor. Launder contaminated clothing before reuse.

**Eye contact:** Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. Immediately call a POISON CENTER/doctor.

**Most important symptoms/effects, acute and delayed**

**Symptoms:** Symptoms may be delayed.

**Indication of immediate medical attention and special treatment needed**

**Treatment:** Treat symptomatically.

## 5. Fire-fighting measures

**General Fire Hazards:** No unusual fire or explosion hazards noted.

**Suitable (and unsuitable) extinguishing media**

**Suitable extinguishing media:** CO2, dry chemical, foam, water spray, water fog.

**Unsuitable extinguishing media:** Not determined.

**Specific hazards arising from the chemical:** See section 10 for additional information.

**Special protective equipment and precautions for firefighters**

**Special fire fighting procedures:** No data available.

**Special protective equipment for fire-fighters:** Recommend wearing self-contained breathing apparatus.

## 6. Accidental release measures

**Personal precautions, protective equipment and emergency procedures:** Evacuate area. Ventilate closed spaces before entering them. Do not touch damaged containers or spilled material unless wearing appropriate protective clothing. Keep upwind. Keep unauthorized personnel away. See Section 8 of the SDS for Personal Protective Equipment.

**Methods and material for containment and cleaning up:** Dike far ahead of larger spill for later recovery and disposal. Pick up free liquid for recycle and/or disposal. Residual liquid can be absorbed on inert material. Stop the flow of material, if this is without risk. Prevent entry into waterways, sewer, basements or confined areas.

**Environmental Precautions:** Avoid release to the environment. Do not contaminate water sources or sewer. Prevent further leakage or spillage if safe to do so.

## 7. Handling and storage

**Precautions for safe handling:** Do not breathe dusts or mists. Do not get in eyes, on skin, on clothing. Do not get in eyes. Avoid contact with eyes, skin, and clothing. Observe good industrial hygiene practices. Use only in well-ventilated areas. In case of inadequate ventilation, use respiratory protection. Wear appropriate personal protective equipment. Wash hands thoroughly after handling. Do not eat, drink or smoke when using this product. Contaminated work clothing should not be allowed out of the workplace. Launder contaminated clothing before reuse. Avoid environmental contamination.

**Maximum Handling Temperature:** Not determined.

**Conditions for safe storage, including any incompatibilities:** Store away from incompatible materials. See section 10 for incompatible materials.

**Maximum Storage Temperature:** Not determined.

## 8. Exposure controls/personal protection

**Control Parameters:**

**Occupational Exposure Limits**

| Chemical name | type | Exposure Limit Values | | Source |
|---|---|---|---|---|
| Glutaraldehyde | Ceiling | 0.2 ppm | 0.8 mg/m3 | US. OSHA Table Z-1-A (29 CFR 1910.1000) (1989) |
| Glutaraldehyde | Ceiling | 0.05 ppm | | US. ACGIH Threshold Limit Values (02 2012) |
| Glutaraldehyde | Ceil_Time | 0.2 ppm | 0.8 mg/m3 | US. NIOSH: Pocket Guide to Chemical Hazards (2010) |

**Appropriate engineering controls:** The use of closed systems is strongly recommended for the handling and transfer of undiluted material. Adequate ventilation should be provided so that exposure limits are not exceeded. Mechanical ventilation or local exhaust ventilation may be required.

**Individual protection measures, such as personal protective equipment**

**General information:** Provide easy access to water supply and eye wash facilities. Good general ventilation (typically 10 air changes per hour) should be used. Ventilation rates should be matched to conditions. If applicable, use process enclosures, local exhaust ventilation, or other engineering controls to maintain airborne levels below recommended exposure limits. If exposure limits have not been established, maintain airborne levels to an acceptable level.

**Eye/face protection:** Wear tight-fitting goggles or face shield.

**Skin Protection**

**Hand Protection:** Suitable gloves can be recommended by the glove supplier. Nitrile.

| | |
|---|---|
| **Other:** | Wear apron or protective clothing in case of contact. Chemical resistant boots. Do not wear rings, watches or similar apparel that could entrap the material. |
| **Respiratory Protection:** | A respiratory protection program compliant with all applicable regulations must be followed whenever workplace conditions require the use of a respirator. Use respirator with an organic vapor and dust/mist cartridge if the recommended exposure limit is exceeded. Use self-contained breathing apparatus for entry into confined space, for other poorly ventilated areas and for large spill clean-up sites. |
| **Hygiene measures:** | Observe good industrial hygiene practices. Do not get this material in contact with skin. Do not eat, drink or smoke when using the product. Do not get in eyes. Avoid contact with skin. Wash contaminated clothing before reuse. Wash hands before breaks and immediately after handling the product. Wash hands after handling. Contaminated work clothing should not be allowed out of the workplace. |

## 9. Physical and chemical properties

| | |
|---|---|
| **Appearance** | |
| **Physical state:** | liquid |
| **Form:** | liquid |
| **Color:** | Light yellow |
| **Odor:** | Fruity |
| **Odor threshold:** | No data available. |
| **pH:** | 3 - 5 |
| **Freezing point:** | -7 °C |
| **Boiling Point:** | No data available. |
| **Flash Point:** | > 199.99 °F (93.33 °C) (Test method unavailable) |
| **Evaporation rate:** | No data available. |
| **Flammability (solid, gas):** | No data available. |
| **Upper/lower limit on flammability or explosive limits** | |
| **Flammability limit - upper (%):** | No data available. |
| **Flammability limit - lower (%):** | No data available. |
| **Explosive limit - upper (%):** | No data available. |
| **Explosive limit - lower (%):** | No data available. |
| **Vapor pressure:** | No data available. |
| **Vapor density:** | No data available. |
| **Relative density:** | 1.013 - 1.043 68 °F (20 °C) |
| **Solubility(ies)** | |
| **Solubility in water:** | Miscible with water. |
| **Solubility (other):** | No data available. |
| **Partition coefficient (n-octanol/water):** | No data available. |
| **Auto-ignition temperature:** | No data available. |
| **Decomposition temperature:** | No data available. |
| **Viscosity:** | No data available. |

## 10. Stability and reactivity

**Reactivity:** No data available.

**Chemical Stability:** Material is stable under normal conditions.

**Possibility of hazardous reactions:** Will not occur.

**Conditions to avoid:** Not determined.

**Incompatible Materials:** Alkalies. Bases.

**Hazardous Decomposition Products:** Thermal decomposition or combustion may generate smoke, carbon monoxide, carbon dioxide, and other products of incomplete combustion.

## 11. Toxicological information

**Information on likely routes of exposure**

**Inhalation:** Harmful if inhaled.

**Ingestion:** Harmful if swallowed.

**Skin Contact:** Causes severe skin burns.

**Eye contact:** Causes serious eye damage.

**Information on toxicological effects**

**Acute toxicity**

**Oral**

Product: ATEmix 300 - 2,000 mg/kg.
Swallowing this material can cause burns to the mouth and esophagus. Asphyxiation can occur from swelling of the throat. Perforation of the esophagus and stomach can occur. Swallowing material may cause irritation of the gastrointestinal lining, nausea, vomiting, diarrhea, and abdominal pain.

**Dermal**

Product: ATEmix > 5,000 mg/kg
Prolonged or widespread contact with this material could result in the absorption of potentially harmful amounts.

**Inhalation**

Product: ATEmix (, 4 h): 2 - 5 mg/l. Dusts, mists and fumes

**Skin Corrosion/Irritation:**

Product: Causes severe skin burns.

**Serious Eye Damage/Eye Irritation:**

Product: Remarks: Causes serious eye damage.

**Respiratory sensitization:**

Glutaraldehyde: Classification: May cause sensitization by inhalation. (Literature)

**Skin sensitization:**

| | |
|---|---|
| Glutaraldehyde | Classification: May cause sensitization by skin contact. (Literature) |
| Alkyl dimethyl benzyl ammonium chloride | Classification: Not a skin sensitizer. (Read across) Not a skin sensitizer. |

**Specific Target Organ Toxicity - Single Exposure:**

| | |
|---|---|
| Glutaraldehyde | Nose, throat and lung irritant. |
| Alkyl dimethyl benzyl ammonium chloride | May cause irritation to the mucous membranes and upper respiratory tract. |
| Dimethylamine | Nose, throat and lung irritant. |

**Aspiration Hazard:**

No data available

**Chronic Effects**

**Carcinogenicity:**

No data available

**IARC Monographs on the Evaluation of Carcinogenic Risks to Humans:**

No carcinogenic components identified

**US. National Toxicology Program (NTP) Report on Carcinogens:**

No carcinogenic components identified

**US. OSHA Specifically Regulated Substances (29 CFR 1910.1001-1050):**

No carcinogenic components identified

**Germ Cell Mutagenicity:**

| | |
|---|---|
| Alkyl dimethyl benzyl ammonium chloride | This material has not exhibited mutagenic or genotoxic potential in laboratory tests. |

**Reproductive toxicity:**

No data available

**Specific Target Organ Toxicity - Repeated Exposure:**

No data available

## 12. Ecological information

**Ecotoxicity**

**Fish**

| | |
|---|---|
| Glutaraldehyde | LC 50 (Bluegill Sunfish, 4 d): 11 mg/l<br>LC 50 (Rainbow Trout, 4 d): 12 mg/l<br>LC 50 (Sheepshead Minnow, 4 d): 32 mg/l<br>NOEC (Bluegill Sunfish, 4 d): 5 mg/l<br>NOEC (Rainbow Trout, 4 d): 9 mg/l |

| | |
|---|---|
| Alkyl dimethyl benzyl ammonium chloride | LC 50 (Not reported, 4 d): 0.38 mg/l |
| Dimethylamine | LC 50 (Zebra Fish, 4 Days): < 1 mg/l |

**Aquatic Invertebrates**

| | |
|---|---|
| Glutaraldehyde | EC 50 (Shrimp (Mysidopsis Bahia), 4 d): 7.1 mg/l<br>NOEC (Shrimp (Mysidopsis Bahia), 4 d): 0.78 mg/l<br>EC 50 (Water flea (Daphnia magna), 21 d): 5 mg/l<br>NOEC (Water flea (Daphnia magna), 21 d): 4.25 mg/l |
| Alkyl dimethyl benzyl ammonium chloride | EC 50 (Water flea (Daphnia magna), 2 d): 0.0059 mg/l |
| Dimethylamine | EC 50 (Water flea (Daphnia magna), 2 Days): <= 1 mg/l |

**Toxicity to Aquatic Plants**

| | |
|---|---|
| Glutaraldehyde | EC 50 (Alga, 3 d): 0.17 mg/l<br>EC 50 (Alga, 4 d): 0.97 mg/l<br>EC 50 (Green algae (Selenastrum capricornutum), 5 d): 0.81 mg/l<br>NOEC (Alga, 4 d): 0.31 mg/l<br>NOEC (Green algae (Scenedesmus quadricauda), 3 h): 0.05 mg/l |
| Dimethylamine | NOEC (Alga, 3 Days): 0.00761 mg/l |

**Toxicity to soil dwelling organisms**

No data available

**Sediment Toxicity**

No data available

**Toxicity to Terrestrial Plants**

No data available

**Toxicity to Above-Ground Organisms**

| | |
|---|---|
| Glutaraldehyde | LC 50 (5 d): > 5,000 mg/kg |

**Toxicity to microorganisms**

| | |
|---|---|
| Glutaraldehyde | EC 50 (Bacteria, 0.6 d): 25 mg/l<br>EC 50 (Sludge, 0.1 d): 50 mg/l<br>NOEC (Sludge, 0.1 d): 16 mg/l |

**Persistence and Degradability**

**Biodegradation**

| | |
|---|---|
| Glutaraldehyde | Miscellaneous, 83 %, 5 d, Readily biodegradable |
| Alkyl dimethyl benzyl ammonium chloride | 93.3 %, 28 d, Readily biodegradable |
| Dimethylamine | OECD TG 301 B, 67 %, 28 d, Readily biodegradable (Readily biodegradable) |

**Bioaccumulative Potential**

**Bioconcentration Factor (BCF)**

No data available

**Partition Coefficient n-octanol / water (log Kow)**

| | |
|---|---|
| Glutaraldehyde | Log Kow: -0.33 (Measured) |

**Mobility:** No data available

**Other Adverse Effects:** No data available.

## 13. Disposal considerations

**Disposal instructions:** Treatment, storage, transportation, and disposal must be in accordance with applicable Federal, State/Provincial, and Local regulations. Dispose of packaging or containers in accordance with local, regional, national and international regulations. Empty container contains product residue which may exhibit hazards of product.

**Contaminated Packaging:** Container packaging may exhibit hazards.

## 14. Transport information

**DOT**

| | |
|---|---|
| UN Number: | UN 3265 |
| UN Proper Shipping Name: | Corrosive liquid, acidic, organic, n.o.s.(Glutaraldehyde, Alkyl dimethyl benzyl ammonium chloride) |
| Transport Hazard Class(es) | |
| Class: | 8 |
| Label(s): | 8 |
| Packing Group: | II |
| Marine Pollutant: | Yes |
| Special precautions for user: | None established |

**IMDG**

| | |
|---|---|
| UN Number: | UN 3265 |
| UN Proper Shipping Name: | CORROSIVE LIQUID, ACIDIC, ORGANIC, N.O.S.(Glutaraldehyde, Alkyl dimethyl benzyl ammonium chloride) |
| Transport Hazard Class(es) | |
| Class: | 8 |
| Label(s): | 8 |
| EmS No.: | F-A, S-B |
| Packing Group: | II |
| Marine Pollutant: | Yes |
| Limited quantity | 1.00L |
| Excepted quantity | E2 |
| Special precautions for user: | None established |

**IATA**

| | |
|---|---|
| UN Number: | UN 3265 |
| Proper Shipping Name: | Corrosive liquid, acidic, organic, n.o.s.(Glutaraldehyde, Alkyl dimethyl benzyl ammonium chloride) |
| Transport Hazard Class(es): | |
| Class: | 8 |
| Label(s): | 8 |
| Marine Pollutant: | Yes |
| Packing Group: | II |
| Limited quantity | 0.50L |
| Excepted quantity | E2 |
| Environmental Hazards | Marine Pollutant |
| Special precautions for user: | None established |
| Other information | |
| Passenger and cargo aircraft: | Allowed. |
| Cargo aircraft only: | Allowed. |

**Transport in bulk according to Annex II of MARPOL73/78 and the IBC Code**

None known.

The DOT shipping information in this section is based on a bulk container. Please review the accompanying shipping papers for the correct shipping descriptions based the size of the package. Shipping descriptions may vary based on mode of transport, quantities, temperature of the material, package size, and/or origin and destination. It is the responsibility of the transporting organization to follow all applicable laws, regulations and rules relating to the transportation of the material. During transportation, steps must be taken to prevent load shifting or materials falling, and all relating legal statutes should be obeyed. Review classification requirements before shipping materials at elevated temperatures.

## 15. Regulatory information

### US Federal Regulations

**TSCA Section 12(b) Export Notification (40 CFR 707, Subpt. D)**

None present or none present in regulated quantities.

**CERCLA Hazardous Substance List (40 CFR 302.4)**

None present or none present in regulated quantities.

**Superfund Amendments and Reauthorization Act of 1986 (SARA)**

**SARA 311 Classifications**

Immediate (Acute) Health Hazards
Delayed (Chronic) Health Hazard

**SARA 302 Extremely Hazardous Substance**

None present or none present in regulated quantities.

**SARA 304 Emergency Release Notification**

None present or none present in regulated quantities.

**SARA 313 (TRI Reporting)**

None present or none present in regulated quantities.

**US State Regulations**

**US. California Proposition 65**

No ingredient regulated by CA Prop 65 present.

**Inventory Status**

Australia (AICS)
All components are in compliance with chemical notification requirements in Australia.

Canada (DSL/NDSL)
All components are in compliance with the Canadian Environmental Protection Act and are present on the Domestic Substances List.

China (IECSC)
All components of this product are listed on the Inventory of Existing Chemical Substances in China.

European Union (REACh)
To obtain information on the REACH compliance status of this product, please e-mail REACH@SDSInquiries.com.

Japan (ENCS)
All components are in compliance with the Chemical Substances Control Law of Japan.

Korea (ECL)
All components are in compliance in Korea.

New Zealand (NZIoC)
All components are in compliance with chemical notification requirements in New Zealand.

Philippines (PICCS)
All components are in compliance with the Philippines Toxic Substances and Hazardous and Nuclear Wastes Control Act of 1990 (R.A. 6969).

Switzerland (SWISS)
All components are in compliance with the Environmentally Hazardous Substances Ordinance in Switzerland.

Taiwan (TCSCA)
All components of this product are listed on the Taiwan inventory.

United States (TSCA)
This product is on the TSCA inventory. When used as a biocide it is regulated under the Federal Insecticide, Fungicide and Rodenticide Act (FIFRA). This product is not FIFRA registered.

*The information that was used to confirm the compliance status of this product may deviate from the chemical information shown in Section 3.*

## 16.Other information, including date of preparation or last revision

**HMIS Hazard ID**

| | | |
|---|---|---|
| Health | * | 3 |
| Flammability | | 1 |
| Physical Hazards | | 0 |

Hazard rating: 0 - Minimal; 1 - Slight; 2 - Moderate; 3 - Serious; 4 - Severe; RNP - Rating not possible; *Chronic health effect

Lubrizol

Version: 1.0
Revision Date: 02/26/2016

**NFPA Hazard ID**




Hazard rating: 0 - Minimal; 1 - Slight; 2 - Moderate; 3 - Serious; 4 - Severe; RNP - Rating not possible

| | |
|---|---|
| **Issue Date:** | 02/26/2016 |
| **Version #:** | 1.0 |
| **Source of information:** | Internal company data and other publically available resources. |
| **Further Information:** | Contact supplier (see Section 1) |
| **Disclaimer:** | As the conditions or methods of use are beyond our control, we do not assume any responsibility and expressly disclaim any liability for any use of this product. Information contained herein is believed to be true and accurate but all statements or suggestions are made without warranty, expressed or implied, regarding accuracy of the information, the hazards connected with the use of the material or the results to be obtained from the use thereof. Compliance with all applicable federal, state, and local regulations remains the responsibility of the user. |

Lubrizol

Version: 1.0
Revision Date: 02/26/2016

# SAFETY DATA SHEET

## 1. Identification

**Identification**
**Product name:** **BIOCLEAR 1430**

**Additional identification**
**Chemical name:** Mixture

**Recommended use and restriction on use**
**Recommended use:** EC Intermediates & Surfactants
**Restrictions on use:** None identified.

**Details of the supplier of the safety data sheet**
**Supplier**
Company Name: LUBRIZOL OILFIELD SOLUTIONS
Address: 2000 WEST SAM HOUSTON PKWY S.
SUITE 400
HOUSTON, TX 77042
US
Telephone: (713) 339-8771

**Emergency telephone number:**
FOR TRANSPORT EMERGENCY CALL CHEMTREC (+1)703 527 3887, OR WITHIN USA 800 424 9300

## 2. Hazard(s) identification

**Hazard Classification**

**Health Hazards**

| | |
|---|---|
| Acute toxicity (Oral) | Category 4 |
| Acute toxicity (Inhalation - dust and mist) | Category 4 |
| Skin Corrosion/Irritation | Category 1B |
| Serious Eye Damage/Eye Irritation | Category 1 |
| Respiratory sensitizer | Category 1 |
| Skin sensitizer | Category 1 |
| Specific Target Organ Toxicity - Single Exposure | Category 3 |

**Unknown toxicity**

| | |
|---|---|
| Acute toxicity, oral | 0.0 % |
| Acute toxicity, dermal | 0.1 % |
| Acute toxicity, inhalation, vapor | 16.8 % |
| Acute toxicity, inhalation, dust or mist | 3.1 % |

**Label Elements:**

**Hazard Symbol:**

**SDS Corrosion Inhibitor (Evirohib 600)**

Lubrizol

Version: 3.0
Revision Date: 12/11/2017

# SAFETY DATA SHEET

## 1. Identification

**Identification**
**Product name:** **ENVIROHIB™ 600**

**Additional identification**
**Chemical name:** Mixture

**Recommended use and restriction on use**
**Recommended use:** EC Fracturing & Acidizing
**Restrictions on use:** None identified.

**Details of the supplier of the safety data sheet**
**Supplier**
Company Name: THE LUBRIZOL CORPORATION
Address: 29400 LAKELAND BOULEVARD
WICKLIFFE, OH 44092-2298
US
Telephone: (440)943-1200

**Emergency telephone number:**
FOR TRANSPORT EMERGENCY CALL CHEMTREC (+1)703 527 3887, OR WITHIN USA 800 424 9300

## 2. Hazard(s) identification

**Hazard Classification**

**Physical Hazards**

| | |
|---|---|
| Flammable liquids | Category 4 |

**Health Hazards**

| | |
|---|---|
| Acute toxicity (Oral) | Category 4 |
| Skin Corrosion/Irritation | Category 2 |
| Serious Eye Damage/Eye Irritation | Category 1 |
| Skin sensitizer | Category 1 |
| Specific Target Organ Toxicity - Single Exposure | Category 3 |
| Specific Target Organ Toxicity - Repeated Exposure | Category 2 |

**Unknown toxicity**

| | |
|---|---|
| Acute toxicity, oral | 0.0 % |
| Acute toxicity, dermal | 16.6 % |
| Acute toxicity, inhalation, vapor | 64.4 % |
| Acute toxicity, inhalation, dust or mist | 70.1 % |

**Label Elements:**

**Hazard Symbol:**



**Signal Word:** Danger

**Hazard Statement:**

Combustible liquid.
Harmful if swallowed.
Causes skin irritation.
Causes serious eye damage.
May cause an allergic skin reaction.
May cause respiratory irritation.
May cause damage to organs through prolonged or repeated exposure.

**Precautionary Statements:**

**Prevention:**

Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Wear protective gloves/protective clothing/eye protection/face protection. Wash thoroughly after handling. Do not eat, drink or smoke when using this product. Contaminated work clothing should not be allowed out of the workplace. Use only outdoors or in a well-ventilated area. Do not breathe dust/fume/gas/mist/vapours/spray.

**Response:**

IF INHALED: Remove person to fresh air and keep comfortable for breathing. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. IF ON SKIN: Wash with plenty of water/… If skin irritation or rash occurs: Get medical advice/attention. IF SWALLOWED: Call a POISON CENTRE/doctor/… if you feel unwell. Rinse mouth. Immediately call a POISON CENTER/doctor. Specific treatment (see on this label). Wash contaminated clothing before reuse. In case of fire: Use CO2, dry chemical or foam for extinction. Water can be used to cool and protect exposed material.

**Storage:**

Store in a well-ventilated place. Keep cool. Keep container tightly closed. Store locked up.

**Disposal:**

Dispose of contents/container to an appropriate treatment and disposal facility in accordance with applicable laws and regulations, and product characteristics at time of disposal.

**Other hazards which do not result in GHS classification:** None identified.

## 3. Composition/information on ingredients

Lubrizol

Version: 3.0
Revision Date: 12/11/2017

| Chemical name | CAS number | Percent by Weight |
|---|---|---|
| Ethylene glycol | 107-21-1 | 30 - 40% |
| Dipropylene glycol, monomethyl ether | 34590-94-8 | 10 - 20% |
| Ethoxylated alcohol | 68131-39-5 | 5 - 10% |
| Formic acid | 64-18-6 | 5 - 10% |
| Tar bases, quinoline derivs., benzyl chloride-quaternized | 72480-70-7 | 5 - 10% |
| Cinnamaldehyde | 104-55-2 | 5 - 10% |
| Isopropyl alcohol | 67-63-0 | 1 - 5% |

## 4. First-aid measures

**General information:** Get medical advice/attention if you feel unwell.

**Ingestion:** Rinse mouth. Call a POISON CENTRE/doctor if you feel unwell.

**Inhalation:** Remove to fresh air and keep at rest in a position comfortable for breathing. Call a POISON CENTRE/doctor if you feel unwell.

**Skin Contact:** Take off contaminated clothing and wash before re-use. Wash skin thoroughly with soap and water. If skin irritation or rash occurs: Get medical attention. Launder contaminated clothing before reuse.

**Eye contact:** Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. Immediately call a POISON CENTER/doctor.

**Most important symptoms/effects, acute and delayed**

**Symptoms:** See section 11.

**Indication of immediate medical attention and special treatment needed**

**Treatment:** Treat symptomatically.

## 5. Fire-fighting measures

**General Fire Hazards:** Move containers from fire area if you can do so without risk.

**Suitable (and unsuitable) extinguishing media**

**Suitable extinguishing media:** CO2, Dry chemical or Foam. Water can be used to cool and protect exposed material.

**Unsuitable extinguishing media:** Not determined.

**Specific hazards arising from the chemical:** Vapors may cause a flash fire or ignite explosively. Prevent buildup of vapors or gases to explosive concentrations. Vapors may travel considerable distance to a source of ignition and flash back. Water may cause splattering. Container may rupture on heating. See section 10 for additional information.

**Special protective equipment and precautions for firefighters**

**Special fire fighting procedures:** No data available.

**Special protective equipment for fire-fighters:** Firefighters must use standard protective equipment including flame retardant coat, helmet with face shield, gloves, rubber boots, and in enclosed spaces, SCBA.

## 6. Accidental release measures

**Personal precautions, protective equipment and emergency procedures:** Ventilate closed spaces before entering them. ELIMINATE all ignition sources (no smoking, flares, sparks or flames in immediate area). Do not touch damaged containers or spilled material unless wearing appropriate protective clothing. Keep upwind. Keep unauthorized personnel away. See Section 8 of the SDS for Personal Protective Equipment.

**Methods and material for containment and cleaning up:** In case of leakage, eliminate all ignition sources. Dike far ahead of larger spill for later recovery and disposal. Pick up free liquid for recycle and/or disposal. Residual liquid can be absorbed on inert material. Stop the flow of material, if this is without risk. Prevent entry into waterways, sewer, basements or confined areas.

**Environmental Precautions:** Avoid release to the environment. Do not contaminate water sources or sewer. Prevent further leakage or spillage if safe to do so.

## 7. Handling and storage

**Precautions for safe handling:** Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Do not breathe dust/fume/gas/mist/vapours/spray. Do not get in eyes. Avoid contact with eyes, skin, and clothing. Avoid contact with skin. Observe good industrial hygiene practices. Use only in well-ventilated areas. Wear appropriate personal protective equipment. Wash hands thoroughly after handling. Do not eat, drink or smoke when using this product. Contaminated work clothing should not be allowed out of the workplace. Launder contaminated clothing before reuse. Avoid environmental contamination.

**Maximum Handling Temperature:** Not determined.

**Conditions for safe storage, including any incompatibilities:** Keep cool. Store in a well-ventilated place. Do not store near potential sources of ignition.

**Maximum Storage Temperature:** Not determined.

## 8. Exposure controls/personal protection

**Control Parameters:**

**Occupational Exposure Limits**

| Chemical name | Type | Exposure Limit Values | | Source |
|---|---|---|---|---|
| Ethylene glycol - Aerosol. | Ceiling | | 100 mg/m3 | US. ACGIH Threshold Limit Values (02 2012) |
| Ethylene glycol | STEL | 50 ppm | | US. ACGIH Notice of Intended Changes (NIC) to Threshold Limit Values (03 2015) |
| Ethylene glycol | TWA | | 10 mg/m3 | US. ACGIH Notice of Intended Changes (NIC) to Threshold Limit Values (03 2015) |
| Ethylene glycol | TWA | 25 ppm | | US. ACGIH Notice of Intended Changes (NIC) to Threshold Limit Values (03 2015) |
| Ethylene glycol | Ceiling | 50 ppm | 125 mg/m3 | US. OSHA Table Z-1-A (29 CFR 1910.1000) (1989) |
| Dipropylene glycol, monomethyl ether | PEL | 100 ppm | 600 mg/m3 | US. OSHA Table Z-1 Limits for Air Contaminants (29 CFR 1910.1000) (02 2006) |
| Dipropylene glycol, monomethyl ether | TWA | 100 ppm | 600 mg/m3 | US. OSHA Table Z-1-A (29 CFR 1910.1000) (1989) |
| Dipropylene glycol, monomethyl ether | STEL | 150 ppm | 900 mg/m3 | US. OSHA Table Z-1-A (29 CFR 1910.1000) (1989) |
| Dipropylene glycol, monomethyl ether | TWA | 100 ppm | | US. ACGIH Threshold Limit Values (02 2012) |
| Dipropylene glycol, monomethyl ether | STEL | 150 ppm | | US. ACGIH Threshold Limit Values (02 2012) |
| Dipropylene glycol, monomethyl ether | REL | 100 ppm | 600 mg/m3 | US. NIOSH: Pocket Guide to Chemical Hazards (2010) |
| Dipropylene glycol, monomethyl ether | STEL | 150 ppm | 900 mg/m3 | US. NIOSH: Pocket Guide to Chemical Hazards (2010) |
| Formic acid | PEL | 5 ppm | 9 mg/m3 | US. OSHA Table Z-1 Limits for Air Contaminants (29 CFR 1910.1000) (02 2006) |
| Formic acid | TWA | 5 ppm | 9 mg/m3 | US. OSHA Table Z-1-A (29 CFR 1910.1000) (1989) |
| Formic acid | TWA | 5 ppm | | US. ACGIH Threshold Limit Values (02 2012) |
| Formic acid | STEL | 10 ppm | | US. ACGIH Threshold Limit Values (02 2012) |
| Formic acid | REL | 5 ppm | 9 mg/m3 | US. NIOSH: Pocket Guide to Chemical Hazards (2010) |
| Isopropyl alcohol | TWA | 200 ppm | | US. ACGIH Threshold Limit Values (02 2012) |
| Isopropyl alcohol | STEL | 400 ppm | | US. ACGIH Threshold Limit Values (02 2012) |
| Isopropyl alcohol | REL | 400 ppm | 980 mg/m3 | US. NIOSH: Pocket Guide to Chemical Hazards (2010) |
| Isopropyl alcohol | STEL | 500 ppm | 1,225 mg/m3 | US. NIOSH: Pocket Guide to Chemical Hazards (2010) |
| Isopropyl alcohol | PEL | 400 ppm | 980 mg/m3 | US. OSHA Table Z-1 Limits for Air Contaminants (29 CFR 1910.1000) (02 2006) |

**Other exposure limits**

| Chemical name | Type | Exposure Limit Values | Source |
|---|---|---|---|
| Formic acid | TWA | 5 ppm | |
| Formic acid | STEL | 10 ppm | |

**Biological Limit Values**

| Chemical name | Exposure Limit Values | Source |
|---|---|---|
| Isopropyl alcohol (acetone: Sampling time: End of shift at end of work week.) | 40 mg/l (Urine) | ACGIH BEI (03 2013) |

**Appropriate engineering controls:** Use material in well ventilated area only. No special requirements under ordinary conditions of use and with adequate ventilation.

**Individual protection measures, such as personal protective equipment**

**General information:** Provide easy access to water supply and eye wash facilities. Good general ventilation (typically 10 air changes per hour) should be used. Ventilation rates should be matched to conditions. If applicable, use process enclosures, local exhaust ventilation, or other engineering controls to maintain airborne levels below recommended exposure limits. If exposure limits have not been established, maintain airborne levels to an acceptable level.

**Eye/face protection:** Wear tight-fitting goggles or face shield.

**Skin Protection**

**Hand Protection:** Use nitrile or neoprene gloves. Use good industrial hygiene practices. In case of skin contact, wash hands and arms with soap and water.

**Other:** Wear apron or protective clothing in case of contact. Do not wear rings, watches or similar apparel that could entrap the material.

**Respiratory Protection:** Use respirator if irritation is experienced or if the recommended exposure limit is exceeded. A respiratory protection program compliant with all applicable regulations must be followed whenever workplace conditions require the use of a respirator. Use respirator with an organic vapor and dust/mist cartridge if the recommended exposure limit is exceeded. Use self-contained breathing apparatus for entry into confined space, for other poorly ventilated areas and for large spill clean-up sites.

**Hygiene measures:** Observe good industrial hygiene practices. Do not eat, drink or smoke when using the product. Do not get in eyes. Avoid contact with skin. Wash contaminated clothing before reuse. When using do not smoke. Wash hands before breaks and immediately after handling the product. Wash hands after handling. Contaminated work clothing should not be allowed out of the workplace.

## 9. Physical and chemical properties

**Appearance**

| | |
|---|---|
| **Physical state:** | liquid |
| **Form:** | liquid |
| **Color:** | Dark amber |
| **Odor:** | Alcohol |
| **Odor threshold:** | No data available. |
| **pH:** | No data available. |
| **Freezing point:** | No data available. |
| **Boiling Point:** | 239 °F (115 °C) |
| **Flash Point:** | 181 °F (83 °C) (Closed Cup) |
| **Evaporation rate:** | No data available. |
| **Flammability (solid, gas):** | No data available. |

**Upper/lower limit on flammability or explosive limits**

| | |
|---|---|
| **Flammability limit - upper (%):** | No data available. |
| **Flammability limit - lower (%):** | No data available. |
| **Explosive limit - upper (%):** | No data available. |
| **Explosive limit - lower (%):** | No data available. |
| **Vapor pressure:** | No data available. |
| **Vapor density:** | No data available. |
| **Relative density:** | 1.08 - 1.13 60.1 °F (15.6 °C) |
| **Solubility(ies)** | |
| **Solubility in water:** | Soluble |
| **Solubility (other):** | No data available. |
| **Partition coefficient (n-octanol/water):** | No data available. |
| **Auto-ignition temperature:** | No data available. |
| **Decomposition temperature:** | No data available. |
| **Viscosity:** | No data available. |

## 10. Stability and reactivity

| | |
|---|---|
| **Reactivity:** | No data available. |
| **Chemical Stability:** | Material is stable under normal conditions. |
| **Possibility of hazardous reactions:** | Will not occur. |
| **Conditions to avoid:** | Heat, sparks, flames. |
| **Incompatible Materials:** | Oxidizing agents. Hypochlorites. Materials reactive with hydroxyl compounds. Avoid reactive metals such as sodium, calcium, zinc, etc. Reaction with peroxides may result in violent decomposition of peroxide possible creating an explosion. Strong acids. Strong oxidizing agents. |
| **Hazardous Decomposition Products:** | Thermal decomposition or combustion may generate smoke, carbon monoxide, carbon dioxide, and other products of incomplete combustion. |

## 11. Toxicological information

**Information on likely routes of exposure**

| | |
|---|---|
| **Inhalation:** | Harmful if inhaled. |
| **Ingestion:** | Harmful if swallowed. |
| **Skin Contact:** | Causes skin irritation. |
| **Eye contact:** | Causes serious eye damage. |

**Information on toxicological effects**

**Acute toxicity**

**Oral**

Product: Ingestion can cause central nervous system effects such as

headache, dizziness, drowsiness, and generalized weakness. Swallowing material may cause irritation of the gastrointestinal lining, nausea, vomiting, diarrhea, and abdominal pain. Swallowing this material causes severe irritation and may cause burns of the mouth, esophagus and stomach, abdominal pain, nausea, vomiting and diarrhea.
ATEmix 300 - 2,000 mg/kg.

**Dermal**
Product: Prolonged or widespread contact with this material could result in the absorption of potentially harmful amounts. May be harmful through skin absorption.
Not classified for acute toxicity based on available data.

**Inhalation**
Product: High concentrations may cause headaches, dizziness, weakness, and nausea. Inhalation of formic acid may damage the upper respiratory tract and lungs. Effects caused will vary with the severity of exposure, ranging from mild irritation of the nasal membranes to severe pneumonitis. Breathing high vapor concentrations may cause adverse central nervous system effects such as dizziness, light-headedness, headache, drowsiness, nausea and loss of coordination.
ATEmix (, 4 h): > 20 mg/l. Vapour

**Skin Corrosion/Irritation:**
Product: Prolonged or repeated exposure may cause a slight flaking, tenderness, and softening of skin. Prolonged or repeated contact may cause irritation. Prolonged or repeated skin contact as from clothing wet with material may cause dermatitis. Symptoms may include redness, edema, drying, and cracking of the skin.
Remarks: Causes skin irritation.

**Serious Eye Damage/Eye Irritation:**
Product: Remarks: Causes serious eye damage.

**Respiratory sensitization:**
No data available

**Skin sensitization:**

| | |
|---|---|
| Ethylene glycol | Classification: Not a skin sensitizer. (Literature) Not a skin sensitizer. |
| Formic acid | Classification: Not a skin sensitizer. (Literature) Not a skin sensitizer. |
| Cinnamaldehyde | Remarks: Category 1<br>Classification: May cause sensitization by skin contact. (Literature) |
| Isopropyl alcohol | Classification: Not a skin sensitizer. (Literature) Not a skin sensitizer. |

**Specific Target Organ Toxicity - Single Exposure:**
Ethylene glycol: If material is misted or if vapors are generated from heating, exposure may cause irritation of mucous membranes and the upper respiratory tract.

| | |
|---|---|
| Dipropylene glycol, monomethyl ether | May cause irritation to the mucous membranes and upper respiratory tract. |
| Ethoxylated alcohol | If material is misted or if vapors are generated from heating, exposure may cause irritation of mucous membranes and the upper respiratory tract. |
| Formic acid | Respiratory tract irritation. |
| Cinnamaldehyde | Nose, throat and lung irritant. |
| Isopropyl alcohol | May cause irritation to the mucous membranes and upper respiratory tract. |

**Aspiration Hazard:**

No data available

**Other effects:**

| | |
|---|---|
| Dipropylene glycol, monomethyl ether | Central nervous system |
| Isopropyl alcohol | Central nervous system May cause drowsiness or dizziness. |

**Chronic Effects**

**Carcinogenicity:**

No data available

**IARC Monographs on the Evaluation of Carcinogenic Risks to Humans:**

No carcinogenic components identified

**US. National Toxicology Program (NTP) Report on Carcinogens:**

No carcinogenic components identified

**US. OSHA Specifically Regulated Substances (29 CFR 1910.1001-1050):**

No carcinogenic components identified

**Germ Cell Mutagenicity:**

| | |
|---|---|
| Ethylene glycol | In vitro and in vivo genetic toxicity studies were negative. |
| Isopropyl alcohol | In vitro mutagenicity tests have been negative. |

**Reproductive toxicity:**

| | |
|---|---|
| Ethylene glycol | Not Classified based on available data.<br>In studies on rats, ethylene glycol has been shown not to interfere with reproduction. In studies on mice, ingestion of ethylene glycol in large amounts caused a small decrease in the number of litters per pair, live pups per litter, and in live pupweight. Based on animal studies, ingestion of ethylene glycol appears to be the major and possibly only route of exposure to produce birth defects. Exposures by inhalation (tested nose only in animals) or skin contact, the primary routes of occupational exposure, have minimal or essentially no effect on the fetus. |
| Isopropyl alcohol | Teratogenic effects have been observed in laboratory animals only at maternally toxic doses. |

**Specific Target Organ Toxicity - Repeated Exposure:**

| | |
|---|---|
| Ethylene glycol | Long term dietary intake of ethylene glycol caused liver and kidney effects and deposition of calcium salts in various tissues in animals. Excessive exposure may cause CNS effects, cardiopulmonary effects (metabolic acid- osis), and kidney failure. Oral: Target Organ(s): Kidney |

## 12. Ecological information

**Ecotoxicity**

**Fish**

| | |
|---|---|
| Ethylene glycol | LC 50 (Fathead Minnow, 4 d): 72,860 mg/l<br>NOEC (Fathead Minnow, 7 d): 15,380 mg/l |
| Dipropylene glycol, monomethyl ether | LC 50 (Not reported, 4 d): > 1,000 mg/l |
| Formic acid | LC 50 (Zebra danio (Danio rerio), 96 h): 130 mg/l |

**Aquatic Invertebrates**

| | |
|---|---|
| Ethylene glycol | EC 50 (Water Flea (Daphnia Magna), 2 d): > 100 mg/l<br>NOEC (Water Flea (Daphnia Magna), 7 d): 8,590 mg/l |
| Dipropylene glycol, monomethyl ether | EC 50 (Water flea (Daphnia magna), 2 d): > 1,000 mg/l |
| Formic acid | EC 50 (Water Flea (Daphnia Magna), 2 d): 365 mg/l<br>NOEC (Water flea (Daphnia magna), 21 d): < 100 mg/l |

**Toxicity to Aquatic Plants**

| | |
|---|---|
| Ethylene glycol | EC 50 (Algae (Pseudokirchneriella subcapitata), 4 d): 6,500 - 13,000 mg/l |
| Formic acid | EC 50 (Alga, 72 h): 1,240 mg/l |

**Toxicity to soil dwelling organisms**

No data available

**Sediment Toxicity**
No data available

**Toxicity to Terrestrial Plants**
No data available

**Toxicity to Above-Ground Organisms**
No data available

**Toxicity to microorganisms**
No data available

**Persistence and Degradability**
**Biodegradation**

| | |
|---|---|
| Ethylene glycol | OECD TG 301 A, 90 - 100 %, Readily biodegradable |
| Dipropylene glycol, monomethyl ether | Miscellaneous, 75 %, 28 d, Readily biodegradable |
| Formic acid | OECD TG 301 D, 100 %, 9 d, Readily biodegradable |

**Bioaccumulative Potential**
**Bioconcentration Factor (BCF)**
No data available

**Partition Coefficient n-octanol / water (log Kow)**

| | |
|---|---|
| Ethylene glycol | Log Kow: -1.36 |
| Dipropylene glycol, monomethyl ether | Log Kow: 0.004 25 °C 77 °F |
| Formic acid | Log Kow: -1.9 (Measured) |

**Mobility:**
No data available

**Other Adverse Effects:** No data available.

## 13. Disposal considerations

**Disposal instructions:** Treatment, storage, transportation, and disposal must be in accordance with applicable Federal, State/Provincial, and Local regulations. Dispose of packaging or containers in accordance with local, regional, national and international regulations. Empty container contains product residue which may exhibit hazards of product.

**Contaminated Packaging:** Container packaging may exhibit hazards.

## 14. Transport information

**DOT**

| | |
|---|---|
| UN Number: | NA 1993 |
| UN Proper Shipping Name: | Combustible liquid, n.o.s.(Dipropylene glycol, monomethyl ether) |
| Transport Hazard Class(es) | |
| Class: | CBL |
| Label(s): | NONE |
| Packing Group: | III |
| Marine Pollutant: | No |
| Special precautions for user: | None established |
| Reportable quantity | Ethylene glycol 5000 lbs |

**IMDG**

Not regulated.

**IATA**

Not regulated.

**Transport in bulk according to Annex II of MARPOL and the IBC Code**

None known.

The DOT shipping information in this section is based on a bulk container. Please review the accompanying shipping papers for the correct shipping descriptions based the size of the package. Shipping descriptions may vary based on mode of transport, quantities, temperature of the material, package size, and/or origin and destination. It is the responsibility of the transporting organization to follow all applicable laws, regulations and rules relating to the transportation of the material. During transportation, steps must be taken to prevent load shifting or materials falling, and all relating legal statutes should be obeyed. Review classification requirements before shipping materials at elevated temperatures.

## 15. Regulatory information

**US Federal Regulations**

**TSCA Section 12(b) Export Notification (40 CFR 707, Subpt. D)**

None present or none present in regulated quantities.

**CERCLA Hazardous Substance List (40 CFR 302.4)**

| Chemical Identity | CAS number | Reportable quantity | Calculated[1] |
|---|---|---|---|
| Ethylene glycol | 107-21-1 | 5000 lbs | 12896 lbs<br>5850 kgs |
| Formic acid | 64-18-6 | 5000 lbs | > 50000 lbs<br>> 22680 kgs |

[1]This is the amount product/material required to be released before CERCLA reporting is required.

**Superfund Amendments and Reauthorization Act of 1986 (SARA)**

**SARA 311 Classifications**

Fire Hazard
Immediate (Acute) Health Hazards
Delayed (Chronic) Health Hazard

**SARA 302 Extremely Hazardous Substance**

None present or none present in regulated quantities.

**SARA 304 Emergency Release Notification**

| Chemical Identity | CAS number | Percent by Weight | Reportable quantity |
|---|---|---|---|
| Ethylene glycol | 107-21-1 | 38.8 % | 5000 lbs |
| Formic acid | 64-18-6 | 8.1 % | 5000 lbs |

**SARA 313 (TRI Reporting)**

| Chemical Identity | CAS number | Percent by Weight | Reporting threshold for other uses | Reporting threshold for manufacturing and processing |
|---|---|---|---|---|
| Ethylene glycol | 107-21-1 | 38.8 % | 10000 lbs | 25000 lbs |
| Formic acid | 64-18-6 | 8.1 % | 10000 lbs | 25000 lbs |
| Isopropyl alcohol | 67-63-0 | 2.4 % | 10000 lbs | 25000 lbs |

**US State Regulations**

**US. California Proposition 65**

This product contains chemical(s) known to the State of California to cause cancer and/or to cause birth defects or other reproductive harm.

Ethylene glycol 38.773%

**Inventory Status**

Australia (AICS)
May require notification before sale under Australian regulations.

Canada (DSL/NDSL)
This product contains a substance or polymer that has been notified and is restricted to import by specific legal entities.

China (IECSC)
This product may require notification in China.

European Union (REACh)
To obtain information on the REACH compliance status of this product, please e-mail REACH@SDSInquiries.com.

Japan (ENCS)
May require notification in Japan.

Korea (ECL)
May require notification before sale in Korea.

New Zealand (NZIoC)
May require notification before sale under New Zealand regulations.

Philippines (PICCS)
May require notification before sale under Philippines Republic Act 6969.

Switzerland (SWISS)
All components are in compliance with the Environmentally Hazardous Substances Ordinance in Switzerland.

Taiwan (TCSCA)
May require notification before sale in Taiwan.

United States (TSCA)
All substances contained in this product are listed on the TSCA inventory or are exempt.

*The information that was used to confirm the compliance status of this product may deviate from the chemical information shown in Section 3.*


## 16.Other information, including date of preparation or last revision

**HMIS Hazard ID**




Hazard rating: 0 - Minimal; 1 - Slight; 2 - Moderate; 3 - Serious; 4 - Severe; RNP - Rating not possible; *Chronic health effect

**NFPA Hazard ID**




Hazard rating: 0 - Minimal; 1 - Slight; 2 - Moderate; 3 - Serious; 4 - Severe; RNP - Rating not possible

| | |
|---|---|
| **Issue Date:** | 12/11/2017 |
| **Version #:** | 3.0 |
| **Source of information:** | Internal company data and other publically available resources. |
| **Further Information:** | Contact supplier (see Section 1) |
| **Disclaimer:** | As the conditions or methods of use are beyond our control, we do not assume any responsibility and expressly disclaim any liability for any use of this product. Information contained herein is believed to be true and accurate but all statements or suggestions are made without warranty, expressed or implied, regarding accuracy of the information, the hazards connected with the use of the material or the results to be obtained from the use thereof. Compliance with all applicable federal, state, and local regulations remains the responsibility of the user. |

**SDS Surfactant (Waxaid 19)**

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

## SECTION 1: Identification of the substance/mixture and of the company/undertaking

### 1.1 Product identifier

- Trade name WAXAID 19

### 1.2 Relevant identified uses of the substance or mixture and uses advised against

**Uses of the Substance / Mixture**

- Oil & gas industry

### 1.3 Details of the supplier of the safety data sheet

**Company**

Chemplex
Solvay USA Inc.
NOVECARE
506 CR 137
P.O. Box 1071
Snyder, TX 79550
Phone (325) 573-7298

### 1.4 Emergency telephone

FOR EMERGENCIES INVOLVING A SPILL, LEAK, FIRE, EXPOSURE OR ACCIDENT CONTACT: CHEMTREC 800-424-9300 within the United States and Canada, or 703-527-3887 for international collect calls.

## SECTION 2: Hazards identification

Although OSHA has not adopted the environmental portion of the GHS regulations, this document may include information on environmental effects.

### 2.1 Classification of the substance or mixture

**HCS 2012 (29 CFR 1910.1200)**

| | |
|---|---|
| Flammable liquids, Category 3 | H226: Flammable liquid and vapor. |
| Acute toxicity, Category 4 | H332: Harmful if inhaled. |
| Acute toxicity, Category 4 | H312: Harmful in contact with skin. |
| Skin irritation, Category 2 | H315: Causes skin irritation. |
| Serious eye damage, Category 1 | H318: Causes serious eye damage. |
| Skin sensitization, Category 1 | H317: May cause an allergic skin reaction. |
| Specific target organ systemic toxicity - single exposure, Category 3 | H335: May cause respiratory irritation. (Respiratory system) |
| Specific target organ systemic toxicity - repeated exposure, Category 2 | H373: May cause damage to organs through prolonged or repeated exposure. |
| Aspiration hazard, Category 1 | H304: May be fatal if swallowed and enters airways. |

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**2.2 Label elements**

**HCS 2012 (29 CFR 1910.1200)**

**Pictogram**



**Signal Word**
- Danger

**Hazard Statements**

| | |
|---|---|
| - H226 | Flammable liquid and vapor. |
| - H304 | May be fatal if swallowed and enters airways. |
| - H312 + H332 | Harmful in contact with skin or if inhaled. |
| - H315 | Causes skin irritation. |
| - H317 | May cause an allergic skin reaction. |
| - H318 | Causes serious eye damage. |
| - H335 | May cause respiratory irritation. |
| - H373 | May cause damage to organs through prolonged or repeated exposure. |

**Precautionary Statements**

Prevention

| | |
|---|---|
| - P210 | Keep away from heat/sparks/open flames/hot surfaces. No smoking. |
| - P233 | Keep container tightly closed. |
| - P240 | Ground/bond container and receiving equipment. |
| - P241 | Use explosion-proof electrical/ ventilating/ lighting/ equipment. |
| - P242 | Use only non-sparking tools. |
| - P243 | Take precautionary measures against static discharge. |
| - P260 | Do not breathe dust/ fume/ gas/ mist/ vapors/ spray. |
| - P264 | Wash skin thoroughly after handling. |
| - P271 | Use only outdoors or in a well-ventilated area. |
| - P272 | Contaminated work clothing must not be allowed out of the workplace. |
| - P280 | Wear protective gloves/ eye protection/ face protection. |

Response

| | |
|---|---|
| - P301 + P310 | IF SWALLOWED: Immediately call a POISON CENTER/doctor. |
| - P303 + P361 + P353 | IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water/shower. |
| - P304 + P340 + P312 | IF INHALED: Remove person to fresh air and keep comfortable for breathing. Call a POISON CENTER/doctor if you feel unwell. |
| - P305 + P351 + P338 + P310 | IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. Immediately call a POISON CENTER/doctor. |
| - P314 | Get medical advice/ attention if you feel unwell. |
| - P331 | Do NOT induce vomiting. |
| - P333 + P313 | If skin irritation or rash occurs: Get medical advice/ attention. |
| - P362 | Take off contaminated clothing and wash before reuse. |
| - P370 + P378 | In case of fire: Use dry sand, dry chemical or alcohol-resistant foam to extinguish. |

Storage

| | |
|---|---|
| - P403 + P233 | Store in a well-ventilated place. Keep container tightly closed. |
| - P403 + P235 | Store in a well-ventilated place. Keep cool. |
| - P405 | Store locked up. |

Disposal

| | |
|---|---|
| - P501 | Dispose of contents/ container to an approved waste disposal plant. |

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**2.3 Other hazards which do not result in classification**

- H401: Toxic to aquatic life.
- H412: Harmful to aquatic life with long lasting effects.

## SECTION 3: Composition/information on ingredients

**3.1 Substance**

- Not applicable, this product is a mixture.

**3.2 Mixture**

**Hazardous Ingredients and Impurities**

| Chemical name | Identification number CAS-No. | Concentration [%] |
|---|---|---|
| Xylene | 1330-20-7 | >= 70 - < 90 |
| Benzenesulfonic acid, C10-16-alkyl derivs., compds. with 2-propanamine | 68584-24-7 | >= 5 - < 10 |
| Ethylbenzene | 100-41-4 | >= 5 - < 10 |
| Fatty acid dimethylamide | ***** | >= 1 - < 5 |

The specific chemical identity and/or exact percentage (concentration) of composition has been withheld as a trade secret.

## SECTION 4: First aid measures

**4.1 Description of first-aid measures**

**General advice**

- Show this material safety data sheet to the doctor in attendance.
- First responder needs to protect himself.
- Place affected apparel in a sealed bag for subsequent decontamination.

**In case of inhalation**

- Remove victim from exposure and then have him lie down in the recovery position.
- If breathing is difficult, give oxygen.
- If victim has stopped breathing:
- administer CPR (cardio-pulmonary resuscitation)
- Get immediate medical advice/ attention.

**In case of skin contact**

- In case of contact, immediately flush skin with plenty of water for at least 15 minutes while removing contaminated clothing and shoes.
- Seek medical advice.
- Wash contaminated clothing before reuse.

**In case of eye contact**

- Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes.
- Seek medical advice.

**In case of ingestion**

- Do not induce vomiting without medical advice.
- If victim is conscious:
- Rinse mouth with water.
- Keep at rest.
- Do not give anything to drink.
- Do not leave the victim unattended.
- Vomiting may occur spontaneously
- Risk of product entering the lungs on vomiting after ingestion.
- Lay victim on side.
- Get immediate medical advice/ attention.

### 4.2 Most important symptoms and effects, both acute and delayed

**Effects**

- Skin contact may aggravate existing skin disease
- Inhalation of product may aggravate existing chronic respiratory problems such as asthma, emphysema or bronchitis

### 4.3 Indication of any immediate medical attention and special treatment needed

**Notes to physician**

- All treatments should be based on observed signs and symptoms of distress in the patient. Consideration should be given to the possibility that overexposure to materials other than this product may have occurred.
- Treat symptomatically.
- There is no specific antidote available.
- Aspiration of the swallowed or vomited product can cause severe pulmonary complications.

## SECTION 5: Firefighting measures

| | |
|---|---|
| **Flash point** | 77 °F (25 °C)<br>closed cup<br><br>Flammability class: Flammable |
| **Autoignition temperature** | no data available |
| **Flammability / Explosive limit** | no data available |

### 5.1 Extinguishing media

**Suitable extinguishing media**

- Extinguishing media - small fires
- Dry chemical
- Carbon dioxide ($CO_2$)
- Extinguishing media - large fires
- Foam
- Water spray

**Unsuitable extinguishing media**

- High volume water jet
- (frothing possible)

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**5.2 Special hazards arising from the substance or mixture**

**Specific hazards during fire fighting**

- Under fire conditions:
- Will burn
- Container may explode if heated.
- Vapors may spread long distances and ignite.
- Vapors are heavier than air and may spread along floors.
- Take measures to prevent the build up of electrostatic charge.

**Hazardous combustion products:**

- On combustion or on thermal decomposition (pyrolysis), releases:
- Carbon oxides
- Nitrogen oxides (NOx)
- Sulfur oxides

**5.3 Advice for firefighters**

**Special protective equipment for fire-fighters**

- Firefighters should wear NIOSH/MSHA approved self-contained breathing apparatus and full protective clothing.

**Specific fire fighting methods**

- Cool closed containers exposed to fire with water spray.
- Collect contaminated fire extinguishing water separately. This must not be discharged into drains.

## SECTION 6: Accidental release measures

**6.1 Personal precautions, protective equipment and emergency procedures**

- Ventilate the area.
- Eliminate all ignition sources if safe to do so.
- Evacuate personnel to safe areas.
- Mark the contaminated area with signs and prevent access to unauthorized personnel.

- Wear suitable protective equipment.
- For further information refer to section 8 "Exposure controls / personal protection."
- Avoid contact with eyes, skin, and respiratory system.

**6.2 Environmental precautions**

- Do not flush into surface water or sanitary sewer system.
- Take all necessary measures to avoid accidental discharge of products into drains and waterways due to the rupture of containers or transfer systems.
- Spills may be reportable to the National Response Center (800-424-8802) and to state and/or local agencies

**6.3 Methods and materials for containment and cleaning up**

***Prohibition***

- Use only non-sparking tools.

***Methods for containment***

- Stop the leak. Turn leaking containers leak-side up to prevent the escape of liquid.
- Dam up with sand or inert earth (do not use combustible materials).

***Recovery***

- Pump or collect any free spillage into an appropriate closed container. (see Section 7: Handling and Storage)
- Soak up with inert absorbent material (e.g. sand, silica gel, acid binder, universal binder, sawdust).

- Shovel or sweep up.
- Keep in suitable, closed containers for disposal.
- Never return spills in original containers for re-use.

***Decontamination / cleaning***
- Clean contaminated surface thoroughly.
- Wash nonrecoverable remainder with large amounts of water.
- Recover the cleaning water for subsequent disposal.
- Decontaminate tools, equipment and personal protective equipment in a segregated area.

***Disposal***
- Dispose of in accordance with local regulations.

**Additional advice**

- Material can create slippery conditions.

**6.4 Reference to other sections**

- 7. HANDLING AND STORAGE
- 8. EXPOSURE CONTROLS/PERSONAL PROTECTION
- 13. DISPOSAL CONSIDERATIONS

## SECTION 7: Handling and storage

**7.1 Precautions for safe handling**

- Do not use sparking tools.
- Ensure all equipment is electrically grounded before beginning transfer operations.

- Handle in accordance with good industrial hygiene and safety practice.
- Avoid contact with skin and eyes.

- Do not ingest.
- Do not breathe vapors or spray mist.

**Hygiene measures**

- Personal hygiene is an important work practice exposure control measure and the following general measures should be taken when working with or handling this materials:
- 1) Do not store, use, and/or consume foods, beverages, tobacco products, or cosmetics in areas where this material is stored.
- 2) Wash hands and face carefully before eating, drinking, using tobacco, applying cosmetics, or using the toilet.
- 3) Wash exposed skin promptly to remove accidental splashes or contact with material.

**7.2 Conditions for safe storage, including any incompatibilities**

**Technical measures/Storage conditions**

- Keep container tightly closed in a dry and well-ventilated place.

- Keep away from open flames, hot surfaces and sources of ignition.
- Keep away from incompatible materials to be indicated by the manufacturer

- Keep away from: Strong oxidizing agents

**Packaging material**

**Suitable material**
- Steel

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**Requirements for storage rooms and vessels**

**Recommended storage temperature:** < 70 °F (< 21 °C)

**7.3 Specific end use(s)**

- no data available

## SECTION 8: Exposure controls/personal protection

Introductory Remarks: These recommendations provide general guidance for handling this product. Because specific work environments and material handling practices vary, safety procedures should be developed for each intended application. Assistance with selection, use and maintenance of worker protection equipment is generally available from equipment manufacturers.

**8.1 Control parameters**

**Components with workplace occupational exposure limits**

| Ingredients | Value type | Value | Basis |
|---|---|---|---|
| Xylene | TWA | 100 ppm<br>435 mg/m3 | Occupational Safety and Health Administration - Table Z-1 Limits for Air Contaminants |
| | The value in mg/m3 is approximate. | | |
| Ethylbenzene | TWA | 20 ppm | American Conference of Governmental Industrial Hygienists |
| Ethylbenzene | TWA | 100 ppm<br>435 mg/m3 | National Institute for Occupational Safety and Health |
| Ethylbenzene | ST | 125 ppm<br>545 mg/m3 | National Institute for Occupational Safety and Health |
| Ethylbenzene | TWA | 100 ppm<br>435 mg/m3 | Occupational Safety and Health Administration - Table Z-1 Limits for Air Contaminants |
| | The value in mg/m3 is approximate. | | |

**NIOSH IDLH (Immediately Dangerous to Life or Health Concentrations)**

| Ingredients | CAS-No. | Concentration |
|---|---|---|
| Xylene | 1330-20-7 | 900 ppm |
| Ethylbenzene | 100-41-4 | 800 ppm |

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**Biological Exposure Indices**

| Ingredients | Value type | Value | Basis |
|---|---|---|---|
| Xylene | BEI | 1.5 g/g creatinine<br>Methylhippuric acids<br>Urine<br>End of shift (As soon as possible after exposure ceases) | American Conference of Governmental Industrial Hygienists |
| Ethylbenzene | BEI | 0.15 g/g creatinine<br>Sum of mandelic acid and phenyl glyoxylic acid<br>Urine<br>End of shift (As soon as possible after exposure ceases) | American Conference of Governmental Industrial Hygienists |

**8.2 Exposure controls**

**Control measures**

**Engineering measures**

- Where engineering controls are indicated by use conditions or a potential for excessive exposure exists, the following traditional exposure control techniques may be used to effectively minimize employee exposures :

- Effective exhaust ventilation system
- Extract at emission point.

**Individual protection measures**

**Respiratory protection**

- When respirators are required, select NIOSH/MSHA approved equipment based on actual or potential airborne concentrations and in accordance with the appropriate regulatory standards and/or industrial recommendations.
- Under normal conditions, in the absence of other airborne contaminants, the following devices should provide protection from this material up to the conditions specified by the appropriate local standard(s):
- Respirator with filter for organic vapor
- In the event of insufficient ventilation:
- If the occupational exposure limit is exceeded:
- Wear a positive-pressure supplied-air respirator with full facepiece.
- Have available emergency self-contained breathing apparatus or full-face airline respirator when using this chemical.

**Hand protection**

- Where there is a risk of contact with hands, use appropriate gloves
- Please observe the instructions regarding permeability and breakthrough time which are provided by the supplier of the gloves. Also take into consideration the specific local conditions under which the product is used, such as the danger of cuts, abrasion, and the contact time.
- Gloves must be inspected prior to use.
- Gloves should be discarded and replaced if there is any indication of degradation or chemical breakthrough.

**Eye protection**

- Eye and face protection requirements will vary dependent upon work environment conditions and material handling practices. Appropriate ANSI Z87 approved equipment should be selected for the particular use intended for this material.
- Eye contact should be prevented through the use of:

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

- Safety glasses with side-shields
- In case of contact through splashing:
- Face-shield

**Skin and body protection**
- Recommended preventive skin protection
- Footwear protecting against chemicals
- Impervious clothing
- Full protective suit
- Choose body protection according to the amount and concentration of the dangerous substance at the work place.

**Hygiene measures**
- Personal hygiene is an important work practice exposure control measure and the following general measures should be taken when working with or handling this materials:
- 1) Do not store, use, and/or consume foods, beverages, tobacco products, or cosmetics in areas where this material is stored.
- 2) Wash hands and face carefully before eating, drinking, using tobacco, applying cosmetics, or using the toilet.
- 3) Wash exposed skin promptly to remove accidental splashes or contact with material.

**Protective measures**
- Ensure that eyewash stations and safety showers are close to the workstation location.
- Emergency equipment immediately accessible, with instructions for use.
- The protective equipment must be selected in accordance with current local standards and in cooperation with the supplier of the protective equipment.
- Selection of appropriate personal protective equipment should be based on an evaluation of the performance characteristics of the protective equipment relative to the task(s) to be performed, conditions present, duration of use, and the potential hazards, and/or risks that may occur during use.

## SECTION 9: Physical and chemical properties

Physical and Chemical properties here represent typical properties of this product. Contact the business area using the Product information phone number in Section 1 for its exact specifications.

**9.1 Information on basic physical and chemical properties**

| | |
|---|---|
| **Appearance** | Physical state: liquid<br>Color: amber |
| **Odor** | aromatic |
| **Odor Threshold** | no data available |
| **pH** | no data available |
| **Melting point/freezing point** | no data available |
| **Initial boiling point and boiling range** | > Boiling point/boiling range: 145 - 250 °F (63 - 121 °C) |
| **Flash point** | 77 °F (25 °C) closed cup<br>Flammability class: Flammable |
| **Evaporation rate (Butylacetate = 1)** | no data available |
| **Flammability (solid, gas)** | no data available |
| **Flammability (liquids)** | no data available |
| **Flammability / Explosive limit** | no data available |

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

| | |
|---|---|
| **Autoignition temperature** | no data available |
| **Vapor pressure** | no data available |
| **Vapor density** | 3.34<br>(Air = 1.0) |
| **Density** | 7.57 LB/GAL |
| **Relative density** | 0.9<br>Water = 1 |
| **Solubility** | Water solubility:<br>negligible |
| **Partition coefficient: n-octanol/water** | no data available |
| **Decomposition temperature** | no data available |
| **Viscosity** | no data available |
| **Explosive properties** | no data available |
| **Oxidizing properties** | no data available |

**9.2 Other information**

no data available

## SECTION 10: Stability and reactivity

**10.1 Reactivity**

- no data available

**10.2 Chemical stability**

- Stable under recommended storage conditions.

**10.3 Possibility of hazardous reactions**

**polymerization**

- Hazardous polymerization does not occur.

**10.4 Conditions to avoid**

- Keep away from heat and sources of ignition.
- Keep away from flames and sparks.
- Static electricity

**10.5 Incompatible materials**

- Strong oxidizing agents

**10.6 Hazardous decomposition products**

**Hazardous decomposition products**

- On combustion or on thermal decomposition (pyrolysis), releases:
- Carbon oxides
- Nitrogen oxides (NOx)
- Sulfur oxides

## SECTION 11: Toxicological information

### 11.1 Information on toxicological effects

**Acute toxicity**

| | |
|---|---|
| **Acute oral toxicity** | Not classified as hazardous for acute oral toxicity according to GHS.<br>According to the available data on the components<br>According to the classification criteria for mixtures. |
| **Acute inhalation toxicity** | Harmful if inhaled.<br>According to the available data on the components<br>According to the classification criteria for mixtures. |
| **Acute dermal toxicity** | According to the available data on the components<br>According to the classification criteria for mixtures.<br>Harmful in contact with skin. |
| **Acute toxicity (other routes of administration)** | no data available |
| **Skin corrosion/irritation** | Causes skin irritation.<br>According to the available data on the components<br>According to the classification criteria for mixtures. |
| **Serious eye damage/eye irritation** | Risk of serious damage to eyes.<br>According to the available data on the components<br>According to the classification criteria for mixtures. |

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**Respiratory or skin sensitization**

| | |
|---|---|
| Xylene | Maximization Test - Mouse<br>Does not cause skin sensitization.<br>Method: OECD Test Guideline 429<br>Published data |
| Benzenesulfonic acid, C10-16-alkyl derivs., compds. with 2-propanamine | By analogy<br><br>Does not cause skin sensitization.<br>Published data<br>Unpublished reports |
| Ethylbenzene | Repeated Insult Patch Test - Humans<br>Dermal<br>Does not cause skin sensitization.<br>Not classified as sensitising by skin contact according to GHS criteria<br>Patch test on human volunteers did not demonstrate sensitization properties.<br>Published data |
| Fatty acid dimethylamide | Local lymph node assay - Mouse<br>EC 3 value > 2 %<br>Classified as a skin sensitizer sub-category 1B according to GHS criteria<br>Method: OECD Test Guideline 429<br>Unpublished reports |

**Mutagenicity**

| | |
|---|---|
| **Genotoxicity in vitro** | Product is not considered to be genotoxic<br>According to the available data on the components<br>According to the classification criteria for mixtures. |
| **Genotoxicity in vivo** | Product is not considered to be genotoxic<br>According to the available data on the components<br>According to the classification criteria for mixtures. |

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**Carcinogenicity**

Xylene

Rat , male and female
Oral
Exposure duration: 103 Weeks
NOAEL: > 500mg/kg bw/day
Method: Directive 67/548/EEC, Annex V, B.32.
Published data

Ethylbenzene

Rat , male and female
Inhalation
Exposure duration: 104 Weeks
NOAEL: 0.325mg/kg bw/day
Target Organs: Kidney
Method: according to a standardized method
Published data

Rat , male and female
Inhalation
Exposure duration: 104 Weeks
LOAEL: 1.084mg/kg bw/dayTarget Organs: Kidney
Method: according to a standardized method
Published data

Mouse , male and female
Inhalation
Exposure duration: 103 Weeks
NOAEC: 1.1mg/l
Method: OECD Test Guideline 453
Published data

| Ingredients | CAS-No. | Rating | Basis |
|---|---|---|---|
| Ethylbenzene | 100-41-4 | Group 2B: Possibly carcinogenic to humans | IARC |

This product does not contain any ingredient designated as probable or suspected human carcinogens by:
NTP
OSHA

**Toxicity for reproduction and development**

**Toxicity to reproduction / fertility**

According to the available data on the components, The product is not considered to affect fertility., According to the classification criteria for mixtures.

**Developmental Toxicity/Teratogenicity**

The product is not considered to be teratogenic., The product is not considered to be toxic for development., According to the available data on the components, According to the classification criteria for mixtures.

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**STOT**

| | |
|---|---|
| **STOT-single exposure** | The substance or mixture is classified as specific target organ toxicant, single exposure, category 3 with respiratory tract irritation according to GHS criteria.<br>According to the available data on the components, According to the classification criteria for mixtures. |
| **STOT-repeated exposure** | The substance or mixture is classified as specific target organ toxicant, repeated exposure, category 2 according to GHS criteria.<br>According to the available data on the components, According to the classification criteria for mixtures. |
| Xylene | Oral Chronic - Rat , male and female<br>NOAEL: 250 mg/kg<br>Method: Directive 67/548/EEC, Annex V, B.32.<br>Published data<br><br>Oral Subchronic exposure - Rat , male<br>NOAEC: 150 mg/kg<br>Target Organs: Liver, Kidney<br>Method: OECD Test Guideline 408<br>Published data<br><br>Oral Subchronic exposure - Rat , female<br>LOAEL: 150 mg/kg<br>Target Organs: Liver, Kidney<br>Method: OECD Test Guideline 408<br>Published data<br><br>Inhalation (vapor) Subchronic exposure - Rat , male<br>NOAEC: >= 3515 mg/m3<br>Method: according to a standardized method<br>Published data |
| Ethylbenzene | Oral 90-day - Rat , male and female<br>NOAEL: 75 mg/kg<br>Target Organs: Kidney<br>Method: OECD Test Guideline 408<br>Gavage<br>Effects on the kidney not relevant for humans.<br>Published data<br><br>inhalation (vapor) two-year - Rat , male and female<br>LOAEC: 325 mg/m3<br>Target Organs: Kidney<br>Method: OECD Test Guideline 453<br>Effects on the kidney not relevant for humans.<br>Published data<br><br>May cause damage to organs through prolonged or repeated exposure if inhaled.<br>inhalation (vapor) 90-day - Rat<br>LOAEC: 200 ppm<br>Target Organs: hearing organs<br>Published data |
| Fatty acid dimethylamide | Oral - Rat , male<br>NOAEL: 50 mg/kg bw/day<br>Method: OECD Test Guideline 422<br>Unpublished reports |

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**Neurological effects**
Xylene — Rat, male and female, inhalation (vapor), Published data, OPPTS 870.3800

**Experience with human exposure** — no data available

**CMR effects**

**Carcinogenicity**
Xylene — Animal testing did not show any carcinogenic effects.

**Mutagenicity**
Xylene — Animal testing did not show any mutagenic effects.

**Teratogenicity**
Xylene — Did not show teratogenic effects in animal experiments.

**Reproductive toxicity**
Xylene — Animal testing did not show any effects on fertility.

**Aspiration toxicity** — According to the available data on the components, May be fatal if swallowed and enters airways., According to the classification criteria for mixtures.

## SECTION 12: Ecological information

**12.1 Toxicity**

**Aquatic Compartment**

| | |
|---|---|
| **Acute toxicity to fish** | The product itself has not been tested. |
| **Acute toxicity to daphnia and other aquatic invertebrates.** | The product itself has not been tested. |
| **Toxicity to aquatic plants** | The product itself has not been tested. |
| **Toxicity to microorganisms** | The product itself has not been tested. |
| **Chronic toxicity to fish** | The product itself has not been tested. |
| **Chronic toxicity to daphnia and other aquatic invertebrates.** | The product itself has not been tested. |

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**Chronic Toxicity to aquatic plants** The product itself has not been tested.

**Terrestrial Compartment**

**Toxicity to soil dwelling organisms** The product itself has not been tested.

**Toxicity to terrestrial plants** The product itself has not been tested.

**Toxicity to above ground organisms** The product itself has not been tested.

**12.2 Persistence and degradability**

**Abiotic degradation** no data available

**Physical- and photo-chemical elimination** no data available

**Biodegradation** no data available

**12.3 Bioaccumulative potential**

**Partition coefficient: n-octanol/water** no data available

**Bioconcentration factor (BCF)** no data available

**12.4 Mobility in soil**

**Adsorption potential (Koc)** no data available

**Known distribution to environmental compartments** no data available

**12.5 Results of PBT and vPvB assessment** no data available

**12.6 Other adverse effects**

**Ecotoxicity assessment**

**Acute aquatic toxicity** According to the available data on the components Toxic to aquatic life.
According to the classification criteria for mixtures.

**Chronic aquatic toxicity** According to the available data on the components Harmful to aquatic life with long lasting effects.
According to the classification criteria for mixtures.

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

## SECTION 13: Disposal considerations

**13.1 Waste treatment methods**

**Product Disposal**

- Chemical additions, processing or otherwise altering this material may make the waste management information presented in this SDS incomplete, inaccurate or otherwise inappropriate. Please be advised that state and local requirements for waste disposal may be more restrictive or otherwise different from federal laws and regulations. Consult state and local regulations regarding the proper disposal of this material.

**Waste Code**

- Environmental Protection Agency
- Hazardous Waste – YES

- RCRA Hazardous Waste (40 CFR 302)
- D001 - Ignitable waste – (I)

**Advice on cleaning and disposal of packaging**

- Rinse with an appropriate solvent.
- Dispose of contents/container in accordance with local regulation.

## SECTION 14: Transport information

Transportation status: IMPORTANT! Statements below provide additional data on listed transport classification.
The listed Transportation Classification does not address regulatory variations due to changes in package size, mode of shipment or other regulatory descriptors.

**DOT**

| | |
|---|---|
| **14.1 UN number** | UN 1993 |
| **14.2 Proper shipping name** | FLAMMABLE LIQUIDS, N.O.S. (Xylene, Ethylbenzene) |
| **14.3 Transport hazard class**<br>Label(s) | 3<br>3 |
| **14.4 Packing group**<br>Packing group<br>ERG No | <br>III<br>128 |
| **14.5 Environmental hazards**<br>**Marine pollutant** | NO |

**14.6 Special precautions for user**

This product contains one or more ingredients identified as a hazardous substance in Appendix A of 49 CFR 172.101. The product quantity, in one package, which triggers the RQ requirements under 49 CFR for each hazardous substance is shown.

| | | |
|---|---|---|
| Reportable quantities | : | RQ substance: Xylene<br>RQ limit for substance: 100 lb<br>RQ limit for product: 129 lb<br><br>RQ substance: Ethylbenzene<br>RQ limit for substance: 1,000 lb<br>RQ limit for product: 11,656 lb |

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**TDG**

| | |
|---|---|
| **14.1 UN number** | UN 1993 |
| **14.2 Proper shipping name** | FLAMMABLE LIQUID, N.O.S. (Xylene, Ethylbenzene) |
| **14.3 Transport hazard class**<br>Label(s) | 3<br>3 |
| **14.4 Packing group**<br>Packing group<br>ERG No | <br>III<br>128 |
| **14.5 Environmental hazards**<br>**Marine pollutant** | NO |

**NOM**

no data available

**IMDG**

| | |
|---|---|
| **14.1 UN number** | UN 1993 |
| **14.2 Proper shipping name** | FLAMMABLE LIQUID, N.O.S. (Xylene, Ethylbenzene) |
| **14.3 Transport hazard class**<br>Label(s) | 3<br>3 |
| **14.4 Packing group**<br>Packing group | <br>III |
| **14.5 Environmental hazards**<br>**Marine pollutant** | NO |
| **14.6 Special precautions for user**<br>EmS | <br>F-E , S-E |

For personal protection see section 8.

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**IATA**

| | |
|---|---|
| **14.1 UN number** | UN 1993 |
| **14.2 Proper shipping name** | FLAMMABLE LIQUID, N.O.S. (Xylene, Ethylbenzene) |
| **14.3 Transport hazard class**<br>Label(s): | 3<br>3 |
| **14.4 Packing group**<br>Packing group | III |
| Packing instruction (cargo aircraft)<br>Max net qty / pkg<br>Packing instruction (passenger aircraft)<br>Max net qty / pkg | 366<br>220.00 L<br>355<br>60.00 L |
| **14.5 Environmental hazards** | NO |

**14.6 Special precautions for user**
For personal protection see section 8.

Note: The above regulatory prescriptions are those valid on the date of publication of this sheet. Given the possible evolution of transportation regulations for hazardous materials, it would be advisable to check their validity with your sales office.

## SECTION 15: Regulatory information

**15.1 Notification status**

| Inventory Information | Status |
|---|---|
| United States TSCA Inventory | - Listed on Inventory |
| Canadian Domestic Substances List (DSL) | - Listed on Inventory |
| Australia Inventory of Chemical Substances (AICS) | - Listed on Inventory |
| Japan. CSCL - Inventory of Existing and New Chemical Substances | - One or more components not listed on inventory |
| Korea. Korean Existing Chemicals Inventory (KECI) | - One or more components not listed on inventory |
| China. Inventory of Existing Chemical Substances in China (IECSC) | - One or more components not listed on inventory |
| Philippines Inventory of Chemicals and Chemical Substances (PICCS) | - One or more components not listed on inventory |
| Taiwan Chemical Substance Inventory (TCSI) | - Listed on Inventory |

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**15.2 Federal Regulations**

**US. EPA EPCRA SARA Title III**

**SARA Hazard Designation Sections 311/312 (40 CFR 370)**

| | |
|---|---|
| Fire Hazard | yes |
| Reactivity Hazard | no |
| Sudden Release of Pressure Hazard | no |
| Acute Health Hazard | yes |
| Chronic Health Hazard | yes |

**Section 313 Toxic Chemicals (40 CFR 372.65)**
The following components are subject to reporting levels established by SARA Title III, Section 313:

| Ingredients | CAS-No. | Concentration |
|---|---|---|
| Xylene | 1330-20-7 | 70- 90% |
| Ethylbenzene | 100-41-4 | 5- 10% |

**Section 302 Emergency Planning Extremely Hazardous Substance Threshold Planning Quantity (40 CFR 355)**
This material does not contain any components with a section 302 EHS TPQ.

**Section 302 Emergency Planning Extremely Hazardous Substance Reportable Quantity (40 CFR 355)**
This material does not contain any components with a SARA 302 RQ.

**Section 304 Emergency Release Notification Reportable Quantity (40 CFR 355)**
This material does not contain any components with a section 304 EHS RQ.

**US. EPA CERCLA Hazardous Substances and Reportable Quantities (40 CFR 302.4)**

| Ingredients | CAS-No. | Reportable quantity |
|---|---|---|
| Xylene | 1330-20-7 | 100 lb |
| Selenium | 7782-49-2 | 100 lb |
| Selenium | 7782-49-2 | 10 lb |

**15.3 State Regulations**

**US. California Safe Drinking Water & Toxic Enforcement Act (Proposition 65)**

WARNING! This product contains a chemical known in the State of California to cause cancer.

| Ingredients | CAS-No. |
|---|---|
| Ethylbenzene | 100-41-4 |
| Arsenic | 7440-38-2 |
| Methanamine, N-methyl-N-nitroso- | 62-75-9 |

## SECTION 16: Other information

**NFPA (National Fire Protection Association) - Classification**

| | |
|---|---|
| Health | 2 moderate |
| Flammability | 3 Liquids and solids that can be ignited under almost all ambient temperature conditions. |
| Instability or Reactivity | 0 minimal |

SAFETY DATA SHEET

**WAXAID 19**

Revision Date 11/20/2017

**HMIS (Hazardous Materials Identification System (Paint & Coating)) - Classification**

| | |
|---|---|
| Health | 2 moderate |
| Flammability | 3 serious |
| Reactivity | 0 minimal |
| PPE | Determined by User; dependent on local conditions |

**Date Prepared:** 11/20/2017

**Key or legend to abbreviations and acronyms used in the safety data sheet**

| | |
|---|---|
| - ST | STEL - 15-minute TWA exposure that should not be exceeded at any time during a workday |
| - STEL | Short-term exposure limit |
| - TWA | 8-hour, time-weighted average |
| - ACGIH | American Conference of Governmental Industrial Hygienists |
| - OSHA | Occupational Safety and Health Administration |
| - NTP | National Toxicology Program |
| - IARC | International Agency for Research on Cancer |
| - NIOSH | National Institute for Occupational Safety and Health |


The information provided in this Safety Data Sheet is correct to the best of our knowledge, information, and belief at the date of its publication. Such information is only given as a guidance to help the user handle, use, process, store, transport, dispose, and release the product in satisfactory safety conditions and is not to be considered as a warranty or quality specification. It should be used in conjunction with technical sheets but do not replace them. Thus, the information only relates to the designated specific product and may not be applicable if such product is used in combination with other materials or in any other manufacturing process, unless otherwise specifically indicated. It does not release the user from ensuring he is in conformity with all regulations linked to its activity.

# CCS2 Backflow Maintenance Procedure



**Approved By:** **Plant Manager**
**Alcohol Superintendent**

## 1.0 Scope

**1.1** The CCS2 well can experience particulate fouling of the perforations leading to higher downhole tubing pressure. The higher downhole pressure reaches the limit of 4,125 PSIA at progressively lower injection rates. A controlled backflow of the well will displace the particulates from the well perforations and allow them to settle to the bottom of the wellbore.

## 2.0 Definitions

2.1 **CCS2:** Carbon Capture Sequestration Injection Well #2

2.2 **RF8:** Location RF8 is the building associated with CO2 Phase 2 blowers and compression

2.3 **PPE:** Personal Protective Equipment

## 3.0 Responsibilities

**3.1 CCS Project Manager (PM):**

3.1.1 Oversees the operation of the CO2 well injection process and backflow operation.

3.1.2 Ensures operability of radio communication and maintains communication with all affected colleagues: at the well, production personnel monitoring the parameters of the well, ADM Security and others as applicable.

3.1.3 Monitors atmospheric conditions to ensure adequacy prior to commencement ofthe backflow operation.

3.1.4 Maintains responsibility for work conducted on the CCS2 equipment.

3.1.5 Ensures all necessary tools and equipment are on site.

3.1.6 In conjunction with the S/E Manager, will determine the level of PPE required for the backflow operation and will ensure personnel on site are trained and/or certified on the use of PPE. If warranted by the environmental conditions, the CCS and S/E managers may designate backup personnel wearing supplied breathing air to block in the well.

3.1.7 Confirms nitrogen supply at well site. Nitrogen is required to open the automatic upper master valve.

3.1.8 Communicates the backflow operation date and time to Richland Community College (RCC).

3.1.9 Coordinates with ADM Security to ensure security personnel are available during times of the backflow operation to limit access to the well site.

**3.2 Safety/Environmental (S/E) Manager:**

3.2.1 Confirms personal CO2 monitors are available for all personnel at the wellsite during backflow operations.

3.2.2 Confirms all on site CO2 atmospheric monitors are operating properly and in good working order.

3.2.3 Confirms all personnel at the well site have adequate PPE including, but not limited to, hard hat, goggles, long sleeve shirts, gloves with a cut rating of 2 or higher, and double hearing protection (ear plugs and soundproof earmuffs).

3.2.4 Conducts a Job Safety Analysis (JSA) form on the day of the event prior to the back flow operation.

3.2.5 Maintains full authority to stop operations at any time during the backflow operation.

**3.3 Engineer in Charge**

3.3.1 Strictly focuses on incoming and outgoing communications as needed.

**3.4 ADM Security:**

3.4.1 Limits access to the road entrance to the well site.

3.4.2 Ensures constant monitoring of backflow operation radio communication.

3.4.3 Maintains constant radio communication with the CCS PM and S/E Manager for the duration of the backflow operation.

## 4.0 Potential Hazards

**4.1** **Carbon dioxide (CO2):** Carbon Dioxide gas is colorless. At low concentrations, the gas is odorless. At higher concentrations it has a sharp, acidic odor. It will act as an asphyxiant and an irritant. Carbon Dioxide is a powerful cerebral dilator. At concentrations between 2 and 10%, Carbon Dioxide can cause nausea, dizziness, headache, mental confusion, increased blood pressure and respiratory rate. Above 8% nausea and vomiting appear. Above 10%, suffocation and death can occur within minutes. Contact with the cold gas can cause freezing of exposed tissue. Moisture in the air can lead to formation of carbonic acid that can irritate the eyes. All forms of Carbon Dioxide are noncombustible. Carbon Dioxide is heavier than air and should not be allowed to accumulate in low lying areas.

**4.2** **Noise:** The CO2 backflow operation will produce noise levels in excess of 85 decibels. Noise levels above 85 decibels can cause permanent damage to the hair cells in the inner ear, leading to hearing loss. It is required by OSHA to wear double hearing protection consisting of ear plugs and earmuffs when noise levels reach 140 decibels or more.

**4.3** **Particulate:** The backflow operation may produce minor levels of sandy particulate to be suspended in the air. The operation should be stopped at the discretion of the S/E Manager if particulate levels are higher than expected.

**4.4** **Temperature**: A pressure drop in the lower assembly causes it to become cold. If temperatures extend outside the backflow range, particularly below -10°F, operations will begin to close the valve to decrease the flowback operation.

- **Operating Range**: Wellhead valves have an operating range of -20° to 1,300°F.
- **During Backflow**: Typically, 0° to 5°F.

**IMPORTANT:** ***All activity <u>shall cease</u> if temperature falls below -10°F.***

**4.5** Pressure:

- **Operational Rating**: All wellhead valves except the bottom casing flange are rated up to 5,000 PSIG. The bottom casing flange is rated up to 3,000 PSIG.
- **During Backflow**: 135 PSIG or less.

**IMPORTANT:** ***All activity shall cease if pressure exceeds 3,000 PSIG.***

**4.6** **Emergency and Remedial Response**: In the event that the Backflow Emergency and Remedial Response Plan (180.05.CO2.207 CCS Backflow Emergency and Remedial Response Plan) is activated and/or followed, ADM shall implement the verbal and written reporting requirements set forth in Section N(3) of Permit #IL-115-6A-0001.

## 5.0 Procedure

**5.1** CCS PM and S/E Manager confirms all site conditions are met before proceeding with backflow operationtemperature and wind conditions are conducive to CO2 mixing in atmosphere. Because multiple factors can affect these criteria, they will determine if the site conditions allow safe operation or additional PPE and/or monitoring instruments are necessary to perform the operation. The general environmental conditions considered optimal for this activity are as follows:

5.1.1 Temperature greater than or equal to 40°F and 5 mph wind speed, or

5.1.2 Temperature less than 40°F and wind speed greater than 10 mph.

**5.2** All personnel at well site on day of backflow operation must participate in the review of a Job Safety Analysis (JSA) led by the S/E Manager.

5.2.1 At any time during the backflow operation, the S/E Manager has full authority to stop operation.

**5.3** S/E Manager confirms all colleagues at well site have proper PPE and personal CO2 monitors.

**5.4** CCS PM and S/E Manager conduct a test of the automatic (upper) valve to verify closure.

**5.5** After verifying valve closure, open the automatic (upper) valve.

**5.6** CCS PM verifies radio communication is operational between all affected personnel.

**5.7** CCS PM informs ADM Security to limit public access to the road entrance to the well site.

**5.8** CCS PM informs ADM Security – GSOC operations will begin.

**5.9** CCS PM coordinates stopping well injection at the plant.

**5.10** CCS PM communicates their intention to commence the backflow operation.

**5.11** S/E Manager assesses the area confirming no colleagues are downwind of the wellinjection valve.

**5.12** **S/E Manager provides confirmation backflow operation may begin.**

**5.13** CCS PM ensures radio communication with CO2 Operator and that they are standing by at RF8 Control Room. CCS PM confirms phone communication as a backup method.

**5.14** CCS PM continuously monitors operation of surface and downhole sensors (e.g., pressure, temperature) during and after the backflow operations.

**5.15** **Close** the Lower Master Valve and record number of turns (29.5) for closure.

**5.16** Disengage the open Automatic (Upper) Master Valve by deactivating the local solenoid or engaging a mechanical locking device. In either case, field personnel will be able to manually activate these devices if the valve is needed for well isolation.

**5.17** **Close** the Injection Wing Valve and record number of turns (29) for closure.

**5.18** Check the top cap making sure it is secure and tight.

**5.19** Check the position of the Crown Valve by opening the valve 5 turns and fully closing the valve. The valve is in the **closed** position.

**5.20** Open the Needle Valve located above the Crown Valve. Allow pressure to bleed off the upper section of the wellhead (above the Crown Valve).

**5.21** After pressure is bled from the upper section of the wellhead, slowly remove the top cap located above the Crown Valve (Operator has the option to install a choke or throttle valve on top of wellhead or diversion connection and valve from secondary wing valve).

**5.22** Ensure all personnel onsite are prepared for commencement of backflow operation.

5.22.1 Check in with all key personnel off site via Radio or Telephone to inform them backflow operation will begin.

5.22.2 CCS PM ensures all conditions are met and all are personnel are ready.

5.22.3 Engineer in charge is on site and will strictly focus on incoming andoutgoing communications as needed.

5.22.4 S/E Manager confirms all onsite personnel are wearing the proper PPE and prepared for operating and communicating in a loud environment

5.22.5 Remove all unnecessary vehicles proximate or downwind of the wellhead as someliquids or fines may possibly settle.

**Backflow Operation Commencement**

**5.23** **Slowly** open the Crown Valve allowing the pressure above the Lower Master Valve to bleed off. Record the number of turns (29) required to open the valve.

**5.24** **Quickly** open Lower Master Valve counting the number of turns (29.5 turns) to open (matching recorded turns in step 5.15) and observing the developing CO2 plume.

**5.25** Back flow the well for the allotted time period.

**5.26** Monitor atmospheric conditions at the wellhead via CO2 monitors.

**5.27** Maintain all personnel (not monitoring environmental conditions) upwind.

**5.28** **Quickly** close Lower Master Valve (29.5 turns).

**5.29** Allow reservoir pressure to recover for the allotted time period.

**5.30** Repeat step 5.24.

**5.31** Engineer in charge will designate the number of valve cycles that will be conducted during the backflow period.

**5.32** Engineer in charge may elect to suspend venting if environmental or operating conditions deteriorate.

**5.33** Monitor DTS temperature profile and wellhead temperature and pressure.

**5.34** Maintain communications with the Control Room CO2 Operator.

**5.35** Maintain communications with security rover with CO2 monitors that aremonitoring environmental conditions.

**5.36** Secure additional areas as needed.

**5.37** Upon completion of the valve cycling, on the last open cycle, allow the well to back flow

for the allotted time (to displace all material in the wellbore).

**5.38** Close the Lower Master Valve counting the turns (29.5).

**5.39** Close the Crown Valve counting the turns (29).

**5.40** Continue monitoring site conditions for an additional 30 minutes.

**5.41** At this point, the backflow operation is complete and the engineer in charge will determine the time and coordinate the starting of injection operations.

## 6.0 Required Training

**6.1** **Supplied Air Respirator Fit Testing:** Personnel using supplied air respirator equipment are trained on the proper fitting and operation of the supplied air respirator.

## 7.0 Records

**7.1** **Carbon Dioxide Venting Calculation:** The amount of CO2 emitted to the atmosphere must be calculated to be included on the greenhouse gas report for submittal the following year.

**7.2** **Particulate Matter Venting Calculation:** The amount of particulate matter estimated to be emitted to the atmosphere must be calculated to demonstrate the backflow operation is insignificant and an air construction permit is not required to be issued prior to the operation.


**7.3** **Job Safety Analysis:** A completed JSA form must be reviewed by all affected colleagues prior to the start of the backflow operation.

**7.4** **Air Supply Respirator Training:** Training records will be available upon request for the personnel wearing a supplied air respirator.

## 8.0 References - None

## 9.0 Figures

**9.1 Figure 1: CCS#2 Well Head Diagram**


(67.15)
Optional 4 ½" Choke
Optional
(22.80)
(36.68)
Crown Valve
Injection
Wing Valve
2-1/16" 5K WING
5-1/8" 5K WING
13'- 8"
Upper
Master Valve
Automatic
S/D Valve
5-1/
(104.34)
Lower
Master Valve
Annulus
Wing Valve
11" 5K FLANGE
2-1/16" 5K OUTLET
(23.87)
(10.81)
13-5/8" 3K FLANGE
Ø9 5/8" CASING
Ø5 1/2" CASING
NATIONAL OILWELL VARCO
SCHLUMBERGER WELLHEAD LAYOUT
13-5/8" 3K X 11" 5K X 5-1/8" 5K
DRAWING NUMBER SL-644
01

## 10.0 Attachments

### 10.1 Job Safety Analysis

#### 10.1.1 Front

## JOB SAFETY ANALYSIS (JSA)

Nº

Department/Area/Floor: | Date: ____/____/____ | Time: ____:____h

Task/Job name:

Description of the work:

Participants (print names):

**POTENTIAL HAZARDS**

| | | | | | |
|---|---|---|---|---|---|
| 01 | **Slips, trips or falls from same level** (surface condition, slippery floor, lack of housekeeping) | 11 | **Electricity** (shock, fire, arc flash, blast or stored electrical energy, static) | 21 | **Manual lifting** (physical effort, weight, position, duration, shape) |
| 02 | **Fall from height or into pit or floor opening** (scaffolds, ladder) | 12 | **Hot or cold material, equipment or environment** | 22 | **Hoisting, lifting** (use of mechanical equipment) |
| 03 | **Hit by projectile or defleected objects** (disintegration, rupture, debries) | 13 | **Chemical** (irritant, toxic, poison, corrosive) | 23 | **Ergonomic** (pushing, vibration, pulling, reaching, force, repetitive) |
| 04 | **Hit from above** (falling or collapsing object or product) | 14 | **Atmospheric** (dust, toxic, poison, lack of oxygen) | 24 | **Access** (difficult to reach, reduced space to work or rescue) |
| 05 | **Contacted by** (animals, insects, plants, chemicals, product) | 15 | **Static energy** (shock, ignition source) | 25 | **Weather condition** (excessive heat, snow, ice, rain, lightning, flood, wind) |
| 06 | **Caught in or between, being drawn in** (movable parts) | 16 | **Energy release** (gravity, hydraulic, system under pressure, springs, mechanical releases) | 26 | **Biological** (Pathogens, hygiene, bacteria, pest control, mold) |
| 07 | **Sharp edges, stabbing, puncturing** (equipment or tools) | 17 | **Fire, explosion** (flammable liquid or gas, vapor, dust in suspension, mechanical releases) | 27 | **Radiation** (Ionizing, non-ionizing, laser, electromagnetic) |
| 08 | **Pinch, crush** | 18 | **Excavation** (collapse, egress, underground utilities, trenching) | 28 | **Environmental** (contamination of air, water or soil) |
| 09 | **Struck by** (collision, impact with fixed object or vehicles) | 19 | **Noise, vibration** (continuous, intermittent, impact) | 29 | **Product contamination** |
| 10 | **Lighting, visibility, reflections, glare** | 20 | **Engulfment, entrapment** (product, moving equipment or configuration, excavation) | 30 | |


**ADM RISK ASSESSMENT TOOL**

**JSA Work Permit Requirements:**
**16:** Unacceptable level of risk. Task should not be performed at current risk level.
**12:** Requires review from reporting level above plant manager.
**8 - 9:** Requires review by management.
**4 - 6:** Review by management is recommended.
**1 - 3:** Trained participants can perform task without further approval.
**Every effort should be made to reduce the risk to below 8.**

| | | L - LIKELIHOOD (CONSIDERING THE SAFEGUARDS) | | | |
|---|---|---|---|---|---|
| | | Control measure non existent or inadequate | Control measure exists, but effectiveness is not guaranteed | Multiple control measures exist, but effectiveness is not guaranteed | Multiple control measures are effective |
| | | Likely | Occasional | Improbable | Very Unlikely |
| S - Injury Severity | | 4 | 3 | 2 | 1 |
| **Catastrophic:** Fatalities or incapacitating cases. | 4 | 16 | 12 | 8 | 4 |
| **Very Serious:** Permanent disability, but not incapacitating. | 3 | 12 | 9 | 6 | 3 |
| **Serious:** Lost or restricted work day cases. | 2 | 8 | 6 | 4 | 2 |
| **Minor:** Medical treatment or first aid cases (recordable and below). | 1 | 4 | 3 | 2 | 1 |

| STEP Nº. | SEQUENCE OF BASIC STEPS | POTENTIAL HAZARDS | S Factor | SAFE PRACTICES / CONTROL MEASURES (see reverse for supporting checklist) | L Factor | RISK (S x L) |
|---|---|---|---|---|---|---|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

### 10.1.2 Back



**REQUIRED PERMITS AND FORMS**

- ☐ Confined space/bin entry
- ☐ Hot work
- ☐ Equipment-specific lock out/ tag out procedure
- ☐ Line breaking
- ☐ Fire protection impairment
- ☐ Working at height/roof access
- ☐ Energized electrical work
- ☐ Crane/critical lift
- ☐ Rail track encroachment
- ☐ Soil disturbance/excavation
- ☐ Other_____

**PERSONAL PROTECTIVE EQUIPMENT**

**EYE/FACE**
- ☐ Sealed/tightfitting eyewear
- ☐ Welding hood/shaded lens
- ☐ Goggles ☐ Face shield
- ☐ Other: _____

**HAND/ARM**
- ☐ Cut resistant ☐ Chemical
- ☐ Thermal ☐ Leather
- ☐ Disposable ☐ Mechanical
- ☐ Arm/sleeve ☐ Other: ____

**FOOT**
- ☐ Safety toe boots ☐ Chemical boots
- ☐ Chainsaw footwear ☐ Puncture resistant
- ☐ Meta tarsal guards/boot covers
- ☐ Other: _____

**ELECTRICAL**
- ☐ Hard hat - class E ☐ Gloves
- ☐ Leather protectors ☐ Grounding
- ☐ Arc rated suit ☐ Safety glasses
- ☐ Arc rated balaclava ☐ Dielectric mat
- ☐ Arc rated clothing ☐ Voltage rated gloves
- ☐ Arc rated face shield
- ☐ Dielectric blankets/sleeves ☐ Double layered switching hood
- ☐ Hearing protection

**RESPIRATORY PROTECTION**
- ☐ Filtering face piece ☐ SCBA
- ☐ Supplied air ☐ PAPR
- ☐ Emergency escape ☐ Half face
- ☐ Air purifying respirator ☐ Full face
- ☐ Other: _____ ☐ Cartridge type: ____

**SPECIAL CLOTHING**
- ☐ Chemical suit
- ☐ Rain suit
- ☐ Anti-exposure suit
- ☐ Contaminate protection
- ☐ Other: _____

**FALL**
- ☐ Harness ☐ Double lanyard
- ☐ Appropriate anchorage point
- ☐ Additional anchorage connector
- ☐ SRL/retractable device
- ☐ Horizontal lifeline system

**ADDITIONAL OR TASK-SPECIFIC PPE**

**SAFE PRACTICES / CONTROL MEASURES SUPPORTING CHECKLIST**

**01**
- ☐ Mark hazards ☐ Store tools and materials ☐ Keep eyes on path
- ☐ Review work pace ☐ Create designated walkway ☐ Install barricade
- ☐ Clear work zone of debris, grain, product

**02**
- ☐ Use fall protection with proper anchorage ☐ Use fall restraint system
- ☐ Install barricade, rigid cable, railing, cover ☐ Post signage for pedestrians
- ☐ Use correct ladder, mobile platform, scaffolding on even, solid surface

**03**
- ☐ Use eye and face protection properly ☐ Ensure proper distance between workers
- ☐ Coordinate work in same area ☐ Install barricade ☐ Inspect hand-held power tools
- ☐ Ensure nearby machines are properly guarded or shut down

**04**
- ☐ Install warning barricade, signage ☐ Ensure proper distance between workers, tools
- ☐ Coordinate work in area ☐ Prevent tools and materials from falling
- ☐ Check for, communicate with workers above or below

**05**
- ☐ Inspect and clear area of animals, insects, poisonous plants
- ☐ Inspect for chemical exposure ☐ Locate eyewash/shower station: _____

**06**
- ☐ Use anchorage, secure load ☐ Maintain proper distance
- ☐ Install guarding ☐ Follow LOTO procedure
- ☐ Use proper body position, hand placement

**07**
- ☐ Wear puncture, cut resistant PPE ☐ Use proper body position, hand placement
- ☐ Install temporary guarding, covers ☐ Avoid blind reaches ☐ Use extension tools
- ☐ Inspect immediate area for other sharp edges

**08**
- ☐ Secure or cover openings, doors, manways ☐ Use blocks for placing objects on floor
- ☐ Use tool holder or impact protection device (chisel punch, etc.)
- ☐ Coordinate manual movement of equipment, material with team
- ☐ Use proper body position, hand placement (evaluate tool for hand slippage)

**09**
- ☐ Review work pace ☐ Use or create designated walkways
- ☐ Install barricade, signage ☐ Wear reflective vest or clothing
- ☐ Pad, guard fixed objects to lessen impact or avoid striking

**10**
- ☐ Use portable lights, flashlights ☐ Use shading
- ☐ Use proper body position
- ☐ Block reflection to improve visibility

**11**
- ☐ Use voltage tester, multi-meter ☐ Identify interlocks or automation
- ☐ Install signage, barrier (set at_____ft) ☐ Use proper clearances, distance
- ☐ Follow de-energized LOTO procedure ☐ Coordinate with other work in area
- ☐ Use GFCI ☐ Identify potential stored energy
- ☐ Define hazard risk category _____ (cal/cm2) and use appropriate tools, PPE
- ☐ Ensure cords are in good condition, properly secured and protected from pinch points

**12**
- ☐ Monitor for heat stress ☐ Provide, use ventilation
- ☐ Take rest breaks, hydrate ☐ Use proper PPE, clothing, tools
- ☐ Rotate workers ☐ Install warning signage
- ☐ Install guarding, temporary covers

**13**
- ☐ Review SDS (MSDS), evaluate reactive chemicals ☐ Use less toxic chemical, substitute
- ☐ Ensure proper containment, labeling/signs, ventilation ☐ Isolate chemicals
- ☐ Locate and test nearest eye wash, shower ☐ Ensure clean-up kit is available
- ☐ Use proper PPE (goggles, gloves, face shield, chemical suits, boots, respirator)
- ☐ Decontaminate, remove chemical residue, hygiene (tools, clothing, equipment, skin, work area)

**14**
- ☐ Provide, use ventilation/dust collection ☐ Move task to open air environment
- ☐ Use monitoring equipment (TLV, LEL, ILDH) ☐ Ensure safe work distance
- ☐ Use proper PPE, respiratory protection ☐ Review emergency response plan

**15**
- ☐ Provide and/or verify grounding, bonding
- ☐ Use static dissipating devices (computer)

**16**
- ☐ Provide blocks, wedges ☐ Provide isolation, disconnection
- ☐ Bleed, relieve pressure or tension ☐ Follow LOTO procedure

**17**
- ☐ Move work to safer location ☐ Obtain Hot Work permit
- ☐ Ensure safe work distance ☐ Ensure fire extinguisher or hose available
- ☐ Provide fire retardant clothing ☐ Install fire barriers to prevent access
- ☐ Remove combustibles
- ☐ Use approved tools in classified areas

**18**
- ☐ Secure open pits with barricades, signage ☐ Provide proper benching, terracing
- ☐ Check for underground utilities ☐ Clear, manage water
- ☐ Install shoring, trench box

**19**
- ☐ Use hearing protection ☐ Keep appropriate distance, separation
- ☐ Install sound barriers ☐ Take frequent breaks, rotate activity
- ☐ Wear anti-vibration gloves, other gear; Use anti-vibration mats

**20**
- ☐ Obtain Confined Space/Bin Entry permit
- ☐ Install temporary platform, ladders ☐ Utilize tripod or system to prevent engulfment
- ☐ Utilize non-entry equipment, tools ☐ Lock out, block movable parts, equipment

**21**
- ☐ Utilize NIOSH lifting equation (weight, distance, frequency)
- ☐ Ask for assistance, use team lift
- ☐ Use mechanical means or lift assistance devices

**22**
- ☐ Inspect rigging and lift devices, equipment ☐ Utilize tag lines, other guide tools
- ☐ Maintain safe distance from utilities ☐ Ensure adequate anchorage capacity
- ☐ Install barricades ☐ Use lift calculating checklist
- ☐ Maintain safe distance from lift ☐ Use lift checklist

**23**
- ☐ Warm up, stretch before work ☐ Utilize NIOSH lifting equation
- ☐ Use proper body position ☐ Utilize available ergonomically-designed or power tools
- ☐ Take breaks, rotate workers ☐ Arrange work station to improve positions

**24**
- ☐ Review, discuss the rescue plan, methods of egress
- ☐ Use life lines, communication
- ☐ Obtain Confined Space/Bin Entry permit (if required)
- ☐ Use proper body position

**25**
- ☐ Evaluate weather forecast before task, monitor during task if needed
- ☐ Define conditions that require work to be stopped
- ☐ Wear proper PPE, clothing for weather conditions

**26**
- ☐ Evaluate industrial hygiene hazard ☐ Isolate or neutralize the hazard
- ☐ Utilize body substance isolation, PPE ☐ Ensure proper ventilation, based on hazard

**27**
- ☐ Install barriers, shields ☐ Maintain proper distance
- ☐ Secure, isolate shutters

**28**
- ☐ Use methods to prevent spillage. If a leak or spill occurs, immediately control the source and clean up the material. Locate the spill kit and review the control measures prior to starting clean-up. Report any leaks immediately.
- ☐ Use methods that prevent the release of solids, dust, liquids or gasses.
- ☐ Ensure that chemicals are in approved containers, properly labeled and stored.

**29**
- ☐ Use food grade lubricants and approved tools for food contact
- ☐ Seal process equipment to avoid external contamination
- ☐ Ensure post-maintenance inspection performed (HACCP equipment)

**JSA WORK PERMIT** | Required when risk level is 8 or higher

I approve the assigned participants to perform the work described in this Job Safety Analysis, with the additional safe practices/control measures and the amended risk level documented below, in addition to those previously identified.


**Step No., Added Control Measures, Amended Risk:** _____

**Emergency Contact:** (include phone number, radio channel or other information needed)

**Appropriate Approval Signature:** _____

**"JSA Work Permit Requirements": 16:** Unacceptable level of risk. Task should not be performed at current risk level. **12:** Requires review from reporting level above plant manager. **8 - 9:** Requires review by management. **4 - 6:** Review by management is recommended. **1 - 3:** Trained participants can perform task without further approval.

GasGun



- **Create flow paths in zone**
- **Controlled vertically**
- **Reduce acid job pressure**

Many oil & gas formations are located in close proximity to water bearing zones. For example the Arbuckle dolomite in Kansas is a natural waterdrive reservoir. Traditional frac & acid stimulation methods pressurize the wellbore and formation slowly (quasi-static) to initiate a single bi-wing fracture, perpendicular to the least principal stress. This slow process allows the intu-stress to dominate fracture growth and can break out of zone.


The GasGun propellant stimulation tool delivers pressure to the rock face in 10-20 milliseconds which creates multiple radial flow paths (like slices in a cake) that penetrate directly out into the formation. Due to the speed of the event, vertical containment of GasGun stimulation is limited to 1'-2' above and below the tool.

Full-scale mine-back experiments conducted by Sandia National Laboratories (SPE8934) provided invaluable information about the exact performance of propellants (GasGun), high explosives, and hydraulic fracturing which led to the development of modern hydraulic fracturing modeling (Warpinski).

O 281-272-6580
11999 FM 529 Rd. Houston, TX 77041
www.enhancedenergetics.com

ENHANCED ENERGETICS

# Energetics Testing
# Wellbore Mine-back




Nevada Test Site – Tunnel Layout


**Onsite Team:**

Dr. Richard A. Schmidt

Dr. Norm Warpinski


Henry (Hans) Mohaupt

# Mine-Back Operation





# High Explosive - Crushed Zone and Debris





# Regressive Burning Propellant






# Progressive Burning Propellant





NATURAL RESOURCES AGENCY OF CALIFORNIA
DEPARTMENT OF CONSERVATION
DIVISION OF OIL, GAS, & GEOTHERMAL RESOURCES

# Well Stimulation Determination

Sacramento, California
4/12/2019

Division Engineers have reviewed your request for a Well Stimulation Determination dated, 3/15/2019 and have concluded that the operations described therein do not meet the definition of a well stimulation treatment as defined by § 14 CCR 1761 (a)(1).

This determination applies to the following well:
API: 05902007, 05902008, 05902009, 05901979, 05902011, 05901980, and 05901981
Field: Huntington Beach
County: Orange

This determination applies to the following operations:

Using a 3-3/8" gas propellant gun to perforate and may reach more than 36 inches outside of the well bore omni directionally.

The described operations are not a well stimulation treatment because:

The Kraken and GasGun is a propellant perforating gun that designed to overcome near wellbore damage. This has been confirmed in the underground mine-back studies conducted by Sandia National labs. The WST Unit feels that projects utilizing this technique should be documented, and that operators should therefore be required to submit a routine maintenance form for this work (Well Maintenance form OG 179). For more information on well maintenance, please refer to SB4 Regulation section 1777.4. Note that if acid is injected after perforation and penetrate more than 36", it will be consider as well stimulation treatment.

Your determination number for reporting is: DD19-017

May Soe

May Soe, Well Stimulation Supervisor

# Kraken-enhanced Perforating Flow Performance Tests

ENHANCED ENERGETICS

## API RP19B Section 4 Test Results

- Increased perforation flow rate 2.5x
- Decreased breakdown pressure 50%
- Successful field results proven in controlled lab experiment
- Dynamic overbalance created in wellbore

### Overview


The Kraken® system is field proven to be significantly more effective than standard perforating guns at improving completion and recompletion performance in conventional, unconventional and saltwater disposal wells. Enhanced Energetics set out to further validate the performance of the Kraken system by performing the API Recommended Practices (RP) 19B, Section 4 Test at Halliburton's Jet Research Center (JRC). This test method is the gold standard in evaluating perforation flow performance.

### Test Program and Objectives

The purpose of the test was to assess the perforating and injectivity performance of Halliburton's MaxForce®-FRAC charge assisted with Enhanced Energetics' Kraken propellant boosters. The API RP19B Section 4 Test simulates downhole conditions to measure the flow through a perforation into stressed rock. The test setup allows a core rock sample to be perforated with a shaped charge under in-situ stress, temperature and pore pressure conditions. Fluid is then flowed into the perforation to measure the injectivity through the core.

A Nugget sandstone core was used as the perforating rock target because its characteristics closely match that of many North American land reservoirs. A summary of the test parameters is shown in the table on the right. Three Section 4 Tests were performed in separate Nugget cores. The first test was performed with a single shaped charge as the control experiment. The other two tests were performed with a single shaped charge and Kraken propellant boosters. All tests were conducted at identical stress and pressure conditions as described.

*Pressure vessel with a Nugget sandstone core used to test the Kraken system.*




(Provided courtesy of Halliburton)

### Test Parameters

**Rock type**
Nugget sandstone

**Unconfined strength**
~16,000 psi

**Permeability**
~1–5 mD

**Porosity**
~12%

**Wellbore fluid**
Odorless mineral spirits (OMS)

**Overburden pressure**
~3,500 psi

**Pore pressure**
~2,500 psi

**Wellbore pressure**
~2,500 psi

**Core size**
9-in. OD × 30-in. long

**Kraken size**
25 g

**Charge type**
23 g MaxForce-FRAC



© 2020 Enhanced Energetics. All rights reserved.


# Kraken-enhanced Perforating Flow Performance Tests

## API RP19B Section 4 Test Results


### Perforating Test Results

The conventional perforating control test, performed with only a shaped charge and no Kraken boosters, resulted in a dynamic-underbalance (DUB) pressure event as seen in the graph below. DUB perforating creates a rapid decrease in pressure (underbalance) in the wellbore because of fluid entering the perforating gun immediately after the explosive event occurs. In the two Kraken perforating tests performed with a shaped charge assisted by Kraken propellant boosters, propellant ignition occurred immediately after the explosion of the shaped charge. The burning of the propellant boosters generated high-pressure gas inside the gun and exited out into the perforation tunnel. This process created a dynamic-overbalance event (DOB) inside the wellbore as seen below. The DOB created by the Kraken system enhances the perforation and creates fractures past the compacted rock (skin) produced by conventional shaped charges, thereby improving access to the formation.

*Perforating Pressure Pulse Comparison*




*Fracture Created in Core*




## Flow Test Results


The difference in flow performance between a perforation with no Kraken boosters and a perforation with Kraken boosters was dramatic. The injectivity performance is shown in the graphs below. **Kraken achieved over 2.5x the flow rate through the core sample with a ~50% reduction in pressure compared to the shaped charge alone.**




*Conventional Perforating Flow Performance*




*Kraken Perforating Flow Performance*




## Conclusion

The improved flow performance of the Kraken perforations in the lab closely matches the successful field results reported by customers. Kraken technology has proved to be a step change in completion performance compared with conventional perforating designs.




www.enhancedenergetics.com | 281.272.6580

© 2020 Enhanced Energetics. All rights reserved.

SPE/DOE 8934

SPE
Society of Petroleum Engineers

# IN SITU EVALUATION OF SEVERAL TAILORED-PULSE WELL-SHOOTING CONCEPTS

by Richard A. Schmidt, Norman R. Warpinski and Paul W. Cooper, Sandia National Laboratories

This paper was presented at the 1980 SPE/DOE Symposium on Unconventional Gas Recovery held in Pittsburgh, Pennsylvania, May 18-21, 1980. The material is subject to correction by the author. Permission to copy is restricted to an abstract of not more than 300 words. Write: 6200 N. Central Expwy., Dallas, Texas 75206

## ABSTRACT

Dynamic stimulation techniques that produce multiple fracturing in a wellbore are being investigated for enhanced gas recovery. Multiple fracturing appears to be especially promising for stimulating naturally-fractured reservoirs, such as the Devonian shales, since this may be the most effective technique for connecting a wellbore to a pre-existing fracture network. Previous studies have demonstrated that detrimental effects can occur with high-strength explosive techniques and that these effects can be avoided through the use of propellants.[1,2] The use of propellants and other so-called tailored-pulse techniques depend on a controlled pressure-time behavior to minimize wellbore damage and maximize fracture growth by gas penetration.

This paper describes a series of five full-scale tests performed to evaluate various multi-frac concepts. The tests were conducted at the Nevada Test Site in cased, horizontal boreholes drilled in ash-fall tuff from a tunnel under 430 m of overburden. This site provides both realistic in situ conditions for the tests and access to the stimulated regions by mineback which permits direct observation of results. The five tailored-pulse concepts tested involve:

Case A - a decoupled explosive,[3]
Case B - a decoupled explosive with propellant booster,[3]
Case C - a small-diameter propellant charge with pressurized water pad,[4]
Case D - three successive shots of Case C, and
Case E - a full-diameter charge of a progressively-burning propellant.[2]

While direct observation by mineback is highly beneficial, evaluation and analysis of these test results also depended heavily on other diagnostics. Thirty-six stress-meters and accelerometers were fielded in the surrounding rock to record the dynamic disturbances, and each borehole contained transducers to measure the actual cavity pressures. Pre-test and post-test evaluations include TV log, caliper log, and permeability measurements. Permeability, which evaluates the effectiveness of the created fracture network to transmit fluids, was determined by analysis of constant-pressure, water-injection tests and the subsequent pressure decline after shut-in.

Results show a large increase in formation permeability for Case E, modest increases for Cases B, C, and D and a decrease for Case A that appears due to the formation of a stress cage. A comparison of Case E results with previous tests suggests a multiple fracture criterion based on pressure rate with little effect of peak pressures.

References and illustrations at end of paper.

## INTRODUCTION

Oil and gas wells have been stimulated with high-energy explosives since the late 1800's. It appears, however, that the term "well shooting" originated many years before this in days when a water well was sometimes rejuvenated by shooting a rifle down the well. Well shooting as discussed herein refers to any rapid release of energy from a chemical reaction in a wellbore for the purpose of stimulating production, presumably by fracturing the reservoir rock. This includes explosives (solid, liquid, and gas) and propellants that deflagrate rather than explode. In a broad sense, well shooting has been applied in several geotechnical fields; e.g., preparation of oil shale beds for true in situ processing, preparation of underground mineral deposits for solution mining, etc.

Problems of wellbore damage, safety hazards, and upredictable results have

reduced the relative number of wells stimulated by high-strength explosives. In recent years hydraulic fracturing has been favored, and sophisticated techniques, equipment, fracturing fluids, and proppant have been developed to optimize the hydraulic fracturing process.

Unfortunately, similar efforts toward general understanding and process optimization have been lacking for well shooting. However, recent findings (summarized in Ref. 1) have shed new light on the process of dynamic wellbore fracturing. These findings indicate that vast improvements may be possible using "tailored-pulse" loading techniques.

Tailored-pulse loading involves using propellants, decoupled explosives, or explosive gases to produce a controlled, but rapid, release of energy. This concept is more fully described in a later section, but first the general behavior and limitations of conventional well shooting with high-strength explosives need to be described to understand better the benefits derived from tailored-pulse loading.

## GENERAL BEHAVIOR OF A DEEPLY-BURIED CHARGE

One important aspect common to most well shooting configurations is the fact that there is no free surface near enough to the charge to affect the behavior. The phenomena associated with deeply-buried charges, as they are called, differ significantly from those of blasts that occur near a free surface as in excavations, quarries, and road cuts.

Briefly, the high pressures of a detonation in a wellbore are known to be sufficient to cause the nearby rock to yield and compact (plastic flow). When the stress wave passes, the rock unloads elastically leaving an increased borehole diameter and a residual stress field which is compressive near the wellbore. Figure 1 depicts these general steps that take place during such an event.

The creation of this residual stress field is closely analogous to the process of autofrettage or the "gun barrel problem" in which pressure vessels are often overpressurized sufficiently to yield the inside wall and develop residual compressive stresses that help prevent crack growth during service. The zone of highly compacted rock with its associated residual compressive stresses is sometimes referred to as a stress cage, and the phenomena is sometimes called the bladder effect. Fracturing caused by high pressure gas may also be inhibited in this situation since fines are created during the compaction process that can plug newly formed cracks and prevent gas penetration. Some or all of these effects may actually cause decreased permeability near the wellbore and are probably responsible for many well-shooting failures.

The existence of residual stress regions around boreholes that have been subjected to explosive detonations is a well documented phenomenon. Most of these observations have been made with regard to field experiments at the Nevada Test Site[1,5] as well as laboratory experiments[6] and computer code calculations[1,5,7] for the purpose of understanding containment of underground nuclear blasts. This general behavior of a deeply-buried charge, however, is rather universal since it has been demonstrated to occur for detonations ranging from a one pound charge of TNT to a nuclear detonation of several kilotons. Further description of these general phenomena and details of the supporting evidence can be found in Ref. 1.

## TAILORED-PULSE LOADING

### ADVANTAGES

With the basic knowledge that the bladder effect impedes fracture growth near an explosively loaded cavity, one might wonder how conventional well shooting would ever enhance production. Experience has shown, however, that improved production is sometimes realized. There are several reasons for such results, including the possibility that explosive stimulation may at times be capable of removing skin damage, and that leakage paths may be formed that connect the cavity to the region outside the stress cage. Situations can also occur in which the stress cage will break up and slough into the wellbore. These possibilities are not necessarily predictable or applicable in all formations. It would, of course, be desirable if reliable procedures could be developed to replace conventional well shooting.

Several viable alternatives to explosive well shooting have been considered and tested in recent years that show promise of substantial improvement.[2-4] An approach that has received considerable attention is to tailor the pressure-time behavior of the explosive or a suitable propellant so as to keep the maximum pressure and the loading rate below a level that would cause the rock to crush and undergo plastic flow. The intent here is to avoid entirely the formation of a stress cage while still loading at a sufficiently high rate to produce multiple fractures from the wellbore. Unfortunately, the proper combination of loading parameters that will produce optimal multiple fracturing and avoid the formation of a stress cage are not, as yet, well known.

Tailored-pulse loading of a wellbore has several advantages over hydraulic fracturing that make this technique attractive in certain situations. For example, hydraulic fractures, which are propagated at pressures that are slightly higher than the minimum in situ stress and pumping times that are on the order of hundreds of seconds, typically produce only a single fracture whose orientation is perpendicular to the minimum principal stress.[8,9] Higher wellbore pressures, such as are achieved in tailored-pulse loading, are needed to drive cracks in less favorable directions with respect to the in

situ stresses in order to produce multiple fractures.

Multiple fractures may be highly desirable in naturally fractured reservoirs such as Devonian shale for reasons depicted in Figure 2. The production from an unstimulated well, Figure 2a, depends strongly on the number of fractures intersected. Hydraulic fracturing typically produces a single fracture that is likely to run parallel to most of the existing fractures, Figure 2b, since its orientation is governed by in situ stresses that probably also govern the pattern of the natural fractures. Multiple fractures may not extend as far as a hydraulic fracture but may link the well to more, natural fractures, Figure 2c.

In addition, tailored-pulse loading with propellants are likely to produce little formation damage due to the interaction of fluids with the rock. Very little water is produced by these materials, and the products have very little time to react with the rock. Some hydraulic fracturing fluids, on the other hand, are known to cause swelling in shale and other deleterious effects.

Cost is also a factor that may make tailored-pulse techniques very attractive, particularly in marginal wells that probably are not promising enough for expensive hydraulic fracturing treatments. Igniting an explosive or a propellant charge in a well requires very little equipment or time when compared to even a small hydraulic fracture job.

## CONCEPTS

Several tailored-pulse concepts rely on the use of propellants which deflagrate rather than detonate. Unlike explosives, the burn front in these materials travels slower than the sound speed, and the burning rate can be varied over a wide range. Pressure-time behavior of propellants differ from explosives in that peak pressures are lower, and burn times are longer. Total energy available, however, is similar in both materials (typically 4kJ/g).

One of the first tailored-pulse concepts investigated was a decoupled explosive such as that used for Case A.[3] A conventional explosive is used, but the charge diameter is some eight times less than the wellbore diameter. The charge is surrounded by water, and the peak pressure reaching the rock after detonation is thus mitigated, presumably to a value below the yield stress. The total explosive energy, however, is limited by the small diameter of the charge.

The concept employed in Case B uses the same decoupled explosive in conjunction with a small propellant charge.[3] The decoupled explosive is designed to initiate multiple cracks and the propellant is then burned to drive water into these cracks to extend them. The propellant is essentially a rocket motor that burns for several seconds. Some field testing has been performed using this device but results are inconclusive.

Case C is a small diameter (4cm) pressure-insensitive propellant charge that is designed both to initiate and propagate multiple cracks.[4] A typical rise time is 3 ms with a burn time of 0.5 s. This device is also designed to push water into the cracks ahead of the gas generated by the propellant reaction products. It has been used in the field as a cleaning tool and as a fracture initiating device to reduce the breakdown pressure for hydraulic fracturing. The number and size of the fractures created by this tool are largely unknown. Case D was three successive shots using the same configuration as Case C.

Case E consists of a gas-producing, progressively-burning propellant with a suitable rise time to initiate and propagate multiple fractures while avoiding the damage of a stress cage.[2,10] This concept differs from the others in three main areas: 1) A full-diameter charge is used that fills the wellbore to maximize the energy released. 2) Lightweight gas products from the propellant itself, rather than water, are pushed into the created fractures. This maximizes the speed in which fractures are penetrated and pressure loaded. 3) The propellant is of the progressively-burning type in that the burning rate increases as material is consumed. This allows energy to be saved and not released until it is most needed, later in time, when fractures are long and system volume is large.

## MULTI-FRAC TEST SERIES

### FEASIBILITY STUDY

Experiments to investigate tailored-pulse concepts have been conducted in a tunnel complex at the Nevada Test Site. The tunnel facility provides a means of performing realistic tests of deeply-buried charges in rock formations at depth and yet allows for direct observation of resulting fracture behavior by mining back to uncover the test bed itself. The purpose of this test series is two-fold: (1) evaluate and compare several tailored-pulse concepts in a controlled test bed to determine the ability of each to produce multiple fractures and to enhance formation permeability and (2) provide data for testing and verification of various modeling schemes presently being used to describe the complex behavior of tailored-pulse loading.

The feasibility of performing such experiments was demonstrated previously in a test series conducted on Gas Frac.[2] Three canisters, each containing propellant with markedly different burning rates, were ignited in grouted horizontal holes drilled in a water-saturated ash-fall tuff formation. The results of the three tests showed phenomenologically different behavior as depicted in Figure 3. The slowest-burning propellant created a single fracture similar to a hydraulic fracture, the intermediate-rate

propellant produced extensive multiple fractures, and the fast-burning propellant produced explosive-type behavior as evidenced by an enlarged borehole and minimal fracturing.

## TEST SETUP

The previous Gas Frac tests were not instrumented except for a pressure transducer to measure dynamic cavity pressures. The five tests described below make up the so-called Multi-Frac Test Series and involved thirty-six stressmeters and accelerometers to measure rock formation response as well as pressure transducers to record dynamic cavity pressures. Along with direct observation by mineback, post-test evaluation included a reentry into each test zone for borehole television log, caliper log, and permeability measurements. The caliper log is intended to detect the degree of borehole enlargement (indicating plastic flow) and the permeability test is designed to measure the effectiveness of each test to increase the formation's ability to transmit fluids (i.e., conductivity of fracture network). The rock formation is a water-saturated ash-fall tuff having material properties as listed in Table 1.

The experiments were all conducted in 15 cm diameter, nearly horizontal holes drilled 12.2 m deep from a tunnel drift as depicted in Figure 4. The holes were spaced 6.1 m apart. Experiments A and B were conducted with 3.05 m of open hole and 9.15 m of casing while Experiments C, D, and E had 6.1 m of open hole and 6.1 m of casing. The mineback (not completed as of this writing) is planned so that half of each test zone will be mined out and examined thoroughly, leaving any fracture patterns occurring at the midpoint displayed on the right rib of the tunnel (Figure 4). All test setups were similar and a cross-section of the Case B configuration is seen in Figure 5.

Rock mass instrumentation consisted of an array of stressmeters and accelerometers as depicted in Figure 6. This array of gages was fielded only for Experiments B, D, and E. The stressmeters were special, strain-gaged, borehole-inclusion stressmeters.[11] Two of these transducers were set and preloaded in each instrumentation hole to measure diameteral deformations in the radial and transverse directions. Calibration of these gages was accomplished by static loading of a block of ash-fall tuff that contained a gage mounted in a hole drilled in the sample. Commercially available accelerometers were also set and preloaded in a similar fashion to measure radial and transverse accelerations. (Note that transverse accelerations would not be expected in a symmetric displacement field but could result from motions due to the dynamic propagation of a nearby crack.)

## SPECIFIC TEST CONFIGURATIONS

The device fielded in Experiment A was simply a 2 cm diameter by 3 m long PVC tube filled with 2.3 kg of Comp C4 explosive. This was centralized in the hole and the cavity filled with water under atmospheric pressure. The water contained a blue dye to stain the created fractures and to ease identification and mapping during mineback. Dynamic cavity pressure was measured in this experiment using both Kulite* sensors and specially designed ytterbium paddle gages[12] located near the end of the casing section (Figure 5). The Kulite gage model HKM-375, is a piezoresistive integrated sensor. This gage has a 200 MPa pressure range and consists of a miniature silicon member on which a temperature compensated wheatstone bridge is atomically bonded. The miniaturization results in a natural frequency of 400 kHz.

Experiment B involved the same Comp C4 explosive setup but also contained a 2.7 kg charge of propellant. This relatively slow-burning propellant charge consisted of a single, internal-star rocket grain ignited with a black-powder-filled spit tube and housed in a sealed aluminuim canister. The canister was located in the casing section against the bulkhead and was designed to act as a dynamic plunger to push the dyed water down the casing and into fractures initiated by the explosive charge. The fire set was designed to ignite the propellant charge first and then to detonate the explosive 70 msec later by which time the propellant would have reached sufficient pressure. Transducers fielded in this experiment to measure the dynamic cavity pressure event included Kulite and ytterbium gages at the end of the casing section and a fluid-coupled-plate gage[13] located at the bulkhead near the propellant canister. The sensing element used in the fluid-coupled-plate transducer is the same Kulite gage mentioned previously.

The device used for Experiments C and D consisted of a 2 cm diameter by 6.1 m long soft aluminum tube filled with 2.3 kg of propellant which was ignited at one end. The device was centralized in the test hole and the cavity filled with dyed water. The water was pressurized statically to 3.4 MPa using a hydraulic pump just prior to these shots in order to simulate the containment from a 300 m column of water. Dynamic cavity pressure was measured in each of these shots by means of Kulite gages located near the end of the casing section.

The device fielded in Experiment E included a number of design improvements over the previous configuration.[2] The device (Figure 7) consisted of six canisters, each 12.7 cm diameter by 1 m long that screwed together. The canisters were made of perforated plastic tubes with a heat-shrinkable vinyl covering to make the unit watertight. Each canister contained 9.1 kg of M5 multi-perf propellant grains with a 1 mm web thickness. This propellant was ignited by means of a 3.2 cm diameter perforated-steel primer tube that runs through the center of each canister and becomes a continuous igniter when the units are screwed together. The

*Kulite Semiconductor Products, Inc., Ridgefield, NJ.

primer tube contained an explosive and igniter which provided ignition along the entire 6 meter length in less than 1 msec. The primer tube itself was initiated with an exploding bridge wire device as were all other experiments.

Since the propellant burns cleanly, several bags containing carbon black were taped to the outside of the canisters (Figure 7) to act as crack markers so that the created fractures would be more visible during mineback. Also, a number of 1.3 cm diameter ceramic spheres and 0.6 cm diameter cylinders were taped to this device in hopes that they would be propelled into the fractures and thereby act as dynamic crack width indicators when located during mineback. (These spheres and cylinders were used in the other experiments as well.) The assembly was placed in the dry 6.1 meter test section and sealed with a grout plug. The opposite end of the test zone contained a fluid-coupled plate transducer to measure dynamic cavity pressure.

Estimates of the grout-to-casing and grout-to-rock shear strength indicated that sufficient load-carrying capacity was available to contain these shots (refer to Figure 5). However, a strong-back brace was added as a backup measure (Figure 8). The brace was designed to transmit the load from the casing and bulkhead to the opposite tunnel rib if complete containment was not achieved. All shots were fired remotely and were monitored by close-circuit television.

All shots were fired using a capacitive discharge unit which dumps to an exploding bridge wire. Data was recorded in a separate instrumentation trailer using a 50 kHz analog system with voltage-controlled-oscillator and multiplexer. The analog data was recorded on magnetic tape and later digitized, reduced, and plotted.

## RESULTS AND DISCUSSION

Note: Reduction and analysis of the test data and mineback evaluation were not complete at the deadline of this paper. Thus, the results and conclusions presented here are preliminary.

All shots were fired successfully except Experiment B. On that test, the propellant charge was ignited as planned. After a 70 msec delay, a signal was sent to the explosive charge, but detonation did not occur. Post-shot evaluation disclosed that the exploding bridge wire was intact, but that the detonation cables had been severed in two places by the propellant charge, preventing the bridge from receiving the impulse required.

Pressure-time and stress-time records from Experiment D are displayed in Figure 9. The stress-time behavior is for radial and transverse stress at a location 1 m from the test section. Note that the presure-time record shows a second pressure peak that occurs 9 msec after the first. This corresponds to the transit time of the stress pulse propagating from the gage to the steel bulkhead and back. This second pulse is also observed in the stress records.

Peak borehole pressure is seen to be 46 MPa. If this pressure were assumed constant and confined to the borehole, a 0.32 MPa stress would be expected at the 1 m stressmeters (with radial stress being compressive and tangential being tension). Peak stresses, however, were much higher: 1.06 MPa tangential tension and 2.16 MPa radial compression. Wave-code analysis indicates that little dynamic effect is present in this rate regime. Note that the tangential and radial stress become nearly equal in magnitude at late times as expected from quasi-static analysis. The discrepancy is likely due, instead, to pressure escaping from the borehole and loading the created fractures, thereby strongly affecting the loading configuration.

Preliminary results of stressmeter data from Experiment E indicate that stresses were more than 10 times larger than calculated from assumptions of a static borehole pressure. This discrepancy must be a result of substantial gas penetration into fractures and is consistent with observations of extensive fracturing detected in this experiment as discussed later.

A pre-test and post-test evaluation of in situ permeability was made for each test to indicate the capability of each device to increase the formation's ability to transmit fluids. Since this water-saturated ash-fall tuff formation has no "reservoir" pressure, *per se*, measurements were made by pressurizing each zone with water at a constant pressure of 2.8 MPa and recording the decay of flow with time. The flow rate data could then be fit to give the appropriate parameters which characterize the porous media and boundary conditions. However, since flowing time was always greater than a few minutes, the analysis was greatly simplified by an approximate logarithmic equation. The inverse of the flow rate (1/q) is plotted against the logarithm of time, and the permeability is determined from the slope of this line by

$$K = \frac{(185.7)\mu}{H(P_o - P_\infty)m}$$

where

K is permeability in md
$\mu$ is viscosity in kPa·s
H is zone length in m,
$P_o - P_\infty$ is injection over-pressure in kPa, and
m is slope in $(cm^3/sec)^{-1}$/cycle

An example of this measurement scheme is displayed in Figure 10. The pressure decay after shut-in was also analyzed in a manner similar to that for a standard pressure buildup record in a gas well.

Results of the pre-test and post-test permeability measurements are presented in Table 2. Each value of permeability is the average of the flow test and the shut-in. A large permeability enhancement is seen for Experiment E which is a clear indication of extensive fracturing. Experiments B, C, and D display a moderate increase in permeability. Experiment A, however, produced a decrease in formation permeability. This is apparently due to the creation of a stress cage (the bladder effect) even though the explosive was "decoupled" from the formation by an 8 to 1 ratio of hole diameter to charge diameter.

These observations are consistent with post-test TV logs. Several, wide radial fractures were seen in the log of Experiment E, and a few narrow fractures were seen in C and D. While no fractures were seen in the log of Experiment B, a single hydraulic-type fracture is expected here due to the very low pressure-loading rate of the propellant used. The presumption of a stress cage in Experiment A was confirmed in the TV log by the observation of an enlarged, distorted borehole with no apparent fractures.

Closed circuit television of Experiment E also showed indications of extensive fracturing. Shortly after ignition, a gas-driven fracture apparently reached an instrumentation hole located 2 m from the test section, which then pressurized the hole and propelled a 3 m long grout plug across the tunnel. Shortly after this another fracture apparently reached the test section of Experiment C (see Figure 4) 6.1 m away and propelled water and debris out of that hole. These observations were confirmed upon reentry in the tunnel when significant levels of combustion gas (carbon monoxide) were monitored coming out of these holes.

An enlightening comparison can also be made among the three previous Gas Frac shots[2] and Experiment E. Pressure-time characteristics and observed fracture behavior are compared in Table 3. Note that a good correlation between pressure rate and resulting behavior exists while no such correlation occurs with peak pressure. This indicates that pressure rate may be the governing parameter in determining whether resulting behavior is hydraulic fracturing, multiple fracturing, or explosive compaction. A preliminary closed-form analysis was performed that indicates the pressure rates in GF2 and Experiment E were low enough such that tangential stress at the borehole wall begins and remains tensile. On the other hand, the pressure rate of GF3 was sufficiently high to cause tangential compression initially. These initial compressions probably delay the tensile failure until after the compaction process has begun causing the bladder effect. This suggests a multiple fracture criterion that is based on a pressure rate being less than a value that would produce tangential compressive stress at the borehole wall. This criterion was previously suggested by Bligh as a means to avoid explosive compaction.[14]

## CONCLUSIONS

These experiments have shown that multiple fractures can be created from a borehole while avoiding the formation of a stress cage by using an appropriately designed tailored-pulse technique. In particular, results of TV logs, permeability tests and other indirect data showed that the Case E technique produced a highly stimulated zone around the wellbore; Case B, C, and D resulted in a modest stimulation; and Case A, which apparently induced a stress cage to be formed in this rock even though it was a decoupled charge, actually decreased the formation permeability.

The results of these tests and previous experiments suggest that a multiple fracture criterion be based on borehole pressure-loading rate. Peak pressure conditions may not be important if loading-rate requirements are adequate.

Finally, these tests show the value of carefully designed in situ experiments for evaluating stimulation techniques. Instrumentation such as stressmeters, accelerometers, and pressure transducers can be fielded in critical locations, evaluation techniques such as TV and caliper logs and permeability tests can be conveniently employed, and ultimately, mineback can provide a complete diagnosis of the resultant fracture patterns.

## ACKNOWLEDGEMENTS

Appreciation is extended to all who worked on the Multi-Frac Test Series with special thanks to Tom Laws for field engineering, Jack Schwarz for mechanical design, Rod Shear, Mike Burke, and Gary Miller for instrumentation and data acquisition, Lew McEwen and Fred Shoemaker for arming and firing, Bob Beyatte for data reduction, Sharon Finley for mineback evaluation and Clarence Huddle for material property measurements. The excellent work of the skilled mining crew at the Nevada Test Site is also acknowledged. The authors would also like to thank Stuart McHugh of SRI International for initial wave code calculations that helped determine gage settings. This investigation was sponsored under the Eastern Gas Shales Project which is managed by R. L. Wise and C. A. Komar, Morgantown Energy Technology Center. This work was supported by the United States Department of Energy (DOE) under contract number DE-AC04-76000789.

## REFERENCES

1. Schmidt, R. A., Boade, R. R., and Bass, R. C., "A New Perspective on Well Shooting - The Behavior of Contained Explosions and Deflagrations," Proceedings of 1979 Society of Petroleum Engineers Annual Technical Conference and Exhibtion, SPE 8346 (1979).

2. Warpinski, N. R., Schmidt, R. A., Cooper, P. W., Walling, H. C., and Northrop, D. A., "High-Energy Gas Frac: Multiple Fracturing in a Wellbore," Proceedings of 20th U. S. Symposium on Rock Mechanics, Austin, TX, (1979).

3. Moore, E. T., Mumma, D. M., and Seifert, K. D., "Dynafrac - Application of a Novel Rock Fracturing Method to Oil and Gas Recovery," Physics International Final Report 827, April 1977.

4. Fitzgerald, R. and Anderson, R., "Kine-Frac: A New Approach to Well Stimulation," ASME Paper 78-PET-25, ASME Energy Technology Conference and Exhibition, Houston, TX, November 5-19, 1978.

5. Smith, C. W., Bass, R. C., and Tyler, L. D., Puff 'n Tuff, A Residual Stress - Gas Fracturing Experiment," Proceedings of 19th U. S. Symposium on Rock Mechanics, Stateline, Nevada (1978).

6. Florence, A. L., and Gates, R. W., "Explosive Cavity Residual Stress Experiment," 76-3702-2, Stanford Research Institute, Menlo Park, CA (1976).

7. Boade, R. R., Stevens, A. L., Harak, A. E., and Long, A., "Bed Preparation Concepts for True In Situ Oil Shale Processing: An Evaluation of Current Technology," Proceedings of the 1979 Society of Petroleum Engineers Annual Technical Conference and Exhibition, SPE 8447 (1979).

8. Howard, G. C., and Fast, C. R., Hydraulic Fracturing, Society of Petroleum Engineers of AIME Monograph Series, Dallas, TX, (1970).

9. Northrop, D. A., Warpinski, N. R., Schmidt, R. A., Smith, C. W., "Stimulation and Mineback Experiment Project - The Direct Observation of Hydraulic and Explosive Fracturing Tests," Proceedings of the Fourth Annual DOE Symposium on Enhanced Oil and Gas Recovery, Tulsa, OK, August 1978, p. E-4.

10. Schmidt, R. A., Warpinski, N. R., and Northrop, D. A., "In Situ Testing of Well-Shooting Concepts," Proceedings of Third Eastern Gas Shales Symposium, Morgantown, WV (1979).

11. Cook, C. W. and Ames, E. S., "Borehole-Inclusion Stressmeter Measurements in Bedded Salt," Proceedings of 20th U. S. Symposium on Rock Mechanics, Austin, TX, (1979).

12. Ginsberg, M. J., Grady, D. E., Decarli, P. S., and Rosenberg, J. T., "Effects of Stress on the Electrial Resistance of Ytterbium and Calibration of Ytterbrium Stress Transducers," Stanford Research Insitute, DNA 3577F, Menlo Park, CA (1973).

13. Cook, C. W. and Ames E. S., "Pressure Measurements in Harsh Environments," Proceedings of the 25th International Symposium of Instrument Society of America, May 7-10, 1979, Anaheim, CA.

14. Bligh, T. P., "Principles of Breaking Rock Using High Pressure Gases," Advances in Rock Mechanics, Proceedings of the Third Congress of the International Society for Rock Mechanics, Denver, CO, 1974, Vol. II, Part B, p. 1421.

TABLE 1

ASH-FALL TUFF MATERIAL PROPERTIES

| | |
|---|---|
| DENSITY | 1.8 $gm/cm^3$ |
| POROSITY (WATER FILLED) | 40% |
| PERMEABILITY | SEE TABLE 2 |
| ELASTIC MODULUS | 5 GPa |
| COMPRESSIONAL WAVE VELOCITY | 2.1 mm/μs |
| SHEAR WAVE VELOCITY | 1.2 mm/μs |
| TENSILE STRENGTH | 700 kPa |
| COMPRESSIVE STRENGTH (UNCONFINED) | 30 MPa |
| FRACTURE TOUGHNESS | 400 kPa $\sqrt{m}$ |

TABLE 2

PERMEABILITY ENHANCEMENT

| CASE | TAILORED-PULSE CONCEPT | PRE-TEST PERMEABILITY (md) | POST-TEST PERMEABILITY (md) | FACTOR OF INCREASE | OBSERVATIONS FROM TV LOG |
|---|---|---|---|---|---|
| A | DECOUPLED EXPLOSIVE WITH WATER PAD | 0.20 | 0.05 | 0.25 | ENLARGED, DISTORTED BOREHOLE |
| B | DECOUPLED EXPLOSIVE* WITH PROPELLANT PUSHER (WATER PAD) | 0.83 | 5.6 | 7 | NO FRACTURES APPARENT |
| C | SMALL DIAMETER PROPELLANT WITH PRESSURIZED WATER PAD | 0.0015 | 0.008** | 5** | MULTIPLE FRACTURES (VERY NARROW) |
| D | THREE SHOTS OF CASE C WITH PRESSURIZED WATER PAD | 0.007 | 0.034 | 5 | MULTIPLE FRACTURES (NARROW) |
| E | FULL BORE, PROGRESSIVELY-BURNING PROPELLANT WITH AIR PAD | 0.014 | 25.0 | 1800 | MULTIPLE FRACTURES (WIDE) |

*EXPLOSIVE DID NOT DETONATE

**SOME PERMEABILITY INCREASE MAY BE DUE TO FRACTURE CAUSED BY EXPERIMENT E

TABLE 3

PRESSURE LOADING CHARACTERISTICS VS. OBSERVED BEHAVIOR

| | EXPERIMENT | PEAK PRESSURE (MPa) | PRESSURE RATE (kPa/μs) | RESULTING BEHAVIOR |
|---|---|---|---|---|
| PREVIOUS GAS FRAC TEST SERIES[2] | GF1 | 43 | 0.6 | HYDRAULIC FRACTURE |
| | GF2 | 95 | 140 | MULTIPLE FRACTURES |
| | GF3 | ~200 | >10,000 | EXPLOSIVE STRESS CAGE |
| | EXPERIMENT E | 250 | 430 | MULTIPLE FRACTURES |





Fig. 1 - General behavior of deeply-buried charge.





Fig. 2 - Stimulation of naturally fractured reservoir.

| | GF1 "SLOW" | GF2 "INTERMEDIATE" | GF3 "FAST" |
|---|---|---|---|
| LOADING RATE (kPa/μs) | 0.6 | 140 | >10,000 |
| PEAK PRESSURE (MPa) | 43 | 95 | >~200 |
| PULSE DURATION (msec) | 900 | 9 | ~1 |

MINEBACK OBSERVATION (SCHEMATIC)





Fig. 3 - Results of gas frac experiments[2].





Fig. 4 - Tunnel plan for multi-frac test series.





Fig. 5 - Cross section of test setup for experiment B.





Fig. 6 - Layout of instrumentation holes.





Fig. 7 - Loading of propellant device for experiment E.





Fig. 8 - Typical view of experiment ready for arming and firing.





Fig. 9 – Record of cavity pressure and stress at 1 m for experiment D.





Fig. 10 – Pre-shot permeability measurement for experiment A.

# APPENDIX F: Cross-Reference Table of Class VI Injection Well Rules (40 CFR Subpart H)

| Class VI Well Regulatory Requirements | Application Section Where Addressed |
|---|---|
| **Sec. 146.82 Required Class VI permit information.**<br>(a) Prior to the issuance of a permit for the construction of a new Class VI well or the conversion of an existing Class I, Class II, or Class V well to a Class VI well, the owner or operator shall submit, pursuant to § 146.91(e), and the Director shall consider the following: | |
| (1) Information required in § 144.31(e)(1) through (6) of this chapter; | Attachment A |
| (2) A map showing the injection well for which a permit is sought and the applicable area of review consistent with § 146.84. Within the area of review, the map must show the number or name, and location of all injection wells, producing wells, abandoned wells, plugged wells or dry holes, deep stratigraphic boreholes, State- or EPA-approved subsurface cleanup sites, surface bodies of water, springs, mines (surface and subsurface), quarries, water wells, other pertinent surface features including structures intended for human occupancy, State, Tribal, and Territory boundaries, and roads. The map should also show faults, if known or suspected. Only information of public record is<br>required to be included on this map; | Section 4 |
| (3) Information on the geologic structure and hydrogeologic properties of the proposed storage site and overlying formations, including:<br>(i) Maps and cross sections of the area of review;<br>(ii) The location, orientation, and properties of known or suspected faults and fractures that may transect the confining zone(s) in the area of review and a determination that they would not interfere with containment;<br>(iii) Data on the depth, areal extent, thickness, mineralogy, porosity, permeability, and capillary pressure of the injection and confining zone(s); including geology/facies changes based on field data which may include geologic cores, outcrop data, seismic surveys, well logs, and names and lithologic descriptions;<br>(iv) Geomechanical information on fractures, stress, ductility, rock strength, and in situ fluid pressures within the confining zone(s);<br>(v) Information on the seismic history including the presence and depth of seismic sources and a determination that the seismicity would not interfere with containment; and<br>(vi) Geologic and topographic maps and cross sections illustrating regional geology, hydrogeology, and the geologic structure of the local area. | Section 3<br>Sec. 3.2<br>Sec. 3.3.2<br>Sec. 3.6<br>Sec. 3.8<br>Sec. 3.4 |
| (4) A tabulation of all wells within the area of review which penetrate the injection or confining zone(s). Such data must include a description of each well's type, construction, date drilled, location, depth, record of plugging and/ or completion, and any additional information the Director may<br>require; | Appendix B |
| (5) Maps and stratigraphic cross sections indicating the general vertical and lateral limits of all USDWs, water wells and springs within the area of review, their positions relative to the injection<br>zone(s), and the direction of water movement, where known; | Appendix B |
| (6) Baseline geochemical data on subsurface formations, including all USDWs in the area of review; | Sec. 3.5, Sec. 4.3 |
| (7) Proposed operating data for the proposed geologic sequestration site:<br>(i) Average and maximum daily rate and volume and/or mass and total anticipated volume and/or mass of the carbon dioxide stream;<br>(ii) Average and maximum injection pressure;<br>(iii) The source(s) of the carbon dioxide stream; and | Section 4.1.4<br>Section 8.2<br>Sec. 1.1 |

| | |
|---|---|
| (iv) An analysis of the chemical and physical characteristics of the carbon dioxide stream. | Sec. 8.6 |
| (8) Proposed pre-operational formation testing program to obtain an analysis of the chemical and physical characteristics of the injection zone(s) and confining zone(s) and that meets the requirements at § 146.87; | Sec. 7.5 |
| **Sec. 146.82 Required Class VI permit information.** (cont'd)<br>(9) Proposed stimulation program, a description of stimulation fluids to be used and a determination that stimulation will not interfere with containment; | Sec. 8.5.2 |
| (10) Proposed procedure to outline steps necessary to conduct injection operation; | Sec. 8.5 |
| (11) Schematics or other appropriate drawings of the surface and subsurface construction details of<br>the well; | Fig. 6.1.6-1, Fig. 6.1.6-2 |
| (12) Injection well construction procedures that meet the requirements of § 146.86; | Sec. 6 |
| (13) Proposed area of review and corrective action plan that meets the requirements under § 146.84; | Sec. 4.4 |
| (14) A demonstration, satisfactory to the Director, that the applicant has met the financial<br>responsibility requirements under § 146.85; | Sec. 5 and Appendix A |
| (15) Proposed testing and monitoring plan required by § 146.90; | Sec. 9 |
| (16) Proposed injection well plugging plan required by § 146.92(b); | Sec. 10 |
| (17) Proposed post-injection site care and site closure plan required by § 146.93(a); | Sec. 11 |
| (18) At the Director's discretion, a demonstration of an alternative post-injection site care timeframe<br>required by § 146.93(c); | Sec. 11.3 |
| (19) Proposed emergency and remedial response plan required by § 146.94(a); | Sec. 12 |
| (20) A list of contacts, submitted to the Director, for those States, Tribes, and Territories identified<br>to be within the area of review of the Class VI project based on information provided in paragraph (a)(2) of this section; and | Section 2 |
| (21) Any other information requested by the Director. | Agency action |
| (b) The Director shall notify, in writing, any States, Tribes, or Territories identified to be within the area of review of the Class VI project based on information provided in paragraphs (a)(2) and<br>(a)(20) of this section of the permit application and pursuant to the requirements at § 145.23(f)(13) of this chapter. | Agency action |
| (c) Prior to granting approval for the operation of a Class VI well, the Director shall consider the<br>following information:<br>(1) The final area of review based on modeling, using data obtained during logging and testing of the well and the formation as required by paragraphs (c)(2), (3), (4), (6), (7), and (10) of this section;<br>(2) Any relevant updates, based on data obtained during logging and testing of the well and the formation as required by paragraphs (c)(3), (4), (6), (7), and (10) of this section, to the information on the geologic structure and hydrogeologic properties of the proposed storage site and overlying formations, submitted to satisfy the requirements of paragraph (a)(3) of this section;<br>(3) Information on the compatibility of the carbon dioxide stream with fluids in the injection zone(s) and minerals in both the injection and the confining zone(s), based on the results of the formation testing program, and with the materials used to construct the well; | |

| | |
|---|---|
| (4) The results of the formation testing program required at paragraph (a)(8) of this section;<br>(5) Final injection well construction procedures that meet the requirements of § 146.86;<br>(6) The status of corrective action on wells in the area of review;<br>(7) All available logging and testing program data on the well required by § 146.87;<br>(8) A demonstration of mechanical integrity pursuant to § 146.89;<br>(9) Any updates to the proposed area of review and corrective action plan, testing and monitoring plan, injection well plugging plan, post-injection site care and site closure plan, or the emergency and remedial response plan submitted under paragraph (a) of this section, which are necessary to address new information collected during logging and testing of the well and the formation as required by all paragraphs of this section, and any updates to the alternative post-injection site care timeframe demonstration submitted under paragraph (a) of this section, which are necessary to address new information collected during the logging and testing of the well and the formation as required by all paragraphs of this section; and<br>(10) Any other information requested by the Director. | Agency action |
| (d) Owners or operators seeking a waiver of the requirement to inject below the lowermost USDW must also refer to § 146.95 and submit a supplemental report, as required at § 146.95(a). The supplemental report is not part of the permit application. | Not applicable |

| | |
|---|---|
| **§ 146.83 Minimum criteria for siting.** | |
| (a) Owners or operators of Class VI wells must demonstrate to the satisfaction of the Director that the wells will be sited in areas with a suitable geologic system. The owners or operators must demonstrate that the geologic system comprises: | Section 2 |
| (1) An injection zone(s) of sufficient areal extent, thickness, porosity, and permeability to receive the total anticipated volume of the carbon dioxide stream; | Sec. 3.3.2 |
| (2) Confining zone(s) free of transmissive faults or fractures and of sufficient areal extent and integrity to contain the injected carbon dioxide stream and displaced formation fluids and allow injection at proposed maximum pressures and volumes without initiating or propagating fractures in the confining zone(s). | Sec. 3.3<br>Sec. 3.12 |
| (b) The Director may require owners or operators of Class VI wells to identify and characterize additional zones that will impede vertical fluid movement, are free of faults and fractures that may interfere with containment, allow for pressure dissipation, and provide additional opportunities for monitoring, mitigation, and remediation. | Agency action |
| **§ 146.84 Area of review and corrective action.** | |
| (a) The area of review is the region surrounding the geologic sequestration project where USDWs may be endangered by the injection activity. The area of review is delineated using computational modeling that accounts for the physical and chemical properties of all phases of the injected carbon dioxide stream and is based on available site characterization, monitoring, and operational data. | Sections 5.1 and Attachment B |

| | |
|---|---|
| (b) The owner or operator of a Class VI well must prepare, maintain, and comply with a plan to delineate the area of review for a proposed geologic sequestration project, periodically reevaluate the delineation, and perform corrective action that meets the requirements of this section and is acceptable to the Director. The requirement to maintain and implement an approved plan is directly enforceable regardless of whether the requirement is a condition of the permit. As a part of the permit application for approval by the Director, the owner or operator must submit an area of review and corrective action plan that includes the following information: | Section 5.6 |
| (1) The method for delineating the area of review that meets the requirements of paragraph (c) of this section, including the model to be used, assumptions that will be made, and the site characterization data on which the model will be based; | Sec. 4.2 |
| (2) A description of:<br>(i) The minimum fixed frequency, not to exceed five years, at which the owner or operator proposes to reevaluate the area of review;<br>(ii) The monitoring and operational conditions that would warrant a reevaluation of the area of review prior to the next scheduled reevaluation as determined by the minimum fixed frequency established in paragraph (b)(2)(i) of this section.<br>(iii) How monitoring and operational data (e.g., injection rate and pressure) will be used to inform an area of review reevaluation; and<br>(iv) How corrective action will be conducted to meet the requirements of paragraph (d) of this section, including what corrective action will be performed prior to injection and what, if any, portions of the area of review will have corrective action addressed on a phased basis and how the phasing will be determined; how corrective action will be adjusted if there are changes in the area of review; and how site access will be guaranteed for future corrective action. | Section 4.4 |
| (c) Owners or operators of Class VI wells must perform the following actions to delineate the area of review and identify all wells that require corrective action:<br>(1) Predict, using existing site characterization, monitoring and operational data, and computational modeling, the projected lateral and vertical migration of the carbon dioxide plume and formation fluids in the subsurface from the commencement of injection activities until the plume movement ceases, until pressure differentials sufficient to cause the movement of injected fluids or formation fluids into a USDW are no longer present, or until the end of a fixed time period as determined by the Director. The model must:<br>(i) Be based on detailed geologic data collected to characterize the injection zone(s), confining zone(s) and any additional zones; and anticipated operating data, including injection pressures, rates, and total volumes over the proposed life of the geologic sequestration project;<br>(ii) Take into account any geologic heterogeneities, other discontinuities, data quality, and their possible impact on model predictions; and<br>(iii) Consider potential migration through faults, fractures, and artificial penetrations. (iv) | Sec. 9.5 |
| **§ 146.84 Area of review and corrective action.(cont'd)**<br>(2) Using methods approved by the Director, identify all penetrations, including active and abandoned wells and underground mines, in the area of review that may penetrate the confining zone(s). Provide a description of each well's type, construction, date drilled, location, depth, record of plugging and/ or completion, and any additional information the Director may require; and | Appendix B |

| | |
|---|---|
| (3) Determine which abandoned wells in the area of review have been plugged in a manner that<br>prevents the movement of carbon dioxide or other fluids that may endanger USDWs, including use of materials compatible with the carbon dioxide stream. | Appendix B |
| (d) Owners or operators of Class VI wells must perform corrective action on all wells in the area of<br>review that are determined to need corrective action, using methods designed to prevent the movement of fluid into or between USDWs, including use of materials compatible with the carbon dioxide stream, where appropriate. | Sec. 4.4 |
| (e) At the minimum fixed frequency, not to exceed five years, as specified in the area of review and corrective action plan, or when monitoring and operational conditions warrant, owners or operators<br>must:<br>(1) Reevaluate the area of review in the same manner specified in paragraph (c)(1) of this section;<br>(2) Identify all wells in the reevaluated area of review that require corrective action in the same manner specified in paragraph (c) of this section;<br>(3) Perform corrective action on wells requiring corrective action in the reevaluated area of review in the same manner specified in paragraph (d) of this section; and<br>(4) Submit an amended area of review and corrective action plan or demonstrate to the Director through monitoring data and modeling results that no amendment to the area of review and corrective action plan is needed. Any amendments to the area of review and corrective action plan must be<br>approved by the Director, must be incorporated into the permit, and are subject to the permit modification requirements at §§ 144.39 or 144.41 of this chapter, as appropriate. | Sec. 4 |
| (f) The emergency and remedial response plan (as required by § 146.94) and the demonstration of<br>financial responsibility (as described by § 146.85) must account for the area of review delineated as specified in paragraph (c)(1) of this section or the most recently evaluated area of review delineated under paragraph (e) of this section, regardless of whether or not corrective action in the area of review is phased. | Sec. 12 and Sec. 5 |
| (g) All modeling inputs and data used to support area of review reevaluations under paragraph (e) of<br>this section shall be retained for 10 years. | Sec. 9 |
| **§ 146.85 Financial responsibility.**<br>(a) The owner or operator must demonstrate and maintain financial responsibility as determined by the Director that meets the following conditions: …<br>(b) The requirement to maintain adequate financial responsibility and resources is directly enforceable regardless of whether the requirement is a condition of the permit. …<br>(c) The owner or operator must have a detailed written estimate, in current dollars, of the cost of performing corrective action on wells in the area of review, plugging the injection well(s), post- injection site care and site closure, and emergency and remedial response. …<br>(d) The owner or operator must notify the Director by certified mail of adverse financial conditions such as bankruptcy that may affect the ability to carry out injection well plugging and post-injection site care and site closure. … | Sec. 5, Appendix A |

| | |
|---|---|
| (e) The owner or operator must provide an adjustment of the cost estimate to the Director within 60 days of notification by the Director, as required by § 146.84, if the Director determines during the annual evaluation of the qualifying financial instrument(s) that the most recent demonstration is no longer adequate to cover the cost of corrective action (as required by § 146.84), injection well plugging (as required by § 146.92), post-injection site care and site closure (as required by § 146.93), and emergency and remedial response (as required by § 146.94).<br>(f) The Director must approve the use and length of pay-in-periods for trust funds or escrow accounts. | Agency action |
| **§ 146.86 Injection well construction requirements.**<br>(a) *General.* The owner or operator must ensure that all Class VI wells are constructed and completed to:<br>(1) Prevent the movement of fluids into or between USDWs or into any unauthorized zones;<br>(2) Permit the use of appropriate testing devices and workover tools; and<br>(3) Permit continuous monitoring of the annulus space between the injection tbg and long string casing. | Sec. 6 |
| *(b) Casing and Cementing of Class VI Wells.*<br>(1) Casing and cement or other materials used in the construction of each Class VI well must have sufficient structural strength and be designed for the life of the geologic sequestration project. All well materials must be compatible with fluids with which the materials may be expected to come into contact and must meet or exceed standards developed for such materials by the American Petroleum Institute, ASTM International, or comparable standards acceptable to the Director. The casing and cementing program must be designed to prevent the movement of fluids into or between USDWs. In order to allow the Director to determine and specify casing and cementing requirements, the owner or operator must provide the following information: | Sec. 6.1, Sec. 6.2 |
| (i) Depth to the injection zone(s); | 6.1.1 |
| (ii) Injection pressure, external pressure, internal pressure, and axial loading; | Fig 6.1-3 Fig.6.1-4, Fig. 6.1.7.3 |
| (iii) Hole size; | Sec. 6.2.7.1, Table 6.2.7.1-1 |
| (iv) Size and grade of all casing strings (wall thickness, external diameter, nominal weight, length, joint specification, and construction material); | Sec. 6.1.7.2 Table 6.1.7.2-1 |
| (v) Corrosiveness of the carbon dioxide stream and formation fluids; | Sec. 3.5 |
| (vi) Down-hole temperatures; | Sec. 7.3.7, Table 7.3.7-1 |
| (vii) Lithology of injection and confining zone(s); | Sec. 7.3.1 |
| (viii) Type or grade of cement and cement additives; and | Sec. 6.1.7.2 Table 6.1.7.2-1 |
| (ix) Quantity, chemical composition, and temperature of the carbon dioxide stream. | Sec. 8.6 |
| (2) Surface casing must extend through the base of the lowermost USDW and be cemented to the surface through the use of a single or multiple strings of casing and cement. | Sec. 6.1.7.1, Table 6.1.7.1-1 |
| (3) At least one long string casing, using a sufficient number of centralizers, must extend to the injection zone and must be cemented by circulating cement to the surface in one or more stages. | 6.1.7.2, Table 6.1.7.2-1 |
| (4) Circulation of cement may be accomplished by staging. The Director may approve an alternative method of cementing in cases where the cement cannot be recirculated to the surface, provided the owner or operator can demonstrate by using logs that the cement does not allow fluid movement behind wellbore. | Sec. 6.1.7.4 |

| | |
|---|---|
| (5) Cement and cement additives must be compatible with the carbon dioxide stream and formation fluids and of sufficient quality and quantity to maintain integrity over the design life of the geologic sequestration project. The integrity and location of the cement shall be verified using technology capable of evaluating cement quality radially and identifying the location of channels to ensure that USDWs are not endangered. | Sec. 6.1.7 |
| *(c) Tubing and packer.*<br>(1) Tubing and packer materials used in the construction of each Class VI well must be compatible with fluids with which the materials may be expected to come into contact and must meet or exceed standards developed for such materials by the American Petroleum Institute, ASTM International, or comparable standards acceptable to the Director. | Sec. 6.1.7 |
| (2) All owners or operators of Class VI wells must inject fluids through tubing with a packer set at a depth opposite a cemented interval at the location approved by the Director. | Packer depth TBD. |
| (3) In order for the Director to determine and specify requirements for tubing and packer, the owner or operator must submit the following information:<br>(i) Depth of setting;<br>(ii) Characteristics of the carbon dioxide stream (chemical content, corrosiveness, temperature, and density) and formation fluids;<br>(iii) Maximum proposed injection pressure;<br>(iv) Maximum proposed annular pressure;<br>(v) Proposed injection rate (intermittent or continuous) and volume and/or mass of the carbon dioxide stream;<br>(vi) Size of tubing and casing; and<br>(vii) Tubing tensile, burst, and collapse strengths. | Packer depth TBD.<br>Sec. 8.6<br>Sec. 8.2, Table 8.2-1<br>Fig. 6.1-3, 6.1-4, 6.1-5<br>Sec. 8.1<br>Table 6.1.7.3-1<br>Sec. 6.1.7.3, Table 6.1.7.3-1 |

| | |
|---|---|
| **§ 146.87 Logging, sampling, and testing prior to injection well operation.**<br>(a) During the drilling and construction of a Class VI injection well, the owner or operator must run appropriate logs, surveys and tests to determine or verify the depth, thickness, porosity, permeability, and lithology of, and the salinity of any formation fluids in all relevant geologic formations to ensure conformance with the injection well construction requirements under § 146.86 and to establish accurate baseline data against which future measurements may be compared. The owner or operator must submit to the Director a descriptive report prepared by a knowledgeable log analyst that includes an interpretation of the results of such logs and tests. At a minimum, such logs and tests must include: | |
| (1) Deviation checks during drilling on all holes constructed by drilling a pilot hole which is enlarged by reaming or another method. Such checks must be at sufficiently frequent intervals to determine the location of the borehole and to ensure that vertical avenues for fluid movement in the form of diverging holes are not created during drilling; and | Sec. 7.1 |
| (2) Before and upon installation of the surface casing:<br>(i) Resistivity, spontaneous potential, and caliper logs before the casing is installed; and | Sec. 6.1.7.9 |
| (ii) A cement bond and variable density log to evaluate cement quality radially, and a temperature log after the casing is set and cemented. | Sec. 6.1.7.9 |
| (3) Before and upon installation of the long string casing:<br>(i) Resistivity, spontaneous potential, porosity, caliper, gamma ray, fracture finder logs, and any other logs the Director requires for the given geology before the casing is installed; and | 6.1.7.4 |

| | |
|---|---|
| (ii) A cement bond and variable density log, and a temperature log after the casing is set and cemented.<br>(4) A series of tests designed to demonstrate the internal and external mechanical integrity of injection wells, which may include:<br>(i) A pressure test with liquid or gas;<br>(ii) A tracer survey such as oxygen-activation logging;<br>(iii) A temperature or noise log;<br>(iv) A casing inspection log; and<br>(5) Any alternative methods that provide equivalent or better information and that are required by and/or approved of by the Director. | 6.1.7.4<br><br><br><br>Sec. 6.2.9.3<br>Sec. 7.5.3.2<br>Sec. 7.5.3.2<br>Sec. 7.5.3.2<br>N/a |
| (b) The owner or operator must take whole cores or sidewall cores of the injection zone and confining<br>system and formation fluid samples from the injection zone(s), and must submit to the Director a detailed report prepared by a log analyst that includes: Well log analyses (including well logs), core analyses, and formation fluid sample information. The Director may accept information on cores from nearby wells if the owner or operator can demonstrate that core retrieval is not possible and that such<br>cores are representative of conditions at the well. The Director may require the owner or operator to core other formations in the borehole. | Sec. 7.3 |
| (c) The owner or operator must record the fluid temperature, pH, conductivity, reservoir pressure, and<br>static fluid level of the injection zone(s). | Sect. 7.5.3.6 |
| (d) At a minimum, the owner or operator must determine or calculate the following information<br>concerning the injection and confining zone(s):<br>(1) Fracture pressure;<br>(2) Other physical and chemical characteristics of the injection and confining zone(s); and<br>(3) Physical and chemical characteristics of the formation fluids in the injection zone(s). | <br><br><br>Sec. 7.4.2.9<br>Sec. 7.2<br><br>Sec. 7.3.3.1 |
| (e) Upon completion, but prior to operation, the owner or operator must conduct the following tests to<br>verify hydrogeologic characteristics of the injection zone(s):<br>(1) A pressure fall-off test; and,<br>(2) A pump test; or<br>(3) Injectivity tests. | <br><br><br>Sec. 7.5.3.6<br>Sec. 7.1.2<br>N/a |
| (f) The owner or operator must provide the Director with the opportunity to witness all logging and testing by this subpart. The owner or operator must submit a schedule of such activities to the Director<br>30 days prior to conducting the first test and submit any changes to the schedule 30 days prior to the next scheduled test. | Sec. 6.1.7.9 |

| | |
|---|---|
| **§ 146.88 Injection well operating requirements.**<br>(a) Except during stimulation, the owner or operator must ensure that injection pressure does not exceed 90 percent of the fracture pressure of the injection zone(s) so as to ensure that the injection does not initiate new fractures or propagate existing fractures in the injection zone(s). In no case may injection pressure initiate fractures in the confining zone(s) or cause the movement of injection or formation fluids that endangers a USDW. Pursuant to requirements at § 146.82(a)(9), all stimulation<br>programs must be approved by the Director as part of the permit application and incorporated into the permit. | Sec. 8.2 |
| (b) Injection between the outermost casing protecting USDWs and the well bore is prohibited. | Sec. 8.5 |

| | |
|---|---|
| (c) The owner or operator must fill the annulus between the tubing and the long string casing with a non-corrosive fluid approved by the Director. The owner or operator must maintain on the annulus a pressure that exceeds the operating injection pressure, unless the Director determines that such requirement might harm the integrity of the well or endanger USDWs. | Sec. 8.4.2 |
| (d) Other than during periods of well workover (maintenance) approved by the Director in which the sealed tubing-casing annulus is disassembled for maintenance or corrective procedures, the owner or operator must maintain mechanical integrity of the injection well at all times. | Sec. 7.5.3.7 |
| (e) The owner or operator must install and use:<br>(1) Continuous recording devices to monitor: The injection pressure; the rate, volume and/or mass, and temperature of the carbon dioxide stream; and the pressure on the annulus between the tubing and the long string casing and annulus fluid volume; and<br>(2) Alarms and automatic surface shut-off systems or, at the discretion of the Director, down-hole shut- off systems (*e.g.,* automatic shut-off, check valves) for onshore wells or, other mechanical devices that provide equivalent protection; and<br>(3) Alarms and automatic down-hole shut-off systems for wells located offshore but within State territorial waters, designed to alert the operator and shut-in the well when operating parameters such as annulus pressure, injection rate, or other parameters diverge beyond permitted ranges and/or gradients specified in the permit. | Sec. 6.4<br>Sect. 8.7<br>N/A |
| (f) If a shutdown (*i.e.,* down-hole or at the surface) is triggered or a loss of mechanical integrity is discovered, the owner or operator must immediately investigate and identify as expeditiously as possible the cause of the shutoff. If, upon such investigation, the well appears to be lacking mechanical integrity, or if monitoring required under paragraph (e) of this section otherwise indicates that the well may be lacking mechanical integrity, the owner or operator must:<br>(1) Immediately cease injection;<br>(2) Take all steps reasonably necessary to determine whether there may have been a release of the injected carbon dioxide stream or formation fluids into any unauthorized zone;<br>(3) Notify the Director within 24 hours;<br>(4) Restore and demonstrate mechanical integrity to the satisfaction of the Director prior to resuming injection; and<br>(5) Notify the Director when injection can be expected to resume. | Sect. 12 ERRP |

| | |
|---|---|
| **§ 146.89 Mechanical integrity.**<br>(a) A Class VI well has mechanical integrity if:<br>(1) There is no significant leak in the casing, tubing, or packer; and<br>(2) There is no significant fluid movement into a USDW through channels adjacent to the injection well bore. | Sec. 7.5.3.7, Sec. 9.2 |
| (b) To evaluate the absence of significant leaks under paragraph (a)(1) of this section, owners or operators must, following an initial annulus pressure test, continuously monitor injection pressure, rate, injected volumes; pressure on the annulus between tubing and long-string casing; and annulus fluid volume as specified in § 146.88 (e); | Sec. 9.5.2.1 and Sec. 6.5 |
| (c) At least once per year, the owner or operator must use one of the following methods to determine the absence of significant fluid movement under paragraph (a)(2) of this section:<br>(1) An approved tracer survey such as an oxygen-activation log; or<br>(2) A temperature or noise log. | Sec. 7.5.3.2 |

| | |
|---|---|
| (d) If required by the Director, at a frequency specified in the testing and monitoring plan required at § 146.90, the owner or operator must run a casing inspection log to determine the presence or absence of corrosion in the long-string casing. | Agency action |
| (e) The Director may require any other test to evaluate mechanical integrity under paragraphs (a)(1) or (a)(2) of this section. Also, the Director may allow the use of a test to demonstrate mechanical integrity other than those listed above with the written approval of the Administrator. To obtain approval for a new mechanical integrity test, the Director must submit a written request to the Administrator setting forth the proposed test and all technical data supporting its use. The Administrator may approve the request if he or she determines that it will reliably demonstrate the mechanical integrity of wells for which its use is proposed. Any alternate method approved by the Administrator will be published in the Federal Register and may be used in all States in accordance with applicable State law unless its use is restricted at the time of approval by the Administrator. | Agency action |
| (f) In conducting and evaluating the tests enumerated in this section or others to be allowed by the Director, the owner or operator and the Director must apply methods and standards generally accepted in the industry. When the owner or operator reports the results of mechanical integrity tests to the Director, he/she shall include a description of the test(s) and the method(s) used. In making his/her evaluation, the Director must review monitoring and other test data submitted since the previous evaluation. | Sec. 7.5.3.7 |
| (g) The Director may require additional or alternative tests if the results presented by the owner or operator under paragraphs (a) through (d) of this section are not satisfactory to the Director to demonstrate that there is no significant leak in the casing, tubing, or packer, or to demonstrate that there is no significant movement of fluid into a USDW resulting from the injection activity as stated in paragraphs (a)(1) and (2) of this section. | Agency action |

| | |
|---|---|
| **§ 146.90 Testing and monitoring requirements.** The owner or operator of a Class VI well must prepare, maintain, and comply with a testing and monitoring plan to verify that the geologic sequestration project is operating as permitted and is not endangering USDWs. The requirement to maintain and implement an approved plan is directly enforceable regardless of whether the requirement is a condition of the permit. The testing and monitoring plan must be submitted with the permit application, for Director approval, and must include a description of how the owner or operator will meet the requirements of this section, including accessing sites for all necessary monitoring and testing during the life of the project. Testing and monitoring associated with geologic sequestration projects must, at a minimum, include: | Sec. 9 |
| (a) Analysis of the carbon dioxide stream with sufficient frequency to yield data representative of its chemical and physical characteristics; | Sec. 9.1 |
| (b) Installation and use, except during well workovers as defined in § 146.88(d), of continuous recording devices to monitor injection pressure, rate, and volume; the pressure on the annulus between the tubing and the long string casing; and the annulus fluid volume added; | Sec. 6.4 |
| (c) Corrosion monitoring of the well materials for loss of mass, thickness, cracking, pitting, and other signs of corrosion, which must be performed on a quarterly basis to ensure that the well components meet the minimum standards for material strength and performance set forth in § 146.86(b), by:<br>(1) Analyzing coupons of the well construction materials placed in contact with the carbon dioxide stream; or | Sec. 9.2 |

| | |
|---|---|
| (2) Routing the carbon dioxide stream through a loop constructed with the material used in the well and inspecting the materials in the loop; or<br>(3) Using an alternative method approved by the Director; | |
| (d) Periodic monitoring of the ground water quality and geochemical changes above the confining zone(s) that may be a result of carbon dioxide movement through the confining zone(s) or additional identified zones including:<br>(1) The location and number of monitoring wells based on specific information about the geologic sequestration project, including injection rate and volume, geology, the presence of artificial penetrations, and other factors; and<br>(2) The monitoring frequency and spatial distribution of monitoring wells based on baseline<br>geochemical data that has been collected under § 146.82(a)(6) and on any modeling results in the area of review evaluation required by § 146.84(c). | Sec. 9.5.2.1, Table 9.5.2-2 |
| (e) A demonstration of external mechanical integrity pursuant to § 146.89(c) at least once per year until the injection well is plugged; and, if required by the Director, a casing inspection log pursuant to<br>requirements at § 146.89(d) at a frequency established in the testing and monitoring plan; | Sec. 7.5.3.7 |
| (f) A pressure fall-off test at least once every five years unless more frequent testing is required by the<br>Director based on site-specific information; | Sec. 9.3 |
| (g) Testing and monitoring to track the extent of the carbon dioxide plume and the presence or absence of elevated pressure (*e.g.,* the pressure front) by using: | |
| (1) Direct methods in the injection zone(s); and, | Sec. 9.5.2.1 |
| (2) Indirect methods (*e.g.,* seismic, electrical, gravity, or electromagnetic surveys and/or down-hole carbon dioxide detection tools), unless the Director determines, based on site-specific geology, that such methods are not appropriate; | Sec. 9.5.2.2 |

| | |
|---|---|
| **§ 146.90 Testing and monitoring requirements. (cont'd)**<br>(h) The Director may require surface air monitoring and/or soil gas monitoring to detect movement of carbon dioxide that could endanger a USDW.<br>(1) Design of Class VI surface air and/ or soil gas monitoring must be based on potential risks to USDWs within the area of review;<br>(2) The monitoring frequency and spatial distribution of surface air monitoring and/or soil gas monitoring must be decided using baseline data, and the monitoring plan must describe how the proposed monitoring will yield useful information on the area of review delineation and/or compliance with standards under § 144.12 of this chapter;<br>(3) If an owner or operator demonstrates that monitoring employed under §§ 98.440 to 98.449 of this chapter (Clean Air Act, 42 U.S.C. 7401 *et seq.* ) accomplishes the goals of paragraphs (h)(1) and (2) of this section, and meets the requirements pursuant to § 146.91(c)(5), a Director that requires surface air/soil gas monitoring must approve the use of monitoring employed under §§ 98.440 to 98.449 of this<br>chapter. Compliance with §§ 98.440 to 98.449 of this chapter pursuant to this provision is considered a condition of the Class VI permit; | Sec. 3.9 |
| (i) Any additional monitoring, as required by the Director, necessary to support, upgrade, and improve computational modeling of the area of review evaluation required under § 146.84(c) and to determine<br>compliance with standards under § 144.12 of this chapter; | Agency action |

| | |
|---|---|
| (j) The owner or operator shall periodically review the testing and monitoring plan to incorporate monitoring data collected under this subpart, operational data collected under § 146.88, and the most recent area of review reevaluation performed under § 146.84(e). In no case shall the owner or operator review the testing and monitoring plan less often than once every five years. Based on this review, the owner or operator shall submit an amended testing and monitoring plan or demonstrate to the Director that no amendment to the testing and monitoring plan is needed. Any amendments to the testing and monitoring plan must be approved by the Director, must be incorporated into the permit, and are subject to the permit modification requirements at §§ 144.39 or 144.41 of this chapter, as appropriate. Amended plans or demonstrations shall be submitted to the Director as follows:<br>(1) Within one year of an area of review reevaluation;<br>(2) Following any significant changes to the facility, such as addition of monitoring wells or newly permitted injection wells within the area of review, on a schedule determined by the Director; or<br>(3) When required by the Director. | Section 9 |
| (k) A quality assurance and surveillance plan for all testing and monitoring requirements. | |

| | |
|---|---|
| **§ 146.91 Reporting requirements.**<br>The owner or operator must, at a minimum, provide, as specified in paragraph (e) of this section, the following reports to the Director, for each permitted Class VI well:<br>(a) Semi-annual reports containing:<br>(1) Any changes to the physical, chemical, and other relevant characteristics of the carbon dioxide stream from the proposed operating data;<br>(2) Monthly average, maximum, and minimum values for injection pressure, flow rate and volume, and annular pressure;<br>(3) A description of any event that exceeds operating parameters for annulus pressure or injection pressure specified in the permit;<br>(4) A description of any event which triggers a shut-off device required pursuant to § 146.88(e) and the response taken;<br>(5) The monthly volume and/or mass of the carbon dioxide stream injected over the reporting period and the volume injected cumulatively over the life of the project;<br>(6) Monthly annulus fluid volume added; and<br>(7) The results of monitoring prescribed under § 146.90. | |
| (b) Report, within 30 days, the results of:<br>(1) Periodic tests of mechanical integrity;<br>(2) Any well workover; and,<br>(3) Any other test of the injection well conducted by the permittee if required by the Director. | |
| (c) Report, within 24 hours:<br>(1) Any evidence that the injected carbon dioxide stream or associated pressure front may cause an endangerment to a USDW;<br>(2) Any noncompliance with a permit condition, or malfunction of the injection system, which may cause fluid migration into or between USDWs;<br>(3) Any triggering of a shut-off system (*i.e.,* down-hole or at the surface);<br>(4) Any failure to maintain mechanical integrity; or.<br>(5) Pursuant to compliance with the requirement at § 146.90(h) for surface air/soil gas monitoring or other monitoring technologies, if required by the Director, any release of carbon dioxide to the atmosphere or biosphere. | Sec. 9.7 |
| (d) Owners or operators must notify the Director in writing 30 days in advance of: | |

| | |
|---|---|
| (1) Any planned well workover;<br>(2) Any planned stimulation activities, other than stimulation for formation testing conducted under § 146.82; and<br>(3) Any other planned test of the injection well conducted by the permittee. | |
| (e) Regardless of whether a State has primary enforcement responsibility, owners or operators must submit all required reports, submittals, and notifications under subpart H of this part to EPA in an<br>electronic format approved by EPA. | |
| (f) Records shall be retained by the owner or operator as follows:<br>(1) All data collected under § 146.82 for Class VI permit applications shall be retained throughout the life of the geologic sequestration project and for 10 years following site closure.<br>(2) Data on the nature and composition of all injected fluids collected pursuant to § 146.90(a) shall be retained until 10 years after site closure. The Director may require the owner or operator to deliver the records to the Director at the conclusion of the retention period.<br>(3) Monitoring data collected pursuant to § 146.90(b) through (i) shall be retained for 10 years after it is collected.<br>(4) Well plugging reports, post-injection site care data, including, if appropriate, data and information used to develop the demonstration of the alternative post-injection site care timeframe, and the site closure report collected pursuant to requirements at §§ 146.93(f) and (h) shall be retained for 10 years following site closure.<br>(5) The Director has authority to require the owner or operator to retain any records required in this subpart for longer than 10 years after site closure. | |

| | |
|---|---|
| **§ 146.92 Injection well plugging.**<br>(a) Prior to the well plugging, the owner or operator must flush each Class VI injection well with a<br>buffer fluid, determine bottomhole reservoir pressure, and perform a final external mechanical integrity test. | Sec. 10.2.1 |
| (b) *Well plugging plan.* The owner or operator of a Class VI well must prepare, maintain, and comply with a plan that is acceptable to the Director. The requirement to maintain and implement an approved plan is directly enforceable regardless of whether the requirement is a condition of the permit. The well plugging plan must be submitted as part of the permit application and must include the following information:<br>(1) Appropriate tests or measures for determining bottomhole reservoir pressure;<br>(2) Appropriate testing methods to ensure external mechanical integrity as specified in § 146.89;<br>(3) The type and number of plugs to be used;<br>(4) The placement of each plug, including the elevation of the top and bottom of each plug;<br>(5) The type, grade, and quantity of material to be used in plugging. The material must be compatible with the carbon dioxide stream; and<br>(6) The method of placement of the plugs. | Sec. 10.3 and Attachment D |
| (c) *Notice of intent to plug.* The owner or operator must notify the Director in writing pursuant to § 146.91(e), at least 60 days before plugging of a well. At this time, if any changes have been made to the original well plugging plan, the owner or operator must also provide the revised well plugging plan. The Director may allow for a shorter notice period. Any amendments to the injection well plugging plan must be approved by the Director, must be incorporated into the permit, and are subject<br>to the permit modification requirements at §§ 144.39 or 144.41 of this chapter, as appropriate. | Sec. 10.1 |

| | |
|---|---|
| (d) *Plugging report.* Within 60 days after plugging, the owner or operator must submit, pursuant to § 146.91(e), a plugging report to the Director. The report must be certified as accurate by the owner or operator and by the person who performed the plugging operation (if other than the owner or operator.)<br>The owner or operator shall retain the well plugging report for 10 years following site closure. | Sec. 10.3 |

| | |
|---|---|
| **§ 146.93 Post-injection site care and site closure.**<br>(a) The owner or operator of a Class VI well must prepare, maintain, and comply with a plan for post- injection site care and site closure that meets the requirements of paragraph (a)(2) of this section and is acceptable to the Director. The requirement to maintain and implement an approved plan is directly enforceable regardless of whether the requirement is a condition of the permit.<br>(1) The owner or operator must submit the post-injection site care and site closure plan as a part of the permit application to be approved by the Director. | Sec. 11 |
| (2) The post-injection site care and site closure plan must include the following information:<br>(i) The pressure differential between pre-injection and predicted post-injection pressures in the injection zone(s);<br>(ii) The predicted position of the carbon dioxide plume and associated pressure front at site closure as demonstrated in the area of review evaluation required under § 146.84(c)(1);<br>(iii) A description of post-injection monitoring location, methods, and proposed frequency;<br>(iv) A proposed schedule for submitting post-injection site care monitoring results to the Director pursuant to § 146.91(e); and,<br>(v) The duration of the post-injection site care timeframe and, if approved by the Director, the demonstration of the alternative post-injection site care timeframe that ensures non- endangerment of USDWs. | Sec. 11.1<br>Sec. 11.2<br>Sec. 11.5<br>Sec. 1.1 and Sec. 11.3 |
| (3) Upon cessation of injection, owners or operators of Class VI wells must either submit an amended post-injection site care and site closure plan or demonstrate to the Director through monitoring data and modeling results that no amendment to the plan is needed. Any amendments to the post-injection site care and site closure plan must be approved by the Director, be incorporated into the permit, and are subject to the permit modification requirements at §§ 144.39 or 144.41 of this chapter, as appropriate. | Sec. 11.4 and 11.5 |
| (4) At any time during the life of the geologic sequestration project, the owner or operator may modify and resubmit the post-injection site care and site closure plan for the Director's approval within 30 days of such change. | As noted |
| (b) The owner or operator shall monitor the site following the cessation of injection to show the position of the carbon dioxide plume and pressure front and demonstrate that USDWs are not being endangered. | Sec. 11.2 and 11.5 |

| | |
|---|---|
| (1) Following the cessation of injection, the owner or operator shall continue to conduct monitoring as specified in the Director-approved post-injection site care and site closure plan for at least 50 years or for the duration of the alternative timeframe approved by the Director pursuant to requirements in paragraph (c) of this section, unless he/she makes a demonstration under (b)(2) of this section. The monitoring must continue until the geologic sequestration project no longer poses an endangerment to USDWs and the demonstration under (b)(2) of this section is submitted and approved by the Director. | Sec. 11.2 and 11.3 |
| (2) If the owner or operator can demonstrate to the satisfaction of the Director before 50 years or prior to the end of the approved alternative timeframe based on monitoring and other site-specific data, that the geologic sequestration project no longer poses an endangerment to USDWs, the Director may approve an amendment to the post-injection site care and site closure plan to reduce the frequency of monitoring or may authorize site closure before the end of the 50-year period or prior to the end of the approved alternative timeframe, where he or she has substantial evidence that the geologic sequestration project no longer poses a risk of endangerment to USDWs. | Sec. 11.3 |
| (3) Prior to authorization for site closure, the owner or operator must submit to the Director for review and approval a demonstration, based on monitoring and other site-specific data, that no additional monitoring is needed to ensure that the geologic sequestration project does not pose an endangerment to USDWs. | Sec. 11.5 |
| (4) If the demonstration in paragraph (b)(3) of this section cannot be made (*i.e.,* additional monitoring is needed to ensure that the geologic sequestration project does not pose an endangerment to USDWs) at the end of the 50-year period or at the end of the approved alternative timeframe, or if the Director does not approve the demonstration, the owner or operator must submit to the Director a plan to continue post-injection site care until a demonstration can be made and approved by the Director. | Sec. 11.3 |

| | |
|---|---|
| **§ 146.93 Post-injection site care and site closure. (cont'd)**<br>(c) *Demonstration of alternative post-injection site care timeframe.* At the Director's discretion, the Director may approve, in consultation with EPA, an alternative post-injection site care timeframe other than the 50 year default, if an owner or operator can demonstrate during the permitting process that an alternative post-injection site care timeframe is appropriate and ensures non-endangerment of USDWs. The demonstration must be based on significant, site-specific data and information including all data and information collected pursuant to §§ 146.82 and 146.83, and must contain substantial evidence that the geologic sequestration project will no longer pose a risk of endangerment to USDWs at the end of the alternative post-injection site care timeframe.<br>(1) A demonstration of an alternative post-injection site care timeframe must include consideration and documentation of:<br>(i) The results of computational modeling performed pursuant to delineation of the area of review under § 146.84;<br>(ii) The predicted timeframe for pressure decline within the injection zone, and any other zones, such that formation fluids may not be forced into any USDWs; and/or the timeframe for pressure decline to pre-injection pressures; (iii) The predicted rate of carbon dioxide plume migration within the injection zone, and the predicted timeframe for the cessation of migration;<br>(iii) A description of the site-specific processes that will result in carbon dioxide trapping including immobilization by capillary trapping, dissolution, and mineralization at the site; | |

| | |
|---|---|
| (iv) The predicted rate of carbon dioxide trapping in the immobile capillary phase, dissolved phase, and/or mineral phase;<br>(v) The results of laboratory analyses, research studies, and/or field or site-specific studies to verify the information required in paragraphs (iv) and (v) of this section;<br>(vi) A characterization of the confining zone(s) including a demonstration that it is free of transmissive faults, fractures, and micro-fractures and of appropriate thickness, permeability, and integrity to impede fluid (e.g., carbon dioxide, formation fluids) movement;<br>(vii) The presence of potential conduits for fluid movement including planned injection wells and project monitoring wells associated with the proposed geologic sequestration project or any other projects in proximity to the predicted/modeled, final extent of the carbon dioxide plume and area of elevated pressure;<br>(viii) A description of the well construction and an assessment of the quality of plugs of all abandoned wells within the area of review;<br>(ix) The distance between the injection zone and the nearest USDWs above and/ or below the injection zone; and<br>(x) Any additional site-specific factors required by the Director.<br>(2) Information submitted to support the demonstration in paragraph (c)(1) of this section must meet the following criteria:<br>(i) All analyses and tests performed to support the demonstration must be accurate, reproducible, and performed in accordance with the established quality assurance standards;<br>(ii) Estimation techniques must be appropriate and EPA-certified test protocols must be used where available; (iii) Predictive models must be appropriate and tailored to the site conditions, composition of the carbon dioxide stream and injection and site conditions over the life of the geologic sequestration project;<br>(iii) Predictive models must be calibrated using existing information (*e.g.,* at Class I, Class II, or Class V experimental technology well sites) where sufficient data are available;<br>(iv) Reasonably conservative values and modeling assumptions must be used and disclosed to the Director whenever values are estimated on the basis of known, historical information instead of site-specific measurements;<br>(v) An analysis must be performed to identify and assess aspects of the alternative post-injection site care timeframe demonstration that contribute significantly to uncertainty. The owner or operator must conduct sensitivity analyses to determine the effect that significant uncertainty may contribute to the modeling demonstration.<br>(vi) An approved quality assurance and quality control plan must address all aspects of the demonstration; and,<br>(vii) Any additional criteria required by the Director. (viii) | Sec. 11.3 |

| | |
|---|---|
| **§ 146.93 Post-injection site care and site closure. (cont'd)**<br>(d) *Notice of intent for site closure.* The owner or operator must notify the Director in writing at least 120 days before site closure. At this time, if any changes have been made to the original post-injection<br>site care and site closure plan, the owner or operator must also provide the revised plan. The Director may allow for a shorter notice period. | Sec. 11.5 |
| (e) After the Director has authorized site closure, the owner or operator must plug all monitoring wells | Sec. 11.5 |

| | |
|---|---|
| in a manner which will not allow movement of injection or formation fluids that endangers a USDW. | Sec. 11.5 |
| (f) The owner or operator must submit a site closure report to the Director within 90 days of site closure, which must thereafter be retained at a location designated by the Director for 10 years. The report must include:<br>(1) Documentation of appropriate injection and monitoring well plugging as specified in § 146.92 and paragraph (e) of this section. The owner or operator must provide a copy of a survey plat which has been submitted to the local zoning authority designated by the Director. The plat must indicate the location of the injection well relative to permanently surveyed benchmarks. The owner or operator must also submit a copy of the plat to the Regional Administrator of the appropriate EPA Regional Office;<br>(2) Documentation of appropriate notification and information to such State, local and Tribal authorities that have authority over drilling activities to enable such State, local, and Tribal authorities to impose appropriate conditions on subsequent drilling activities that may penetrate the injection and confining zone(s); and<br>(3) Records reflecting the nature, composition, and volume of the carbon dioxide stream. | Sec. 11.5 |
| (g) Each owner or operator of a Class VI injection well must record a notation on the deed to the facility property or any other document that is normally examined during title search that will in perpetuity provide any potential purchaser of the property the following information:<br>(1) The fact that land has been used to sequester carbon dioxide;<br>(2) The name of the State agency, local authority, and/or Tribe with which the survey plat was filed, as well as the address of the Environmental Protection Agency Regional Office to which it was submitted; and<br>(3) The volume of fluid injected, the injection zone or zones into which it was injected, and the period over which injection occurred. | Sec. 11.5 |
| (h) The owner or operator must retain for 10 years following site closure, records collected during the post-injection site care period. The owner or operator must deliver the records to the Director at the conclusion of the retention period, and the records must thereafter be retained at a location designated by the Director for that purpose. | Sec. 11.5 |

| | |
|---|---|
| **§ 146.94 Emergency and remedial response.**<br>(a) As part of the permit application, the owner or operator must provide the Director with an emergency and remedial response plan that describes actions the owner or operator must take to address movement of the injection or formation fluids that may cause an endangerment to a USDW during construction, operation, and post-injection site care periods. The requirement to maintain and implement an approved plan is directly enforceable regardless of whether the requirement is a condition of the permit. | Sec. 12.1 and Attachment F |
| (b) If the owner or operator obtains evidence that the injected carbon dioxide stream and associated pressure front may cause an endangerment to a USDW, the owner or operator must:<br>(1) Immediately cease injection;<br>(2) Take all steps reasonably necessary to identify and characterize any release;<br>(3) Notify the Director within 24 hours; and<br>(4) Implement the emergency and remedial response plan approved by the Director. | Sec. 12.1 and Attachment F |

| | |
|---|---|
| (c) The Director may allow the operator to resume injection prior to remediation if the owner or<br>operator demonstrates that the injection operation will not endanger USDWs. | Agency action |
| (d) The owner or operator shall periodically review the emergency and remedial response plan developed under paragraph (a) of this section. In no case shall the owner or operator review the emergency and remedial response plan less often than once every five years. Based on this review, the owner or operator shall submit an amended emergency and remedial response plan or demonstrate to the Director that no amendment to the emergency and remedial response plan is needed. Any amendments to the emergency and remedial response plan must be approved by the Director, must be incorporated into the permit, and are subject to the permit modification requirements at §§ 144.39 or<br>144.41 of this chapter, as appropriate. Amended plans or demonstrations shall be submitted to the Director as follows:<br>(1) Within one year of an area of review reevaluation;<br>(2) Following any significant changes to the facility, such as addition of injection or monitoring wells, on a schedule determined by the Director; or<br>(3) When required by the Director. | Sec. 12.1 and Attachment F |

# APPENDIX G: $CO_2$ Resistant Cement Technical Specification

# $CO_2$ Resistant Cement

**Temperature range (BHST): 40 – 110 degC (104 – 230 degF)**

**Density range: 12.5 – 16.0 lbm/gal [1.5 – 1.92 SG]**

| System | Initial | | 6 months |
|---|---|---|---|
| Portland Cement 15.8 lbm/gal |  | |  |
| CRC 15.8 lbm/gal |  | |  |
| CRC 12.5 lbm/gal |  | |  |

*Physical aspect of conventional Portland and CRC before and after six months in carbon dioxide environments at 280 bars – 90 degC*

*Properties of the CRC slurry as a function of the density and of the BHCT*

| Design | | | | | | |
|---|---|---|---|---|---|---|
| BHCT | 40 degC [104 degF] | | | 85 degC [185 degF] | | |
| BHST | 50 degC [122 degF] | | | 110 degC [230 degF] | | |
| Specific gravity [lbm/gal] | 12.5 | 14.5 | 15.8 | 12.5 | 14.5 | 15.8 |
| **Rheological properties determined with R1B5** | | | | | | |
| **After mixing** | | | | | | |
| PV (cp) | 247 | 234 | 208 | 264 | 214 | 175 |
| $T_y$ (lbf/100ft$^2$) | 4.5 | 8.5 | 9 | 16.5 | 16.8 | 11.4 |
| **After conditioning at BHCT** | | | | | | |
| PV (cp) | 262 | 292 | 207 | 189 | 216 | 226 |
| $T_y$ (lbf/100ft$^2$) | 4.4 | 11.2 | 15 | 9.0 | 2.2 | 2.7 |
| 10" [deg] | 5 | 8 | 7 | 4 | 3 | 4 |
| 10' [deg] | 41 | 40 | 32 | 40 | 32 | 33 |
| 1' [deg] | 9 | 14 | 14 | 10 | 8 | 8 |
| Stability | Ok | Ok | Ok | Ok | Ok | Ok |
| API Fluid loss at BHCT | 34 | 40 | 54 | 54 | 56 | 50 |
| **Thickening time at BHCT** | | | | | | |
| 30 Bc | 6h 03min | 5h 04min | 3h 54min | 4h 25min | 5h 22min | 6h 20min |
| 70 Bc | 7h 01min | 5h 43min | 4h 31min | 4h 39min | 5h 33min | 6h 28min |
| **UCA at BHST** | | | | | | |
| 50 psi | 9h 52min | 9h 04min | 6h 16min | 10h 08min | 9h 56min | 6h 16min |
| 500 psi | 11h 24min | 11h 20min | 8h 04min | 10h 36min | 10h 36min | 6h 52min |
| CS at 24h [psi] | 3036 | 2396 | 2982 | 2459 | 3463 | 2882 |

Schlumberger

Client Cement Support Laboratory
16115 Park Row, Suite 190
Houston, Texas 77084

# Laboratory Cement Test Report - $CO_2$ Resistant EverCRETE®

| | | | | | |
|---|---|---|---|---|---|
| Fluid No : CCS08040004 | Client | : ADM Company | Location | : Illinois Basin | Signatures |
| Date : Jun-6-2008 | Well Name | : CO2 Injection | Field | : Mt. Simon | Terry Dammel |
| | | | | | Lab Specialist |

| | | | | | |
|---|---|---|---|---|---|
| Job Type | Casing | Depth | 7500 ft | TVD | 7500 ft |
| BHST | 130 degF | BHCT | 110 degF | BHP | 2900 psi |
| Starting Temp. | 80 degF | Time to Temp. | 00:29 hr:mn | Heating Rate | 1.03 degF/min |
| Starting Pressure | 400 psi | Time to Pressure | 00:29 hr:mn | Schedule | 9.5-2 |

## Composition

| | | | | | |
|---|---|---|---|---|---|
| Slurry Density | 15.80 lb/gal | Yield | 1.09 ft3/sk | Mix Fluid | 3.42 gal/sk |
| Solid Vol. Fraction | 58.0 % | Porosity | 42.0 % | Slurry type | Other |

## EverCRETE® Blend 1.9 SG_pilot

| Code | Mass Per Sack |
|---|---|
| D189 CSL Hou | 30 lb |
| S100 CLS Hou | 57 lb |
| D195 CLS Hou | 2 lb |
| D178 CSL Hou | 11 lb |

| Code | Concentration | Sack Reference | Component | Blend Density | Lot Number |
|---|---|---|---|---|---|
| 1.9 SG_pilot | | 100 lb of BLEND | Blend | 2.54 g/cm3 | W2007.0150 |
| Mix water | 3.16 gal/sk | | Base Fluid | | |
| D175 | 0.03 gal/sk | | Antifoam | | W2002-0033 |
| D168 | 0.17 gal/sk | | Fluid loss | | W2007.0289 |
| D080 | 0.05 gal/sk | | Dispersant | | W2007.0398 |
| D081 | 0.01 gal/sk | | Retarder | | W2005.0253 |

## Rheology (Average readings) (R1, B1, F1)

| (rpm) | (deg) | (deg) |
|---|---|---|
| 300 | 163.0 | 163.0 |
| 200 | 119.5 | 122.5 |
| 100 | 71.5 | 75.0 |
| 60 | 48.5 | 51.5 |
| 30 | 29.5 | 32.0 |
| 6 | 11.0 | 11.0 |
| 3 | 8.0 | 7.0 |
| 10 sec Gel | | 8 |
| 10 min Gel | | 27 |
| 1 min Stirring | | 15 |
| Temperature | 80 degF | 110 degF |
| | k : 1.29E-2 lbf.s^n/ft2<br>n : 0.781<br>Ty: 3.38 lbf/100ft2 | k : 1.92E-2 lbf.s^n/ft2<br>n : 0.719<br>Ty: 1.22 lbf/100ft2 |

## Thickening Time Results

| Consistency | Time (Lab DI Water) | Time (Corn Processing Water) | Time (Treated Waste Water) |
|---|---|---|---|
| POD : | 3:22 hr:mn | 2:45 hr:mn | 5:24 hr:mn |
| 30 Bc | 4:09 hr:mn | 3:32 hr:mn | 4:20 hr:mn |
| 70 Bc | 5:05 hr:mn | 4:27 hr:mn | 6:18 hr:mn |
| 100 Bc | 5:14 hr:mn | 4:39 hr:mn | 6:29 hr:mn |

NOTE: Testing at a higher pressure of 4550 psi in 39 minutes resulted in a thickening time of 4:07 hr:mn to 70 Bc with DI Water. This compares to the time of 5:05 hr:mn at 2900 psi in 29 minutes.

## Free Fluid

| | |
|---|---|
| 0.0 mL/250mL<br>At 110 degF and 0 deg incl. | in 2 hrs |
| Sedimentation | None |

| | | | |
|---|---|---|---|
| Client | : ADM Company | Well | : Mt. Simon Sandstone |
| String | : Casing L/S | District | : Illinois Basin |
| Country | : USA | | |

Schlumberger

## Fluid Loss

| | | | |
|---|---|---|---|
| API Fluid Loss | | 36 | mL |
| 18 mL in | 30:00 mn:sc | at 110 degF | and 1000 psi |

## UCA Compressive Strength @ 130°F


| Time | CS |
|---|---|
| 06:04 hr:mn | 50 psi |
| 07:25 hr:mn | 500 psi |
| 12:00 hr:mn | 1604 psi |
| 24:00 hr:mn | 3322 psi |
| 72:00 hr:mn | 4379 psi |

## Crush CS (water bath @ 130°F)

| Time | CS |
|---|---|
| 24 hours | 3230 psi |
| **Time** | **Young's Modulus** |
| 24 hours | 1,004,400 psi |

## Comments

General Comment: Thickening Time test with new Location Water source from ADM Corn Processing
Fann Reading Comment: R1, B1, F1.
Thickening Time Comment: See attached plot with varying retarder D081 concentrations.
Other test Comment: Fluid Loss tested with filter paper.





Thickening Time Test with Corn Processing Mix Water


Client : ADM Company
String : Casing L/S
Country : USA

Well : Mt. Simon Sandstone
District : Illinois Basin

Schlumberger




Thickening Time Test with Lab DI Mix Water





Ultrasonic Cement Analyzer Strength Test at 130°F

Client : ADM Company
String : Casing L/S
Country : USA

Well : Mt. Simon Sandstone
District : Illinois Basin

Schlumberger



-End-