# MONITORING, REPORTING, AND VERIFICATION PLAN

Bull Moose AGI #1

Targa Delaware, LLC (Targa)

Version 1.0
November, 2024

Table of Contents

1 Introduction

Targa Delaware, LLC (Targa) proposes an underground injection project at the Targa Bull Moose Gas Processing Plant (the Plant) located approximately 15 miles west of Kermit in Winkler County, district 08, Texas. The Plant is within the eastern part of the Delaware Basin region of the Permian Basin. (**Figure 1-1**).

Targa submitted a Class II Acid Gas Injection (AGI) permit application (Form W-14) for the Bull Moose AGI #1 well (BM AGI #1) to the Texas Railroad Commission (TRRC). Targa intends to drill BM AGI #1 in Q4 of 2024 for the purpose of disposing of the treated acid gas (TAG) that is a byproduct of natural gas processing operations at the Plant. The TAG stream is anticipated to consist of approximately 70% CO_2 (carbon dioxide) and 30% H_2S (hydrogen sulfide), with trace components of hydrocarbons (C1(methane) – C7(heptane)) and nitrogen. The project, with a design life of 30 years, plans to inject TAG through BM AGI #1 into the deep subsurface in the Siluro-Devonian, Fusselman, and Montoya formations.

The project allows Targa to run the Plant at full capacity without discharging large amounts of CO_2 to the atmosphere; replacing the flare with deep injection decreases the negative environmental footprint of the gas plant.

Targa has significant experience in the handling and disposal of TAG in this remotely populated area. Targa submitted forms and supporting documentation designed to meet the requirements of Texas Administrative Code Title 16 Chapter 3 Rule §3.9 and current best engineering practices to ensure that the USDW and the atmosphere are protected from any contamination from injection.

Targa is currently authorized to inject a total of up to 20 million standard cubic feet per day (MMSCFD) of TAG in the approved BM AGI #1 (API 42-495-34978) in accordance with Statewide Rule 9 of the TRRC. Targa received authorization to inject H_2S under the TRRC Rule 36. BM AGI #1 is located on the Plant property (**Figure 1-2**). The permitted injection interval is between 17,889 feet (ft) and 19,488 ft.

The BM AGI #1 well will be constructed with four strings of casing cemented to surface. Corrosion resistant alloys will be used in the bottom 300 ft of the long-string, in the confining zone. Acid resistant cements will also be used across the upper confining zone. Monitoring systems will be installed to ensure that bottomhole injection pressure does not exceed 90% of the determined fracture gradient of the injection interval. Targa is requesting a maximum allowable surface pressure of 0.5 psi/ft (pounds per square inch per foot), or 8,969 psi.

Targa submits this Monitoring, Reporting, and Verification (MRV) plan for the BM AGI #1 well to the United States Environmental Protection Agency (U.S. EPA) for approval according to 40 CFR 98.440 (c)(1), Subpart RR of the Greenhouse Gas Reporting Program (GHGRP) for the purpose of qualifying for the tax credit in section 45Q of the federal Internal Revenue Code. Targa intends to inject CO_2 in BM AGI #1 for 30 years. Following the operational period, Targa proposes a post-injection monitoring and site closure period of 15 years.

Figure 1-1: *Location of the Bull Moose Facility in the Permian Basin, Texas*

Figure 1-2: *Location of the Bull Moose Gas Plant and BM AGI #1 Well*

This MRV Plan contains twelve sections:

Section 1 is this Introduction.

Section 2 contains facility information.

Section 3 contains the project description.

Section 4 contains the delineation of the maximum monitoring area (MMA) and the active monitoring area (AMA), both defined in 40CFR98.449, and as required by 40CFR98.448(a)(1), Subpart RR of the GHGRP.

Section 5 identifies the potential surface leakage pathways for CO_2 in the MMA and evaluates the likelihood, magnitude, and timing of surface leakage of CO_2 through these pathways as required by 40CFR98.448(a)(2), Subpart RR of the GHGRP.

Section 6 describes the detection, verification, and quantification of leakage from the identified potential sources of leakage as required by 40CFR98.448(a)(3).

Section 7 describes the strategy for establishing the expected baselines for monitoring CO_2 surface leakage as required by 40CFR98.448(a)(4), Subpart RR of the GHGRP.

Section 8 provides a summary of the considerations used to calculate site-specific variables for the mass balance equation as required by 40CFR98.448(a)(5), Subpart RR of the GHGRP.

Section 9 provides the estimated schedule for implementation of this MRV Plan as required by 40CFR98.448(a)(7).

Section 10 describes the quality assurance and quality control procedures that will be implemented for each technology applied in the leak detection and quantification process. This section also includes a discussion of the procedures for estimating missing data as detailed in 40CFR98.445.

Section 11 describes the records to be retained according to the requirements of 40CFR98.3(g) of Subpart A of the GHGRP and 40CFR98.447 of Subpart RR of the GRGRP.

Section 12 includes Appendices supporting the narrative of the MRV Plan, including information required by 40CFR98.448(a)(6).

2 Facility Information

2.1 Reporter number

Greenhouse Gas Reporting Program ID is 589241.

2.2 UIC injection well identification numbers

This MRV plan is for the BM AGI #1 well (**Appendix 1**). The details of the injection process are provided in Section 3.7.

2.3 UIC permit class

The TRRC has issued a permit (number 17541) to inject non-hazardous oil and gas waste under its Statewide Rule 9 (**Appendix 2**) for the Bull Moose AGI lease. All oil- and gas-related wells around the BM AGI #1 well, including both injection and production wells, are regulated by the TRRC which has primacy to implement the UIC Class II program.

Well identification and permit parameters:

- BM AGI #1 API Number: 42-495-34978

- UIC Permit Number: 000126603

3 Project Description

The following project description was developed by the Petroleum Recovery Research Center (PRRC) at New Mexico Institute of Mining and Technology (NMT) for Targa.

3.1 General Geologic Setting / Surficial Geology

The Plant is located in Sec. 42, A-433, Blk 27, approximately 10.5 miles south-west of Kermit in Winkler County, Texas, immediately adjacent to the BM AGI #1 well (**Figs 1-1, 1-2**). The plant location is within a portion of the Pecos River basin referred to as the Querecho Plains reach (Nicholson & Clebsch, 1961). This area is relatively flat and largely covered by sand dunes underlain by a hard caliche surface. The dune sands are locally stabilized with shin oak, mesquite, and some burr-grass. There are no natural surface bodies of water or groundwater discharge sites within one mile of the plant and where drainages exist in interdunal areas, they are ephemeral, discontinuous, dry washes. The plant site is underlain by Quaternary alluvium overlying the Triassic red beds of the Santa Rosa Formation (Dockum Group), both of which are local sources of groundwater.

3.2 Bedrock Geology

3.2.1 Basin Development

The Bull Moose Gas Plant and the BM AGI #1 well are located on the eastern margin of the Delaware Basin, a sub-basin of the larger, encompassing Permian Basin (**Figure 3.2-1**).

Figure 3.2-1: *Structural features of the Permian Basin during the Late Permian. Location of the Targa BM AGI well is shown by the black circle. (Modified from Ward, et al (1986))*

The BM AGI well is in the Delaware Basin portion of the broader Permian Basin. **Figure 3.2-2** is a generalized stratigraphic column showing the formations that underlie the Bull Moose Gas Plant and BM AGI #1 well site. The thick sequences of Permian through Cambrian rocks are described below. A general description of the stratigraphy of the area is provided in this section. A more detailed discussion of the injection zone and the upper and lower confining zones is presented in Section 3.3 below. Throughout this narrative, the numbers after the formations indicate the range in thickness for that unit.

Sediments in the area date back to the Cambrian Bliss Sandstone (Broadhead, 2017; **Figure 3.2-2**) and overlay Precambrian granites. These late Cambrian transgressive sandstones were the initial deposits from a shallow marine sea that covered most of North America and Greenland (**Figure 3.2-3**). With continued down warping and/or sea-level rise, a broad, relatively shallow marine basin formed. The Ellenburger Formation (with formation thickness varying from 0 – 1000 ft) is dominated by dolostones and limestones that were deposited on restricted carbonate shelves (Broadhead, 2017; Loucks and Kerans, 2019). Tectonic activity near the end of Ellenburger deposition resulted in subaerial exposure and karstification of these carbonates which increased the unit's overall porosity and permeability.

AGE		CENTRAL BASIN PLATFORM-NORTHWEST SHELF		DELAWARE BASIN	
Cenozoic		Alluvium		Alluvium	
Triassic		Chinle Formation		Chinle Formation	
		Santa Rosa Sandstone		Santa Rosa Sandstone	
Permian	Lopingian (Ochoan)	Dewey Lake Formation		Dewey Lake Formation	
		Rustler Formation		Rustler Formation	
		Salado Formation		Salado Formation	
				Castile Formation	
	Guadalupian	Artesia Group	Tansill Formation	Delaware Mountain Group	Lamar Limestone
			Yates Formation		Bell Canyon Formation
			Seven Rivers Formation		
			Queen Formation		Cherry Canyon Formation
			Grayburg Formation		
			San Andres Formation		Brushy Canyon Formation
	Cisuralian (Leonardian)		Glorieta Formation		
		Yeso	Paddock Mbr.		Bone Spring Formation
			Blinebry Mbr		
			Tubb Sandstone Mbr.		
			Drinkard Mbr.		
	Wolfcampian	Abo Formation			
		Hueco ("Wolfcamp") Fm.		Hueco ("Wolfcamp") Fm.	
Pennsylvanian	Virgilian	Cisco Formation		Cisco	
	Missourian	Canyon Formation		Canyon	
	Des Moinesian	Strawn Formation		Strawn	
	Atokan	Atoka Formation		Atoka	
	Morrowan	Morrow Formation		Morrow	
Mississippian	Upper	Barnett Shale		Barnett Shale	
	Lower	"Mississippian limestone"		"Mississippian limestone"	
Devonian	Upper	Woodford Shale		Woodford Shale	
	Middle				
	Lower	Thirtyone Formation		Thirtyone Formation	
Silurian	Upper	Wristen Group		Wristen Group	
	Middle				
	Lower	Fusselman Formation		Fusselman Formation	
Ordovician	Upper	Montoya Formation		Montoya Formation	
	Middle	Simpson Group		Simpson Group	
	Lower	Ellenburger Formation		Ellenburger Formation	
Cambrian		Bliss Ss.		Bliss Ss.	
Precambrian		Miscellaneous igneous, metamorphic, volcanic rocks		Miscellaneous igneous, metamorphic, volcanic rocks	

Figure 3.2-2: Stratigraphic column for the Delaware basin, the Northwest Shelf and Central Basin Platform (modified from Broadhead, 2017).

During Middle to Upper Ordovician time, the seas once again covered the area and deposited the carbonates, sandstones and shales of the Simpson Group (0 – 1,000 ft) and then the Montoya Formation (0 – 600 ft). This is the period when the Tobosa Basin formed due to the Pedernal uplift and development of the Texas Arch (**Figure 3.2-4**; Harrington, 2019) shedding Precambrian crystalline clasts into the basin. Reservoirs in New Mexico are typically within deposits of shoreline sandstones (Broadhead, 2017). A subaerial exposure and karstification event followed the deposition of the Simpson Group. The Montoya Formation marked a return to dominantly carbonate sedimentation with minor siliciclastic sedimentation within the Tobosa Basin (Broadhead, 2017; Harrington and Loucks, 2019). The Montoya Formation consists of sandstones and dolomites and have also undergone karstification.

Figure 3.2-3: *A subsidence chart from Reeves County, Texas showing the timing of development of the Tobosa and Delaware basins during Paleozoic deposition (from Ewing, 2019)*

Figure 3.2-4: *Tectonic Development of the Tobosa and Permian Basins. A) Late Mississippian (Ewing, 2019). Note the lateral extent (pinchout) for the lower Paleozoic strata. B) Late Permian (Ruppel, 2019a).*

Siluro-Devonian formations consist of the Upper Ordovician to Lower Silurian Fusselman Formation (0 – 1,500 ft), the Upper Silurian to Lower Devonian Wristen Group (0 – 1,400 ft), and the Lower Devonian Thirtyone Formation (0 – 250 ft). The Fusselman Formation is composed of shallow-marine platform deposits of dolostones and limestones (Broadhead, 2017; Ruppel, 2019b). Subaerial exposure and karstification associated with another unconformity at top of the Fusselman Formation as well as intraformational exposure events created brecciated fabrics, widespread dolomitization, and solution-enlarged pores and fractures (Broadhead, 2017). The Wristen and Thirtyone units appear to be conformable. The Wristen Group consists of tidal to high-energy platform margin carbonate deposits of dolostones, limestones, and cherts with minor siliciclastics (Broadhead, 2017; Ruppel, 2020). The Thirtyone Formation is present in the southeastern corner of New Mexico although it appears to be either removed by erosion or not deposited elsewhere in New Mexico (**Figure 3.2-5**). It is a shelf carbonate with varying amounts of chert nodules and represents the last carbonate deposition in the area during Devonian time (Ruppel et al., 2020a).

Figure 3.2-5: *A subcrop map of the Thirtyone and Woodford formations. The Woodford (brown) lies unconformably on top of the Wristen Group where there are no Thirtyone sediments (yellow). Diagram is from Ruppel (2020).*

The Siluro-Devonian units are saltwater injection zones within the Delaware Basin and are typically dolomitized, shallow marine limestones that have secondary porosity produced by subaerial

exposure, karstification and later fracturing/faulting. These units will be discussed in more detail in Section 3.2.2.

The Devonian Woodford Shale, an un-named Mississippian limestone, and the Upper Mississippian Barnett Shale are seals for the underlying Siluro-Devonian strata. While the Mississippian recrystallized limestones have minor porosity and permeability, the Woodford and Barnett shales have extremely low porosity and permeability and would be effective barriers to upward migration of acid gas out of the injection zone. The Woodford Shale (0 – 300 ft) ranges from organic–rich argillaceous mudstones with abundant siliceous microfossils to organic-poor argillaceous mudstones (Ruppel et al., 2020b). The Woodford sediments represent stratified deeper marine basinal deposits with their organic content being a function of the oxygenation within the bottom waters – the more anoxic the waters the higher the organic content.

The Mississippian strata within the Delaware Basin consists of an un-named carbonate member and the Barnett Shale and unconformably overlies the Woodford Shale. The lower Mississippian limestone (0 – 800 ft) are mostly carbonate mudstones with minor argillaceous mudstones and cherts. These units were deposited on a Mississippian ramp/shelf and have mostly been overlooked because of the reservoirs limited size. Where the units have undergone karstification, porosity may approach 4 to 9% (Broadhead, 2017), otherwise it is tight. The Barnett Shale (0 – 400 ft) unconformably overlies the Lower Mississippian carbonates and consists of Upper Mississippian carbonates deposited on a shelf to basinal, siliciclastic deposits (the Barnett Shale).

Pennsylvanian sedimentation is dominated by glacio-eustatic sea-level cycles that produced shallowing upward cycles of sediments, ranging from deep marine siliciclastic and carbonate deposits to shallow-water limestones and siliciclastics, and capping terrestrial siliciclastic sediments and karsted limestones. Lower Pennsylvanian sediments include the Morrow and Atoka formations. The Morrow Formation (0 – 2,000 ft) within the northern Delaware Basin was deposited as part of a deepening upward cycle with depositional environments ranging from fluvial/deltaic deposits at the base, sourced from the crystalline rocks of the Pedernal Uplift to the northwest, to high-energy, near-shore coastal sandstones and deeper and/or low-energy mudstones (Broadhead, 2017; Wright, 2020). In the area, the Atoka Formation (0-500 ft) was deposited during another sea-level transgression. is dominated by siliciclastic sediments, with depositional environments ranging from fluvial/deltas, shoreline to near-shore coastal barrier bar systems to occasional shallow-marine carbonates (Broadhead, 2017; Wright, 2020).

The Middle Pennsylvanian Strawn group (an informal name used by industry). is comprised of 250 - 1,000 ft of marine sediments that range from ramp carbonates, containing patch reefs, and marine sandstone bars to deeper marine shales (Broadhead, 2017).

Upper Pennsylvanian Canyon (0 – 1,200 ft) and Cisco (0 – 500 ft) group deposits are dominated by marine, carbonate-ramp deposits and basinal, anoxic, organic-rich shales.

Deformation, folding and high-angle faulting, associated with the Upper Pennsylvanian/Early Permian Ouachita Orogeny, created the Permian Basin and its two sub-basins, the Midland and Delaware basins (Hills, 1984; King, 1948), the Northwest Shelf (NW Shelf), and the Central Basin Platform (CBP; **Figures 3.2-4, 3.2-6, 3.2-7**). The Permian "Wolfcamp" or Hueco Formation was deposited after the creation of the Permian Basin. The Wolfcampian sediments were the first sediments to fill in the structural relief (**Figure 3.2-6**). The Wolfcampian Hueco Group (~400 ft on the NW Shelf, >2,000 ft in the Delaware Basin) consists of shelf margin deposits ranging from barrier reefs and fore slope deposits, bioherms, shallow-water carbonate shoals, and basinal carbonate mudstones (Broadhead, 2017; Fu et al., 2020). Since deformation continued throughout

the Permian, the Wolfcampian sediments were truncated in places like the Central Basin Platform (**Figure 3.2-6**).

Figure 3.2-6: *Cross section through the western Central Basin Platform showing the structural relationship between the Pennsylvanian and older units and Permian strata (modified from Ward et al., 1986; from Scholle et al., 2007).*

Figure 3.2-7: *Reconstruction of southwestern United States about 278 million years ago. The Midland Basin (MB), Delaware Basin (DB) and Orogrande Basin (OB) were the main depositional centers at that time (Scholle et al., 2020).*

Differential sedimentation, continual subsidence, and glacial eustasy impacted Permian sedimentation after Hueco deposition and produced carbonate shelves around the edges of deep sub-basins. Within the Delaware Basin, this subsidence resulted in deposition of roughly 12,000 ft of siliciclastics, carbonates, and evaporites (King, 1948). Eustatic sea-level changes and differential sedimentation played an important role in the distribution of sediments/facies within the Permian Basin (**Figure 3.2-2**). During sea-level lowstands, thousands of feet of siliciclastic sediments bypassed the shelves and were deposited in the basin. Scattered, thin sandstones and siltstones as well as fracture and pore filling sands found up on the shelves correlate to those lowstands. During sea-level highstands, thick sequences of carbonates were deposited by a "carbonate factory" on the shelf and shelf edge. Carbonate debris beds shed off the shelf margin were transported into the basin (Wilson, 1972; Scholle et al., 2007). Individual debris flows thinned substantially from the margin to the basin center (from 100s of feet to feet).

Unconformably overlying the Hueco Group is the Abo Formation (700 – 1,400 ft). Abo deposits range from carbonate grainstone banks and buildups along Northwest Shelf margin to shallow-marine, back-reef carbonates behind the shelf margin. Further back on the margin, the backreef sediments grade into intertidal carbonates to siliciclastic-rich sabkha red beds to eolian and fluvial deposits closer to the Sierra Grande and Uncompahgre uplifts (Broadhead, 2017, Ruppel, 2019a). Sediments basinward of the Abo margin are equivalent to the lower Bone Spring Formation. The Yeso Formation (1,500 – 2,500 ft), like the Abo Formation, consists of carbonate banks and buildups along the Abo margin. Unlike Abo sediments, the Yeso Formation contains more siliciclastic sediments associated with eolian, sabkha, and tidal flat facies (Ruppel, 2019a). The Yeso shelf sandstones are commonly subdivided into the Drinkard, Tubb, Blinebry, Paddock members (from base to top of section). The Yeso Formation is equivalent to the upper Bone Spring Formation. The Bone Spring Formation is a thick sequence of alternating carbonate and siliciclastic horizons that formed because of changes in sea level; the carbonates during highstands, and siliciclastics during lowstands. Overlying the Yeso are the clean white eolian sandstones of the Glorietta Formation, a key marker bed in the region, both on outcrop and in the subsurface. Within

17

the basin, it is equivalent to the lowermost Brushy Canyon Formation of the Delaware Mountain Group.

The Guadalupian San Andres Formation (600 – 1,600 ft) and Artesia Group (<1,800 ft) reflect the change in the shelf margin from a distally steepened ramp to a well-developed barrier reef complex. The San Andres Formation consists of supratidal to sandy subtidal carbonates and banks deposited a distally steepened ramp. Within the San Andres Formation, several periods of subaerial exposure have resulted in karstification and pervasive dolomitization of the unit. These exposure events/sea-level lowstands are correlated to sandstones/siltstones that moved out over the exposed shelf leaving on minor traces of their presence on the shelf but formed thick sections of sandstones and siltstones in the basin. Within the Delaware Basin, the San Andres Formation is equivalent to the Brushy and lower Cherry Canyon formations.

The Artesia Group (Grayburg, Queen, Seven Rivers, Yates, and Tansill formations, ascending order) is equivalent to Capitan Limestone, the Guadalupian barrier/fringing reef facies. Within the basin, the Artesia Group is equivalent to the upper Cherry and Bell Canyon formations, a series of relatively featureless sandstones and siltstones. The Queen and Yates formations contain more sandstones than the Grayburg, Seven Rivers, and Tansill formations. The Artesia units and the shelf edge equivalent Capitan reef sediments represent the period when the carbonate factory was at its greatest productivity with the shelf margin/Capitan reef prograding nearly 6 miles into the basin (Scholle et al., 2007). The Artesia Group sediments were deposited in back-reef, shallow marine to supratidal/evaporite environments. Like the San Andres Formation, the individual formations were periodically exposed during lowstands.

The final stage of Permian deposition on the NW Shelf consists of the Ochoan/Lopingian Salado Formation (<2,800 ft, Nance, 2020). Within the basin, the Castile Formation, a thick sequence (total thickness ~1,800 ft, Scholle et al., 2007) of cyclic laminae of deep-water gypsum/anhydrite interbedded with calcite and organics, formed due to the restriction of marine waters flowing into the basin. Gypsum/anhydrite laminae precipitated during evaporative conditions, and the calcite and organic-rich horizons were a result of seasonal "freshening" of the basin waters by both marine and freshwaters. Unlike the Castile Formation, the Salado Formation is a relatively shallow water evaporite deposit. Halite, sylvite, anhydrite, gypsum, and numerous potash minerals were precipitated. The Rustler Formation (500 ft , Nance, 2020) consists of gypsum/anhydrite, a few magnesitic and dolomitic limestone horizons, and red beds. These are mostly shallow marginal marine deposits and represents the last Permian marine deposits in the Delaware Basin. The Rustler Formation was followed by terrestrial sabkha red beds of the Dewey Lake Formation (~350', Nance, 2020), ending Permian deposition in the area.

Beginning early in the Triassic, uplift and the breakup of Pangea resulted in another regional unconformity and the deposition of non-marine, alluvial Triassic sediments (Santa Rosa Sandstone and Chinle Formation). They are unconformably overlain by Cenozoic alluvium (which is present at the surface). Cenozoic Basin and Range tectonics resulted in the current configuration of the region and reactivated numerous Paleozoic faults.

3.2.2   Stratigraphy

The Permian rocks found in the Delaware Basin are divided into four series, the Ochoa (most recent, renamed Lopingian), Guadalupian, Leonardian (renamed Cisuralian), and Wolfcampian (oldest) (Figure 3.2-2). This sequence of shallow marine carbonates and thick, basinal siliciclastic deposits contains abundant oil and gas resources and are the main source of oil within New Mexico. In the area around the Bull Moose AGI well, Permian strata are mainly basin deposits consisting of sandstones, siltstones, shales, and lesser amounts of carbonates. Within the Bull

Moose area, there is no active production from the Permian Delaware Mountain Group, but there is production from the basinal Bone Spring and Wolfcamp formations. The injection and confining zones for BM AGI #1 are discussed below.

3.3 Injection Interval Properties

3.3.1 Siluro-Devonian to Ellenburger Group

In the context of BM AGI #1, the designated injection targets encompass the Siluro-Devonian formations, specifically the Devonian, Wristen, Fusselman and Montoya strata. The total thickness of the injection interval is estimated to be 1,594 ft (**Table 3.3-1**).

Table 3.3-1: Estimated BM AGI #1 formation top depths, formation thicknesses, seal and reservoir thicknesses (total), and average porosity, and permeability.

Formation	Measured Depth (ft)	Formation thickness (ft)	Unit Thickness (ft)	Porosity (%)	Permeability (mD)	Behaviour	Notes*
Rustler Fm.	934	255	4,165			Seal	450' base of useable groundwater
Salado Fm.	1,189	1,400		2.5	0.2	Seal	1200' base of USDW
Castile Fm.	2,589	2,510		1	0.01	Seal	
Lamar Ls.	5,099	45	3,990	15	100	Reservoir	
Bell Canyon Fm.	5,144	1,100		23	110	Reservoir	
Cherry Canyon Fm.	6,244	995		15	12	Reservoir	
Brushy Canyon Fm.	7,239	1,850		12	11	Reservoir	
Bone Spring Fm.	9,089	2,860	2,860	2	0.2	Seal	
Wolfcamp	11,979	1,600				Reservoir	Deepest nearby production wells
Strawn Fm.	13,579	760				Reservoir	
Atoka Fm.	14,339	215				Reservoir	
Morrow Fm.	14,554	1,795				Reservoir	
Barnett Sh.	16,349	440	1,540	1	0.1	3° Seal	
Mississippian Ls.	16,789	440		2	1	2° Seal	
Woodford Sh.	17,229	660		1	0.1	1° Seal	
Wristen Grp. And Thirtyone Fm.(Siluro Devonian)	17,889	289	1,594	5	1	Injection interval	
Fusselman Fm.	18,184	1,055		7	1	Injection interval	
Montoya Grp.	19,239	250		3	1	Injection interval	
Simpson Sands*	19,489	1,000		15	45	Not Drilled	
Ellenburger Grp.	20,489	550		6	15	Not Drilled	
Bliss/Precambrian	21,039					Lower seal	

*Simpson Sands consist of three discrete sand bodies (~300 ft of sands) within the over thousand-feet-thick unit.

ORDOVICIAN.

ELLENBURGER GROUP – The Ordovician Ellenburger Group is below the injection interval and is comprised of dolomites and limestones that are approximately 550 ft thick. The Ellenburger Group sediments were deposited in subtropical to tropical belt of shallow-water platform carbonates that covered most of what is now North America and Greenland. The Ellenburger carbonates in the Permian Basin area have been extensively altered by later diagenesis that includes several intervals of exposure and karstification, dolomitization, and fracturing and faulting during later tectonic events (**Figure 3.3-1**).

Figure 3.3-1: *Depositional model for Ellenburger Group deposits. The diagram shows a sequence of transgressive sandstones (Bliss Sandstone, yellow) to carbonates (Panels a through c followed by a regressive sequence (Panels c – d) with exposure and karstification in Panel d (from Loucks and Kerans, 2019).*

Within the Ellenburger Group strata, the upper and middle section typically has the highest porosity and permeability due to karsting and cave development as well as later faulting and fracturing (**Figure 3.3-2**). Late diagenesis plays an important role in porosity destruction and resurrection. Based on work by Loucks (2016, unpublished report), the best karst-related porosity is to the east of the Bull Moose area, whereas the Bull Moose area is in the zone of porosity due to tectonically controlled faulting and fracturing.

Porosity and permeability in the Ellenburger section can vary greatly due to the above considerations, but a realistic value for the porosity and permeability, at approximate 20,000 ft depth, is 5-6% and 15 mD (**Table 3.3-1**). Potentially the range of porosity and permeability can range up to 12% and greater than 100 mD (Loucks and Kerans, 2019).

*Figure 3.3-2: Karst development. **A)** Cave development in the upper Ellenburger rocks and their potential impact to produce porosity and permeability (from Loucks and Kerans, 2019). **B)** Zones of potential porosity creation: karst related (blue), fault and fracture (green) and enhanced primary porosity (orange) (from unpublished manuscript by R. Loucks, 2016).*

SIMPSON GROUP – The deposits of the Simpson Group represent a regional transgression after the unconformity at the end of Ellenburger deposition. This group is a thick sequence of carbonates, sandstones, and shales (~1,000 ft) which has a depocenter roughly equivalent to the Delaware Basin/Tobosa Basin. There are several transgressive/regressive cycles within the section, but only the transgressive sandstone sections have significant porosity. The rest of the section typically consists of mud-rich carbonates and shales. Within the sandstones (particularly the McKee Sandstone member), well logs indicate porosity averages around 15% (**Table 3.3-1**). Permeability averages 45 mD (Harrington, 2019), though cementation and compaction may decrease that in the area.

MONTOYA GROUP – The Montoya deposits (~250 feet) are dominated by shallow-water, ramp limestones that were deposited in the Tobosa Basin (**Figure 3.3-3**). Like the Ellenburger Group, the porosity within the Montoya Group is dependent on depositional environment and diagenesis. Sediments deposited in higher energy environments tend to have better initial porosity than those of low-energy environments. Compaction destroys porosity, while dolomitization produces

secondary porosity and local interactions of these factors determine porosity and permeability in a given area. Based on well logs, the average porosity is approximately 3%, with scattered zones over 5% (**Table 3.3-1**). The probable average permeability is probably less than 1 mD, but fracturing may enhance it.

Figure 3.3-3: Tectonic features during development of the Tobosa and Permian Basins during Late Mississippian time (Ewing, 2019).

ORDOVICIAN – SILURIAN.

FUSSELMAN FORMATION – The Fusselman Formation is a shallow-water carbonate system that was deposited in the Tobosa Basin. In the Bull Moose area, the Fusselman thickens to around 1,000 ft of high-energy packstones to grainstones. Like the Montoya Group, these high-energy sediments started out with the best primary porosity, but diagenesis usually has decreased both the porosity and permeability unless impacted by exposure and dissolution. Based on well logs, the porosity averages around 2%, but there are zones, like in well API No. 42-495-31047, with over 70 ft of greater than 5% porosity. Reported permeability for shallower sections range from 0.001 to 10 mD (Ruppel, 2019).

LOWER DEVONIAN – SILURIAN.

THIRTYONE AND WRISTEN FORMATIONS – Underlying the Woodford Shale are the interbedded dolomites and dolomitic limestones of the Devonian Thirtyone Formation and the Silurian Wristen Group, collectively referred to as the Siluro-Devonian section (~275 ft thick). Unlike the Fusselman, Montoya and Ellenburger carbonates, these deposits represent deposition in deeper waters in the Bull Moose area. These deposits range from deeper ramp mudstones and wackestones, to chert- and sponge/radiolarian-rich hemipelagic mudstones (Wristen/Thirtyone) to outer ramp packstones (**Figure 3.3-4**, Thirtyone; Ruppel, 2020; Ruppel et al., 2020a). Porosity and permeability in the Wristen are limited in the main body of the unit (1-2%), but exposure events and carbonate dissolution can improve the porosity (~5%). Within Thirtyone deposits, the chert-rich hemipelagic

deposits maintain the best porosity (up to 40%, up to 80 mD), while the limestones have less than 7% porosity and less than 1 mD of permeability (**Table 3.3-1**; Ruppel et al., 2020a).

*Figure 3.3-4: Generalized Paleogeography. **A)** Generalized paleogeography for the Wristen Group (from Ruppel, 2020). **B)** Generalized paleogeography for the Thirtyone Formation. (a) represents the earliest deposition and the presence of deep-water environments in the Bull Moose area. (b) represents the latter deposition (from Ruppel et al., 2020a).*

3.3.2   Upper Confining Zone Properties: Woodford Shale/Mississippian Limestone

Mississippian. Mississippian age deposits are commonly divided (from youngest to oldest) into the Barnett Shale and the Mississippian limestone (an un-named unit) of Lower Mississippian age. The Mississippian section is approximately 1,420 ft thick in the Bull Moose area and is regionally extensive. The Lower Mississippian limestone is a dark colored, deep marine limestone with minor cherts and shales and is ~555 ft thick. Known production from this limestone comes from small, one to two well fields that normally have poor porosity (4-9%) and permeability (Broadhead, 2017)

23

in New Mexico and a few isolated fields in the shallow water, high-energy limestones in Texas. The Barnett Shale is a widespread, dark, organic shale with very low porosity and permeability and is ~750 ft thick. Overall, Mississippian units would be good seals in preventing upward fluid movement through the section (**Table 3.3-1**).

Upper Devonian. Within the Permian Basin, the Upper Devonian Woodford Shale serves as a seal to hydrocarbon migration out of Devonian and older units. In combination with the Mississippian section, it makes an excellent seal for potential injection. the Woodford Shale is ~620 ft thick in the Bull Moose area and is laterally continuous, organic- and shale-rich, siliceous (radiolarians) mudstone. Porosity in the Woodford Shale is usually micro-porosity associated with organic material and not connected (i.e., low permeability). Porosity can reach 10% (Jarvie et al., 2001), but it averages around 1% with very low permeabilities (**Table 3.3-1**).

3.3.3   Lower Confining Zone Properties: Ordovician to Precambrian

Ordovician. The lower approximately 150 to 200 ft of the Ellenburger Group sediments are normally less porous and have lower permeability (1 – 2% porosity and <2 mD) due their original depositional environment and the depth of burial (Loucks and Kerans, 2019), making this zone a potential underlying seal.

Cambrian to Precambrian. The oldest sediment in the area is Cambrian Bliss Sandstone (Broadhead, 2017) which overlies Precambrian granites. These late Cambrian transgressive sandstones were the initial deposits from a shallow marine sea that covered most of North America and Greenland. With continued down warping and/or sea-level rise, a broad, relatively shallow marine basin formed. The Bliss Sandstone and crystalline Precambrian rocks are potential lower seals. Within the Bull Moose area, no porosity and permeability data could be found. Considering their depth, compactional history, and potential diagenetic alteration, the Bliss sandstones and associated granitic debris (from weathering of the basement rock) are probably relatively tight.

3.4   Structure/Faulting

Structure maps and cross sections for the injection interval and confining zones are provided in **Figures 3.3-5** through **3.3-15**.

Figure 3.3-5: Mississippian Limestone Subsea Structure Map. CI = 100 ft.

Figure 3.3-6: Woodford Shale Subsea Structure Map. CI = 100 ft.

Figure 3.3-7: Siluro-Devonian Strata Subsea Structure Map. CI = 100 ft.

Figure 3.3-8: Fusselman Formation Subsea Structure Map. CI = 100 ft.

Figure 3.3-9: Montoya Group Subsea Structure Map. CI = 100 ft.

Figure 3.3-10: Simpson Group Subsea Structure Map. CI = 100 ft.

Figure 3.3-11: Ellenburger Group Subsea Structure Map. CI = 100 ft.

Figure 3.3-12: Precambrian Subsea Structure Map. CI = 100 ft.

Figure 3.3-13: Base Map for Cross Sections

Figure 3.3-14: West to East Cross Section

Figure 3.3-15: North to South Cross Section

3.5   Formation Fluid Chemistry

Water data was retrieved from the U.S. Geological Survey National Produced Waters Geochemical Database v2.3 (05/22/2019) to determine formation chemistry in the Siluro-Devonian, Fusselman, and Montoya injection intervals for BM AGI #1. Chemical data was plotted in a geographical interface and delineated to a 15-mile boundary around the Bull Moose site to fully constrain each formation's geochemical signature.

There are 12 wells with analyses collected from the Siluro-Devonian, Fusselman, Montoya, and Simpson formations within 15 miles of BM #1 (red squares **Figure 3.5-1).** Samples taken in these formations generally fall within a saline (NaCl) hydrofacies, and concentrations of total dissolved solids (TDS) range from 69,140 to 341,260 milligrams per liter (mg/L) with an average of 140,024 mg/L. High salinity in these formations indicate they are compatible with injection (**Table 3.5-1**).

Figure 3.5-1: *Wells with water chemistry in the Silurian, Fusselman, or Devonian formations within 7 to 15 miles of the Bull Moose AGI well from the U.S. Geological Survey National Produced Waters Geochemical Database. Data show these formations are NaCl waters with average TDS of 140,024 mg/L.*

Table 3.5-1: *Water chemistry in mg/L for wells in the Silurian, Fusselman, or Devonian formations within ≈7 to 15 miles of BM AGI #1 from the USGS National Produced Waters Geochemical Database.*

API	Latitude	Longitude	Formation	HCO$_3$	Ca	Mg	KNa	Cl	SO$_4$	TDS
4249503296	31.8171	-103.0914	Devonian	1,347	12,410	1,799	10,290	40,390	2,904	69,140
4249503296	31.8171	-103.0914	Devonian	97	14,610	4,052	36,590	92,530	2,480	150,359
4249503296	31.8171	-103.0914	Devonian	145	14,510	4,163	36,590	92,830	2,520	150,758
4249503296	31.8171	-103.0914	Devonian	80	14,610	4,153	36,790	92,830	2,500	150,963
4249503296	31.8171	-103.0914	Devonian	122	14,600	4,028	37,050	92,940	2,437	151,177
4249503362	31.7759	-103.1165	Devonian	352	10,780	2,806	6,470	36,010	1,403	57,821
4249503447	31.7713	-103.0791	Devonian	635	2,900	300	35,500	60,000	475	99,810
4249505366	31.7771	-103.0587	Devonian	151	11,804	2,578	59,112	118,202	1,703	193,550
4249500556	31.7808	-103.0659	Fusselman	362	4,232	881	29,090	53,850	2,857	91,273
4249502061	31.7892	-103.0632	Fusselman	148	6,960	4,440	118,800	208,800	2,112	341,260
4249504327	31.7947	-103.1054	Fusselman	458	4,244	706	29,620	53,810	1,568	90,406
4249504328	31.789	-103.1145	Fusselman	427	4,236	1,016	45,650	78,800	2,420	132,549
4249505210	31.7873	-103.0894	Fusselman	849	10,640	945	24,780	59,440	460	97,114
4249505412	31.9086	-103.0894	Fusselman	202	1,733	536	48,589	73,421	4,400	128,881
4249510248	31.8322	-103.1845	Fusselman	706	499	386	91,284	139,300	4,317	236,491
4249505234	31.8297	-103.1579	Silurian	327	4,758	962	31,960	59,200	1,625	98,832

3.6   Groundwater Hydrology in the Vicinity of the Bull Moose Gas Plant

Regionally, groundwater near the BM AGI #1 site is drawn from one of five sources. From shallow to deep those are Quaternary-Late Tertiary Pecos Valley Deposits, Cretaceous sediments of the Edwards-Trinity Groups, Triassic deposits of the Dockum Group, the Permian (Oochan) aged Rustler Formation, and the Permian (Guadalupian) aged Capitan Reef Complex. Based on current water data with the Texas Water Development Board (TWDB), the primary groundwater sources at the site are the Pecos Valley Alluvium and the Dockum Group (**Figure 3.6-1**). Below we provide a general description of the groundwater sources and the wells within the MMA at the BM AGI #1 site.

3.6.1   Pecos Valley Aquifer

The Pecos Valley Aquifer lies unconformably on portions of the Edwards-Trinity Plateau, Dockum, Rustler, and Capitan Reef aquifers. It covers an area of 6,829 mi^2 and is comprised of sediments that range in size from clay to boulder which were deposited in a variety of continental settings including fluvial, valley-fill, eolian, lacustrine, and solution-collapse environments (Wise et al., 2012). Sediments of the Pecos Valley Aquifer fill several structural basins, the largest of which are Monument Draw Trough in the east and the Pecos Trough in the west. Maximum thickness of the alluvial fill reaches approximately 1,500 ft, and freshwater saturated thickness averages around 250 ft (George et al., 2011).

The water quality is highly variable, with the water typically being hard, and generally better in the Monument Draw Trough than in the Pecos Trough. Total dissolved solids have been found to range from 116 to over 15,000 mg/L depending on location and proximity to oil and gas or halite mining operations in the region (Wise et al., 2012). The aquifer is generally characterized by high levels of sulfate and chloride in excess of secondary drinking water standards which has been linked to previous oil field activities. Also, naturally occurring radionuclides and arsenic can be found in excess of primary drinking water standards (George et al., 2011). More than 80 percent of Pecos

Valley groundwater is used for irrigation, while the remainder is used for municipal supplies, power generation, and industrial use.

3.6.2   Dockum Aquifer

The Upper Triassic Dockum Group covers about 96,000 square miles in parts of Kansas, Oklahoma, Colorado, New Mexico, and Texas. From young to old the Dockum includes the Santa Rosa and Tecovas formations, the Trujillo Sandstone, and the Cooper Canyon Formation. These formations consist of conglomerate, gravel, sandstone, siltstone, mudstone, and shale with recoverable quantities of groundwater located in the sandstone and conglomerate. The largest yields are typically found in the coarsest deposits in the middle and base of the group. Locally any water-bearing sandstone of the Dockum Group is referred to as the Santa Rosa Aquifer (Bradley and Kalaswad, 2003; 2004; George et al., 2011).

Water quality in the Dockum Aquifer varies, ranging from fresh (TDS <1,000 mg/L) on outcrop to brine (TDS >10,000mg/L) where it is confined, typically deteriorating with depth. TDS concentrations have been found to be >60,000 mg/L in the deepest parts of the aquifer. Groundwater in the Dockum aquifer is typically hard, average of 470 mg/L, and radionuclides naturally derived from uranium can be found at concentrations a >5 pCi/L in many areas of the aquifer (Bradley and Kalaswad, 2003; 2004). Locally, the Dockum Aquifer can be vital for irrigation, public supply, livestock watering, manufacturing, and oil-field activity. However, a combination of deep pumping depths, low yields, poor water quality, and declining water levels have hindered a more widespread use (Bradley and Kalaswad, 2003).

3.6.3   Groundwater Wells Within the Bull Moose AGI Site MMA

Data collected from the Texas Water Development Board's (TWDB) Groundwater Database and Submitted Driller Report Database indicate there are 2 freshwater wells located within the MMA for BM AGI #1. Both wells are permitted for domestic use and are shallow, collecting water from 152 to 245 ft depth in Pecos Alluvium and Triassic redbeds of the Dockum Group (Garza and Wesselman, 1963; Ashworth, 1990; Bradley and Kalaswad, 2003; **Table 3.6-1**). General chemistry analysis of one well within the MMA indicates that the Pecos Valley Alluvium/Dockum Group is a Ca-HCO$_3$/SO$_4^{2-}$ water with TDS of 567 mg/L (**Table 3.6-2**). The shallow freshwater aquifers are protected by the surface and intermediate casings and cements in the BM AGI #1 well. While the casings and cements protect shallow freshwater aquifers, they also serve to prevent CO$_2$ leakage to the surface along the borehole.

Figure 3.6-1: *Major and minor aquifers of the region. Groundwater at the proposed site is derived from the Pecos Valley Alluvium and Dockum Group.*

Table 3.6-1: *Groundwater wells within the MMA of the Bull Moose AGI site with from the Texas Water Development Board (TWDB) Groundwater Database (GWDB) and Submitted Driller Report (SDR) Database. Well depth is from 152 to 245 ft. and used for domestic purposes.*

Well ID/Report	Owner_Name	Use	County	Well_Depth	Latitude	Longitude
4614901	D P Anderson	Domestic	Winkler	152	31.76806	-103.285
409232	Frontier Energy	Domestic	Winkler	245	31.79591	-103.277

Table 3.6-2: *Groundwater chemistry for well 4614901 from Table 3.5-1 indicates that the Pecos Valley Alluvium/Dockum Group is a Ca-HCO₃/SO₄²⁻ water with TDS of 567 mg/L.*

StateWellID	Aquifer_Code	Date	HCO$_3$	Ca	Mg	Na	Cl	SO4	TDS
4614901	100CPDG	8/23/1940	256	97	38	43	53	189	557

3.7   Historical Operations

3.7.1   Bull Moose Site

In response to increasing production and to meet the infrastructure needs of producers, Targa is constructing a new Bull Moose 275 MMSCFD cryogenic natural gas processing plant. **Figure 3.7-1** shows the simplified process block flow diagram, with the entry point for the CO_2, the flow meter location and the sampling point, before BM AGI #1 well.

3.7.2   Operations within the MMA for the BM AGI Well

TRRC records identify a total of 29 oil- and gas-related wells within the MMA (see **Appendix 3**). **Figure 3.7-2** shows the geometry of producing and injection wells within the MMA. **Appendix 3** summarizes the relevant information for those wells.

Among the 29 wells identified, 25 are horizontal oil wells completed in the Bone Spring (8 wells) or Wolfcamp (17 wells) formations, at depths between 11,564 and 12,545 ft. One is inactive and three are plugged and abandoned.

There are four other vertical wells. There are two vertical plugged and abandoned gas well in the Morrow Formation (16,000 ft). There are also two Saltwater Disposal (SWD) wells that are injecting in the Brushy Canyon (7,516 and 7,630 ft).

All of these productive zones are more than 5,300 ft above the BM AGI #1 injection zone.

SP-SAMPLE POINT FOR GAS ANALYSIS, MONTHLY

Flow Meter

FM

SP

BULL MOOSE CO2

BULL MOOSE WELL

BM AGI #1

FUTURE PLANT CONNECT

Figure 3.7-1: Process Block Flow Diagram with CO_2 entry, Flow meter (FM), Sampling point (SP) and BM AGI #1.

Legend

- 🔵 TWDB_Groundwater

Well Type

- ·
- ✧ DRY HOLE
- ✺ GAS
- ⊘ INJECTOR
- ● OIL
- ✹ OIL & GAS
- 🔵 SWD
- 🟠 UNREPORTED
- ⊙ Bullmoose AGI #1
- —— Plume 2070
- +++ Plume 2060
- —— Plume 2055
- ▮ BM MMA

Bullmoose AGI #1

0   0.25   0.5   1   1.5   2
Miles

Figure 3.7-2: *Location of all oil- and gas-related wells within the MMA for the BM AGI #1 well. Both the surface hole locations (SHL) and bottom hole locations (BHL) are labeled on the figure.*

39

3.8   Description of Injection Process

The Bull Moose Gas Plant, including the BM AGI #1 well, will be in operation and staffed 24-hours-a-day, 7-days-a week. The plant gathers and processes produced natural gas. Once gathered at the plant, the produced natural gas is compressed, dehydrated to remove the water content, and processed to remove and recover natural gas liquids. The processed natural gas and recovered natural gas liquids are then sold and shipped to various customers. The inlet gathering lines and pipelines that bring gas into the plant are regulated by U.S. Department of Transportation (DOT), National Association of Corrosion Engineers (NACE) and other applicable standards which require that they be constructed and marked with appropriate warning signs along their respective rights-of-way. TAG from the plant's sweeteners will be routed to a central compressor facility. Compressed TAG is then routed to the well via high-pressure rated lines.

The natural gas to be treated at this facility is produced from oil and gas wells in the Permian Basin region, including Culberson, Jeff Davis, Loving, Pecos, Reeves, Ward and Winkler counties, Texas plus Lea and Eddy counties in New Mexico. A sample from Targa 's nearby Wildcat facility (5 miles west) was taken on 11/10/2023 and is representative of the injection stream for the Bull Moose facility. The results of that analysis are provided in **Table 3.8-1**.

Table 3.8-1: Sample Gas Composition for Wildcat AGI #1

Component	Mol %
Carbon Dioxide	91.339
Methane	0.350
Ethane	0.054
Propane	0.061
Iso-Butane	0.003
N-Butane	0.022
Iso-Pentane	0.000
Hexanes Plus	0.099
Hydrogen Sulfide	8.072
Nitrogen	0.000
TOTAL	100.00

The composition may change over time based on the amount of H_2S in the natural gas processing inlet stream. For modeling purposes, an injectate composition of 30% H_2S and 70% CO_2 was assumed as a conservative approach.

3.9   Reservoir Characterization Modeling

3.9.1   Inputs and Assumptions

Dynamic reservoir simulation was performed based on a high resolution geological model. The modeling predicts the well injectivity, pressure behaviors, and TAG plume migration.

Schlumberger's Petrel® (Version 2023.3) software was used to construct the geological models used in this work. Computer Modelling Group (CMG) software was used to perform the reservoir simulations presented in this MRV plan. The software was used to perform PVT calculation through Equation of States and properties interactions among various compositions to feed the hydrodynamic modeling. The hydrodynamical model considers aqueous, gaseous, and supercritical phases of the CO_2, simulates the storage mechanisms including structural trapping, residual gas trapping, and solubility trapping. Injected TAG may exist in an aqueous phase or in a gaseous phase, in a supercritical state.

The static model is constructed using well tops picked from logs and interpretations from 3D seismic survey to interpret and delineate formations and structural features. The geologic model covers a 3.2-miles by 3.0-miles area (**Figure 3.9-1**). The model is divided into 745,200 cells. The average cell size of the active injection area is 150 square ft. **Figure 3.9-2** shows the simulation model in 3D view. The porosity and permeability of the model are evaluated using existing well logs and 3D seismic inversion. The range of the porosity is between 0.01 to 0.31. The initial permeability is interpolated between 0.02 to 155 millidarcy (mD), and the vertical permeability anisotropy is 0.1. (**Figure 3.9-2**).

Figure 3.9-1: BM AGI #1 model boundaries

41

Figure 3.9-2: *3D view of the geological model for the BM AGI #1 well. The model displays the Salado-Castille Formation, Lamar limestone, Bell Canyon, Cherry Canyon, Brushy Canyon, Bone Spring, Wolfcamp, Woodford, Siluro-Devonian, Fusselman, Simpson and Ellenburger formations. Color legends represent the zones.*

At the initialization of the simulation, the water saturation in the storage reservoir is assumed to be 100%, with a residual water saturation of 20% (Krause, M. H., and Benson, S. M., 2015). The initial salinity is assumed to be 150,000 ppm (Nicot et al., 2020). A geothermal gradient of 1.25°F/100 ft was adopted (Ge, J. et al., 2022). Following standard industry practices, a pore pressure gradient of 0.43 psi/ft is used. Therefore, the reservoir pressure at the top of the Siluro-Devonian at the location is estimated to be 7,650 psi.

The fracture gradient (FG) for the injection interval is calculated using Eaton's equation.

$$FG = \frac{\nu}{1-\nu}\left(OBG - p_p\right) + p_p$$

Where,

ν is the Poisson's ratio,

OBG is the overburden gradient,

p_p is the pore pressure gradient.

An overburden gradient of 1.05 psi/ft is adopted in the calculation. This value is considered best practice when a site-specific number is not available. Poisson's ratio is inferred to be 0.3 in the injection interval. A minimum value of 0.29 and a maximum value of 0.31 are used to quantify uncertainty (Smye et al, 2021, Dvory and Zoback, 2021). The fracture gradient is estimated to be 0.62 to 0.68 psi/ft, therefore the formation fracture pressure calculated at the top of the injection interval is 12,350 psi. In addition, a safety factor of 10% is applied to the resulting fracture gradient. This safety factor ensures injecting pressure will not exceed the fracture gradient in the injection interval, where the maximum bottomhole pressure was set to 0.63 psi/ft during active injection in the simulation. The results are summarized in **Table 3.9-1 & Table 3.9-2**. As these values are calculated based on available legacy well logs and literature listed in the reference, the actual gradient will be measured upon completion of the proposed well, and the modeling and simulation efforts will be updated accordingly.

A review of the TRRC databases identified no saltwater disposal (SWDs) or other injection wells within the model boundaries in the proposed injection interval.

Table 3.9-1: Summary of reservoir simulation inputs.

Reservoir properties of injection zones	Wristen & Fusselman
Porosity	As shown in geologic model
Permeability	As shown in geologic model
Pore pressure gradient	0.43 – 0.45 psi/ft (estimated from DST data in Winkler county – Dvory and Zoback (2021); Luo et al. (1994)
Formation fracture gradient	0.65 $\pm$0.03 psi/ft

Reservoir properties of injection zones	Wristen & Fusselman
Formation temperature	0.014 F/ ft (45 wells BHT data in Winkler–Luo et al. 1994)
Water salinity	150,000 ppm (Nicot et al. 2020 based on P50 of TDS in Winkler County showing 150kppm)
Initial water saturation	100% (assumption made for conservative CO_2 plume)

Table 3.9-2: Summary of well simulation inputs.

Injection well setup	Wristen & Fusselman
Bottom hole pressure	90% of formation fracture pressure or 11,300 psi at bottom hole
Well head pressure	0.5 psi/ft to the top of injection interval (approximately 8,945 psi) – RRC Standards and Procedures for Class II Wells
Wellhead temperature	90-100 °F
Injection fluid	70% CO_2, 30% H_2S
Injection rate	20 MMSCFD over 30 years (2025 – 2055)

BM AGI #1 is simulated to inject at the injection rate of 20 MMSCFD. In accordance with the TRRC Injection Storage Manual; Chapter III - Standards and Procedures for Class II Wells, the maximum surface injection pressure may not ordinarily exceed 0.5 psi per foot of depth to the top of the authorized injection or disposal interval. Therefore, a maximum allowable surface injection pressure of 8,945 psi is used in the simulation. Additionally, a maximum bottomhole pressure of 11,300 is enforced and 90% of the estimated formation fracture gradient is set as a secondary

constraint in the simulation. The composition of the injection stream is estimated to be 30% H$_2$S and 70% CO$_2$. The simulated injection starts on 01/01/2025 and stops on 01/01/2055, after a 30-year active injection phase. The termination of the simulation is on 01/01/2085, with an additional 30 years of post-injection, to estimate the maximum plume extent and the stabilized plume.

3.9.2   Model Outputs

Simulations indicate BM AGI #1 can inject at the proposed rate throughout the 30-year period without any complications. Linear cumulative injection behavior (**Figure 3.9-3**) also indicates that the Siluro-Devonian, Fusselman and Montoya formations receive the TAG stream freely. **Figure 3.9-3** shows a constant injection rate of 20 MMSCFD of the TAG stream injected over 30 years under the proposed bottom-hole pressure constraint. The modeling results indicate that the formations are capable of safely receiving and containing the proposed gas volume without violating the permitted rate and pressure. **Figure 3.9-4** shows the cumulative disposed H$_2$S and CO$_2$ separately in gas mass.

Figure 3.9-3: Average daily injection volume for Bull Moose AGI No. 1 (2025 to 2055, 20 MMSCFD).

Figure 3.9-4: *Predicted cumulative mass of injected CO_2 and H_2S for BM AGI #1 well (injection operation from 2025 to 2055).*

3.9.3   Treated Acid Gas Plume

Figure 3.9-5 shows the TAG plume evolution for BM AGI #1 in the years 2030, 2035, 2040, 2045, 2050, 2055, marking 5-year increments from the beginning of the injection simulation in 2025. The diameter of the most extensive part of the TAG plume is estimated to be 7,500 ft (1.42 mi), with stabilization achieved in 2070

Figure 3.9-5: *Extent of TAG plume (represented by gas saturation with 1% threshold) at years 2030, 2035, 2040, 2045, 2050, 2055 (end of injection = t), 2060 (t+5) and stabilized plume in 2070.*

4 Delineation of the Monitoring Areas

The delineation of the active monitoring area (AMA) and the maximum monitoring area (MMA) are based on the simulation results from section 3.9.

4.1 AMA – Active Monitoring Area

The AMA is shown in **Figure 4-1** and is consistent with the requirements in 40 CFR 98.449 because it is the area projected:

(1) to contain the free phase CO_2 plume for the duration of the project (year t, t = 2055), plus an all-around buffer zone of one-half mile **(Figure 4.1-1);**

(2) to contain the free phase CO_2 plume for at least 5 years after injection ceases (year t + 5, t + 5 = 2060).

Figure 4.1-1: Bull Moose AMA according to definition (1).

Targa intends to define the AMA to be the same area as the MMA. The black polygon at year t=2055 is the BM AGI #1 well plume at the end of injection, and the black cross-hatched polygon in **Figure 4.1-1** is the plume extent at the end of injection plus 5 years. The red polygon in **Figure 4.1-2** is the stabilized plume extent 15 years after injection ceases, i.e. 2070. The AMA, which is the hatched area in **Figure 4.1-1** and the MMA shown as the red-filled polygon in **Figure 4.1-2** contains the CO_2 plume during the duration of the project and at the time the plume has stabilized.

4.2   MMA – Maximum Monitoring Area

As defined in Section 40 CFR 98.449 of Subpart RR, the MMA is "equal to or greater than the area expected to contain the free phase CO_2 plume until the CO_2 plume has stabilized plus an all-around buffer zone of at least one-half mile." A CO_2 saturation threshold of 1% is used in the reservoir characterization modeling in Section 3.9 to define the extent of the plume.

According to the reservoir modeling results, after 30 years of post-injection monitoring (year=2085), the injected gas will remain in the reservoir and no expansion of the TAG footprint is observed after 2070. Therefore, the plume extent at year 2070 is maximal, and the plume plus a one-half-mile buffer is the initial area with which to define the MMA: **Figure 4.1-2**.

In addition, according to EPA regulation: "The buffer is intended to encompass leaks that might migrate laterally as they move towards the surface. EPA has determined that a buffer zone of at least one-half mile will have an acceptable probability of encountering leaks in many circumstances."

Therefore, Targa considered the identified faults surrounding the injection well in order to define the MMA. There was no need to extend the MMA to incorporate the faults plus a one-half-mile buffer around the faults because they are outside the initial AMA and MMA. Therefore, the MMA encompasses the union of two areas:

- The area covered by the stabilized plume plus an all-around buffer zone of one-half mile

- The area covered by the lateral extent of known potential leakage pathways (the trace faults Figure 4.2) plus an all-around buffer zone of one-half mile around the traces.

Figure 4.1-2 shows the MMA as defined by Section 40 CFR 98.449 of Subpart RR. The MMA is expected to contain the free phase CO_2 plume throughout the life of the project and the lateral extent of potential leakage pathway plus a one-half mile buffer. The AMA is set equal to the MMA.

Figure 4.1-2: *Active monitoring area (AMA) and Maximum monitoring area (MMA) for Targa BM AGI #1; and plume at the end of injection (2055), 5 years after end of injection (2060) and stabilized plume (2070)*

5 Identification and Evaluation of Potential Leakage Pathways to the Surface

Subpart RR at 40 CFR 448(a)(2) requires the identification of potential surface leakage pathways for CO_2 within the MMA and the evaluation of the likelihood, magnitude, and timing of surface leakage of CO_2 through these pathways. Targa has identified and evaluated the potential CO_2 leakage pathways to the surface.

An evaluation of each of the potential leakage pathways is described in the following paragraphs, notably:

1. Potential leakage from surface equipment

2. Potential leakage from approved not yet drilled wells

3. Potential leakage from existing wells

4. Potential leakage through the confining / seal system

5. Potential leakage due to lateral migration

6. Potential leakage through fractures and faults

7. Potential leakage due to natural / induced seismicity

Risk estimates were made using a risk matrix (**Figure 5.1-1**) with a methodology to evaluate risk probability and impact. In addition, Targa used the National Risk Assessment Partnership (NRAP) tools, developed by five national laboratories: NETL, Los Alamos National Laboratory (LANL), Lawrence Berkeley National Laboratory (LBNL), Lawrence Livermore National Laboratory (LLNL), and Pacific Northwest National Laboratory (PNNL). The NRAP collaborative research effort leveraged broad technical capabilities across the Department of Energy (DOE) to develop the integrated science base, computational tools, and protocols required to assess and manage leakage risks at geologic carbon storage sites.

Magnitude

Likelihood \ Magnitude	Insignificant 1	Minor 2	Significant 3	Major 4	Severe 5
Almost certain 5	Medium 5	High 10	Very high 15	Extreme 20	Extreme 25
Likely 4	Medium 4	Medium 8	High 12	Very high 16	Extreme 20
Moderate 3	Low 3	Medium 6	Medium 9	High 12	Very high 15
Unlikely 2	Very Low 2	Low 4	Medium 6	Medium 8	High 10
Very Unlikely 1	Very Low 1	Very Low 2	Low 3	Medium 4	Medium 5

Figure 5.1-1: 5x5 Risk Matrix used to evaluate leakage likelihood and magnitude.

5.1 Potential Leakage from Surface Equipment

Due to the corrosive nature of CO_2 and H_2S, there is a potential for leakage from surface equipment at sour gas facilities. Preventative risk mitigation includes adherence to relevant regulatory requirements and industry standards governing the construction, operation, and maintenance of gas plants. Specifically, NMAC 19.15.26.10 requires injection well operators to operate and maintain "surface facilities in such a manner as will confine the injected fluids to the interval or intervals approved and prevent surface damage or pollution resulting from leaks, breaks or spills".

Operational risk mitigation measures relevant to potential CO_2 emissions from surface equipment include a schedule for regular inspection and maintenance of surface equipment. Additionally, Targa implements several methods for detecting gas leaks at the surface. Detection is followed up by immediate response. These methods are described in more detail in sections 6 and 7.

Likelihood:

Although mitigative measures are in place to minimize CO_2 emissions from surface equipment, such emissions are possible. Any leaks from surface equipment would result in immediate (timing) emissions of CO_2 to the atmosphere, the magnitude of which would depend on the duration of the leak and the operational conditions at the time and location of the leak.

The injection well and the pipeline that carries CO_2 to it are the most likely surface components of the system to allow CO_2 to leak to the surface. The accumulation of wear and tear on the surface components, especially at the flanged connection points, is the most probable source of the leakage.

Another possible source of leakage is the release of air through relief valves, which are designed to alleviate pipeline overpressure. Leakage can also occur when the surface components are damaged by an accident or natural disaster, which releases CO_2.

Therefore, Targa infers that there is a potential risk for leakage via this route. However, due to the standards enforced during construction, the monitoring equipment in place and the regular inspections and maintenances, the probability of such leakage is considered very unlikely.

Magnitude and Timing:

Depending on the component's failure mode, the magnitude and timing of the leak can vary greatly. For example, a rapid break or rupture could release thousands of pounds of CO_2 into the atmosphere almost instantly, while a slowly deteriorating seal at a flanged connection could release only a few pounds of CO_2 over several hours or days.

Surface component leakage or venting is only a concern during the injection operation phase. Once the injection phase is complete, the surface components will no longer be able to store or transport CO_2, eliminating any potential risk of leakage.

Therefore, the impact (i.e. magnitude) of such a leakage is considered to vary from insignificant to severe according to scenarios. The timing is also variable.

5.2 Potential Leakage from Approved Not Yet Drilled Wells

Likelihood:

Approval and construction of oil and gas-related wells, including injection wells, are regulated by TRRC rules (Appendix 2), specifically Rule 13 for casing, cementing, drilling, well control, and completion, which require that wells be constructed in such a manner as to prevent vertical migration of fluids, including gases, behind the casing. Adherence to these requirements will

mitigate the risk of potential CO_2 emissions to the surface. In addition, these wells have strict requirements and will be actively monitored for integrity on a regular basis. Therefore, the likelihood of leakage from approved and not yet drilled wells is considered very unlikely.

Magnitude:

Based on worst-case scenario considerations, the following NRAP analysis and the very unlikely risk of leakage happening from approved wells that have not yet been drilled, the magnitude of potential gas leaks through these wells is insignificant.

Timing:

All the wells within the MMA are either injecting, producing, plugged and abandoned or inactive, **Table 5.1-1**. There are no approved and not yet drilled wells based on the available records. Timing evaluations indicate no imminent risk of gas leakage from approved wells that have not yet been drilled.

5.3 Potential Leakage from Existing Wells

Existing oil and gas wells within the MMA, as delineated in Section 4, are shown in **Figure 3.7-2** and detailed in **Appendix 3**.

Targa considered all wells completed and approved within the MMA in the NRAP risk assessment. None of the wells in the MMA penetrate the confining zone nor the injection zone. All of the productive zones lie at more than 5,300 ft above the BM AGI #1 injection zone.

Likelihood:

Even though the risk of CO_2 leakage through the wells that do not penetrate confining zones is very unlikely, (the CO_2 would have to leak through the sealing zone), Targa did not omit any potential source of leakage in the NRAP analysis.

Magnitude:

If leakage through wellbores happens, the worst-case scenario is predicted using the NRAP tool to quantitatively assess the amount of CO_2 leakage through existing and approved wellbores within the MMA. A total of 29 wells inside MMA were addressed in the NRAP analysis. The reservoir properties, well data, formation stratigraphy, and MMA area were incorporated into the NRAP tool to forecast the rate and mass of CO_2 leakage.

There were 22 active oil wells that were considered in the NRAP risk assessment section. The other wells that were considered for the risk leakage assessment include two injection wells, six abandoned and plugged wells, and one inactive well. Reservoir and seal confinement properties were incorporated into the model, together with CO_2 properties and injection rates and pressures. The injection period was set to 30 years. According to the NRAP results, no leakage mass of CO_2 was recorded throughout the injection period.

Timing: The duration for CO_2 to get to the atmosphere via upward migration through the 5,300 ft of sealing and other geologic formations would be several thousands of years.

The **Table 5.1-1** summarizes the oil and gas wells and their evaluated risk. Based on the previous comments, all the wells expect three have a very low risk of CO_2 leakage. The likelihood of CO_2 leakage is very unlikely and the magnitude insignificant. Three wells have a medium risk, they present an unlikely likelihood of CO_2 leakage but can have a significant magnitude.

Table 5.1-1: *Well within the MMA with their evaluated risk.*

API	Well Type	Well Status	Trajectory	Formation	TVD (ft)	Risk Probability (1-5)	Risk Impact (1-5)	Total Risk Rating
42-495-34978	AGI	INJECTING	VERTICAL	Siluro-Devonian	TBD	2	3	6
42-495-34038	SWD	INJECTING	VERTICAL	BRUSHY CANYON	7,516	1	1	1
42-495-33871	SWD	INJECTING	VERTICAL	BRUSHY CANYON	7,630	1	1	1
42-495-34331	OIL	PRODUCING	HORIZONTAL	BONE SPRING	11,564	1	1	1
42-495-34324	OIL	PRODUCING	HORIZONTAL	BONE SPRING	11,621	1	1	1
42-495-34488	OIL	PRODUCING	HORIZONTAL	BONE SPRING	11,627	1	1	1
42-495-34489	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	11,637	1	1	1
42-495-33759	OIL	PRODUCING	HORIZONTAL	BONE SPRING	11,718	1	1	1
42-495-33230	OIL	P & A	HORIZONTAL	BONE SPRING	11,811	1	1	1
42-495-33230	OIL	P & A	HORIZONTAL	BONE SPRING	11,814	1	1	1
42-495-33230	OIL	P & A	HORIZONTAL	BONE SPRING	11,816	1	1	1
42-495-34325	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	11,858	1	1	1
42-495-33236	OIL	INACTIVE PRODUCER	HORIZONTAL	BONE SPRING	11,868	1	1	1
42-495-34332	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	11,897	1	1	1
42-495-34483	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	11,972	1	1	1
42-495-34323	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,106	1	1	1

API	Well Type	Well Status	Trajectory	Formation	TVD (ft)	Risk Probability (1-5)	Risk Impact (1-5)	Total Risk Rating
42-495-34485	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,129	1	1	1
42-495-34481	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,145	1	1	1
42-495-34482	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,176	1	1	1
42-495-33840	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,185	1	1	1
42-495-33726	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,188	1	1	1
42-495-34329	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,193	1	1	1
42-495-33763	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,194	1	1	1
42-495-34326	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,208	1	1	1
42-495-34484	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,217	1	1	1
42-495-34328	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,263	1	1	1
42-495-34330	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,537	1	1	1
42-495-34327	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,545	1	1	1
42-495-32972	GAS	P & A	VERTICAL	MORROW	16,000	3	2	6
42-495-32972	GAS	P & A	VERTICAL	MORROW	16,000	3	2	6

5.3.1 Wells Completed in the Injection Zone

The only well completed in the BM AGI #1 well injection zone is the BM AGI #1 well.

Likelihood:

To minimize the likelihood of leaks from new wells, TRRC regulation regarding the casing and cementing of injection wells requires operators to case injection wells with safe and adequate casing or tubing so as to prevent leakage and set and cement the casing or tubing to prevent the movement of formation or injected fluid from the injection zone into another injection zone or to the surface around the outside of the casing string.

Magnitude and Timing:

To minimize the magnitude and duration (timing) of CO_2 leakage to the surface, TRRC requires the use of blowout preventers in areas of high pressure at or above the projected depth of the well. These requirements apply to any other new well drilled within the MMA for this MRV plan.

In addition, for safety purposes, Targa will be implementing enhanced safety protocols to ensure that no H_2S or CO_2 flow to the surface by:

- Monitoring H_2S at surface at many locations (H_2S can be a proxy to detect CO_2);

- Employing a high level of caution and care while drilling, including use of slower drilling processes and more vigilant mud level monitoring in the returns while drilling into the injection zone.

By drilling through producing zones, there is a possibility of gas emission to the surface from the pressurized zone. The emission would be nearly immediate. The magnitude of such an emission would be estimated based on field conditions at the time of the detected leak. The safety protocols described above are in place to prevent and/or minimize the magnitude of such a leak should one occur.

Due to these safeguards and the continuous monitoring of BM AGI #1 operating parameters by the distributed control system (DCS), Targa considers that while the likelihood of surface emission of CO_2 is possible, the magnitude of such a leak would be minimal as detection of the leak would be nearly instantaneous followed by immediately shutting in the well and remediation.

5.3.2 Horizontal Wells

The table in **Appendix 3** and **Figure 3.7-2** show a number of horizontal wells in the area, many of which are producing. As discussed in 5.3, they are all 5,300 ft above the injection zone and the risk of leakage through these wells is considered very unlikely and insignificant.

5.3.3 Groundwater Wells

According to the Texas Water Development Board water database, there are no water wells within the MMA. There are only one North-East of the MMA and South-West of the MMA. Therefore, the risk of leakage through these wells are considered very unlikely and insignificant TWDB

5.4 Potential Leakage through the Confining / Seal System

Although unlikely, Targa considered leakage through confining zones in the NRAP risk assessment.

Likelihood:

The Barnett shale (440 ft), Mississipian limestone (440 ft) and Woodford Shale (660 ft) serve as the major seals or caprock layer to the injection zones. Their low porosity (1%) and permeability (<0.1

mD) provide high seal integrity (Sections 3.2, 3.3) There is. no evidence of faulting or natural fracturing. It is very unlikely that TAG injected into the injection formation will leak through this confining zone to the surface. Limiting the injection pressure to less than the fracture pressure of the confining zone will minimize the likelihood of CO_2 leakage through this potential pathway to the surface.

Magnitude and Timing:

The worst-case scenario is defined as leakage through the seal immediately above the injection well, where CO_2 saturation is highest.

To simulate this scenario, cell blocks were created to cover the MMA, serving as the most prone zone for CO_2 leakage. These cell block locations and CO_2 saturation at the seal and seal properties were incorporated into the NRAP model.

Figures 5.4-1 and 5.4-2 present the leakage rate and cumulative mass of leakage over 60 years. The total leakage mass recorded after 60 years is about 8,000 kg. According to the total mass of CO_2 injected per year alone, after 60 years, the percentage of leakage through confining zone is estimated to be 0.0021%. This is reliably minimal and considering other stratigraphic strata, Targa concludes that the risk of leakage through this pathway is highly unlikely and insignificant.

Figure 5.4-1: Seal leakage rate

Figure 5.4-1: *Cumulative mass of Seal leakage*

5.5   Potential Leakage due to Lateral Migration

Likelihood:

Regional consideration of the geology (Section 3.3) and the model built suggest that BM AGI #1 injection zones have adequate storage capacity for the proposed injection amount. In addition, simulation (Section 3.9) indicates that the injected TAG will be easily contained close to the injection well, thus minimizing the likelihood of lateral migration of TAG outside the MMA.

Based on the geological discussion and analysis of the injection zone, Targa considers that the likelihood of CO_2 to migrate laterally is unlikely.

Magnitude and Timing:

Based on simulation results, the TAG is projected to be contained within the injection zone close to the injection well. The sealing zones are thick and continuous, which would prevent any upward migration through the confining zone even if lateral migration occurs.

5.6   Potential Leakage through Fractures and Faults

Likelihood:

Prior to injection, a thorough geological characterization of the injection zone and surrounding formations was performed (see Section 3) to understand the geology as well as identify and understand the distribution of faults and fractures. **Figure 5.6-1** shows the fault traces (numbered 4, 5 and 6) in the vicinity of the Bull Moose plant. The fault number 6 shown on **Figure 5.6-1** is above the injection zone for the BM AGI well. No faults were identified in the injection zone or confining zone within the MMA. Therefore, the likelihood of leakage through faults is considered very unlikely.

Magnitude and Timing:

No faults were identified within the MMA which could potentially serve as conduits for surface CO_2 emission. Considering faults that are going through the confining or injection zone, the closest identified fault lies approximately 1.5 miles east of the Bull Moose site and has approximately 1,000 ft of down-to-the-west structural relief.

The nearest fault going through the injection or confining zone is found approximately 7,276 ft east of the BM AGI #1 site. The risk of leakage through faults only occurs if the faults directly cut through the CO_2 plume or lateral migration carries CO_2 to faults. Other nearby faults are 12,031 ft (~2.3 mi)and ft (2.9 mi) east the site, placing them outside the MMA. Hence, leakage through faults will be an unlikely event. This is supported by NRAP simulation results (**Figure 5.6-1**) that consider fault location, geometry, and direction. For faults that do not directly connect with the CO_2 plume, CO_2 leakage rate and mass are estimated to be zero. The estimated cumulative leakage (**Figure 5.6-1**) shows no leakage throughout the period of simulation (60 years).

Figure 5.6-1: Faults 7,276 ft

Therefore, Targa concludes that the risk of CO_2 leakage through the faults are very unlikely and insignificant.

Figure 5.6-1: *Faults surrounding Bull Moose facility relative to the plume and the MMA.*

5.7   Potential Leakage due to Natural / Induced Seismicity

5.7.1   Natural Seismicity

Likelihood:

Due to the distance between the BM AGI #1 well and the location of the seismic events recorded since 2017, the magnitude of these events, and the fact that Targa injects at pressures below fracture opening pressure, Targa considers the likelihood of CO_2 emissions to the surface caused by seismicity to be very unlikely.

Magnitude and Timing:

The magnitude and timing of a seismic event can vary greatly. In the region, the earthquakes ranged from magnitude 1.5 to 4. They are located in clusters that are around 20 miles North-West and South, South-West of Bull Moose.

Based on historical data and the geology of the surroundings, the risk of CO_2 leakage due to seismicity is considered insignificant.

Monitoring of seismic events in the vicinity of the Bull Moose AGI well is discussed in Section 6.7.

Figure 5.7-1: TexNet seismic events since 2017 and seismic monitoring stations close to Bull Moose plant.

5.7.1 Induced Seismicity

The faults that might be affected by pressure changes have been analyzed to evaluate the risk of induced seismicity, and the risk of leakage due to induced seismicity. The examination of faults identified from the 3D seismic data, illustrated in **Figure 5.7-2**, discloses the presence of 6 major faults traversing the reservoir interval. These faults are far east from BM AGI #1 and they have been further subdivided into 41 sub-fault segments, allowing for a detailed analysis of their slip potentials.

Figure 5.7-2: Structure and fault system picked from 3D seismic data on Silu-Devonian to Ellenburger.

The evaluation of Fault Slip Potential (FSP) using the FSP software version 1.07 involved the utilization of specific parameters (**Table 5.7**). The software requires various inputs or parameters to assess the potential for fault slippage. These parameters are fundamental in assessing the likelihood of fault slippage. The FSP software incorporates and processes these inputs to generate an estimation or analysis of the potential for faults to slip under the given conditions. These parameters could include factors such as: Pressure Changes (the magnitude of pore pressure changes within the geological formations), fault geometry (details about the fault, including its orientation, size, and geometry), stress conditions (information on stress distribution within the rock formations, including the magnitudes and orientations of principal stresses), rock properties (data regarding the mechanical properties of the rocks, such as porosity, permeability, and strength), and seismic data (3D seismic data used to identify and characterize faults geometry). These parameters are from published papers and reports.

Table 5.7: *Fault Slip Potential simulation parameters.*

Fault Friction Coeff (mu)	0.58
Vertical Stress Gradient (psi/ft)	1.07+/-0.01
Maximum Horizontal Stress Direction (deg)	82.5 +/- 7.5
Initial Reservoir Pressure Gradient (psi/ft)	0.465 +/- 0.05
Minimum Horizontal Stress Gradient (psi/ft)	0.5
Maximum Horizontal Stress Gradient (psi/ft)	1
A-Phi Parameter	0.8+/-0.1
Reference Friction Coefficient (mu)	0.58+/-.005
Porosity (%)	15
Permeability (mD)	7.2
Injection Years	2025 to 2055

It appears that the results of the FSP (Fault Slip Potential) analysis indicate that over a 30-year injection period, faults have experienced only a small pressure drop in effective stress. The slippage of fault walls is contingent on having sufficient pore pressure to raise the effective stress to a level that would induce slippage. This information suggests that the fault system may be relatively stable or that the pore pressure changes have not been significant enough to cause fault activation. As shown in **Figure 5.7-3**, 97% of interpreted faults require more than 180 psi effective pressure to cause slip. The predicted value of effective pressure changes on **Figure 5.7-4** and **Figure 5.7-5** shows that the pore pressure will change less than 30 psi after 30 years. The probability of fault slip are shown in **Figure 5.7-5**. These values indicate negligible potential for fault slips for major faults. This information suggests that the fault system may be relatively stable or that the pore pressure changes have not been significant enough to cause fault activation.

Therefore, the risk of leakage due to induced seismicity is considered very low. Its **likelihood, timing and magnitude** are considered very unlikely and insignificant.

Figure 5.7-3: *Visualization of pressure change after 30 years of injection*

Figure 5.7-4: *Visualization of pressure change required to cause fault slip and the predicted pressure after 30 years of injection*

Figure 5.7-5: *Fault slip probability after 30 years of injection. Fault color represent the fault slip potential value indicated by color bar and they show almost 0% of fault slip potential.*

6 Strategy for Detecting and Quantifying Surface Leakage of CO_2

Subpart RR at 40 CFR 448(a)(3) requires a strategy for detecting and quantifying surface leakage of CO_2.

Targa will employ the following strategy for detecting, verifying, and quantifying CO_2 leakage to the surface through the potential pathways for CO_2 surface leakage identified in Section 5. Targa considers H_2S to be a proxy for CO_2 leakage to the surface and as such will employ and expand upon methodologies detailed in their H_2S Contingency plan to detect, verify, and quantify CO_2 surface leakage close to the plant equipment. **Table 6-1** summarizes the leakage monitoring of the identified leakage pathways. Monitoring will occur for the duration of injection and the 15-year post-injection period.

Table 6-1: Summary of Leak Detection Monitoring

Potential Leakage Pathway	Detection Monitoring
Surface Equipment	- Distributed control system (DCS) surveillance of plant operations - Visual inspections - Inline inspections - Fixed in-field gas monitors/CO_2 flux monitoring network - Personal and hand-held gas monitors
Wells that have not yet been drilled	- Monitor applications for permit to drill and permit to inject made to the TRRC - Communicate with operators/drillers that are active within the MMA so they are aware that they are drilling in an area that has CO_2/H_2S injection activities.
BM AGI #1 Well	- DCS surveillance of well operating parameters - Visual inspections - Mechanical integrity tests (MIT) - Fixed in-field gas monitors/CO_2 flux monitoring network - Personal and hand-held gas monitors - In-well pressure/temperature (P/T) sensors - Groundwater monitoring
Fractures and Faults	- DCS surveillance of well operating parameters - Fixed in-field gas monitors/CO_2 flux monitoring network - Groundwater monitoring

Confining Zone / Seal	• DCS surveillance of well operating parameters • Fixed in-field gas monitors/CO_2 flux monitoring network • Groundwater monitoring
Natural / Induced Seismicity	• DCS surveillance of well operating parameters • Seismic monitoring station
Lateral Migration	• DCS surveillance of well operating parameters • Fixed in-field gas monitors/CO_2 flux monitoring network • Groundwater monitoring
Additional Monitoring	• Groundwater monitoring • Soil flux monitoring

6.1 Leakage from Surface Equipment

Targa implements several tiers of monitoring for surface leakage including frequent periodic visual inspection of surface equipment, use of fixed in-field and personal H_2S sensors, and continual monitoring of operational parameters. Leaks from surface equipment are detected by Targa field personnel, wearing personal H_2S monitors, following daily and weekly inspection protocols which include reporting and responding to any detected leakage events.

Targa also maintains in-field gas monitors to detect H_2S and CO_2. The in-field gas monitors are connected to the DCS housed in the onsite control room. If one of the gas detectors sets off an alarm, it would trigger an immediate response to address and characterize the situation.

6.2 Leakage from Approved Not Yet Drilled Wells

Special precautions will be taken in the drilling of any new wells that will penetrate the injection zones including more frequent monitoring during drilling operations. This applies to Targa and other operators drilling new wells through the BM AGI #1 injection zone within the MMA.

6.3 Leakage from Existing Wells

6.3.1 BM AGI Well

As part of ongoing Targa operations, Targa continuously monitors and collects flow, pressure, temperature, and gas composition data in its data collection system. These data are monitored continuously by qualified technicians who follow response and reporting protocols when the system delivers alerts that data is not within acceptable limits.

To monitor leakage and wellbore integrity, pressure and temperature gauges as well as Distributed Temperature Sensing (DTS) will be deployed in Targa's BM AGI #1 well.

If operational parameter monitoring and MIT failures indicate a CO_2 leak has occurred, Targa will take actions to quantify the leak based on operating conditions at the time of the detection including pressure at the point of emission, flowrate at the point of emission, duration of the emission, and estimation of the size of the emission site.

Well Schematic for BM AGI #1 showing installation of pressure and temperature sensors are in **Appendix 1**.

6.3.2   Other Existing Wells within the MMA

The CO_2 monitoring network described in Section 7.3 and well surveillance by other operators of existing wells will provide an indication of CO_2 leakage. Additionally, groundwater and soil CO_2 flux monitoring locations throughout the MMA will also provide an indication of CO_2 leakage to the surface. See Sections 7.7 and 7.8 for details.

6.4   Leakage through the Confining / Seal System

As discussed in Section 5, it is very unlikely that CO_2 leakage to the surface will occur through the confining zone. Continuous operational monitoring of the BM AGI #1 well, described in Sections 6.3 and 7.5, will provide an indicator if CO_2 leaks out of the injection zone. Additionally, groundwater and soil flux monitoring locations throughout the MMA will also provide an indication of CO_2 leakage to the surface. See Sections 7.7 and 7.8 for details.

If changes in operating parameters or other monitoring listed in **Table 6-1** indicate leakage of CO_2 through the confining / seal system, Targa will take actions to quantify the amount of CO_2 released and take mitigative action to stop it, including shutting in the well (see Section 6.8).

6.5   Leakage due to Lateral Migration

Continuous operational monitoring of the BM AGI well during and after the period of the injection will provide an indication of the movement of the CO_2 plume migration in the injection zones. The CO_2 monitoring network described in Section 7.3, and routine well surveillance will provide an indicator if CO_2 leaks out of the injection zone. Additionally, groundwater and soil flux monitoring locations throughout the MMA will also provide an indication of CO_2 leakage to the surface. See Sections 7.7 and 7.8 for details.

If monitoring of operational parameters or other monitoring methods listed in Table 6-1 indicates that the CO_2 plume extends beyond the area modeled in Section 3.8 and presented in Section 4, Targa will reassess the plume migration modeling for evidence that the plume may have intersected a pathway for CO_2 migration. As this scenario would be considered a material change per 40CFR98.448(d)(1), Targa will submit a revised MRV plan as required by 40CFR98.448(d). See Section 6.8 for additional information on quantification strategies.

6.6   Leakage from Fractures and Faults

As discussed in Section 5, it is very unlikely that CO_2 leakage to the surface will occur through faults.

However, if monitoring of operational parameters and the fixed in-field gas monitors indicate possible CO_2 leakage to the surface, Targa will identify which of the pathways listed in this section are responsible for the leak, including the possibility of unidentified faults or fractures within the MMA. Targa will take measures to quantify the mass of CO_2 emitted based on the operational conditions that existed at the time of surface emission, including pressure at the point of emission, flowrate at the point of emission, duration of the emission, and estimation of the size of the emission site. Additionally, groundwater and soil flux monitoring locations throughout the MMA will also provide an indication of CO_2 leakage to the surface. See Sections 7.7 and 7.8 for details. See Section 6.8 for additional information on quantification strategies.

6.7   Leakage due to Natural / Induced Seismicity

In order to monitor the influence of natural and/or induced seismicity, Targa will use the established TexNet seismic network. The network consists of seismic monitoring stations that detect and locate seismic events. Continuous monitoring helps differentiate between natural and induced seismicity. The network surrounding the Bull Moose Gas Processing Plant has been displayed on **Figure 5.6-1**. The monitoring network records Helicorder data from UTC (coordinated universal time) all day long. The data are plotted daily. These plots can be browsed either by station or by day. The data are streamed continuously and archived at the Incorporated Research Institutions for Seismology Data Management Center (IRIS DMC).

If the monitoring systems indicate surface leakage of CO_2 linked to seismic events, Targa will assess whether the CO_2 originated from the BM AGI #1 well and, if so, take measures to quantify the mass of CO_2 emitted to the surface based on operational conditions at the time the leak was detected. See Section 7.6 for details regarding seismic monitoring and analysis. See Section 6.8 for additional information on quantification strategies.

6.8   Strategy for Quantifying CO_2 Leakage and Response

6.8.1   Leakage from Surface Equipment

For normal operations, quantification of emissions of CO_2 from surface equipment located between the flow meter used to measure injection quantity and the injection wellhead will be assessed by employing the methods detailed in Subpart W according to the requirements of 98.444(d) of Subpart RR.

Quantification of major leakage events from surface equipment as identified by the detection techniques listed in **Table 6-1** will be assessed by employing methods most appropriate for the site of the identified leak. Once a leak has been identified the leakage location will be isolated to prevent additional emissions to the atmosphere. Quantification will be based on the length of time of the leak and parameters that existed at the time of the leak such as pressure, temperature, composition of the gas stream, and size of the leakage point.

Targa has standard operating procedures to report and quantify all pipeline leaks in accordance with the TRRC regulations. Targa will modify this procedure to quantify the mass of carbon dioxide from each leak discovered by Targa or third parties. Additionally, Targa may employ available leakage models for characterizing and predicting gas leakage from gas pipelines. In addition to the physical conditions listed above, these models are capable of incorporating the thermodynamic parameters relevant to the leak thereby increasing the accuracy of quantification.

Here are example quantification strategies specifically designed for surface leakage:

- Direct measurement techniques: Targa will use mass flow meters in surface equipment. These meters can capture CO_2 mass flow rates in real-time, providing direct quantification of emissions as soon as a leak is detected.

- Leak rate models: Targa will use models that incorporate thermodynamic and fluid dynamics principles to estimate the mass of CO_2 escaping from leaks. For example: empirical leak rate

models employ empirical equations that estimate leak rates based on equipment size, the differential pressure across the leak, and gas composition.

6.8.2 Subsurface Leakage

Selection of a quantification strategy for leaks that occur in the subsurface will be based on the leak detection method (Table 6-1) that identifies the leak. Leaks associated with the point sources, such as the injection wells, and identified by failed MITs, variations of operational parameters outside acceptable ranges, and in-well P/T sensors can be addressed immediately after the injection well has been shut in. Quantification of the mass of CO_2 emitted during the leak will depend on characterization of the subsurface leak, operational conditions at the time of the leak, and knowledge of the geology and hydrogeology at the leakage site. Conservative estimates of the mass of CO_2 emitted to the surface will be made assuming that all CO_2 released during the leak will reach the surface. Targa may choose to estimate the emissions to the surface more accurately by employing transport, geochemical, or reactive transport model simulations.

Other wells within the MMA will be monitored with the atmospheric and CO_2 flux monitoring network placed strategically in their vicinity.

Nonpoint sources of leaks such as through the confining zone, along faults or fractures, or which may be initiated by seismic events and as may be identified by variations of operational parameters outside acceptable ranges will require further investigation to determine the extent of leakage and may result in cessation of operations.

6.8.3 Surface Leakage

A recent review of risk and uncertainty assessment for geologic carbon storage (Xiao et al., 2024) discussed monitoring for sequestered CO_2 leaking back to the surface emphasizing the importance of monitoring network design in detecting such leaks. Leaks detected by visual inspection, hand-held gas sensors, fixed in-field gas sensors, atmospheric, and CO_2 flux monitoring will be assessed to determine if the leaks originate from surface equipment, in which case leaks will be quantified according to the strategies in Section 6.8.1, or from the subsurface. In the latter case, CO_2 flux monitoring methodologies, as described in Section 7.8, will be employed to quantify the surface leaks.

7 Strategy for Establishing Expected Baselines for Monitoring CO_2 Surface Leakage

Targa uses the existing automatic distributed control system to continuously monitor operating parameters and to identify any excursions from normal operating conditions that may indicate leakage of CO_2. Targa considers H_2S to be a proxy for CO_2 leakage to the surface and as such will employ and expand upon methodologies detailed in their H_2S Contingency plan to establish baselines for monitoring CO_2 surface leakage. The following describes Targa's strategy for collecting baseline information.

7.1 Visual Inspection

Targa field personnel conduct frequent periodic inspections of all surface equipment providing opportunities to assess baseline concentrations of H_2S, a proxy for CO_2, at the Bull Moose Gas Plant.

7.2 Fixed In-Field, Handheld, and Personal H$_2$S Monitors

Compositional analysis of Targa's gas injectate at the Bull Moose Gas Plant indicates an approximate H$_2$S concentration of 30% thus requiring Targa to develop and maintain an H$_2$S Contingency Plan (Plan) according to the TRRC Regulations. Targa considers H$_2$S to be a proxy for CO$_2$ leaks at the plant. The Plan contains procedures to provide for an organized response to an unplanned release of H$_2$S from the plant or the associated BM AGI #1 Well and documents procedures that would be followed in case of such an event.

7.2.1 Fixed In-Field H$_2$S Monitors

The Bull Moose Gas Plant utilizes numerous fixed-point monitors, strategically located throughout the plant, to detect the presence of H$_2$S in ambient air. The sensors are connected to the Control Room alarm panel's Programmable Logic Controllers (PLCs), and then to the DCS. Upon detection of H$_2$S at 10 ppm at any detector, visible amber beacons are activated, and horns are activated with a continuous warbling alarm. Upon detection of hydrogen sulfide at 90 ppm at any monitor, an evacuation alarm is sounded throughout the plant at which time all personnel will proceed immediately to a designated evacuation area.

7.2.2 Handheld and Personal H$_2$S Monitors

Handheld gas detection monitors are available at strategic locations around the plant so that plant personnel can check specific areas and equipment prior to initiating maintenance or other work. The handheld gas detectors have sensors for oxygen, LEL (explosive hydrocarbon atmospheres), H$_2$S and CO$_2$.

All personnel, including contractors who perform operations, maintenance and/or repair work in sour gas areas within the plant must wear personal H$_2$S monitoring devices to assist them in detecting the presence of unsafe levels of H$_2$S. Personal monitoring devices will give an audible alarm and vibrate at 10 ppm.

7.3 CO$_2$ Detection

In addition to the handheld gas detection monitors described above, Targa will set up a monitoring network for CO$_2$ leakage detection in the MMA as defined in Section 4.2. In addition, there will be periodic groundwater and soil flux sampling within the MMA. Once the network is set up, Targa will assume responsibility for monitoring, recording, and reporting data collected from the system for the duration of the project.

7.4 Continuous Parameter Monitoring

The DCS of the plant monitors injection rates, pressures, and composition on a continuous basis. High and low set points are programmed into the DCS, and engineering and operations are alerted if a parameter is outside the allowable window. If a parameter is outside the allowable window, this will trigger further investigation to determine if the issue poses a leak threat.

7.5 Well Surveillance

Targa adheres to the requirements of TRRC Rules governing the construction, operation and closing of an injection well under the Oil and Gas Act. It includes requirements for testing and monitoring of Class II injection wells to ensure they maintain mechanical integrity at all times. Furthermore, TRRC rules include special conditions regarding monitoring, reporting, and testing in the individual permits for each injection well, if they are deemed necessary. Targa's Routine Operations and Maintenance Procedures for the BM AGI #1 well ensure frequent periodic inspection of the well and opportunities to detect leaks and implement corrective action.

7.6 Seismic (Microseismic) Monitoring Stations

Targa has Installed a seismometer and a digital recorder to monitor for and record data for any seismic event at the Bull Moose Gas Plant. The seismic station meets the requirements of the TRRC.

In addition, data that is recorded by the TexNet network surrounding the Bull Moose Gas Plant will be analyzed by Targa. A report will be periodically generated with a map showing the magnitudes of recorded events from seismic activity. By examining historical data, a seismic baseline prior to the start of TAG injection can be well established and used to verify anomalous events that occur during current and future injection activities. If necessary, a certain period of time can be extracted from the overall data set to identify anomalous events during that period.

7.7 Groundwater Monitoring

Targa will monitor groundwater wells for CO_2 leakage as defined in Section 4.2. Water samples will be collected and analyzed on a monthly basis for 12 months to establish baseline data. After establishing the water chemistry baseline, samples will be collected and analyzed bi-monthly for one year and then quarterly. Samples will be collected according to EPA methods for groundwater sampling (U.S. EPA, 2015).

The water analysis includes TDS, conductivity, pH, alkalinity, major cations, major anions, oxidation-reduction potentials (ORP), inorganic carbon (IC), and non-purgeable organic carbon (NPOC). Charge balance of ions will be completed as quality control of the collected groundwater samples. See **Table 7.7-1**. Baseline analyses will be compiled and compared with regional historical data to determine patterns of change in groundwater chemistry not related to injection processes at the Bull Moose Gas Plant. A report of groundwater chemistry will be developed from this analysis. Any water quality samples not within the expected variation will be further investigated to determine if leakage has occurred from the injection zone.

Table 7.7-1: Groundwater Monitoring Parameters

Parameters
pH
Alkalinity as HCO^{3-} (mg/L)
Chloride (mg/L)
Fluoride (F^-) (mg/L)
Bromide (mg/L)
Nitrate (NO^{3-}) (mg/L)
Phosphate (mg/L)
Sulfate ($SO4^{2-}$) (mg/L)
Lithium (Li) (mg/L)
Sodium (Na) (mg/L)
Potassium (K) (mg/L)
Magnesium (Mg) (mg/L)
Calcium (Ca) (mg/L)
TDS Calculation (mg/L)
Total cations (meq/L)
Total anions (meq/L)
Percent difference (%)
ORP (mV)
IC (ppm)
NPOC (ppm)

7.8   Soil CO_2 Flux Monitoring

A vital part of the monitoring program is to identify potential leakage of CO_2 and/or brine from the injection horizon into the overlying formations and to the surface. One method that will be deployed is to gather and analyze soil CO_2 flux data which serves as a means for assessing potential migration of CO_2 through the soil and its escape to the atmosphere. By taking CO_2 soil flux measurements at periodic intervals, Targa can continuously characterize the interaction between the subsurface and surface to understand potential leakage pathways. Actionable recommendations can be made based on the collected data.

Soil CO_2 flux will be collected on a monthly basis for 12 months to establish the baseline and understand seasonal and other variation at the Bull Moose Gas Plant. After the baseline is established, data will be collected bi-monthly for one year and then quarterly.

Soil CO_2 flux measurements will be taken using a LI-COR LI-8100A flux chamber, or similar instrument, at pre planned locations at the site. PVC soil collars (8cm diameter) will be installed in accordance with the LI-8100A specifications. Measurements will be subsequently made by placing the LI-8100A chamber on the soil collars and using the integrated iOS app to input relevant parameters, initialize measurement, and record the system's flux and coefficient of variation (CV) output. The soil collars will be left in place such that each subsequent measurement campaign will use the same locations and collars during data collection.

8 Site Specific Considerations for Determining the Mass of CO_2 Sequestered

Appendix 6 summarizes the twelve Subpart RR equations used to calculate the mass of CO_2 sequestered annually. **Appendix 7** includes the twelve equations from Subpart RR. Not all of these equations apply to Targa's current operations at the Bull Moose Gas Plant but are included in the event Targa's operations change in such a way that their use is required.

8.1 CO_2 Received

Currently, Targa receives gas to its Bull Moose Gas Plant through pipelines. The gas is processed as described in Section 3.8 to produce compressed TAG which is then routed to the wellhead and pumped to injection pressure through NACE-rated (National Association of Corrosion Engineers) pipeline suitable for injection. Targa will use Equation RR-2 for Pipelines to calculate the mass of CO_2 received through pipelines and measured through volumetric flow meters. The total annual mass of CO_2 received through these pipelines will be calculated using Equation RR-3. Receiving flow meter r in the following equations corresponds to the flow meter (FM) in **Figure 3.7-1**.

$$CO_{2T,r} = \sum_{p=1}^{4} (Q_{r,p} - S_{r,p}) * D * C_{CO_2,p,r}$$

(Equation RR-2 for Pipelines)

where:

$CO_{2T,r}$ = Net annual mass of CO_2 received through flow meter r (metric tons).

$Q_{r,p}$ = Quarterly volumetric flow through a receiving flow meter r in quarter p at standard conditions (standard cubic meters).

$S_{r,p}$ = Quarterly volumetric flow through a receiving flow meter r that is redelivered to another facility without being injected into your well in quarter p (standard cubic meters).

D = Density of CO_2 at standard conditions (metric tons per standard cubic meter): 0.0018682.

$C_{CO2,p,r}$ = Quarterly CO_2 concentration measurement in flow for flow meter r in quarter p (vol. percent CO_2, expressed as a decimal fraction).

p = Quarter of the year.

r = Receiving flow meter.

$$CO_2 = \sum_{r=1}^{R} CO_{2T,r}$$

(Equation RR-3 for Pipelines)

where:

CO_2 = Total net annual mass of CO_2 received (metric tons).

$CO_{2T,r}$ = Net annual mass of CO_2 received (metric tons) as calculated in Equation RR-1 or RR-2 for flow meter r.

r = Receiving flow meter.

71

Although Targa does not currently receive CO_2 in containers for injection, they wish to include the flexibility in this MRV plan to receive gas from containers. When Targa begins to receive CO_2 in containers, Targa will use Equations RR-1 and RR-2 for Containers to calculate the mass of CO_2 received in containers. Targa will adhere to the requirements in 40CFR98.444(a)(2) for determining the quarterly mass or volume of CO_2 received in containers.

If CO_2 received in containers results in a material change as described in 40CFR98.448(d)(1), Targa will submit a revised MRV plan addressing the material change.

8.2 CO_2 Injected

Upon completion, Targa will commence injection into BM AGI #1. Equation RR-5 will be used to calculate CO_2 measured through volumetric flow meters before being injected into the well. Equation RR-6 will be used to calculate the total annual mass of CO_2 injected into the well. The calculated total annual CO_2 mass injected is the parameter CO_{2I} in Equation RR-12. Volumetric flow meter u in the following equations corresponds to the flow meter (FM) in **Figure 3.7-1**.

$$CO_{2,u} = \sum_{p=1}^{4} Q_{p,u} * D * C_{CO_{2,p,u}}$$

(Equation RR-5)

where:

$CO_{2,u}$ = Annual CO_2 mass injected (metric tons) as measured by flow meter u.

$Q_{p,u}$ = Quarterly volumetric flow rate measurement for flow meter u in quarter p at standard conditions (standard cubic meters per quarter).

D = Density of CO_2 at standard conditions (metric tons per standard cubic meter): 0.0018682.

$C_{CO2,p,u}$ = CO_2 concentration measurement in flow for flow meter u in quarter p (vol. percent CO_2, expressed as a decimal fraction).

p = Quarter of the year.

u = Flow meter.

$$CO_{2I} = \sum_{u=1}^{U} CO_{2,u}$$

(Equation RR-6)

where:

CO_{2I} = Total annual CO_2 mass injected (metric tons) though all injection wells.

$CO_{2,u}$ = Annual CO_2 mass injected (metric tons) as measured by flow meter u.

u = Flow meter.

8.3 CO_2 Produced / Recycled

Targa does not produce oil or gas or any other liquid at its Bull Moose Gas Plant so there is no CO_2 produced or recycled.

8.4 CO_2 Lost through Surface Leakage

Equation RR-10 will be used to calculate the annual mass of CO_2 lost due to surface leakage from the leakage pathways identified and evaluated in Section 5 above. The calculated total annual CO_2 mass emitted by surface leakage is the parameter CO_{2E} in Equation RR-12 addressed in Section 8.6 below. Quantification strategies for leaks from the identified potential leakage pathways is discussed in Section 6.8.

$$CO_{2E} = \sum_{x=1}^{X} CO_{2,x}$$
(Equation RR-10)

where:

CO_{2E} = Total annual CO_2 mass emitted by surface leakage (metric tons) in the reporting year.

$CO_{2,x}$ = Annual CO_2 mass emitted (metric tons) at leakage pathway x in the reporting year.

x = Leakage pathway.

8.5 CO_2 Emitted from Equipment Leaks and Vented Emissions

As required by 98.444(d) of Subpart RR, Targa will assess leakage from the relevant surface equipment listed in Sections 98.233 and 98.234 of Subpart W. According to 98.233(r)(2) of Subpart W, the emissions factor listed in Table W-1A of Subpart W shall be used to estimate all streams of gases. Parameter CO_{2FI} in Equation RR-12 is the total annual CO_2 mass emitted or vented from equipment located between the flow meter for measuring injection quantity and the injection wellhead. A calculation procedure is provided in subpart W.

8.6 CO_2 Sequestered

Since Targa does not actively produce oil or natural gas or any other fluid at its Bull Moose Gas Plant, Equation RR-12 will be used to calculate the total annual CO_2 mass sequestered in subsurface geologic formations.

$$CO_2 = CO_{2I} - CO_{2E} - CO_{2FI}$$
(Equation RR-12)

CO_2 = Total annual CO_2 mass sequestered in subsurface geologic formations (metric tons) at the facility in the reporting year.

CO_{2I} = Total annual CO_2 mass injected (metric tons) in the well or group of wells covered by this source category in the reporting year.

CO_{2E} = Total annual CO_2 mass emitted (metric tons) by surface leakage in the reporting year.

CO_{2FI} = Total annual CO_2 mass emitted (metric tons) from equipment leaks and vented emissions of CO_2 from equipment located on the surface between the flow meter used to measure injection quantity and the injection wellhead, for which a calculation procedure is provided in subpart W of this part [refers to subpart W of the GHGRP rules].

9 Estimated Schedule for Implementation of MRV Plan

The baseline monitoring and leakage detection and quantification strategies described herein have been established by Targa for several years and continues to the present. Targa will begin implementing this MRV plan as soon as it is approved by EPA. After BM AGI #1 is drilled, Targa will reevaluate the MRV plan

and if any modifications are a material change per 40CFR98.448(d)(1), Targa will submit a revised MRV plan as required by 40CFR98.448(d).

10 GHG Monitoring and Quality Assurance Program

Targa will meet the monitoring and QA/QC requirements of 40CFR98.444 of Subpart RR including those of Subpart W for emissions from surface equipment as required by 40CFR98.444(d).

10.1 GHG Monitoring

As required by 40CFR98.3(g)(5)(i), Targa's internal documentation regarding the collection of emissions data includes the following:

- Identification of positions of responsibility (i.e., job titles) for collection of the emissions data

- Explanation of the processes and methods used to collect the necessary data for the GHG calculations

- Description of the procedures and methods that are used for quality assurance, maintenance, and repair of all continuous monitoring systems, flow meters, and other instrumentation used to provide data for the GHGs reported

10.1.1 General

Measurement of CO_2 Concentration – All measurements of CO_2 concentrations of any CO_2 quantity will be conducted according to an appropriate standard method published by a consensus-based standards organization or an industry standard practice such as the Gas Producers Association (GPA) standards. All measurements of CO_2 concentrations of CO_2 received will meet the requirements of 40CFR98.444(a)(3).

Measurement of CO_2 Volume – All measurements of CO_2 volumes will be converted to the following standard industry temperature and pressure conditions for use in Equations RR-2 and RR-5, of Subpart RR of the GHGRP: Standard cubic meters at a temperature of 60 degrees Fahrenheit and at an absolute pressure of 1 atmosphere. Targa will adhere to the American Gas Association (AGA) Report #1 – Orifice Metering.

10.1.2 CO_2 received.

Daily CO_2 received is recorded by totalizers on the volumetric flow meters on each of the pipelines listed in Section 8 using accepted flow calculations for CO_2 according to the AGA Report #1.

10.1.3 CO_2 injected.

Daily CO_2 injected is recorded by totalizers on the volumetric flow meters on the pipelines to the BM AGI #1 well using accepted flow calculations for CO_2 according to the AGA Report #1.

10.1.4 CO_2 produced.

Targa does not produce CO_2 at the Bull Moose Gas Plant.

10.1.5 CO_2 emissions from equipment leaks and vented emissions of CO_2.

As required by 98.444(d), Targa will follow the monitoring and QA/QC requirements specified in Subpart W of the GHGRP for equipment located on the surface between the flow meter used to measure injection quantity and the injection wellhead.

As required by 98.444(d) of Subpart RR, Targa will assess leakage from the relevant surface equipment listed in Sections 98.233 and 98.234 of Subpart W. According to 98.233(r)(2) of Subpart W, the emissions factor listed in Table W-1A of Subpart W shall be used.

10.1.6 Measurement devices.

As required by 40CFR98.444(e), Targa will ensure that:

- All flow meters are operated continuously except as necessary for maintenance and calibration

- All flow meters used to measure quantities reported are calibrated according to the calibration and accuracy requirements in 40CFR98.3(i) of Subpart A of the GHGRP.

- All measurement devices are operated according to an appropriate standard method published by a consensus-based standards organization or an industry standard practice. Consensus-based standards organizations include, but are not limited to, the following: ASTM International, the American National Standards Institute (ANSI), the American Gas Association (AGA), the Gas Producers Association (GPA), the American Society of Mechanical Engineers (ASME), the American Petroleum Institute (API), and the North American Energy Standards Board (NAESB).

- All flow meter calibrations performed are National Institute of Standards and Technology (NIST) traceable.

10.2 QA/QC Procedures

Targa will adhere to all QA/QC requirements in Subparts A, RR, and W of the GHGRP, as required in the development of this MRV plan under Subpart RR. Any measurement devices used to acquire data will be operated and maintained according to the relevant industry standards.

10.3 Estimating Missing Data

Targa will estimate any missing data according to the following procedures in 40CFR98.445 of Subpart RR of the GHGRP, as required.

- A quarterly flow rate of CO_2 received that is missing would be estimated using invoices, purchase statements, or using a representative flow rate value from the nearest previous time period.

- A quarterly CO_2 concentration of a CO_2 stream received that is missing would be estimated using invoices, purchase statements, or using a representative concentration value from the nearest previous time period.

- A quarterly quantity of CO_2 injected that is missing would be estimated using a representative quantity of CO_2 injected from the nearest previous period of time at a similar injection pressure.

- For any values associated with CO_2 emissions from equipment leaks and vented emissions of CO_2 from surface equipment at the facility that are reported in Subpart RR, missing data estimation procedures specified in subpart W of 40 CFR Part 98 would be followed.

10.4 Revisions of the MRV Plan

Targa will revise the MRV plan as needed to reflect changes in monitoring instrumentation and quality assurance procedures; or to improve procedures for the maintenance and repair of monitoring systems to reduce the frequency of monitoring equipment downtime; or to address additional requirements as directed by the USEPA or the State of Texas. If any operational changes constitute a material change as described in 40CFR98.448(d)(1), Targa will submit a revised MRV plan addressing the material change. Targa intends to update the MRV plan after BM AGI #1 has been drilled and characterized.

11 Records Retention

Targa will meet the recordkeeping requirements of paragraph 40CFR98.3(g) of Subpart A of the GHGRP. As required by 40CFR98.3(g) and 40CFR98.447, Targa will retain the following documents:

(1) A list of all units, operations, processes, and activities for which GHG emissions were calculated.

(2) The data used to calculate the GHG emissions for each unit, operation, process, and activity. These data include:

    (i) The GHG emissions calculations and methods used

    (ii) Analytical results for the development of site-specific emissions factors, if applicable

    (iii) The results of all required analyses

    (iv) Any facility operating data or process information used for the GHG emission calculations

(3) The annual GHG reports.

(4) Missing data computations. For each missing data event, Targa will retain a record of the cause of the event and the corrective actions taken to restore malfunctioning monitoring equipment.

(5) A copy of the most recent revision of this MRV Plan.

(6) The results of all required certification and quality assurance tests of continuous monitoring systems, fuel flow meters, and other instrumentation used to provide data for the GHGs reported.

(7) Maintenance records for all continuous monitoring systems, flow meters, and other instrumentation used to provide data for the GHGs reported.

(8) Quarterly records of CO_2 received, including mass flow rate of contents of container (mass or volumetric) at standard conditions and operating conditions, operating temperature and pressure, and concentration of these streams.

(9) Quarterly records of injected CO_2 including mass flow or volumetric flow at standard conditions and operating conditions, operating temperature and pressure, and concentration of these streams.

(10) Annual records of information used to calculate the CO_2 emitted by surface leakage from leakage pathways.

(11) Annual records of information used to calculate the CO_2 emitted from equipment leaks and vented emissions of CO_2 from equipment located on the surface between the flow meter used to measure injection quantity and the injection wellhead.

(12) Any other records as specified for retention in this EPA-approved MRV plan.

12 Appendices

Appendix 1 Targa Well

Well Name	API #	Location	County	Spud Date	Total Depth	Packer
Bull Moose AGI #1 (BM AGI #1)	42-495-34978	1,895' FSL & 2,161' FEL, SEC 42, BLK 27, Public School Land Survey, A-433	KERMIT, TX	To be determined	19,488 ft	17,790 ft

Bull Moose AGI No. 01

Elev: 2,842'
RKB TBD

Rustler @ 934'
Salado @ 1,189'
①

Castile @ 2,589'

Fiber Optic

Bell Canyon @ 5,144'
DV Tool @ 5,100'
Cherry Canyon @ 6,244'
②

Brushy Canyon @ 7,239'
DV Tool @ 7,300'

Bone Spring @ 9,089'

Fiber Optic
Wolfcamp @ 11,979'
③
TEC Line

Corrosion Resistant Tubing

Ported Pressure/Temperature Gauge

Woodford @ 17,229'
Siluro Devonian @ 17,889'
Fusselman @ 18,184'

Montoya @ 19,239'
Simpson @ 19,489'
TD @ 19,488'

Ellenburger @ 20,489'
Bliss/Precambrian @ 21,039'

DV Tool @ 11,900'
⑤
Corrosion Resistant Cement
④
Packer @ 17,840'
Open Hole 17,890' - 19,488'

Injection Interval 17,889' - 19,488'

Casing Information

Label	1	2	3		4		5
Type	Surface	Intermediate 1	Intermediate 2		Production		Tubing
OD	20"	13-3/8"	9-5/8"	9-5/8"	7"	7"	3-1/2"
ID	19"	12.415"	8.681"	8.681"	6.094"	6.094"	2.992"
Drift ID	18.812"	12.259"	8.525"	8.525"	5.969"	5.969"	2.867"
Weight	106.5 lb/ft	68 lb/ft	47 lb/ft	47 lb/ft	32 lb/ft	32 lb/ft	9.2 lb/ft
Grade	K-55 BTC	K-55 BTC	HCL-80 BTC	G3-110 Prem. T & C	P-110 Prem. T & C	G3-110 Prem. T & C	G3-110 Prem. T & C
Hole Size	26"	17-1/2"	12-1/4"	12-1/4"	8-1/2"	8-1/2"	N/A
Depth Set	1,300'	5,150'	0' - 5,100' & 7,300' - 12,100'	5,100' - 7,300'	17,590'	17,590' - 17,890'	17,840'
TOC	Surface	Surface	Surface	Surface	Surface	Surface	N/A
Yield	Lead: 1,162 sx Tail: 1,190 sx	Lead: 1,521 sx Tail: 858 sx	Stage 1 Lead: 1,506 sx Stage 1 Tail: 448 sx Stage 2 Resin: 160 bbls Stage 3 Lead: 1,006 sx Stage 3 Tail: 704 sx		Stage 1: 11 bbls Stage 2 Lead: 413 sx Stage 2 Tail: 198 sx Stage 3 Lead: 883 sx Stage 3 Tail: 206 sx		NA
Excess	100% Open Hole	30% Open Hole	30% Open Hole		30% Open Hole		NA

LONQUIST & CO. LLC
PETROLEUM ENGINEERS | ENERGY ADVISORS
AUSTIN · HOUSTON · CALGARY · WICHITA
DENVER · COLLEGE STATION · BATON ROUGE · EDMONTON

Texas License F-9147

12912 Hill Country Blvd. Ste F-200
Austin, Texas 78738
Tel: 512.732.9812
Fax: 512.732.9816

Targa Delaware LLC

|		
Country: USA	State/Province: Texas	County/Parish: Winkler
Location: Sec. 42, A-433, Blk 27		District: 08
API No: TBD	Field:	Well Type/Status: AGI Disposal
Survey:	Project No: F2345	Date: 5/6/2024
Drawn: CJL	Reviewed: WHG	Approved:
Rev No: 1	Notes: Intermediate 2 Revisions Requested by Targa	

Figure Appendix 1-1: Schematic of Targa BM AGI #1 Well

Appendix 2 Referenced Regulations

U.S. Code > Title 26. INTERNAL REVENUE CODE > Subtitle A. Income Taxes > Chapter 1. NORMAL TAXES AND SURTAXES > Subchapter A. Determination of Tax Liability > Part IV. CREDITS AGAINST TAX > Subpart D. Business Related Credits > Section 45Q - Credit for carbon oxide sequestration

Texas Administrative Code > Title 16, Economic Regulation, > Part 1 Railroad Commissions of Texas > Chapter 3, Oil and Gas Division

CHAPTER 15 - OIL AND GAS

§3.1	Organization Report; Retention of Records; Notice Requirements
§3.2	Commission Access to Properties
§3.3	Identification of Properties, Wells, and Tanks
§3.4	Oil and Geothermal Lease Numbers and Gas Well ID Numbers Required on All Forms
§3.5	Application To Drill, Deepen, Reenter, or Plug Back
§3.6	Application for Multiple Completion
§3.7	Strata To Be Sealed Off
§3.8	Water Protection
§3.9	Disposal Wells
§3.10	Restriction of Production of Oil and Gas from Different Strata
§3.11	Inclination and Directional Surveys Required
§3.12	Directional Survey Company Report
§3.13	Casing, Cementing, Drilling, Well Control, and Completion Requirements
§3.14	Plugging
§3.15	Surface Equipment Removal Requirements and Inactive Wells
§3.16	Log and Completion or Plugging Report
§3.17	Pressure on Bradenhead
§3.18	Mud Circulation Required
§3.19	Density of Mud-Fluid
§3.20	Notification of Fire Breaks, Leaks, or Blow-outs
§3.21	Fire Prevention and Swabbing
§3.22	Protection of Birds
§3.23	Vacuum Pumps
§3.24	Check Valves Required
§3.25	Use of Common Storage

Appendix 3 Oil and Gas Wells within MMA of the BM AGI Well Site

API	Well Name	Operator	Well Type	Well Status	Trajectory	Formation	TVD (ft)
42-495-34323	SILVER DOLLAR 4231-27 A 1H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,106
42-495-33230	MITCHELL 28-37 1H	DEVON	OIL	P & A	HORIZONTAL	BONE SPRING	11,814
42-495-33230	MITCHELL 28-37 1H	DEVON	OIL	P & A	HORIZONTAL	BONE SPRING	11,811
42-495-33230	MITCHELL 28-37 1H	DEVON	OIL	P & A	HORIZONTAL	BONE SPRING	11,816
42-495-34481	BRIDAL VEIL STATE W 4132-27 F 6H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,145
42-495-33759	VALLECITO 37-28 2H	DEVON	OIL	PRODUCING	HORIZONTAL	BONE SPRING	11,718
42-495-34328	SILVER DOLLAR 4231-27 H 8H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,263
42-495-34331	SILVER DOLLAR 4231-27 E 5H	DEVON	OIL	PRODUCING	HORIZONTAL	BONE SPRING	11,564
42-495-34485	BRIDAL VEIL STATE W 4132-27 L 12H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,129
42-495-33871	MITCHELL 42-27 1	PILOT WATER SOLUTIONS	SWD	INJECTING	VERTICAL	BRUSHY CANYON	7,630
42-495-34488	BRIDAL VEIL STATE W 4132-27 G 7H	DEVON	OIL	PRODUCING	HORIZONTAL	BONE SPRING	11,627
42-495-34482	BRIDAL VEIL STATE W 4132-27 H 8H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,176
42-495-33840	SAINT VRAIN 48-28 1H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,185
42-495-33763	AVALANCHE 42-27 2H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,194
42-495-33726	SILVER DOLLAR 31-27 2H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,188
42-495-34484	BRIDAL VEIL STATE W 4132-27 J 10H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,217
42-495-34038	MITCHELL 42-27 2	PILOT WATER SOLUTIONS	SWD	INJECTING	VERTICAL	BRUSHY CANYON	7,516
42-495-34489	BRIDAL VEIL STATE W 4132-27 K 11H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	11,637
42-495-34332	SILVER DOLLAR 4231-27 I 9H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	11,897
42-495-34329	SILVER DOLLAR 4231-27 J 10H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,193
42-495-34327	SILVER DOLLAR 4231-27 G 7H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,545
42-495-34325	SILVER DOLLAR 4231-27 D 4H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	11,858
42-495-32972	MITCHELL 42 1	DEVON	GAS	P & A	VERTICAL	MORROW	16,000
42-495-32972	MITCHELL 42 1	DEVON	GAS	P & A	VERTICAL	MORROW	16,000
42-495-34326	SILVER DOLLAR 4231-27 F 6H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,208

API	Well Name	Operator	Well Type	Well Status	Trajectory	Formation	TVD (ft)
42-495-34324	SILVER DOLLAR 4231-27 B 2H	DEVON	OIL	PRODUCING	HORIZONTAL	BONE SPRING	11,621
42-495-34330	SILVER DOLLAR 4231-27 C 3H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	12,537
42-495-34483	BRIDAL VEIL STATE W 4132-27 I 9H	DEVON	OIL	PRODUCING	HORIZONTAL	WOLFCAMP	11,972
42-495-33236	HARRISON STATE 41 1H	DEVON	OIL	INACTIVE PRODUCER	HORIZONTAL	BONE SPRING	11,868

Appendix 4 References

Ashworth, J. B., 1990, Evaluation of ground-water resources in parts of Loving, Pecos, Reeves, Ward, and Winkler counties, Texas: Texas Water Development Board, Report 317, 51 p.

Broadhead, R.F., 2017. Energy and Mineral Resources of New Mexico: Petroleum Geology; Socorro, New Mexico Bureau of Geology and Mineral Resources: 104 p.

Bradley, R.G., and Kalaswad, S., 2003, The Groundwater Resources of the Dockum Aquifer in Texas: Texas Water Development Board Report, 359

Bradley, R.G. and Kalaswad, S., 2004, The Dockum aquifer in the Edwards Plateau: in. Aquifers of the Edwards Plateau: Texas Water Development Board Report, 360, pp.149-164.

Case No. 20779, Notice Regarding Hearing Exhibits, Application of Lucid Energy Delaware, LLC for Authorization to Inject, Lea County, New Mexico

Garza, S., and Wesselman, J.B., 1963, Geology and ground-water resources of Winkler County, Texas: U.S. Government Printing Office 1582, doi:10.3133/wsp1582.

Ewing, E., 2019. Tectonics of the West Texas (Permian) Basin—Origins, structural geology, subsidence, and later modification: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 1), Austin, The University of Texas at Austin, Bureau of Economic Geology: 63-96.

Fu, Q., Baumgardner, R.W., Jr., and Hamlin, H.S., 2020. Early Permian (Wolfcampian) succession in the Permian Basin: icehouse platform, slope carbonates, and basinal mudrocks: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 2), Austin, The University of Texas at Austin, Bureau of Economic Geology: 185-225.

Ge, J., Nicot, J.P., Hennings, P.H., Smye, K.M., Hosseini, S.A., Gao, R.S., and Breton, C.L., 2022. Recent water disposal and pore pressure evolution in the Delaware Mountain Group, Delaware Basin, Southeast New Mexico and West Texas, USA: Journal of Hydrology: Regional Studies 40: 101041.

George, P.G., Mace, R.E., and Petrossian, R., 2011, Aquifers of Texas: Texas Water Development Board, Report 380, 172 p.

H_2S Contingency Plan, Targa Northern Delaware, August 2023, Bull Moose Gas Processing Plant, Lea County, NM

Harrington, R., 2019. The Middle–Upper Ordovician Simpson Group of the Permian Basin: stratigraphy, lithofacies, and reservoir development: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 1), Austin, The University of Texas at Austin, Bureau of Economic Geology: 331-352.

Harrington, R. and Ruppel, S., 2019. Patterns of Montoya Group (Middle Ordovician) deposition, diagenesis, and reservoir development in the Permian Basin: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 1), Austin, The University of Texas at Austin, Bureau of Economic Geology: 353-378.

Hills, J.M., 1984. Sedimentation, tectonism, and hydrocarbon generation in Delaware Basin, west Texas and southeastern New Mexico: The American Association of Petroleum Geologists Bulletin 68: 250-267.

King, P.B., 1948. Geology of the southern Guadalupe Mountains, Texas: United States Geological Survey Professional Paper 215: 183 p.

Loucks, R. and Kerans, C., 2019. A Geologic review of the Lower Ordovician Ellenburger Group of the Permian Basin, West Texas and southeast New Mexico: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 1), Austin, The University of Texas at Austin, Bureau of Economic Geology: 295-330.

Luo, Ming; Baker, Mark R.; and LeMone, David V.; 1994, *Distribution and Generation of the Overpressure System, Eastern Delaware Basin, Western Texas and Southern New Mexico*, AAPG Bulletin, V.78, No. 9 (September 1994) p. 1386-1405.

Nance, H.S., 2020. Upper Permian Delaware Mountain Group: Record of highstand/lowstand platform: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 2), Austin, The University of Texas at Austin, Bureau of Economic Geology: 399-436.

Nance, H.S., Hamlin, H.S., 2020. The Bone Spring Formation (Leonardian) of the Delaware Basin: deepwater lithofacies and stratigraphy: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 2), Austin, The University of Texas at Austin, Bureau of Economic Geology: 321-348.

Nicholson, A., Jr., Clebsch, A., Jr., 1961. *Geology and ground-water conditions in southern Lea County, New Mexico.* New Mexico Bureau of Mines and Mineral Resources, Ground-Water Report 6, 123 pp., 2 Plates.

Ruppel, S., 2019a. Anatomy of a Paleozoic basin: the Permian Basin, USA: Introduction, overview, and evolution: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 1), Austin, The University of Texas at Austin, Bureau of Economic Geology: 1-27.

Ruppel, S., 2019b. The Fusselman of the Permian Basin: patterns in depositional and diagenetic facies development on a stable platform during the Late Ordovician–Early Silurian icehouse: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 1), Austin, The University of Texas at Austin, Bureau of Economic Geology: 379-399.

Ruppel, S., 2020. The Middle Silurian–Lower Devonian Wristen Group, Permian Basin: impact of tectonic subsidence on patterns of deposition, diagenesis, and reservoir development: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 2), Austin, The University of Texas at Austin, Bureau of Economic Geology: 1-36.

Ruppel, S., Hovorka, S., Barnaby, R., 2020a. Proximal shallow-water carbonates and distal biosiliceous cherts of the Lower Devonian Thirtyone Formation, Permian Basin: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 2), Austin, The University of Texas at Austin, Bureau of Economic Geology: 37-74.

Ruppel, S.C., Rowe, H., Reed, R., Barrick, J.E., James, E.W., Loucks, R.G., 2020b. The Woodford Formation of the Permian Basin: regional, Middle to Late Devonian transgression of the southern Midcontinent and

accompanying global anoxia: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 2), Austin, The University of Texas at Austin, Bureau of Economic Geology: 75-124.

Scholle, P.A., Goldstein, R.H., Ulmer-Scholle, D.S., 2007. Classic Upper Paleozoic reefs and bioherms of West Texas and New Mexico: Field guide to the Guadalupe and Sacramento Mountains of West Texas and New Mexico. Socorro, New Mexico Bureau of Geology and Mineral Resources, Open-File Report 504: 178 p.

Scholle, P., Broadhead, R.F., McLemore, V., 2020. The Permian Basin: Scholle, P., Ulmer-Scholle, D., Cather, and S., Kelley, S. (eds.), The Geology of Southern New Mexico Parks, Monuments, and Public Lands: Socorro, New Mexico Bureau of Geology and Mineral Resources: 285-295.

Smye, K.D., Banerji, A., Eastwood, R., McDaid, G., and Hennings, P., 2021. Lithology and reservoir properties of the Delaware Mountain Group of the Delaware Basin and implications for saltwater disposal and induced seismicity: Journal of Sedimentary Research 91 (11): 1113–1132.

Texas Water Development Board (TWDB), 2024, Groundwater Database and Submitted Driller Report Database, https://www.twdb.texas.gov/groundwater/data/gwdbrpt.asp, accessed April 2024

US EPA, O., 2015, *Procedures for Groundwater Sampling in the Laboratory Services and Applied Science Division*: https://www.epa.gov/quality/procedures-groundwater-sampling-laboratory-services-and-applied-science-division (accessed September 2023).

Ward, R.F., Kendall, C.G.St.C., Harris, P.M., 1986. Upper Permian (Guadalupian) facies and their association with hydrocarbons – Permian Basin, west Texas and New Mexico. *The American Association of Petroleum Geologists Bulletin* 70: 239-262.

Wilson, J.L., 1972. Cyclic and reciprocal sedimentation in Virgilian strata of southern New Mexico: J.G. Elam, S. Chuber (eds.), Cyclic Sedimentation in the Permian Basin (2nd edition), Midland, West Texas Geological Society: 82-99.

Wise, M.R., Kalaswad, S., and Meyer, J.E., 2012, Pecos Valley Aquifer, West Texas : structure and brackish groundwater, https://www.semanticscholar.org/paper/Pecos-Valley-Aquifer%2C-West-Texas-%3A-structure-and-Wise-Kalaswad/1b7d17603b0852b54360271983d3e519eb130afb (accessed November 2023).

Wright, W., 2020. Pennsylvanian (upper Carboniferous) paleodepositional evolution of the greater Permian Basin, Texas and New Mexico: depositional systems and hydrocarbon reservoir: S. Ruppel (ed.), Anatomy of a Paleozoic Basin: The Permian Basin, USA (v. 2), Austin, The University of Texas at Austin, Bureau of Economic Geology: 159-183.

Xiao, Ting et al. (2024). *A review of risk and uncertainty assessment for geologic carbon storage*. Renewable and Sustainable Energy Reviews 189 (2024) 113945

Appendix 5 Abbreviations and Acronyms

3D – 3 dimensional
AGA – American Gas Association
AMA – Active Monitoring Area
API – American Petroleum Institute
CFR – Code of Federal Regulations
C1 – methane
C6 – hexane
C7 - heptane
CO_2 – carbon dioxide
DCS – distributed control system
EPA – US Environmental Protection Agency, also USEPA
ft – foot (feet)
GHGRP – Greenhouse Gas Reporting Program
GPA – Gas Producers Association
m – meter(s)
md – millidarcy(ies)
mg/l – milligrams per liter
MIT – mechanical integrity test
MMA – maximum monitoring area
MSCFD– thousand standard cubic feet per day
MMSCFD – million standard cubic feet per day
MRV – Monitoring, Reporting, and Verification
MT -- Metric tonne
NIST - National Institute of Standards and Technology
PPM – Parts Per Million
QA/QC – quality assurance/quality control
TAG – Treated Acid Gas
TDS – Total Dissolved Solids
TVD – True Vertical Depth
UIC – Underground Injection Control
USDW – Underground Source of Drinking Water

Appendix 6 Targa Bull Moose AGI Well - Subpart RR Equations for Calculating CO_2 Geologic Sequestration

	Subpart RR Equation	Description of Calculations and Measurements*	Pipeline	Containers	Comments
CO₂ Received	RR-1	calculation of CO_2 received and measurement of CO_2 mass…	through mass flow meter.	in containers. **	
	RR-2	calculation of CO_2 received and measurement of CO_2 volume…	through volumetric flow meter.	in containers. ***	
	RR-3	summation of CO_2 mass received …	through multiple meters.		
CO₂ Injected	RR-4	calculation of CO_2 mass injected, measured through mass flow meters.			
	RR-5	calculation of CO_2 mass injected, measured through volumetric flow meters.			
	RR-6	summation of CO_2 mass injected, as calculated in Equations RR-4 and/or RR-5.			
CO₂ Produced / Recycled	RR-7	calculation of CO_2 mass produced / recycled from gas-liquid separator, measured through mass flow meters.			
	RR-8	calculation of CO_2 mass produced / recycled from gas-liquid separator, measured through volumetric flow meters.			
	RR-9	summation of CO_2 mass produced / recycled from multiple gas-liquid separators, as calculated in Equations RR-7 and/or RR8.			
CO₂ Lost to Leakage to the Surface	RR-10	calculation of annual CO_2 mass emitted by surface leakage			
CO₂ Sequestered	RR-11	calculation of annual CO_2 mass sequestered for operators ACTIVELY producing oil or gas or any other fluid; includes terms for CO_2 mass injected, produced, emitted by surface leakage, emitted from surface equipment between injection flow meter and injection well head, and emitted from surface equipment between production well head and production flow meter.		Calculation procedures are provided in Subpart W of GHGRP for CO_{2FI}.
	RR-12	calculation of annual CO_2 mass sequestered for operators NOT ACTIVELY producing oil or gas or any other fluid; includes terms for CO_2 mass injected, emitted by surface leakage, emitted from surface equipment between injection flow meter and injection well head.		Calculation procedures are provided in Subpart W of GHGRP for CO_{2FI}.

* All measurements must be made in accordance with 40 CFR 98.444 – Monitoring and QA/QC Requirements.

** If you measure the mass of contents of containers summed quarterly using weigh bill, scales, or load cells (40 CFR 98.444(a)(2)(i)), use RR-1 for Containers to calculate CO_2 received in containers for injection.

*** If you determine the volume of contents of containers summed quarterly (40 CFR 98.444(a)(2)(ii)), use RR-2 for Containers to calculate CO_2 received in containers for injection.

Appendix 7 Subpart RR Equations for Calculating Annual Mass of CO_2 Sequestered

RR-1 for Calculating Mass of CO_2 Received through Pipeline Mass Flow Meters

$$CO_{2T,r} = \sum_{p=1}^{4}(Q_{r,p} - S_{r,p}) * C_{CO_{2,p,r}}$$

(Equation RR-1 for Pipelines)

where:

$CO_{2T,r}$ = Net annual mass of CO_2 received through flow meter r (metric tons).

$Q_{r,p}$ = Quarterly mass flow through a receiving flow meter r in quarter p (metric tons).

$S_{r,p}$ = Quarterly mass flow through a receiving flow meter r that is redelivered to another facility without being injected into your well in quarter p (metric tons).

$C_{CO2,p,r}$ = Quarterly CO_2 concentration measurement in flow for flow meter r in quarter p (wt. percent CO_2, expressed as a decimal fraction).

p = Quarter of the year.

r = Receiving flow meter.

RR-1 for Calculating Mass of CO_2 Received in Containers by Measuring Mass in Container

$$CO_{2T,r} = \sum_{p=1}^{4}(Q_{r,p} - S_{r,p}) * C_{CO_{2,p,r}}$$

(Equation RR-1 for Containers)

where:

$CO_{2T,r}$ = Net annual mass of CO_2 received in containers r (metric tons).

$C_{CO2,p,r}$ = Quarterly CO_2 concentration measurement of contents in containers r in quarter p (wt. percent CO_2, expressed as a decimal fraction).

$Q_{r,p}$ = Quarterly mass of contents in containers r in quarter p (metric tons).

$S_{r,p}$ = Quarterly mass of contents in containers r redelivered to another facility without being injected into your well in quarter p (metric tons).

p = Quarter of the year.

r = Containers.

RR-2 for Calculating Mass of CO₂ Received through Pipeline Volumetric Flow Meters

$$CO_{2T,r} = \sum_{p=1}^{4} (Q_{r,p} - S_{r,p}) * D * C_{CO_2,p,r}$$

(Equation RR-2 for Pipelines)

where:

$CO_{2T,r}$ = Net annual mass of CO_2 received through flow meter r (metric tons).

$Q_{r,p}$ = Quarterly volumetric flow through a receiving flow meter r in quarter p at standard conditions (standard cubic meters).

$S_{r,p}$ = Quarterly volumetric flow through a receiving flow meter r that is redelivered to another facility without being injected into your well in quarter p (standard cubic meters).

D = Density of CO_2 at standard conditions (metric tons per standard cubic meter): 0.0018682.

$C_{CO2,p,r}$ = Quarterly CO_2 concentration measurement in flow for flow meter r in quarter p (vol. percent CO_2, expressed as a decimal fraction).

p = Quarter of the year.

r = Receiving flow meter.

RR-2 for Calculating Mass of CO₂ Received in Containers by Measuring Volume in Container

$$CO_{2T,r} = \sum_{p=1}^{4} (Q_{r,p} - S_{r,p}) * D * C_{CO_2,p,r}$$

(Equation RR-2 for Containers)

where:

$CO_{2T,r}$ = Net annual mass of CO_2 received in containers r (metric tons).

$C_{CO2,p,r}$ = Quarterly CO_2 concentration measurement of contents in containers r in quarter p (vol. percent CO_2, expressed as a decimal fraction).

$Q_{r,p}$ = Quarterly volume of contents in containers r in quarter p at standard conditions (standard cubic meters).

$S_{r,p}$ = Quarterly volume of contents in containers r redelivered to another facility without being injected into your well in quarter p (standard cubic meters).

D = Density of CO_2 received in containers at standard conditions (metric tons per standard cubic meter): 0.0018682.

p = Quarter of the year.

r = Containers.

RR-3 for Summation of Mass of CO₂ Received through Multiple Flow Meters for Pipelines

$$CO_2 = \sum_{r=1}^{R} CO_{2T,r}$$

(Equation RR-3 for Pipelines)

where:

CO_2 = Total net annual mass of CO_2 received (metric tons).

$CO_{2T,r}$ = Net annual mass of CO_2 received (metric tons) as calculated in Equation RR-1 or RR-2 for flow meter r.

r = Receiving flow meter.

RR-4 for Calculating Mass of CO₂ Injected through Mass Flow Meters into Injection Well

$$CO_{2,u} = \sum_{p=1}^{4} Q_{p,u} * C_{CO_{2,p,u}}$$

(Equation RR-4)

where:

$CO_{2,u}$ = Annual CO_2 mass injected (metric tons) as measured by flow meter u.

$Q_{p,u}$ = Quarterly mass flow rate measurement for flow meter u in quarter p (metric tons per quarter).

$C_{CO2,p,u}$ = Quarterly CO_2 concentration measurement in flow for flow meter u in quarter p (wt. percent CO_2, expressed as a decimal fraction).

p = Quarter of the year.

u = Flow meter.

RR-5 for Calculating Mass of CO₂ Injected through Volumetric Flow Meters into Injection Well

$$CO_{2,u} = \sum_{p=1}^{4} Q_{p,u} * D * C_{CO_{2,p,u}}$$

(Equation RR-5)

where:

$CO_{2,u}$ = Annual CO₂ mass injected (metric tons) as measured by flow meter u.

$Q_{p,u}$ = Quarterly volumetric flow rate measurement for flow meter u in quarter p at standard conditions (standard cubic meters per quarter).

D = Density of CO₂ at standard conditions (metric tons per standard cubic meter): 0.0018682.

$C_{CO2,p,u}$ = CO₂ concentration measurement in flow for flow meter u in quarter p (vol. percent CO₂, expressed as a decimal fraction).

p = Quarter of the year.

u = Flow meter.

RR-6 for Summation of Mass of CO₂ Injected into Multiple Wells

$$CO_{2I} = \sum_{u=1}^{U} CO_{2,u}$$

(Equation RR-6)

where:

CO_{2I} = Total annual CO₂ mass injected (metric tons) though all injection wells.

$CO_{2,u}$ = Annual CO₂ mass injected (metric tons) as measured by flow meter u.

u = Flow meter.

RR-7 for Calculating Mass of CO₂ Produced / Recycled from a Gas-Liquid Separator through Mass Flow Meters

$$CO_{2,w} = \sum_{p=1}^{4} Q_{p,w} * C_{CO_{2,p,w}}$$

(Equation RR-7)

where:

$CO_{2,w}$ = Annual CO_2 mass produced (metric tons) through separator w.

$Q_{p,w}$ = Quarterly gas mass flow rate measurement for separator w in quarter p (metric tons).

$C_{CO2,p,w}$ = Quarterly CO_2 concentration measurement in flow for separator w in quarter p (wt. percent CO_2, expressed as a decimal fraction).

p = Quarter of the year.

w = Separator.

RR-8 for Calculating Mass of CO₂ Produced / Recycled from a Gas-Liquid Separator through Volumetric Flow Meters

$$CO_{2,w} = \sum_{p=1}^{4} Q_{p,w} * D * C_{CO_{2,p,w}}$$

(Equation RR-8)

where:

$CO_{2,w}$ = Annual CO_2 mass produced (metric tons) through separator w.

$Q_{p,w}$ = Volumetric gas flow rate measurement for separator w in quarter p (standard cubic meters).

D = Density of CO_2 at standard conditions (metric tons per standard cubic meter): 0.0018682.

$C_{CO2,p,w}$ = Quarterly CO_2 concentration measurement in flow for separator w in quarter p (vol. percent CO_2, expressed as a decimal fraction).

p = Quarter of the year.

w = Separator.

RR-9 for Summation of Mass of CO$_2$ Produced / Recycled through Multiple Gas Liquid Separators

$$CO_{2P} = (1+X) * \sum_{w=1}^{W} CO_{2,w}$$

(Equation RR-9)

where:

CO $_{2P}$ = Total annual CO$_2$ mass produced (metric tons) though all separators in the reporting year.

CO $_{2,w}$ = Annual CO$_2$ mass produced (metric tons) through separator w in the reporting year.

X = Entrained CO$_2$ in produced oil or other fluid divided by the CO$_2$ separated through all separators in the reporting year (wt. percent CO$_2$ expressed as a decimal fraction).

w = Separator.

RR-10 for Calculating Annual Mass of CO$_2$ Emitted by Surface Leakage

$$CO_{2E} = \sum_{x=1}^{X} CO_{2,x}$$

(Equation RR-10)

where:

CO $_{2E}$ = Total annual CO$_2$ mass emitted by surface leakage (metric tons) in the reporting year.

CO $_{2,x}$ = Annual CO$_2$ mass emitted (metric tons) at leakage pathway x in the reporting year.

x = Leakage pathway.

RR-11 for Calculating Annual Mass of CO₂ Sequestered for Operators Actively Producing Oil or Natural Gas or Any Other Fluid

$$CO_2 = CO_{2I} - CO_{2P} - CO_{2E} - CO_{2FI} - CO_{2FP}$$ (Equation RR-11)

Where:

CO_2 = Total annual CO_2 mass sequestered in subsurface geologic formations (metric tons) at the facility in the reporting year.

CO_{2I} = Total annual CO_2 mass injected (metric tons) in the well or group of wells covered by this source category in the reporting year.

CO_{2P} = Total annual CO_2 mass produced (metric tons) in the reporting year.

CO_{2E} = Total annual CO_2 mass emitted (metric tons) by surface leakage in the reporting year.

CO_{2FI} = Total annual CO_2 mass emitted (metric tons) from equipment leaks and vented emissions of CO_2 from equipment located on the surface between the flow meter used to measure injection quantity and the injection wellhead, for which a calculation procedure is provided in subpart W of this part [refers to subpart W of the GHGRP rules].

CO_{2FP} = Total annual CO_2 mass emitted (metric tons) from equipment leaks and vented emissions of CO_2 from equipment located on the surface between the production wellhead and the flow meter used to measure production quantity, for which a calculation procedure is provided in subpart W of this part.

RR-12 for Calculating Annual Mass of CO₂ Sequestered for Operators NOT Actively Producing Oil or Natural Gas or Any Other Fluid

$$CO_2 = CO_{2I} - CO_{2E} - CO_{2FI}$$ (Equation RR-12)

CO_2 = Total annual CO_2 mass sequestered in subsurface geologic formations (metric tons) at the facility in the reporting year.

CO_{2I} = Total annual CO_2 mass injected (metric tons) in the well or group of wells covered by this source category in the reporting year.

CO_{2E} = Total annual CO_2 mass emitted (metric tons) by surface leakage in the reporting year.

CO_{2FI} = Total annual CO_2 mass emitted (metric tons) from equipment leaks and vented emissions of CO_2 from equipment located on the surface between the flow meter used to measure injection quantity and the injection wellhead, for which a calculation procedure is provided in subpart W of this part.