



# ***QUEST CCS PROJECT***

***PCCC2 CONFERENCE  
BERGEN, NORWAY  
SEPT 19, 2013***



***STEVE PEPLINSKI - QUEST ENGINEERING MANAGER***


# LOCATION



# INTRODUCTION - THE ATHABASCA OIL SANDS PROJECT



**MUSKEG  
RIVER MINE**



**CORRIDOR  
PIPELINE**




**SCOTFORD  
UPGRADER**



**SCOTFORD  
REFINERY  
(SHELL ONLY)**




**ORE**



**BITUMEN TO SYNTHETIC CRUDE  
(255,000 BPD)**


# GENERAL FEATURES

- **QUEST CCS PROJECT - FULLY INTEGRATED CCS (CAPTURE, TRANSPORT & STORAGE)**
- **JV AMONG SHELL (60%); CHEVRON (20%); AND MARATHON (20%) - PART OF AOSP**
- **LOCATED AT SCOTFORD UPGRADER COMPLEX**
- **ONE MILLION TONNES CO<sub>2</sub> PER YEAR CAPACITY FOR 25 YEARS**
- **35% REDUCTION OF UPGRADER CO<sub>2</sub> EMISSIONS**
- **PROJECT APPROVAL - SEPT 2012**



# HARDWARE


- **CAPTURE AT THE SCOTFORD UPGRADER FROM 3 HYDROGEN MANUFACTURING UNITS**
- **CO<sub>2</sub> TRANSPORTED BY 12 INCH PIPELINE TO STORAGE, WITH 6 INCH LATERALS**
- **PIPELINE TO 65 KM NORTH OF THE UPGRADER**
- **ROUTE SELECTED TO MEET STAKEHOLDER REQUIREMENTS:**
  - 28 KM FOLLOWS EXISTING ROW
  - DRILLED UNDER NORTH SASKATCHEWAN RIVER
  - 30+ RE-ROUTES TO ACCOMMODATE LANDOWNER WISHES
- **BASE PLAN: 3 INJECTION WELLS AND ASSOCIATED MONITORING**






# STORAGE

- **SALINE AQUIFER STORAGE**
- **INJECTION FORMATION - BASAL CAMBRIAN SANDS (BCS)**
  - **2,300 M DEPTH, PRAIRIES DEEPEST SANDSTONE**
  - **MULTIPLE CAPROCK AND SALT SEAL LAYERS IN THE STORAGE COMPLEX**
  - **NO SIGNIFICANT FAULTING VISIBLE FROM WELLS OR SEISMIC**
  - **THE BCS IS WELL BELOW HYDROCARBON BEARING FORMATIONS AND POTABLE WATER ZONES IN THE REGION**
  - **RELATIVELY FEW WELLS DRILLED INTO THE BCS, NONE WITHIN 10 KM OF THE PROPOSED STORAGE SITE**
- **WELLS AND DRILLING**



# TIMELINE AND UPCOMING ACTIVITIES



## ■ WELL PROGRAM

- DRILLING FINISHED, COMPLETIONS ONGOING

## ■ CAPTURE & PIPELINE

- ENGINEERING FINALIZED
- SITE UNDERGROUND CONSTRUCTION COMPLETE
- FIRST MODULE DELIVERY Q4 2013
- MAJOR EQUIPMENT DELIVERIES COMPLETE
- PIPELINE CONSTRUCTION BEGINS Q3 2013

## ■ COMMUNITY ADVISORY PANEL

- INITIAL KICKOFF IN JANUARY, WITH REGULAR UPDATES

## ■ FINAL REGULATORY APPROVALS

- PIPELINE LATERALS EXPECTED END 2013

RESTRICTED

SEPTEMBER 19, 2013

# **PROCESS SELECTION & INTEGRATION**

- 1. WHY ACTIVATED AMINE (ADIP-X)?**
- 2. HMU INTEGRATION ISSUES**
- 3. CO2 COMPRESSION, INTEGRATION WITH PIPELINE AND WELLS**



# WHY ACTIVATED AMINE (ADIP-X)?


**PROCESS SELECTION COMPLETED IN Q1 2010 WITH THE FOLLOWING CONSTRAINTS:**

- **DESIGN BASIS CAPACITY OF 1.2 MILLION TONNES PER YEAR, ON-STREAM FACTOR OF 90% = 1.08 MILLION TONNES PER YEAR CALENDAR DAY CAPACITY**
- **MAXIMUM PRESSURE DROP THROUGH THE CO<sub>2</sub> FACILITY LESS THAN 70 KPA**
- **TEMPERATURE OF THE PSA INLET GAS AFTER CO<sub>2</sub> CAPTURE SHALL NOT EXCEED 35°C IN ORDER TO MAINTAIN THE H<sub>2</sub> ABSORPTION CAPACITY**
- **CHEMICAL SOLVENT CARRYOVER TO THE PSA SHOULD BE LESS THAN 1 PPMW. CHEMICAL SOLVENTS CAN CONTAMINATE THE PSA'S ADSORBENTS.**
- **ONSITE ELECTRICAL POWER AVAILABILITY LIMITED DUE TO**

**HV SUBSTATION CONSTRAINTS**

# WHY ACTIVATED AMINE (ADIP-X)? - CO<sub>2</sub> SOURCE SELECTION

SCOTFORD  
UPGRADER



SELECTION DRIVER

PARAMETER	POST-COMB	D/S OF PSA	U/S OF PSA
SYSTEM PRESSURE	<b>X</b>	<b>X</b>	✓
CO <sub>2</sub> CONCENTRATION	<b>X</b>	✓	✓
CO <sub>2</sub> PARTIAL PRESSURE	<b>X</b>	<b>X</b>	✓
OTHER IMPURITIES	<b>X</b>	✓	✓
PLOT SPACE	<b>X</b>	<b>X</b>	✓

# WHY ACTIVATED AMINE (ADIP-X)?



CRITERIA	ADIP-X	MDEA	SELEXOL	MEMBRANE	PSA	METHANOL ABSORPTION	AMMONIA ABSORPTION	LIQUEFACTION
HSE RISKS	Green	Green	Yellow	Green	Green	Yellow	Red	Green
CAPEX	Green	Yellow	Yellow	Yellow	Yellow	Red	Yellow	Yellow
OPEX	Green	Green	Green	Red	Red	Red	Yellow	Green
HMU RELIABILITY EFFECTS	Green	Green	Red	Green	Green	Yellow	Green	Green
COMMERCIAL	Green	Green	Yellow	Red	Red	Green	Red	Red
CONSTRUCTABILITY	Green	Green	Red	Yellow	Yellow	Yellow	Yellow	Yellow

## INFLUENCING FACTORS


- **CONSTRUCTION IN BROWNFIELD LOCATION INFLUENCED 75% OF OPTIONS**
- **COMMERCIAL SCALABILITY UNPROVEN FOR 5 OF 8 OPTIONS**
- **LOCAL OPEX FACTORS - STEAM VERSUS ELECTRICITY COSTS**

# QUEST - CAPTURE FACILITIES

**SCOTFORD  
UPGRADER**




# CAPTURE DESIGN






# CAPTURE 3D MODEL - AMINE STRIPPER & CO2 COMPRESSION



# INTEGRATION WITH EXISTING HMUS




# INTEGRATION WITH EXISTING HMUS

- **WHAT DOES HMU DO WHEN QUEST IS ONLINE/OFFLINE?**
  - **VERIFY REFORMER BOX TRIP OCCURRENCES VIA DYNAMIC ANALYSIS**
  - **CONFIRM STEAM BALANCE WITHIN HMUS FOR FGR ON/OFF**
- **LOSS IN H<sub>2</sub> PRODUCTION DUE TO QUEST?**
  - **PSA REVISED ADSORBENT FILL TO POST QUEST OPTIMIZED LOADING**
- **70 KPA PRESSURE DROP FORCED PIPING UPSIZING**
- **ISSUES - REMOVING CO<sub>2</sub> IMPACTS HMU NOX PRODUCTION**
  - **LOW NOX BURNERS C/W TESTING (BURNER MANAGEMENT SYSTEM RELOOK)**


Emission Source	Air Contaminant/ Parameter	Current Limit	Requested Limit
Expansion HMU flue stack (S-44103)	Nitrogen oxides	62.7 kg/h	130.0 kg/h
Base plant Train 1 hydrogen manufacturing unit flue stack (S-24103)	Nitrogen oxides	47.5 kg/h	76.5 kg/h
Base plant Train 2 hydrogen manufacturing unit flue stack (S-24203)	Nitrogen oxides	47.5 kg/h	76.5 kg/h

□

## Scotford HMU NOx Reduction (Total)




# HMU 1 & 2 SCOPE






# COMPRESSOR OPERATING ENVELOPE INTEGRALLY GEARED, 8 STAGES WITH INLET



# INTEGRATION OF CAPTURE/PIPELINE/WELLS - ENVELOPE



# LEARNINGS AND CONCLUSION

- **QUEST IS THE FIRST COMMERCIAL SCALE CCS PROJECT IN CANADA**
  - **PACE SETTER FOR OTHER EFFORTS TO MANAGE CO<sub>2</sub> FOOTPRINT IN ALBERTA**
  - **ABUNDANT LEARNINGS FOR FUTURE PROJECTS**
- **KEY SUCCESS FACTORS**
  - **EARLY AND EXTENSIVE STAKEHOLDER ENGAGEMENT**
  - **USE OF PROVEN TECHNOLOGY**
- **SYSTEM OPTIMIZATION (FIT FOR PURPOSE) AND INTEGRATION ARE IMPORTANT TO MINIMIZE LIFE CYCLE COST**
  - **HMU INTEGRATION**
  - **UTILITIES INTEGRATION**
  - **CAPTURE OPTIMIZATION**
- **WORTH CONSIDERING**
  - **CAPTURE READY HMU'S OR CO<sub>2</sub> PRODUCERS**
  - **IMPROVEMENTS IN COMPRESSOR CONFIGURATION**
  - **EARLY ID WITH RIGOROUS DATA**



***WWW.SHELL.CA/QU  
EST  
THANK YOU!***

# NEXT STEPS

- INTO 'EXECUTE' PHASE TO STARTUP IN 2015
- 2013 MAJOR ACTIVITIES:
  - COMPLETION OF DETAILED ENGINEERING
  - BEGIN MAJOR CONSTRUCTION END 2012 (MOD YARD WORK)
  - MAJOR EQUIPMENT DELIVERY AND SETTING ONSITE
  - MMV BASELINE DATA GATHERING
  - BEGIN OPERATIONS READINESS AND TRAINING
  - COMPLETION OF REGULATORY APPLICATIONS (PIPELINE LATERALS)
  - ONGOING STAKEHOLDER MANAGEMENT



# ***COSTS/REVENUES AND FUNDING AGREEMENTS***

- ***TOTAL COST OF QUEST - CDN\$1.4 BILLION***
  - ***INCLUDES PRE FID, CAPITAL AND 10 YEARS OPEX***
  - ***CAPITAL RATIO: 80% CAPTURE, 10% PIPELINE, 10% WELLS***
- ***REVENUES - GHG OFFSETS (CREDITS)***
  - ***NET AMOUNT - STORED CO2, LESS DIRECT AND INDIRECT EMISSIONS***
  - ***CREDITS TO BE USED FIRST BY SHELL'S ALBERTA ASSETS FOR REGULATORY COMPLIANCE***
- ***GOVERNMENT FUNDING SUPPORT - CDN\$865 MILLION***
  - ***CDN\$120 MILLION CANADIAN FEDERAL GOVERNMENT (PRE FID)***
  - ***CDN\$ 745 MILLION ALBERTA PROVINCE (CONSTRUCTION, STARTUP AND 10 YEARS OPERATION)***
  - ***EXTENSIVE KNOWLEDGE SHARING***
  - ***STRINGENT MONITORING (MMV) PLAN***
  - ***NPV ZERO COMMITMENT***

# REGULATORY FRAMEWORK

- **PROVINCIAL GHG FRAMEWORK ESTABLISHED**
  - **CCS ACT PASSED IN NOV 2010, ESTABLISHING OVERALL STRUCTURE**
  - **PORE SPACE REGULATIONS IN PLACE WITH QUEST SUCCESSFULLY ACQUIRING REQUIRED AREA IN MAY 2011**
  - **PARTICIPATION IN REGULATORY FRAMEWORK ASSURANCE (RFA) PROCESS AND GHG OFFSET PROTOCOL REVISIONS**
  - **NO FEDERAL FRAMEWORK TO DATE - POSSIBLE 2013**
  
- **REGULATORY APPROVALS NEAR COMPLETE**
  - **FEDERAL COMPLIANCE ACHIEVED - EIA SUBMITTED, COMPLETED INTERNAL AND PUBLIC REVIEW**
  - **BUNDLED PROVINCIAL APPLICATION SUBMITTED - UPGRADE AMENDMENT, PIPELINE, WELL AND STORAGE**
  - **3 ROUNDS OF INFORMATION REQUESTS (200+) BY PROVINCIAL REGULATOR, THE ERCB**
  - **ERCB PUBLIC HEARING MARCH 2012**
  - **SUMMER WORKS AND DRILLING PERMITS TO FOLLOW ERCB DECISION**

# GENERAL PROJECT ASSESSMENT

## ■ GENERAL ASSESSMENT - VERY POSITIVE

- MAJOR PROJECT ATTRIBUTES (TECHNICAL, COSTS, REGULATORY, STAKEHOLDERS) TRACKING AS PLANNED

## ■ PROJECT SUCCESSES

- GOVERNMENT FISCAL SUPPORT
- PORE SPACE TENURE
- CAPTURE AND PIPELINE FRONT END ENGINEERING AND DESIGN (FEED) COMPLETION AND ASSURANCE
- TEST WELL AND AQUIFER PROPERTY VERIFICATION
- STAKEHOLDER ENGAGEMENT
- PIPELINE ROUTING FINALIZATION
- DNV CERTIFICATION OF THE STORAGE DEVELOPMENT PLAN
- REGULATORY HEARING

## ■ CHALLENGES

- CAPITAL COSTS
- SCHEDULE PRESSURE
- REGULATORY UNCERTAINTY (GHG PROTOCOLS, FEDERAL FRAMEWORK)